STATE OF CALIFORNIA
BUSINESS, TRANSPORTATION AND HOUSING AGENCY
DEPARTMENT OF TRANSPORTATION

2010
CONTRACT COST DATA

A SUMMARY OF COST BY ITEMS FOR HIGHWAY CONSTRUCTION PROJECTS

Caltrans

2010
CONTRACT COST DATA

The *Contract Cost Data* book is published annually by the Department of Transportation, Division of Engineering Services - Office Engineer, Office of Contract Awards and Services. This book includes standard contract items for major highway contracts for which bids were *awarded in 2010.* Some of the units of measure for these items were in U.S. Customary Units (English) and were converted to International System of Units (SI) for this publication. The conversion factors used for this purpose are listed in *Appendix A*. For those who wish to convert back to English units, the appropriate conversion factors are listed in *Appendix B*.

Advertised item quantities have been used as source information. Item quantities may vary from the final quantities incorporated into the completed contract. Prices shown in this tabulation are the mechanically weighted average of the awarded bidders' prices and are affected by location, time, quantity in the job and size of the item (relative to the size of the job). In this book, a six-digit item code has been assigned to each standard contract item and the items are listed numerically.

For assistance, contact Division of Engineering Services - Office Engineer, Office of Contract Awards and Services by e-mail at this address: DES-OE_Contract_Service @dot.ca.gov. The Web site address to download this book is http://www.dot.ca.gov/hq/esc/oe/awards.

TABLE OF CONTENTS

INDEX OF ITEM DESCRIPTION ……..A1

CONTRACT ITEM COST DATA……1

APPENDIX A……335
(CONVERSION FACTORS FROM ENGLISH UNITS TO SI UNITS)

APPENDIX B……335
(CONVERSION FACTORS FROM SI UNITS TO ENGLISH UNITS)

Index of Item Description

ITEM DESCRIPTION	ITEM CODE
0 - 9	
1 1/2" BACKFLOW PREVENTER ASSEMBLY	208425
1 1/2" ELECTRIC REMOTE CONTROL VALVE	206604
1 1/2" GATE VALVE	208574
1 1/2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208265
1 1/2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	208597
1 1/2" WYE STRAINER	208628
1 1/4" ELECTRIC REMOTE CONTROL VALVE	206603
1 1/4" GALVANIZED STEEL PIPE (CONDUIT)	208770
1 1/4" GATE VALVE	208573
1 1/4" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208264
1 1/4" WYE STRAINER	208627
1" ELECTRIC REMOTE CONTROL VALVE	206602
1" GALVANIZED STEEL PIPE (SUPPLY LINE)	208003
1" GATE VALVE	208572
1" MANUAL CONTROL VALVE	208618
1" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208263
1" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	208595
1" PRESSURE RELIEF VALVE	208633
1" WYE STRAINER	208626
1.5 M CAST-IN-DRILLED-HOLE CONCRETE PILING	490663
1.5 M CHAIN LINK GATE (TYPE CL-1.8)	802589
1.8 M CHAIN LINK GATE (TYPE CL-1.8)	802590
1/2" PLASTIC PIPE (IRRIGATION LINE)	208211
10' CHAIN LINK GATE (TYPE CL-6)	802560
10" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208739
10" CORRUGATED STEEL FLUME DOWNDRAIN	691004
10" FLUME ANCHOR ASSEMBLY	692364
10" FLUME DOWNDRAIN	691902
10" TAPERED INLET	692104

ITEM DESCRIPTION	ITEM CODE
0 - 9	
10" WELDED STEEL PIPE CONDUIT (.250" THICK)	208809
100 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	208024
100 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	208256
100 MM THERMOPLASTIC TRAFFIC STRIPE	840561
100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 1.83 M - 0.30 M)	840567
100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 10.98 M - 3.66 M)	840570
100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 3.66 M - 0.92 M)	840568
100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 5.18 M - 2.14 M)	840571
1050 MM ALTERNATIVE PIPE CULVERT	620930
12' CHAIN LINK GATE (TYPE CL-6)	802580
12 SINGLEMODE FIBER OPTIC CABLE	867014
12 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	206751
12' WIRE MESH GATE	801190
12" ALTERNATIVE FLARED END SECTION	705307
12" ALTERNATIVE PIPE CULVERT	620060
12" ALTERNATIVE PIPE CULVERT (TYPE A)	620061
12" ALTERNATIVE PIPE CULVERT (TYPE B)	620062
12" ANCHOR ASSEMBLY	692305
12" BITUMINOUS COATED CORRUGATED STEEL PIPE (.079" THICK)	665112
12" BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690212
12" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208740
12" CORRUGATED STEEL PIPE	665010
12" CORRUGATED STEEL PIPE (.064" THICK)	665011
12" CORRUGATED STEEL PIPE (.079" THICK)	665012
12" CORRUGATED STEEL PIPE DOWNDRAIN	690110
12" CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK)	690111
12" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690112

ITEM DESCRIPTION	ITEM CODE
0 - 9	
12" DOWNDRAIN SLIP JOINT	692205
12" ENTRANCE TAPER	692005
12" PERFORATED STEEL PIPE UNDERDRAIN	680410
12" PLASTIC PIPE	641101
12" PLASTIC PIPE DOWNDRAIN	690960
12" PRECAST CONCRETE PIPE INLET	707102
12" REINFORCED CONCRETE PIPE	650010
12" SLOTTED CORRUGATED STEEL PIPE (.079" THICK)	665712
12" SLOTTED CORRUGATED STEEL PIPE (.109" THICK)	665713
12" STEEL FLARED END SECTION	705007
12" TEMPORARY CULVERT	073004
12" WELDED STEEL PIPE (.250" THICK)	703533
12" WELDED STEEL PIPE CONDUIT (.250" THICK)	208812
120" CAST-IN-DRILLED-HOLE CONCRETE PILING	490622
1200 MM ALTERNATIVE PIPE CULVERT	620933
1200 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	664043
1200 MM CORRUGATED STEEL PIPE RISER (2.77 MM THICK)	703288
1200 MM REINFORCED CONCRETE PIPE	650084
1220 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561012
1372 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561013
15" ALTERNATIVE FLARED END SECTION	705309
15" ALTERNATIVE PIPE CULVERT	620080
15" ANCHOR ASSEMBLY	692306
15" CORRUGATED STEEL PIPE (.079" THICK)	665014
15" CORRUGATED STEEL PIPE (.109" THICK)	665015
15" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	690115
15" ENTRANCE TAPER	692006
15" PLASTIC PIPE	641104
15" REINFORCED CONCRETE PIPE	650012
150 MM BITUMINOUS COATED STEEL PIPE CONDUIT (1.63 MM THICK)	208745

ITEM DESCRIPTION	ITEM CODE
0 - 9	
150 MM NON-PERFORATED PLASTIC PIPE UNDERDRAIN	680932
150 MM PERFORATED PLASTIC PIPE UNDERDRAIN	680931
150 MM PLASTIC PIPE	681066
150 MM THERMOPLASTIC TRAFFIC STRIPE	840562
150 MM WELDED STEEL PIPE (3.40 MM THICK)	703522
1500 MM REINFORCED CONCRETE PIPE	650089
1524 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561015
16' CHAIN LINK GATE (TYPE CL-6)	802620
16 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	206756
16' WIRE MESH GATE	801230
16" CAST-IN-DRILLED-HOLE CONCRETE PILING	490601
16" CAST-IN-DRILLED-HOLE CONCRETE PILING (BARRIER)	498009
16" CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	498016
18 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	206752
18" ALTERNATIVE FLARED END SECTION	705311
18" ALTERNATIVE PIPE CULVERT	620100
18" ALTERNATIVE PIPE CULVERT (TYPE A)	620101
18" ALTERNATIVE PIPE CULVERT (TYPE B)	620102
18" ALTERNATIVE PIPE DOWNDRAIN	698100
18" ALTERNATIVE PIPELINER	155115
18" ALTERNATIVE SLOTTED PIPE	620715
18" ANCHOR ASSEMBLY	692307
18" BITUMINOUS COATED CORRUGATED STEEL PIPE (.064" THICK)	665116
18" BITUMINOUS COATED CORRUGATED STEEL PIPE (.079" THICK)	665117
18" BITUMINOUS COATED CORRUGATED STEEL PIPE (.109" THICK)	665118
18" BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK)	690216
18" BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (.079" THICK)	703317
18" BITUMINOUS COATED ENTRANCE TAPER	692037
18" CAST-IN-DRILLED-HOLE CONCRETE PILING	490615

ITEM DESCRIPTION	ITEM CODE
0 - 9	
18" CONCRETE FLARED END SECTION	705204
18" CORRUGATED STEEL PIPE (.064" THICK)	665016
18" CORRUGATED STEEL PIPE (.079" THICK)	665017
18" CORRUGATED STEEL PIPE (.109" THICK)	665018
18" CORRUGATED STEEL PIPE (.138" THICK)	665075
18" CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK)	690116
18" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690117
18" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	690118
18" CORRUGATED STEEL PIPE RISER (.168" THICK)	703220
18" CURED-IN-PLACE PIPELINER	155314
18" ENTRANCE TAPER	692007
18" PLASTIC PIPE	641107
18" REINFORCED CONCRETE PIPE	650014
18" REINFORCED CONCRETE PIPE (CLASS II)	650211
18" REINFORCED CONCRETE PIPE (CLASS V)	650511
18" REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650105
18" SLOTTED CORRUGATED STEEL PIPE (.079" THICK)	665717
18" STEEL FLARED END SECTION	705011
18" TEMPORARY CULVERT	073006
1800 MM REINFORCED CONCRETE PIPE	650092
2 1/2" ELECTRIC REMOTE CONTROL VALVE	206606
2 1/2" GALVANIZED STEEL PIPE (SUPPLY LINE)	208007
2 1/2" GATE VALVE	208576
2 1/2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208267
2 1/2" PLASTIC PIPE (PR 315) (SUPPLY LINE)	208277
2" BACKFLOW PREVENTER ASSEMBLY	208426
2" ELECTRIC REMOTE CONTROL VALVE	206605
2" GALVANIZED STEEL PIPE (SUPPLY LINE ON BRIDGE)	208042
2" GALVANIZED STEEL PIPE (SUPPLY LINE)	208006

ITEM DESCRIPTION	ITEM CODE
0 - 9	
2" GATE VALVE	208575
2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208266
2" PLASTIC PIPE (PR 315) (SUPPLY LINE)	208276
2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	208598
2" WYE STRAINER	208630
2.1 M CAST-IN-DRILLED-HOLE CONCRETE PILING	490669
2.4 M CHAIN LINK GATE (TYPE CL-1.8)	802592
20' CHAIN LINK GATE (TYPE CL-6)	802660
20 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	208017
20 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	208249
20 MM QUICK COUPLING VALVE	208517
200 MM ALTERNATIVE PIPE CULVERT	620902
200 MM BITUMINOUS COATED STEEL PIPE CONDUIT (1.63 MM THICK)	208746
200 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208731
200 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK)	690156
200 MM PERFORATED PLASTIC PIPE UNDERDRAIN	680933
200 MM POLYVINYL CHLORIDE SEWER PIPE	717077
200 MM THERMOPLASTIC TRAFFIC STRIPE	840563
200 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 10.98 M - 3.66 M)	840574
200 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 3.66 M - 0.92 M)	840564
200 MM TWO-COMPONENT PAINT TRAFFIC STRIPE	840577
200 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	208798
21" X 15" CORRUGATED STEEL PIPE ARCH (.109" THICK)	667006
21" X 15" STEEL FLARED END PIPE ARCH SECTION	705403
24 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	206753
24" ALTERNATIVE FLARED END SECTION	705315
24" ALTERNATIVE PIPE CULVERT	620140
24" ALTERNATIVE PIPE DOWNDRAIN	698140
24" ALTERNATIVE PIPELINER	155121

ITEM DESCRIPTION	ITEM CODE
0 - 9	
24" ANCHOR ASSEMBLY	692309
24" BITUMINOUS COATED CORRUGATED STEEL PIPE (.079" THICK)	665123
24" CAST-IN-DRILLED-HOLE CONCRETE PILING	490603
24" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	490683
24" CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	498022
24" CONCRETE FLARED END SECTION	705206
24" CORRUGATED STEEL PIPE (.064" THICK)	665022
24" CORRUGATED STEEL PIPE (.079" THICK)	665023
24" CORRUGATED STEEL PIPE (.109" THICK)	665024
24" CORRUGATED STEEL PIPE (.138" THICK)	665025
24" CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK)	690122
24" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690123
24" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	690124
24" CORRUGATED STEEL PIPE DOWNDRAIN (.138" THICK)	690125
24" CORRUGATED STEEL PIPE RISER (.079" THICK)	703223
24" CURED-IN-PLACE PIPELINER	155316
24" DOWNDRAIN SLIP JOINT	692209
24" PLASTIC PIPE	641113
24" REINFORCED CONCRETE PIPE	650018
24" REINFORCED CONCRETE PIPE (CLASS II, RUBBER GASKET JOINT)	652215
24" REINFORCED CONCRETE PIPE (CLASS IV)	650416
24" REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650107
24" STEEL FLARED END SECTION	705015
24" TEMPORARY CULVERT	073008
24" WELDED STEEL PIPE (.250" THICK)	703575
24" WELDED STEEL PIPE CASING (BRIDGE)	703460
25 MM ELECTRIC REMOTE CONTROL VALVE	206611
25 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	208018

ITEM DESCRIPTION	ITEM CODE
0 - 9	
25 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	208250
25 MM WYE STRAINER	208509
250 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208732
250 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	208799
28" X 20" CORRUGATED STEEL PIPE ARCH (.079" THICK)	667013
3' CHAIN LINK GATE (TYPE CL-6)	802500
3" BACKFLOW PREVENTER ASSEMBLY	208428
3" ELECTRIC REMOTE CONTROL VALVE	206607
3" GALVANIZED STEEL PIPE (SUPPLY LINE)	208008
3" GATE VALVE	208588
3" PLASTIC PIPE	680207
3" PLASTIC PIPE (EDGE DRAIN OUTLET)	681107
3" PLASTIC PIPE (EDGE DRAIN)	681103
3" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208268
3" PLASTIC PIPE (PR 315) (SUPPLY LINE)	208278
3" SLOTTED PLASTIC PIPE	680225
3" SUPPLY LINE (BRIDGE)	208028
3" WYE STRAINER	208634
3.0 M CHAIN LINK GATE (TYPE CL-1.8)	802595
3.7 M CHAIN LINK GATE (TYPE CL-1.8)	802596
3/4" ELECTRIC REMOTE CONTROL VALVE	206601
3/4" PLASTIC PIPE (IRRIGATION LINE)	208213
3/4" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208262
3/4" QUICK COUPLING VALVE	208645
30" ALTERNATIVE FLARED END SECTION	705319
30" ALTERNATIVE PIPE CULVERT	620180
30" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561004
30" CAST-IN-DRILLED-HOLE CONCRETE PILING	490604
30" CONCRETE FLARED END SECTION	705208
30" CORRUGATED STEEL PIPE (.064" THICK)	665030
30" CORRUGATED STEEL PIPE (.079" THICK)	665031

ITEM DESCRIPTION	ITEM CODE
0 - 9	
30" CORRUGATED STEEL PIPE (.109" THICK)	665032
30" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690131
30" CORRUGATED STEEL PIPE DOWNDRAIN (.138" THICK)	690134
30" CURED-IN-PLACE PIPELINER	155318
30" MACHINE SPIRAL WOUND PVC PIPELINER (EXPANDABLE DIAMETER)	155369
30" PLASTIC PIPE	641119
30" REINFORCED CONCRETE PIPE	650022
30" STEEL FLARED END SECTION	705019
300 MM ALTERNATIVE FLARED END SECTION	705334
300 MM ALTERNATIVE PIPE CULVERT	620904
300 MM CONCRETE FLARED END SECTION	705220
300 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208733
300 MM CORRUGATED STEEL PIPE	664008
300 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	664009
300 MM CORRUGATED STEEL PIPE DOWNDRAIN (1.63 MM THICK)	690159
300 MM PLASTIC PIPE	641132
300 MM REINFORCED CONCRETE PIPE	650067
300 MM TEMPORARY CULVERT	073026
300 MM WELDED STEEL PIPE (2.67 MM THICK)	703542
300 MM WELDED STEEL PIPE (3.40 MM THICK)	703543
300 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	208800
32 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	208019
32 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	208251
36" ALTERNATIVE FLARED END SECTION	705321
36" ALTERNATIVE PIPE CULVERT	620220
36" ALTERNATIVE PIPE INLET	708021
36" ANCHOR ASSEMBLY	692313
36" BITUMINOUS COATED CORRUGATED STEEL PIPE (.079" THICK)	665136
36" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561005

ITEM DESCRIPTION	ITEM CODE
0 - 9	
36" CAST-IN-DRILLED-HOLE CONCRETE PILING	490605
36" CORRUGATED STEEL PIPE (.109" THICK)	665037
36" CORRUGATED STEEL PIPE (.138" THICK)	665038
36" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	690136
36" CORRUGATED STEEL PIPE DOWNDRAIN (.138" THICK)	690138
36" CORRUGATED STEEL PIPE INLET (.064" THICK)	700637
36" CORRUGATED STEEL PIPE INLET (.079" THICK)	700638
36" CORRUGATED STEEL PIPE INLET (.109" THICK)	700639
36" CORRUGATED STEEL PIPE INLET (.138" THICK)	700640
36" CORRUGATED STEEL PIPE INLET (.168" THICK)	700641
36" CURED-IN-PLACE PIPELINER	155319
36" PLASTIC PIPE	641125
36" PRECAST CONCRETE PIPE INLET	707117
36" REINFORCED CONCRETE PIPE	650026
36" REINFORCED CONCRETE PIPE RISER	707467
36" STEEL FLARED END SECTION	705023
36" TEMPORARY CULVERT	073011
36" WELDED STEEL PIPE (.375" THICK)	703620
375 MM ALTERNATIVE PIPE CULVERT	620908
375 MM REINFORCED CONCRETE PIPE	650068
4' CHAIN LINK GATE (TYPE CL-6)	802501
4' CHAIN LINK GATE (TYPE CL-6, VINYL-CLAD)	802502
4' CHAIN LINK GATE (TYPE CL-8, EXTENSION ARM)	802902
4' WIRE MESH GATE	801110
4" BACKFLOW PREVENTER ASSEMBLY	208430
4" GALVANIZED STEEL PIPE (SUPPLY LINE)	208009
4" GATE VALVE	208589
4" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208270
4" PLASTIC PIPE (PR 315) (SUPPLY LINE)	208279
4" THERMOPLASTIC TRAFFIC STRIPE	840504

ITEM DESCRIPTION	ITEM CODE
0 - 9	
4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)	840523
4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 17-7)	840526
4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)	840525
4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 6-1)	840521
4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED)	840581
4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED) (BROKEN 17-7)	840580
4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED, BROKEN 36-12)	840545
4" TWO-COMPONENT PAINT TRAFFIC STRIPE	840582
4" TWO-COMPONENT PAINT TRAFFIC STRIPE (BROKEN 17-7)	840608
4.3 M CHAIN LINK GATE (TYPE CL-1.8)	802671
4.6 M WIRE MESH GATE	801273
4.9 M CHAIN LINK GATE (TYPE CL-1.8)	802672
40 MM ELECTRIC REMOTE CONTROL VALVE	206613
40 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	208020
40 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	208252
40 MM WYE STRAINER	208511
400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	490655
400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	498027
42" ALTERNATIVE PIPE CULVERT	620260
42" CAST-IN-DRILLED-HOLE CONCRETE PILE (HIGH MAST LIGHTING)	860140
42" CONCRETE FLARED END SECTION	705212
42" CORRUGATED STEEL PIPE (.138" THICK)	665043
42" CURED-IN-PLACE PIPELINER	155320
42" REINFORCED CONCRETE PIPE	650030
42" STEEL FLARED END SECTION	705027
42" X 29" ALTERNATIVE PIPE ARCH CULVERT	625299
450 MM ALTERNATIVE FLARED END SECTION	705336
450 MM ALTERNATIVE PIPE CULVERT	620909

ITEM DESCRIPTION	ITEM CODE
0 - 9	
450 MM ALTERNATIVE PIPE CULVERT (TYPE A)	620910
450 MM ALTERNATIVE PIPE CULVERT (TYPE B)	620911
450 MM ALTERNATIVE PIPE DOWNDRAIN	698162
450 MM ALTERNATIVE PIPE RISER	708064
450 MM ALTERNATIVE SLOTTED PIPE	621110
450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (2.01 MM THICK)	703361
450 MM BITUMINOUS COATED SLOTTED CORRUGATED STEEL PIPE (2.01 MM THICK)	665833
450 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	490656
450 MM CONCRETE FLARED END SECTION	705222
450 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	664014
450 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	664015
450 MM REINFORCED CONCRETE PIPE	650069
450 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650127
450 MM SLOTTED CORRUGATED STEEL PIPE (1.63 MM THICK)	665732
450 MM SLOTTED CORRUGATED STEEL PIPE (2.01 MM THICK)	665733
450 MM SLOTTED PLASTIC PIPE	641155
450 MM STEEL FLARED END SECTION	705044
450 MM TEMPORARY CULVERT	073028
48" ALTERNATIVE FLARED END SECTION	705325
48" ALTERNATIVE PIPE CULVERT	620300
48" BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (.079" THICK)	703354
48" CAST-IN-DRILLED-HOLE CONCRETE PILING	490607
48" CONCRETE FLARED END SECTION	705214
48" CORRUGATED STEEL PIPE DOWNDRAIN (.138" THICK)	690148
48" CORRUGATED STEEL PIPE INLET (.109" THICK)	700655
48" CURED-IN-PLACE PIPELINER	155321
48" PRECAST CONCRETE PIPE MANHOLE	707225
48" REINFORCED CONCRETE PIPE	650034
48" REINFORCED CONCRETE PIPE (CLASS IV)	650432

ITEM DESCRIPTION	ITEM CODE
0 - 9	
48" STEEL FLARED END SECTION	705031
5' CHAIN LINK GATE (TYPE CL-6)	802510
50 MM BACKFLOW PREVENTER ASSEMBLY	208435
50 MM ELECTRIC REMOTE CONTROL VALVE	206614
50 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	208021
50 MM GATE VALVE	208491
50 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	208253
50 MM WYE STRAINER	208512
54" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561014
6' CHAIN LINK GATE (TYPE CL-6)	802520
6' WIRE MESH GATE	801130
6" ALTERNATIVE PIPE UNDERDRAIN	685000
6" CONDUIT	208708
6" CORRUGATED STEEL PIPE (.064" THICK)	665002
6" CORRUGATED STEEL PIPE CONDUIT (.064" THICK)	208756
6" GATE VALVE	208590
6" NON-PERFORATED PLASTIC PIPE UNDERDRAIN	680903
6" PERFORATED PLASTIC PIPE UNDERDRAIN	680902
6" PLASTIC PIPE	681023
6" PLASTIC PIPE (EDGE DRAIN OUTLET)	681113
6" PLASTIC PIPE (EDGE DRAIN)	681108
6" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208281
6" PLASTIC PIPE (PR 315) (SUPPLY LINE)	208280
6" THERMOPLASTIC TRAFFIC STRIPE	840505
6" WELDED STEEL PIPE (.134" THICK)	703509
6" WELDED STEEL PIPE CONDUIT (.250" THICK)	208805
6.1 M CHAIN LINK GATE (TYPE CL-1.8)	802675
60" ALTERNATIVE PIPE CULVERT	620380
60" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561016
600 MM ALTERNATIVE FLARED END SECTION	705337

ITEM DESCRIPTION	ITEM CODE
0 - 9	
600 MM ALTERNATIVE PIPE CULVERT	620913
600 MM ALTERNATIVE PIPE CULVERT (TYPE A)	620914
600 MM ALTERNATIVE PIPE CULVERT (TYPE B)	620915
600 MM ALTERNATIVE PIPE DOWNDRAIN	698169
600 MM AUTOMATIC DRAINAGE GATE	705566
600 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.01 MM THICK)	664096
600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	490657
600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	498030
600 MM CONCRETE FLARED END SECTION	705224
600 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	664019
600 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	664020
600 MM CORRUGATED STEEL PIPE (3.51 MM THICK)	664022
600 MM PRECAST CONCRETE PIPE MANHOLE	707242
600 MM REINFORCED CONCRETE PIPE	650075
600 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	650128
600 MM SLIDE HEADGATE	705651
600 MM STEEL FLARED END SECTION	705045
600 MM TEMPORARY CULVERT	073029
600 MM WELDED STEEL PIPE CASING (BRIDGE)	703481
65 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	208022
65 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	208254
66" REINFORCED CONCRETE PIPE	650046
675 MM REINFORCED CONCRETE PIPE	650076
72" PRECAST CONCRETE PIPE MANHOLE	707241
75 MM ELECTRIC REMOTE CONTROL VALVE	206616
75 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	208023
75 MM GATE VALVE	208493
75 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	208255
750 MM ALTERNATIVE FLARED END SECTION	705338

ITEM DESCRIPTION	ITEM CODE
0 - 9	
750 MM ALTERNATIVE PIPE CULVERT	620919
750 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	490658
750 MM REINFORCED CONCRETE PIPE	650077
8' CHAIN LINK GATE (TYPE CL-6)	802540
8 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	206749
8" ALTERNATIVE PIPE CULVERT	620020
8" ALTERNATIVE PIPE UNDERDRAIN	685020
8" ANCHOR ASSEMBLY	692303
8" COLLECTOR SYSTEM (HORIZONTAL DRAIN)	681512
8" CONDUIT	208709
8" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	208738
8" CORRUGATED STEEL PIPE (.064" THICK)	665005
8" CORRUGATED STEEL PIPE (.079" THICK)	665006
8" CORRUGATED STEEL PIPE DOWNDRAIN	690104
8" ENTRANCE TAPER	692003
8" PERFORATED PLASTIC PIPE UNDERDRAIN	680905
8" PLASTIC PIPE (PR 200) (SUPPLY LINE)	208282
8" THERMOPLASTIC TRAFFIC STRIPE	840506
8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)	840508
8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)	840550
8" TWO-COMPONENT PAINT TRAFFIC STRIPE	840584
8" WELDED STEEL PIPE (.134" THICK)	703515
8" WELDED STEEL PIPE CONDUIT (.250" THICK)	208808
80 MM PLASTIC PIPE	680256
80 MM PLASTIC PIPE (EDGE DRAIN OUTLET)	681137
825 MM REINFORCED CONCRETE PIPE	650078
900 MM ALTERNATIVE FLARED END SECTION	705339
900 MM ALTERNATIVE PIPE CULVERT	620924
900 MM ALTERNATIVE PIPE RISER	708068
900 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	490675

ITEM DESCRIPTION	ITEM CODE
0 - 9	
900 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	664033
900 MM CORRUGATED STEEL PIPE INLET (2.01 MM THICK)	700658
900 MM CORRUGATED STEEL PIPE INLET (2.77 MM THICK)	700659
900 MM PRECAST CONCRETE PIPE MANHOLE	707244
900 MM REINFORCED CONCRETE PIPE	650079
920 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	561009
975 MM REINFORCED CONCRETE PIPE	650080
A	
ABANDON CULVERT	150206
ABANDON INLET	150221
ABANDON MANHOLE	150224
ABANDON PIPELINE	150227
ABANDON WATER WELL	150229
ABUTMENT LUMBER BLOCKING	570115
ACCESS OPENING, DECK	153530
ACCESS OPENING, SOFFIT	153531
ADJUST FIRE HYDRANT	152427
ADJUST FRAME AND COVER TO GRADE	152438
ADJUST FRAME AND GRATE TO GRADE	152439
ADJUST INLET	152430
ADJUST MANHOLE TO GRADE	152440
ADJUST METAL BEAM GUARD RAILING	152500
ADJUST MONUMENT TO GRADE	152423
ADJUST PULL BOX	869042
ADJUST SEWER CLEANOUT TO GRADE	152400
ADJUST SLOTTED DRAIN TO GRADE	152555
ADJUST UTILITY COVER	152472
ADJUST UTILITY COVER TO GRADE	152469
ADJUST WATER METER BOX TO GRADE	152403
ADJUST WATER METER TO GRADE	152401
ADJUST WATER VALVE	152451

ITEM DESCRIPTION	ITEM CODE
A	
ADJUST WATER VALVE COVER TO GRADE	152402
ADL BURIAL LOCATION REPORT	190111
AGGREGATE BASE (APPROACH SLAB)	260210
ALTERNATIVE FLARED TERMINAL SYSTEM	839585
ALTERNATIVE IN-LINE TERMINAL SYSTEM	839584
ANCHOR ASSEMBLY	692301
ANTI-GRAFFITI COATING	511047
ARCHITECTURAL TREATMENT	511035
ASBESTOS COMPLIANCE PLAN	190113
ASBESTOS COMPLIANCE PLAN (NATURALLY OCCURING ASBESTOS)	190115
ASPHALT BINDER (POLYMER MODIFIED)	370125
ASPHALT MEMBRANE WATERPROOFING	540101
ASPHALT TREATED PERMEABLE BASE	290201
ASPHALTIC EMULSION	373900
ASPHALTIC EMULSION (CURING SEAL)	270065
ASPHALTIC EMULSION (FOG SEAL COAT)	374002
ASPHALTIC EMULSION (PAINT BINDER)	397001
ASPHALTIC EMULSION (POLYMER MODIFIED)	374492
ASPHALTIC EMULSION MEMBRANE (BONDED WEARING COURSE)	390149
ASPHALTIC EMULSION MEMBRANE (BONDED WEARING COURSE)	390151
ASPHALT-RUBBER BINDER	370120
AUTOMATIC DRAINAGE GATE	705500
B	
BACKFLOW PREVENTER ASSEMBLY	208420
BACKFLOW PREVENTER ASSEMBLY BLANKET	208439
BACKFLOW PREVENTER ASSEMBLY ENCLOSURE	208421
BALL VALVE	208683
BAR REINFORCING STEEL	520101
BAR REINFORCING STEEL (BOX CULVERT)	520107
BAR REINFORCING STEEL (BRIDGE)	520102

ITEM DESCRIPTION	ITEM CODE
B	
BAR REINFORCING STEEL (EPOXY COATED)	520106
BAR REINFORCING STEEL (EPOXY COATED) (BRIDGE)	520110
BAR REINFORCING STEEL (RETAINING WALL)	520103
BAR REINFORCING STEEL (SOUND WALL)	520105
BAR REINFORCING STEEL (TUNNEL)	520109
BLANK WELL CASING	760030
BOOSTER PUMP ELECTRICAL SYSTEM	860798
BOOSTER PUMP SYSTEM	209503
BRIDGE DECK DRAINAGE SYSTEM	750505
BRIDGE REMOVAL	157550
BRIDGE REMOVAL (PORTION)	157560
BRIDGE REMOVAL (PORTION), LOCATION A	157561
BRIDGE REMOVAL (PORTION), LOCATION B	157562
BRIDGE REMOVAL (PORTION), LOCATION C	157563
BRIDGE REMOVAL (PORTION), LOCATION D	157564
BRIDGE REMOVAL (PORTION), LOCATION E	157565
BRIDGE REMOVAL (PORTION), LOCATION F	157566
BRIDGE REMOVAL (PORTION), LOCATION G	157567
BRIDGE REMOVAL (PORTION), LOCATION H	157568
BRIDGE REMOVAL (PORTION), LOCATION I	157569
BRIDGE REMOVAL (PORTION), LOCATION J	157570
BRIDGE REMOVAL (PORTION), LOCATION K	157571
BRIDGE REMOVAL (PORTION), LOCATION L	157572
BRIDGE REMOVAL (PORTION), LOCATION M	157573
BRIDGE REMOVAL, LOCATION A	157551
BRIDGE REMOVAL, LOCATION B	157552
BRIDGE REMOVAL, LOCATION C	157553
BRIDGE REMOVAL, LOCATION D	157554
BRIDGE REMOVAL, LOCATION E	157555
BUILDING WORK	994650
C	

ITEM DESCRIPTION	ITEM CODE
C	
CABLE ANCHORAGE SYSTEM	692409
CABLE RAILING	839521
CABLE RAILING (MODIFIED)	839527
CAM COUPLER ASSEMBLY	208562
CAP INLET	155003
CAP MANHOLE	155007
CAP RISER	155006
CEMENT TREATED BASE (PLANT-MIXED, CLASS A)	270011
CEMENT TREATED BASE (ROAD-MIXED, CLASS A)	270001
CEMENT TREATED PERMEABLE BASE	290301
CHAIN LINK FENCE	800300
CHAIN LINK FENCE (ROCK BARRIER)	800600
CHAIN LINK FENCE (TYPE CL-0.9, VINYL-CLAD)	800382
CHAIN LINK FENCE (TYPE CL-1.5)	800389
CHAIN LINK FENCE (TYPE CL-1.8)	800391
CHAIN LINK FENCE (TYPE CL-3, VINYL-CLAD)	800302
CHAIN LINK FENCE (TYPE CL-4)	800320
CHAIN LINK FENCE (TYPE CL-4, VINYL-CLAD)	800321
CHAIN LINK FENCE (TYPE CL-6)	800360
CHAIN LINK FENCE (TYPE CL-6, VINYL-CLAD)	800361
CHAIN LINK FENCE (TYPE CL-8, EXTENSION ARM)	802900
CHAIN LINK GATE	801900
CHAIN LINK RAILING	833020
CHAIN LINK RAILING (TYPE 3L)	833023
CHAIN LINK RAILING (TYPE 7 MODIFIED)	833033
CHAIN LINK RAILING (TYPE 7)	833032
CHANGEABLE MESSAGE SIGN SYSTEM	860530
CHANNELIZER (SURFACE MOUNTED)	120165
CHANNELIZER (SURFACE MOUNTED) (LEFT IN PLACE)	120166
CHECK VALVE	208670
CLASS 1 AGGREGATE SUBBASE	250101

ITEM DESCRIPTION	ITEM CODE
C	
CLASS 1 CONCRETE (BOX CULVERT)	510413
CLASS 1 CONCRETE (MINOR STRUCTURE)	510409
CLASS 1 PERMEABLE MATERIAL	682020
CLASS 1 PERMEABLE MATERIAL (BLANKET)	682022
CLASS 2 AGGREGATE BASE	260201
CLASS 2 AGGREGATE SUBBASE	250201
CLASS 2 CONCRETE (BOX CULVERT)	510129
CLASS 2 CONCRETE (HEADWALL)	510135
CLASS 2 CONCRETE (WINGWALLS)	510138
CLASS 2 PERMEABLE MATERIAL	682040
CLASS 3 AGGREGATE BASE	260301
CLASS 3 AGGREGATE SUBBASE	250301
CLASS 3 CONCRETE	510217
CLASS 3 CONCRETE (BACKFILL)	510220
CLASS 3 PERMEABLE MATERIAL	682045
CLASS 3 PERMEABLE MATERIAL (BLANKET)	682049
CLASS 3 PERMEABLE MATERIAL (UNDERDRAIN)	682048
CLASS 4 AGGREGATE SUBBASE	250401
CLASS 4 CONCRETE (BACKFILL)	510314
CLASS 4 CONCRETE (BACKFILL)	719598
CLEAN AND PAINT BRIDGE RAILING	590229
CLEAN AND PAINT STRUCTURAL STEEL	590115
CLEAN AND PAINT STRUCTURAL STEEL (EXISTING BRIDGE)	590116
CLEAN BRIDGE DECK	153235
CLEAN EXPANSION JOINT	511118
CLEAN STRUCTURAL STEEL (EXISTING BRIDGE)	590106
CLEANING, INSPECTING AND PREPARING HOST PIPE	155210
CLEANOUT ASSEMBLY (EDGE DRAIN)	681111
CLEARING AND GRUBBING	160101
CLOSE ACCESS, DECK	511125
CLOSED CIRCUIT TELEVISION SYSTEM	860990

ITEM DESCRIPTION	ITEM CODE
C	
COLD FOAM IN-PLACE RECYCLING	397100
COLD PLANE ASPHALT CONCRETE PAVEMENT	153103
COLD PLANE ASPHALT CONCRETE PAVEMENT (.15' MAXIMUM)	153112
COLUMN CASING	550110
COMMERCIAL FERTILIZER (GRANULAR)	202030
COMMERCIAL FERTILIZER (PACKET)	202033
COMMERCIAL FERTILIZER (SLOW RELEASE)	202031
COMMUNICATION CONDUIT	860791
COMMUNICATION CONDUIT (BRIDGE)	860792
COMMUNICATION PULL BOX	869039
COMPOST (INCORPORATE)	203025
COMPOST, INCORPORATE	203025
CONCRETE (CHANNEL LINING)	721430
CONCRETE (CONCRETE APRON)	721431
CONCRETE (CONCRETED-ROCK SLOPE PROTECTION)	721501
CONCRETE (DITCH LINING)	721420
CONCRETE (GUTTER LINING)	721410
CONCRETE (RAPID SETTING)	511123
CONCRETE (SLOPE PROTECTION)	721400
CONCRETE BACKFILL	193118
CONCRETE BACKFILL (SOLDIER PILE WALL)	193116
CONCRETE BACKFILL FAST SETTING	193117
CONCRETE BARRIER (TYPE 25 MODIFIED)	833128
CONCRETE BARRIER (TYPE 25R)	833138
CONCRETE BARRIER (TYPE 26 MODIFIED)	833142
CONCRETE BARRIER (TYPE 26)	833140
CONCRETE BARRIER (TYPE 26A MODIFIED)	833143
CONCRETE BARRIER (TYPE 27 MODIFIED)	833187
CONCRETE BARRIER (TYPE 27S)	833179
CONCRETE BARRIER (TYPE 50)	839481
CONCRETE BARRIER (TYPE 50E)	839491

ITEM DESCRIPTION	ITEM CODE
C	
CONCRETE BARRIER (TYPE 60)	839701
CONCRETE BARRIER (TYPE 60A)	839702
CONCRETE BARRIER (TYPE 60C)	839703
CONCRETE BARRIER (TYPE 60D)	839704
CONCRETE BARRIER (TYPE 60E)	839705
CONCRETE BARRIER (TYPE 60G)	839706
CONCRETE BARRIER (TYPE 60GA)	839707
CONCRETE BARRIER (TYPE 60GC)	839708
CONCRETE BARRIER (TYPE 60GE)	839709
CONCRETE BARRIER (TYPE 60S)	839710
CONCRETE BARRIER (TYPE 60SC)	839712
CONCRETE BARRIER (TYPE 732 MODIFIED)	839717
CONCRETE BARRIER (TYPE 732)	839720
CONCRETE BARRIER (TYPE 732A)	839721
CONCRETE BARRIER (TYPE 732B)	839723
CONCRETE BARRIER (TYPE 736 MODIFIED)	839727
CONCRETE BARRIER (TYPE 736)	839725
CONCRETE BARRIER (TYPE 736A)	839726
CONCRETE BARRIER (TYPE 736B)	839731
CONCRETE BARRIER (TYPE 736SV)	839734
CONCRETE BARRIER (TYPE 742B)	839737
CONCRETE BARRIER (TYPE 80)	839714
CONCRETE BARRIER (TYPE K)	833080
CONCRETE CLOSURE WALL	513501
CONCRETE INVERT PAVING	155230
CONCRETE PAVEMENT	401000
CONCRETE PAVEMENT (RAMP TERMINI)	401066
CONCRETE PAVEMENT (WEIGH-IN-MOTION)	401102
CONCRETED-ROCK SLOPE PROTECTION (COBBLE, METHOD B)	721616
CONCRETED-ROCK SLOPE PROTECTION (FACING, METHOD B)	721609
CONDUCTOR CASING	760025
CONSTRUCTION AREA SIGNS	120090

ITEM DESCRIPTION	ITEM CODE
C	
CONSTRUCTION SITE MANAGEMENT	074016
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT	400050
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (EXPANSION JOINT, TYPE AN)	400090
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (EXPANSION JOINT, TYPE WF)	400092
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (PAVEMENT ANCHOR)	400075
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE A)	400061
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE C)	400063
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE D)	400064
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE E)	400065
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (WIDE FLANGE BEAM TERMINAL)	400080
CONTOUR GRADING	197003
CONTRACTOR SUPPLIED BIOLOGIST (DAY)	146001
CONTRACTOR SUPPLIED BIOLOGIST (LS)	146002
CONTROL AND NEUTRAL CONDUCTORS	206560
CORE CONCRETE (0 - 50 MM)	515072
CORE CONCRETE (1 1/2")	515160
CORE CONCRETE (1 1/8")	515157
CORE CONCRETE (101 MM - 150 MM)	515074
CORE CONCRETE (2")	515061
CORE CONCRETE (251 MM - 300 MM)	515077
CORE CONCRETE (5")	515064
CORE CONCRETE (51 MM - 100 MM)	515073
CORE CONCRETE (6")	515065
CORRUGATED STEEL FLUME DOWNDRAIN	691001
CRACK EXISTING CONCRETE PAVEMENT	415101
CRACK TREATMENT	374207
CRASH CUSHION (ADIEM)	839603
CRASH CUSHION (REACT 9CBB)	839604
CRASH CUSHION (REACT 9SCBS)	839605
CRASH CUSHION (TYPE CAT)	839601

ITEM DESCRIPTION	ITEM CODE
C	
CRASH CUSHION (TYPE CAT) BACKUP	839602
CRASH CUSHION MODULE, SAND FILLED	839631
CRASH CUSHION, SAND FILLED	839591
CULTIVATE	200120
CULTIVATE (SOIL AMENDMENT)	200121
CURB RAMP DETECTABLE WARNING SURFACE	731656
D	
DATA CORE	394060
DEBRIS RACK CAGE	706584
DECK SEAL	540100
DECOMPOSED GRANITE (MISCELLANEOUS AREAS) (SQFT)	200117
DECOMPOSED GRANITE (MISCELLANEOUS AREAS) (SQYD)	200118
DELINEATOR (CLASS 1)	820107
DELINEATOR (CLASS 2)	820108
DELINEATOR (SPECIAL)	820105
DETECTOR LOOP	860811
DEVELOP WATER SUPPLY	170101
DIAPHRAGM BOLSTER	510805
DITCH EXCAVATION	194001
DOUBLE METAL BEAM GUARD RAILING (WOOD POST)	839220
DOUBLE THRIE BEAM BARRIER	839310
DOUBLE THRIE BEAM BARRIER (STEEL POST)	839312
DOUBLE THRIE BEAM BARRIER (WOOD POST)	839311
DOWEL BAR (DRILL AND BOND)	406050
DOWEL BAR RETROFIT	406100
DRAINAGE INLET	707050
DRAINAGE INLET MARKER	700617
DRAINAGE MANHOLE	707051
DRAINAGE PUMPING EQUIPMENT	740500
DRILL AND BOND DOWEL	511106

ITEM DESCRIPTION	ITEM CODE
D	
DRILL AND BOND DOWEL (CHEMICAL ADHESIVE)	511110
DRILL HOLE (HORIZONTAL DRAIN)	681502
DRILL HOLE (PRESPLITTING)	190170
DRILL HOLE (SUBSEALING)	410101
DRILL PILOT HOLE	760021
DRINKING FOUNTAIN	994900
DRIVE 24" CAST-IN-STEEL SHELL CONCRETE PILE	495116
DRIVE 48" CAST-IN-STEEL SHELL CONCRETE PILE	495150
DRIVE PILE (CLASS 140)	490739
DRIVE PILE (CLASS 140) (ALTERNATIVE W)	490747
DRIVE PILE (CLASS 200)	490781
DRIVE PILE (CLASS 200) (ALTERNATIVE W)	490783
DRIVE PILE (CLASS 400) (ALTERNATIVE W)	491013
DRIVE PILE (CLASS 625)	490754
DRIVE PILE (CLASS 625) (ALTERNATIVE W)	490773
DRIVE PILE (CLASS 90)	490737
DRIVE PILE (CLASS 900) (ALTERNATIVE W)	490701
DRIVE PILING (CLASS 200)	490752
DRIVE STEEL PILE (HP 10 X 42)	490504
DRIVE STEEL PILE (HP 10 X 57)	490509
DRIVE STEEL PILE (HP 14 X 117)	490539
DRIVE STEEL PILE (HP 14 X 89)	490529
DRIVE STEEL PILE (HP 360 X 132)	490567
DUFF	202007
DUST CONTROL PLAN	190114
DUST CONTROL PLAN (NATURALLY OCCURRING ASBESTOS)	190116
E	
EARTH RETAINING STRUCTURE	197020
EARTH RETAINING STRUCTURE (GUARD RAILING)	197030
EARTH RETAINING STRUCTURE (MECHANICALLY STABILIZED EARTH WALL)	197031

ITEM DESCRIPTION	ITEM CODE
E	
EARTH RETAINING STRUCTURE, LOCATION 3	197028
EARTH RETAINING STRUCTURE, LOCATION 4	197029
EARTH RETAINING STRUCTURE, LOCATION A	197021
EARTH RETAINING STRUCTURE, LOCATION B	197022
EARTH RETAINING STRUCTURE, LOCATION C	197023
EARTH RETAINING STRUCTURE, LOCATION D	197024
ELECTRIC SERVICE (IRRIGATION)	860797
END ANCHOR ASSEMBLY (TYPE CA)	839582
END ANCHOR ASSEMBLY (TYPE SFT)	839581
END CAP	839555
END CAP (TYPE A)	839576
END CAP (TYPE TC)	839578
END SECTION	839553
ENTRANCE TAPER	692001
ENVIRONMENTAL PROTECTION (DESERT TORTOISE)	140009
ENVIRONMENTAL PROTECTION (MOHAVE GROUND SQUIRREL)	140010
ERECT PRECAST PRESTRESSED CONCRETE BOX GIRDER	512502
ERECT PRECAST PRESTRESSED CONCRETE DECK UNIT	512510
ERECT PRECAST PRESTRESSED CONCRETE GIRDER	512500
ERECT STRUCTURAL STEEL (BRIDGE)	550204
EROSION CONTROL (BFM)	203019
EROSION CONTROL (BLANKET)	203001
EROSION CONTROL (BONDED FIBER MATRIX) (SQFT)	203027
EROSION CONTROL (COMPOST BLANKET)	203002
EROSION CONTROL (DRILL SEED)	203012
EROSION CONTROL (DRILL SEED) (ACRE)	203005
EROSION CONTROL (HYDRAULIC MATRIX)	203017
EROSION CONTROL (HYDROSEED) (ACRE)	203032
EROSION CONTROL (HYDROSEED) (SQFT)	203031
EROSION CONTROL (NETTING)	203018

ITEM DESCRIPTION	ITEM CODE
E	
EROSION CONTROL (POLYMER STABILIZED FIBER MATRIX) (ACRE)	203030
EROSION CONTROL (POLYMER STABILIZED FIBER MATRIX) (SQFT)	203029
EROSION CONTROL (PUNCHED STRAW) (ACRE)	203009
EROSION CONTROL (PUNCHED STRAW) (SQFT)	203008
EROSION CONTROL (SEEDING) (SQFT)	203006
EROSION CONTROL (TYPE C)	203011
EROSION CONTROL (TYPE D)	203016
EROSION CONTROL HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX)	203022
EXPANSION DAM	519050
EXTEND 10" CONDUIT	208907
EXTEND 150 MM CONDUIT	208908
EXTEND 250 MM CONDUIT	208910
EXTEND 6" CONDUIT	208905
EXTEND 8" CONDUIT	208906
F	
FENCE (TYPE BW, 4-STRAND, METAL POST)	800008
FENCE (TYPE BW, 4-STRAND, WOOD POST)	800010
FENCE (TYPE BW, 5 STRAND, METAL POST)	800007
FENCE (TYPE BW, METAL POST)	800001
FENCE (TYPE WM, METAL POST)	800051
FENCE (TYPE WM, MODIFIED)	800054
FENCE (TYPE WM, WOOD POST)	800052
FIBER OPTIC SPLICE CLOSURE	867130
FIBER ROLLS	203021
FIELD LEAKAGE TESTING	610001
FILTER ASSEMBLY UNIT	208560
FILTER FABRIC	729000
FILTER FABRIC	681990
FILTER FABRIC (UNDERDRAIN)	681988
FINISHING ROADWAY	220101

ITEM DESCRIPTION	ITEM CODE
F	
FISH PROTECTION	146004
FLASHING ARROW SIGN	120110
FLASHING BEACON	860601
FLASHING BEACON (PORTABLE)	120200
FLASHING BEACON AND LIGHTING	860603
FLASHING BEACON SYSTEM	860604
FLUME ANCHOR ASSEMBLY	692361
FLUME DOWNDRAIN	691900
FOLIAGE PROTECTOR	205051
FRACTURED RIB TEXTURE	511064
FRAME AND GRATE	750007
FURNISH 24" CAST-IN-STEEL SHELL CONCRETE PILING	495115
FURNISH 48" CAST-IN-STEEL SHELL CONCRETE PILING	495149
FURNISH AND INSTALL DRAIN PIPE (HORIZONTAL DRAIN)	681501
FURNISH BRIDGE DECK TREATMENT MATERIAL	540108
FURNISH BRIDGE DECK TREATMENT MATERIAL (LOW ODOR)	540109
FURNISH FORMED PANEL SIGN (OVERHEAD)	560233
FURNISH FORMED PANEL SIGN (ROADSIDE)	560232
FURNISH LAMINATED PANEL SIGN (1"-TYPE A)	560244
FURNISH LAMINATED PANEL SIGN (1"-TYPE B)	560245
FURNISH LAMINATED PANEL SIGN (2 1/2"-TYPE B)	560246
FURNISH LAMINATED PANEL SIGN (2 1/2"-TYPE H)	560247
FURNISH LAMINATED PANEL SIGN (25.4 MM-TYPE A)	560234
FURNISH LAMINATED PANEL SIGN (25.4 MM-TYPE B)	560235
FURNISH PILE (CLASS 200)	490751
FURNISH PILING (CLASS 140)	490738
FURNISH PILING (CLASS 140) (ALTERNATIVE W)	490746
FURNISH PILING (CLASS 200)	490780
FURNISH PILING (CLASS 200) (ALTERNATIVE W)	490782

ITEM DESCRIPTION	ITEM CODE
F	
FURNISH PILING (CLASS 400) (ALTERNATIVE W)	491012
FURNISH PILING (CLASS 625)	490753
FURNISH PILING (CLASS 625) (ALTERNATIVE W)	490772
FURNISH PILING (CLASS 90)	490736
FURNISH PILING (CLASS 900) (ALTERNATIVE W)	490700
FURNISH POLYESTER CONCRETE OVERLAY	515041
FURNISH PRECAST PRESTRESSED CONCRETE BOX GIRDER (20 M - 25 M)	512240
FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (100'-110')	512279
FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (110'-120')	512280
FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (130'-140')	512282
FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (140'-150')	512283
FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (40'-50')	512288
FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (90'-100')	512278
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (10 M - 15 M)	512230
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (15 M - 20 M)	512231
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (20 M - 25 M)	512232
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (25 M - 30 M)	512233
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (30'-40')	512202
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (40'-50')	512203
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (50'-60')	512204
FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (60'-70')	512205
FURNISH PRECAST PRESTRESSED CONCRETE SLAB (TYPE SI)	512351
FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	560203
FURNISH SIGN STRUCTURE (LIGHTWEIGHT)	560213
FURNISH SIGN STRUCTURE (TRUSS)	560218
FURNISH SIGN STRUCTURE (TUBULAR)	560208
FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-FRAMED)	560251

ITEM DESCRIPTION	ITEM CODE
F	
FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED)	560248
FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-FRAMED)	560252
FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-UNFRAMED)	560249
FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-FRAMED)	560241
FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-UNFRAMED)	560238
FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-FRAMED)	560242
FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-UNFRAMED)	560239
FURNISH STEEL PILING (HP 10 X 42)	490503
FURNISH STEEL PILING (HP 10 X 57)	490508
FURNISH STEEL PILING (HP 14 X 117)	490538
FURNISH STEEL PILING (HP 14 X 89)	490528
FURNISH STEEL PILING (HP 360 X 132)	490566
FURNISH STRUCTURAL STEEL (BRIDGE)	550203
G	
GABION	722020
GEOCOMPOSITE DRAIN	681132
GEOSYNTHETIC PAVEMENT INTERLAYER	393003
GEOSYNTHETIC REINFORCEMENT	198250
GRATED LINE DRAIN	703233
GRAVEL (MISCELLANEOUS AREAS) (SQFT)	200115
GRAVEL (MISCELLANEOUS AREAS) (SQYD)	200116
GRAVEL BACKFILL	193120
GRIND EXISTING CONCRETE PAVEMENT	420201
GROUT (SUBSEALING)	410105
GUARD POST	869050
GUARD RAILING DELINEATOR	820118
H	
HEADED BAR REINFORCEMENT	520120
HEALTH AND SAFETY PLAN	074018
HIGH SPEED WEIGH-IN-MOTION SYSTEM	861203

ITEM DESCRIPTION	ITEM CODE
H	
HIGHWAY ADVISORY RADIO SYSTEM	860520
HIGHWAY LIGHTING	860403
HIGHWAY PLANTING	200001
HORIZONTAL DRAIN CONNECTOR UNIT	681510
HOT MIX ASPHALT	390130
HOT MIX ASPHALT	390131
HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED)	390141
HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED)	390142
HOT MIX ASPHALT (BONDED WEARING COURSE-OPEN GRADED)	390158
HOT MIX ASPHALT (LEVELING)	390135
HOT MIX ASPHALT (OPEN GRADED)	390134
HOT MIX ASPHALT (TYPE A)	390132
HOT MIX ASPHALT (TYPE B)	390133
HOT MIX ASPHALT (TYPE C)	390129
HOT MIX ASPHALT DIKE	394070
I	
IMPORTED BORROW	198001
IMPORTED BORROW (LIGHTWEIGHT AGGREGATE)	198009
IMPORTED MATERIAL (SHOULDER BACKING)	198007
IMPORTED ROCKY MATERIAL	198021
IMPORTED TOPSOIL	200101
IMPORTED TOPSOIL (CY)	200102
INDUCTIVE LOOP DETECTOR	860810
INJECT CRACK (EPOXY)	511130
INLET FRAME AND GRATE	750030
INSTALL CONCRETE BARRIER (TYPE K)	833079
INSTALL MEDIAN MILEAGE PANEL	820180
INSTALL ROADSIDE SIGN (LAMINATED WOOD BOX POST)	568023
INSTALL ROADSIDE SIGN PANEL ON EXISTING POST	568017
INSTALL SIGN (MAST-ARM HANGER METHOD)	568015

ITEM DESCRIPTION	ITEM CODE
I	
INSTALL SIGN (STRAP AND SADDLE BRACKET METHOD)	568001
INSTALL SIGN OVERLAY	568007
INSTALL SIGN PANEL ON EXISTING FRAME	568016
INSTALL SIGN PANEL ON EXISTING STRUCTURE	568020
INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	560204
INSTALL SIGN STRUCTURE (LIGHTWEIGHT)	560214
INSTALL SIGN STRUCTURE (TRUSS)	560219
INSTALL SIGN STRUCTURE (TUBULAR)	560209
INTERCONNECTION CONDUIT AND CABLE	860703
INTERCONNECTION SYSTEM	860750
IRON SULFATE	202003
IRRIGATION CONTROLLER (BATTERY)	206929
IRRIGATION CONTROLLER ENCLOSURE CABINET	208301
IRRIGATION SLEEVE	208310
IRRIGATION SYSTEM	208000
ISOLATION CASING	750041
J	
JACKED 12" WELDED STEEL PIPE (.250" THICK)	704133
JACKED 18" WELDED STEEL PIPE (.375" THICK)	704157
JACKED 24" REINFORCED CONCRETE PIPE (CLASS III)	655316
JACKED 24" REINFORCED CONCRETE PIPE (CLASS IV)	655416
JACKED 48" REINFORCED CONCRETE PIPE (CLASS IV)	655432
JACKED 600 MM REINFORCED CONCRETE PIPE (CLASS V)	655574
JACKED 600 MM WELDED STEEL PIPE (6.35 MM THICK)	704189
JOINT SEAL (ASPHALTIC PLUG)	519133
JOINT SEAL (MR 1 1/2")	519091
JOINT SEAL (MR 1")	519088
JOINT SEAL (MR 1/2")	519081
JOINT SEAL (MR 2")	519100
JOINT SEAL (MR 40 MM)	519142

ITEM DESCRIPTION	ITEM CODE
J	
JOINT SEAL (MR 50 MM)	519144
JOINT SEAL (TYPE AL)	519102
JOINT SEAL ASSEMBLY (MR 100 MM)	519128
JOINT SEAL ASSEMBLY (MR 101 MM - 160 MM)	519129
JOINT SEAL ASSEMBLY (MR 161 MM - 240 MM)	519130
JOINT SEAL ASSEMBLY (MR 2 1/2")	519092
JOINT SEAL ASSEMBLY (MR 241 MM - 320 MM)	519131
JOINT SEAL ASSEMBLY (MR 3 1/2")	519094
JOINT SEAL ASSEMBLY (MR 3")	519093
JOINT SEAL ASSEMBLY (MR 4")	519095
JOINT SEAL ASSEMBLY (MR 5 1/2")	519098
JOINT SEAL ASSEMBLY (MR 5")	519097
JOINT SEAL ASSEMBLY (MR 6 1/2")	519109
JOINT SEAL ASSEMBLY (MR 6")	519099
JOINT SEAL ASSEMBLY (MR 60 MM)	519124
JOINT SEAL ASSEMBLY (MR 70 MM)	519125
JOINT SEAL ASSEMBLY (MR 9")	519118
JOINT SEAL ASSEMBLY (MR 90 MM)	519127
JOINTED PLAIN CONCRETE PAVEMENT	401050
JUTE MESH	203561
K	
KIOSK	994444
L	
LEAD COMPLIANCE PLAN	190110
LEAN CONCRETE BACKFILL	193119
LEAN CONCRETE BASE	280000
LIGHTING	860401
LIGHTING (CITY STREET)	860402
LIGHTING (DETOUR)	860435
LIGHTING (LOCATION 1)	860461
LIGHTING (PARKING LOT)	860407

ITEM DESCRIPTION	ITEM CODE
L	
LIGHTING (STAGE CONSTRUCTION)	860415
LIGHTING (TEMPORARY)	860400
LIGHTING (TUNNEL)	860420
LIGHTING AND SIGN ILLUMINATION	860460
LIGHTING AND SIGN ILLUMINATION (LOCATION 1)	860551
LIGHTING AND SIGN ILLUMINATION (LOCATION 2)	860552
LIGHTING AND SIGN ILLUMINATION (LOCATION 3)	860553
LIGHTING AND SIGN ILLUMINATION (LOCATION 4)	860554
LIGHTING CONDUIT (BRIDGE)	860761
LIGHTING CONDUIT (CITY STREET)	860760
LIME	240100
LIME STABILIZED SOIL	240105
LIQUID ASPHALT (PRIME COAT)	395000
M	
MAINTAIN EXISTING IRRIGATION FACILITIES	206401
MAINTAIN EXISTING PLANTED AREAS	204096
MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	860090
MANHOLE (TYPE A)	719305
MANHOLE (TYPE B)	719306
MANHOLE FRAME AND COVER	750010
MARKER	820101
MARKER (CULVERT)	820112
MASONRY BLOCK WALL	518201
METAL (BARRIER MOUNTED SIGN)	562002
METAL (RAIL MOUNTED SIGN)	562004
METAL (ROADSIDE SIGN)	562001
METAL BEAM GUARD RAILING	832001
METAL BEAM GUARD RAILING (2.1 M WOOD POST)	832061
METAL BEAM GUARD RAILING (7' POST)	832013
METAL BEAM GUARD RAILING (7' WOOD POST)	832012

ITEM DESCRIPTION	ITEM CODE
M	
METAL BEAM GUARD RAILING (8' POST)	832014
METAL BEAM GUARD RAILING (ELEMENT)	832008
METAL BEAM GUARD RAILING (SPECIAL)	832004
METAL BEAM GUARD RAILING (STEEL POST)	832002
METAL BEAM GUARD RAILING (WOOD POST)	832003
MICRO-SURFACING	378000
MICROWAVE VEHICLE DETECTION SYSTEM	860812
MILEPOST MARKER	820110
MINOR CONCRETE	510501
MINOR CONCRETE (BACKFILL)	510526
MINOR CONCRETE (BACKFILL)	719589
MINOR CONCRETE (CHANNEL LINING)	727905
MINOR CONCRETE (CONCRETE DRAIN)	510520
MINOR CONCRETE (CURB AND GUTTER)	731504
MINOR CONCRETE (CURB AND SIDEWALK)	731505
MINOR CONCRETE (CURB RAMP)	731623
MINOR CONCRETE (CURB)	731501
MINOR CONCRETE (CURB, SIDEWALK AND CURB RAMP)	731627
MINOR CONCRETE (DITCH LINING)	727901
MINOR CONCRETE (DRIVEWAY)	731516
MINOR CONCRETE (EXPOSED AGGREGATE CONCRETE)	731508
MINOR CONCRETE (GUTTER DEPRESSION)	731507
MINOR CONCRETE (GUTTER LINING)	727906
MINOR CONCRETE (GUTTER)	731517
MINOR CONCRETE (INVERT PAVING)	510510
MINOR CONCRETE (ISLAND PAVING)	731511
MINOR CONCRETE (MEDIAN PAVING)	510509
MINOR CONCRETE (MINOR STRUCTURE)	510502
MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)	731502
MINOR CONCRETE (PILE CAP)	510700
MINOR CONCRETE (PIPE ENCASEMENT)	719569

ITEM DESCRIPTION	ITEM CODE
M	
MINOR CONCRETE (SIDEWALK)	731521
MINOR CONCRETE (SOUND WALL)	510524
MINOR CONCRETE (STAMPED CONCRETE)	731519
MINOR CONCRETE (TEXTURED PAVING)	731530
MINOR HOT MIX ASPHALT	390136
MISCELLANEOUS IRON AND STEEL	750001
MISCELLANEOUS METAL	750500
MISCELLANEOUS METAL (BRIDGE)	750501
MISCELLANEOUS METAL (RESTRAINER - CABLE TYPE)	750498
MISCELLANEOUS METAL (RESTRAINER - PIPE TYPE)	750496
MISCELLANEOUS METAL (RETAINING WALL)	750502
MOBILIZATION	999990
MOBILIZATION, DEMOBILIZATION, AND FINAL CLEANUP	760090
MODIFY FLASHING BEACON	860615
MODIFY INLET	152604
MODIFY INLET TO MANHOLE	152609
MODIFY LIGHTING	861503
MODIFY LIGHTING (LOCATION 1)	861511
MODIFY LIGHTING (LOCATION 2)	861512
MODIFY LIGHTING (LOCATION 3)	861513
MODIFY LIGHTING (LOCATION 4)	861514
MODIFY LIGHTING AND SIGN ILLUMINATION	861504
MODIFY METAL BEAM GUARD RAILING	152632
MODIFY RAMP METERING SYSTEM	861088
MODIFY SIGN ILLUMINATION	860508
MODIFY SIGN STRUCTURE	152641
MODIFY SIGNAL	861502
MODIFY SIGNAL (LOCATION 1)	861491
MODIFY SIGNAL (LOCATION 2)	861492
MODIFY SIGNAL (LOCATION 3)	861493
MODIFY SIGNAL (LOCATION 4)	861494

ITEM DESCRIPTION	ITEM CODE
M	
MODIFY SIGNAL (LOCATION 5)	861495
MODIFY SIGNAL AND LIGHTING	861501
MODIFY SIGNAL AND LIGHTING (LOCATION 1)	861497
MODIFY SIGNAL AND LIGHTING (LOCATION 2)	861498
MODIFY SIGNAL AND LIGHTING (LOCATION 3)	861499
MODIFY SIGNAL AND LIGHTING (LOCATION 4)	861500
MODIFY SIGNAL AND LIGHTING (LOCATION 5)	861505
MODIFY SIGNAL AND LIGHTING (LOCATION 6)	861506
MODIFY SIGNAL AND LIGHTING (LOCATION 7)	861507
MODIFY SIGNAL AND LIGHTING (LOCATION 8)	861508
MODIFY SIGNAL AND LIGHTING (LOCATION 9)	861509
MODIFY TRAFFIC MONITORING STATION	860889
MODIFY TRAFFIC MONITORING STATION (COUNT)	860890
MOVE-IN/MOVE-OUT (EROSION CONTROL)	203026
MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL)	074037
MULCH	202011
N	
NATURAL RESOURCE PROTECTION PLAN	146003
NO. 5 PULL BOX	869035
NO. 5(T) PULL BOX	869034
NOISE MONITORING	148005
NPS 2 SUPPLY LINE (BRIDGE)	208036
NPS 2.5 SUPPLY LINE (BRIDGE)	208037
NPS 3 SUPPLY LINE (BRIDGE)	208038
NPS 4 SUPPLY LINE (BRIDGE)	208039
NPS 6 SUPPLY LINE (BRIDGE)	208040
O	
OBJECT MARKER	820130
OBJECT MARKER (TYPE K)	820131

ITEM DESCRIPTION	ITEM CODE
O	
OBJECT MARKER (TYPE K-1)	820141
OBJECT MARKER (TYPE K-2)	820143
OBJECT MARKER (TYPE L)	820132
OBJECT MARKER (TYPE L-1)	820151
OBJECT MARKER (TYPE P)	820134
OBJECT MARKER (TYPE R)	820135
OBLITERATE SURFACING	150305
P	
PAINT CURB (2-COAT)	597401
PAINT PAVEMENT MARKING	840660
PAINT PAVEMENT MARKING (2-COAT)	840666
PAINT STRUCTURAL STEEL (EXISTING BRIDGE)	590111
PAINT TRAFFIC STRIPE	840653
PAINT TRAFFIC STRIPE (1-COAT)	840655
PAINT TRAFFIC STRIPE (2-COAT)	840656
PARKING BUMPER (PRECAST CONCRETE)	842000
PAVEMENT MARKER (NON-REFLECTIVE-RECESSED)	850121
PAVEMENT MARKER (NON-REFLECTIVE)	850101
PAVEMENT MARKER (REFLECTIVE)	850102
PAVEMENT MARKER (RETROREFLECTIVE)	850111
PAVEMENT MARKER (RETROREFLECTIVE-RECESSED)	850122
PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE C)	850110
PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE G)	850112
PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE H)	850113
PAVEMENT REINFORCING FABRIC	393001
PAVING ASPHALT (BINDER, GEOSYNTHETIC PAVEMENT INTERLAYER)	391007
PAVING ASPHALT (BINDER-PAVEMENT REINFORCING FABRIC)	391031
PAVING ASPHALT (BINDER-PAVEMENT REINFORCING FABRIC)	391005
PAVING NOTCH EXTENSION	510800
PEDESTRIAN BARRICADE	833077

ITEM DESCRIPTION	ITEM CODE
P	
PERMEABLE MATERIAL	682001
PERVIOUS BACKFILL MATERIAL	193030
PERVIOUS BACKFILL MATERIAL (RETAINING WALL)	193031
PICKET RAILING	833040
PIPE HANDRAILING	833085
PIPE HANDRAILING (POST TYPE)	833087
PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA)	394002
PLACE ASPHALT CONCRETE DIKE (TYPE A)	394040
PLACE ASPHALT CONCRETE DIKE (TYPE C)	394044
PLACE ASPHALT CONCRETE DIKE (TYPE D)	394046
PLACE ASPHALT CONCRETE DIKE (TYPE E)	394048
PLACE ASPHALT CONCRETE DIKE (TYPE F)	394049
PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	394090
PLACE HOT MIX ASPHALT DIKE	394071
PLACE HOT MIX ASPHALT DIKE (TYPE A)	394073
PLACE HOT MIX ASPHALT DIKE (TYPE C)	394074
PLACE HOT MIX ASPHALT DIKE (TYPE D)	394075
PLACE HOT MIX ASPHALT DIKE (TYPE E)	394076
PLACE HOT MIX ASPHALT DIKE (TYPE F)	394077
PLACE POLYESTER CONCRETE OVERLAY	515042
PLANT (GROUP A)	204001
PLANT (GROUP A)	204035
PLANT (GROUP B)	204002
PLANT (GROUP B)	204036
PLANT (GROUP F)	204006
PLANT (GROUP G)	204007
PLANT (GROUP H)	204008
PLANT (GROUP I)	204009
PLANT (GROUP K)	204011
PLANT (GROUP M)	204013
PLANT (GROUP O)	204010
PLANT (GROUP U)	204038

ITEM DESCRIPTION	ITEM CODE
P	
PLANT (GROUP U)	204021
PLANT (GROUP W)	204017
PLANT ESTABLISHMENT WORK	204099
PLUG CULVERT	155001
PORTABLE CHANGEABLE MESSAGE SIGN	128650
PORTABLE DELINEATOR	120182
PORTLAND CEMENT CONCRETE BASE	405030
POWER AND TELEPHONE SERVICE	869070
PREPARE AND PAINT CONCRETE	597600
PREPARE AND STAIN CONCRETE	597601
PREPARE CONCRETE BRIDGE DECK SURFACE	153225
PREPARE HOLE	200110
PREPARE STORM WATER POLLUTION PREVENTION PLAN	074019
PREPARE WATER POLLUTION CONTROL PROGRAM	074017
PRESTRESSING	500010
PRESTRESSING CAST-IN-PLACE CONCRETE	500001
PROGRESS SCHEDULE (CRITICAL PATH METHOD)	070012
PRUNE EXISTING PLANTS	200052
PTFE BEARING	518050
PTFE SPHERICAL BEARING	518051
PULL BOX	869040
PUMPING PLANT ELECTRICAL EQUIPMENT	741001
PUMPING PLANT METAL WORK	750520
R	
RAIL TENSIONING ASSEMBLY	839561
RAIN EVENT ACTION PLAN	074056
RAISE BRIDGE	159101
RAMP METERING SYSTEM	861100
RAMP METERING SYSTEM (LOCATION 1)	861101
RAMP METERING SYSTEM (LOCATION 2)	861102
RAMP METERING SYSTEM (LOCATION 3)	861103

ITEM DESCRIPTION	ITEM CODE
R	
RAMP METERING SYSTEM (LOCATION 4)	861104
RAMP METERING SYSTEM (LOCATION 5)	861105
RAMP METERING SYSTEM (LOCATION 6)	861106
RAMP METERING SYSTEM (LOCATION 7)	861107
RAPID SETTING CONCRETE (PATCH)	511124
REAMING WATER WELL	760022
RECONSTRUCT CHAIN LINK FENCE	151540
RECONSTRUCT DOUBLE THRIE BEAM BARRIER	151570
RECONSTRUCT FENCE (TYPE WM)	151537
RECONSTRUCT FENDER	159021
RECONSTRUCT INLET	151512
RECONSTRUCT METAL BEAM GUARD RAILING	151572
RECONSTRUCT METAL BEAM GUARD RAILING (7' POST)	151623
RECONSTRUCT METAL BEAM GUARD RAILING (WOOD POST)	151625
RECONSTRUCT METAL RAILING (BRIDGE)	159010
RECONSTRUCT THRIE BEAM BARRIER	151568
RECYCLED WATER WARNING SIGNS	209202
REFINISH BRIDGE DECK	515020
REINFORCED CONCRETE CRIB WALL (TYPE A)	513601
REINFORCED CONCRETE CRIB WALL (TYPE B)	513602
REINFORCED CONCRETE CRIB WALL (TYPE C)	513603
RELAY ENTRANCE TAPER	152039
RELOCATE CRASH CUSHION	152388
RELOCATE EXTINGUISHABLE MESSAGE SIGN	861295
RELOCATE FENCE	152379
RELOCATE FLASHING BEACON	861303
RELOCATE GATE	152381
RELOCATE HYDRANT	152351
RELOCATE MAILBOX	152370
RELOCATE METAL BEAM GUARD RAILING	152397
RELOCATE ROADSIDE SIGN	152390

ITEM DESCRIPTION	ITEM CODE
R	
RELOCATE ROADSIDE SIGN (METAL POST)	152391
RELOCATE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD)	152393
RELOCATE ROADSIDE SIGN (WOOD POST)	152392
RELOCATE ROADSIDE SIGN-ONE POST	152386
RELOCATE ROADSIDE SIGN-TWO POST	152387
RELOCATE SIGN PANEL	152396
RELOCATE SIGN STRUCTURE	152394
RELOCATE SIGN STRUCTURE (BRIDGE-MOUNTED)	152398
RELOCATE WATER METER	152410
REMODEL INLET	152703
REMODEL MANHOLE	152702
REMOVE ASPHALT CONCRETE	150769
REMOVE ASPHALT CONCRETE DIKE	150771
REMOVE ASPHALT CONCRETE OVERSIDE DRAIN	150859
REMOVE ASPHALT CONCRETE SURFACING	150857
REMOVE BARRICADE	150645
REMOVE BARRIER	150655
REMOVE BARRIER RAILING	156577
REMOVE BASE AND SURFACING	150860
REMOVE BOX CULVERT	156535
REMOVE BRIDGE MOUNTED SIGN	150767
REMOVE BUILDING	160130
REMOVE CABLE BARRIER	150656
REMOVE CABLE RAILING	150676
REMOVE CATCH BASIN	150827
REMOVE CHAIN LINK FENCE	150608
REMOVE CHANNELIZERS	150730
REMOVE CHIP SEAL	153237
REMOVE CONCRETE	153210
REMOVE CONCRETE (CHANNEL)	153220
REMOVE CONCRETE (CURB AND GUTTER)	153215
REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK)	153239

ITEM DESCRIPTION	ITEM CODE
R	
REMOVE CONCRETE (MISCELLANEOUS)	153246
REMOVE CONCRETE (STRUCTURE)	153213
REMOVE CONCRETE BARRIER	153221
REMOVE CONCRETE BARRIER (TYPE 50)	153230
REMOVE CONCRETE BARRIER (TYPE K)	153229
REMOVE CONCRETE CURB	153214
REMOVE CONCRETE CURB AND SIDEWALK	153216
REMOVE CONCRETE DECK SURFACE	150870
REMOVE CONCRETE ISLAND (PORTIONS)	153222
REMOVE CONCRETE PAVEMENT	150846
REMOVE CONCRETE SIDEWALK	153218
REMOVE CONCRETE SIDEWALK AND DRIVEWAY	153211
REMOVE CONTRAST TREATMENT	150720
REMOVE CRASH CUSHION	156585
REMOVE CRASH CUSHION (SAND FILLED)	156590
REMOVE CULVERT	150805
REMOVE CURB	150772
REMOVE DELINEATOR	151224
REMOVE DOUBLE METAL BEAM BARRIER	150667
REMOVE DOWNDRAIN	150823
REMOVE DRAINAGE FACILITY	150804
REMOVE DRAINAGE SYSTEM	150803
REMOVE ENTRANCE TAPER	150615
REMOVE FENCE	150605
REMOVE FENCE (TYPE BW)	150606
REMOVE FENCE (TYPE WM)	150607
REMOVE FLARED END SECTION	150668
REMOVE GATE	150620
REMOVE HEADWALL	150821
REMOVE INLET	150820
REMOVE IRRIGATION FACILITY	150685
REMOVE IRRIGATION SYSTEM	150686

ITEM DESCRIPTION	ITEM CODE
R	
REMOVE MANHOLE	150826
REMOVE MARKER	150630
REMOVE METAL BEAM GUARD RAILING	150662
REMOVE METAL RAILING	156576
REMOVE OVERSIDE DRAIN	150801
REMOVE PAINTED PAVEMENT MARKING	150712
REMOVE PAINTED TRAFFIC STRIPE	150711
REMOVE PAVEMENT	150855
REMOVE PAVEMENT MARKER	150722
REMOVE PAVEMENT MARKING	150713
REMOVE PEDESTRIAN BARRICADE	150646
REMOVE PIPE	150806
REMOVE RAILING	156572
REMOVE REINFORCED CONCRETE BOX CULVERT	150825
REMOVE RETAINING WALL	150829
REMOVE RETAINING WALL (PORTION)	150830
REMOVE ROADSIDE SIGN	150742
REMOVE ROADSIDE SIGN (METAL POST)	150745
REMOVE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD)	150747
REMOVE ROADSIDE SIGN (WOOD POST)	150744
REMOVE ROADSIDE SIGN PANEL	150748
REMOVE SEWER MANHOLE	150824
REMOVE SEWER PIPE	150841
REMOVE SIGN OVERLAY	150764
REMOVE SIGN PANEL	150763
REMOVE SIGN PANEL AND REMOVABLE SIGN PANEL FRAME	150761
REMOVE SIGN STRUCTURE	150760
REMOVE SLOPE PAVING	150844
REMOVE SOUND WALL	153250
REMOVE TERMINAL SECTION	150659
REMOVE THERMOPLASTIC PAVEMENT MARKING	150715

ITEM DESCRIPTION	ITEM CODE
R	
REMOVE THERMOPLASTIC TRAFFIC STRIPE	150714
REMOVE THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING	150718
REMOVE TRAFFIC STRIPE	150710
REMOVE TRAFFIC STRIPE AND PAVEMENT MARKING	150717
REMOVE TREE	160120
REMOVE UNSOUND CONCRETE	153223
REMOVE UNSUITABLE MATERIAL	190167
REMOVE WOOD FENCE	150604
REMOVE YELLOW PAINTED TRAFFIC STRIPE	150701
REMOVE YELLOW PAINTED TRAFFIC STRIPE (HAZARDOUS WASTE)	141101
REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING	150705
REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING (HAZARDOUS WASTE)	141104
REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE	150704
REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE (HAZARDOUS WASTE)	141103
REPAIR SPALLED JOINTS	413111
REPAIR SPALLED SURFACE AREA	515028
REPLACE ASPHALT CONCRETE SURFACING	390095
REPLACE BEARING	518042
REPLACE BEARING PAD	518040
REPLACE CONCRETE PAVEMENT	401100
REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)	401108
REPLACE PULL BOX	862065
REPLACE VALVE BOX COVER	208565
RESET BARRICADE	152310
RESET GATE	152291
RESET MAILBOX	152255
RESET MARKER	152301
RESET MARKERS AND DELINEATORS	152303
RESET MILEPOST MARKER	152299
RESET ROADSIDE SIGN	152320

ITEM DESCRIPTION	ITEM CODE
R	
RESET ROADSIDE SIGN (METAL POST)	152324
RESET ROADSIDE SIGN (ONE POST)	152316
RESET ROADSIDE SIGN (TWO POST)	152317
RESET ROADSIDE SIGN (WOOD POST)	152322
RESET TEMPORARY RAILING (TYPE K)	158210
RETAINING WALL STEM (TYPE 6)	513551
RETURN CAP (TYPE TA)	839572
RIPPED TEXTURE (REINFORCING BAR)	511070
ROADSIDE CLEARING	200002
ROADSIDE PAVING (MISCELLANEOUS AREAS)	394095
ROADSIDE SIGN - ONE POST	566011
ROADSIDE SIGN - TWO POST	566012
ROADSIDE SIGN (METAL POST)	562007
ROADWAY EXCAVATION	190101
ROADWAY EXCAVATION (NATURALLY OCCURRING ASBESTOS)	190109
ROADWAY EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)	190107
ROADWAY EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD)	190108
ROADWAY EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	190105
ROADWAY EXCAVATION (TYPE Z-3) (AERIALLY DEPOSITED LEAD)	190106
ROCK BLANKET	200114
ROCK EXCAVATION	190161
ROCK EXCAVATION (CONTROLLED BLASTING)	190160
ROCK SLOPE PROTECTION (1 TON, METHOD A)	720104
ROCK SLOPE PROTECTION (1 TON, METHOD B)	721004
ROCK SLOPE PROTECTION (1/2 TON, METHOD A)	720106
ROCK SLOPE PROTECTION (1/2 TON, METHOD B)	721006
ROCK SLOPE PROTECTION (1/2T, METHOD B)	721023
ROCK SLOPE PROTECTION (1/4 TON, METHOD B)	721007
ROCK SLOPE PROTECTION (1/4T, METHOD B)	721024

ITEM DESCRIPTION	ITEM CODE
R	
ROCK SLOPE PROTECTION (1T, METHOD A)	720119
ROCK SLOPE PROTECTION (2T, METHOD A)	720118
ROCK SLOPE PROTECTION (4T, METHOD A)	720117
ROCK SLOPE PROTECTION (BACKING NO. 1, METHOD B)	721010
ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	721011
ROCK SLOPE PROTECTION (BACKING NO. 3, METHOD B)	721012
ROCK SLOPE PROTECTION (FACING, METHOD B)	721009
ROCK SLOPE PROTECTION (LIGHT, METHOD B)	721008
ROCK SLOPE PROTECTION FABRIC	729010
ROCK SLOPE PROTECTION(GRANULAR MATERIAL)	720107
ROCK STAIN	203070
ROLLED EROSION CONTROL PRODUCT (BLANKET)	203033
ROLLED EROSION CONTROL PRODUCT (JUTE MESH)	203038
ROLLED EROSION CONTROL PRODUCT (NETTING)	203034
ROLLED EROSION CONTROL PRODUCT (TRM)	203039
ROOT BARRIER	205062
ROOT PROTECTOR	205061
RUBBERIZED ASPHALT CONCRETE (TYPE G)	390126
RUBBERIZED HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED)	390156
RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	390137
RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	390140
RUBBERIZED HOT MIX ASPHALT (OPEN GRADED HIGH BINDER)	390139
RUBBERIZED HOT MIX ASPHALT (OPEN GRADED)	390138
RUMBLE STRIP	394050
S	
SALVAGE CRASH CUSHION	158100
SALVAGE METAL BEAM GUARD RAILING	151272
SALVAGE METAL BRIDGE RAILING	151270

ITEM DESCRIPTION	ITEM CODE
S	
SALVAGE TERMINAL SECTION	158505
SALVAGE TERMINAL SECTION (TYPE C)	158509
SAMPLING AND ANALYSIS PLAN (NATURALLY OCCURRING ASBESTOS)	190117
SAND BACKFILL	193114
SAND BEDDING	192502
SAND COVER	365001
SCREENINGS	375001
SCREENINGS (COARSE)	375023
SCREENINGS (HOT-APPLIED)	375030
SCREENINGS (MEDIUM FINE)	375021
SCREENINGS (MEDIUM)	375022
SEAL COURSE CONCRETE	510000
SEAL ISOLATION JOINT	404093
SEAL JOINT (EXISTING CONCRETE PAVEMENT)	413115
SEAL LONGITUDINAL ISOLATION JOINT	404094
SEAL LONGITUDINAL JOINT	414091
SEAL PAVEMENT JOINT	404092
SEAL RANDOM CRACKS	374206
SEEDING	204051
SEWER MANHOLE	719200
SHOTCRETE	530100
SHOULDER BACKING	190185
SHOULDER RUMBLE STRIP (AC, GROUND-IN INDENTATIONS)	394054
SHOULDER RUMBLE STRIP (CONCRETE PAVEMENT, GROUND-IN	401083
SHOULDER RUMBLE STRIP (CONCRETE PAVEMENT, GROUND-IN INDENTATIONS)	401083
SHOULDER RUMBLE STRIP (CONCRETE PAVEMENT, ROLLED-IN INDENTATIONS)	401081
SHOULDER RUMBLE STRIP (HMA,GROUND-IN INDENTATIONS)	394053
SHOULDER RUMBLE STRIP (HMA,ROLLED-IN INDENTATIONS)	394051
SHOULDER RUMBLE STRIP (PCC, GROUND-IN INDENTATIONS)	401082
SIGN ILLUMINATION	860501

ITEM DESCRIPTION	ITEM CODE
S	
SIGNAL AND LIGHTING	860201
SIGNAL AND LIGHTING	860301
SIGNAL AND LIGHTING (CITY STREET LOCATION 1)	860300
SIGNAL AND LIGHTING (CITY STREET LOCATION 2)	860302
SIGNAL AND LIGHTING (LOCATION 1)	860251
SIGNAL AND LIGHTING (LOCATION 2)	860252
SIGNAL AND LIGHTING (LOCATION 3)	860253
SIGNAL AND LIGHTING (LOCATION 4)	860254
SIGNAL AND LIGHTING (TEMPORARY)	860150
SINGLE THRIE BEAM BARRIER	839301
SINGLE THRIE BEAM BARRIER (STEEL POST)	839303
SINGLE THRIE BEAM BARRIER (WOOD POST)	839302
SLOPE PAVING (CONCRETE)	721810
SLURRY SEAL	377501
SMALL BUSINESS UTILIZATION REPORT	070013
SNOW POLE MARKER	820115
SNOWPLOW DEFLECTOR	519078
SOIL AMENDMENT	202006
SOIL NAIL ASSEMBLY	197060
SOUND WALL (BARRIER) (MASONRY BLOCK)	517961
SOUND WALL (MASONRY BLOCK)	518002
SPLICE VAULT	869047
SPOT BLAST CLEAN AND PAINT UNDERCOAT	590135
SPRINKLER (TYPE A-1)	208461
SPRINKLER (TYPE A-2)	208462
SPRINKLER (TYPE A-3)	208463
SPRINKLER (TYPE A-4)	208464
SPRINKLER (TYPE A-5)	208465
SPRINKLER (TYPE A-6)	208466
SPRINKLER (TYPE A-7)	208467
SPRINKLER (TYPE A-8)	208468

ITEM DESCRIPTION	ITEM CODE
S	
SPRINKLER (TYPE B-1)	208471
SPRINKLER (TYPE B-2)	208472
SPRINKLER (TYPE B-3)	208473
SPRINKLER (TYPE B-4)	208474
SPRINKLER (TYPE B-5)	208475
SPRINKLER (TYPE B-6)	208476
SPRINKLER (TYPE C-1)	208481
SPRINKLER (TYPE C-2 MOD)	208480
SPRINKLER (TYPE C-2)	208482
SPRINKLER (TYPE C-3)	208483
SPRINKLER (TYPE D-1)	208526
SPRINKLER (TYPE D-2)	208527
SPRINKLER (TYPE D-3)	208528
SPRINKLER CONTROL CONDUIT (BRIDGE)	860796
STABILIZING AGENT (CEMENTITIOUS MATERIAL)	397205
STABILIZING AGENT (FOAMED ASPHALT)	397200
STEEL SHEET PILING	490801
STORM WATER ANNUAL REPORT	074057
STORM WATER SAMPLING AND ANALYSIS DAY	074058
STREET SWEEPING	074041
STRIPPING EXCAVATION	190162
STRUCTURAL CONCRETE	510050
STRUCTURAL CONCRETE, APPROACH SLAB	510080
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE EQ)	510085
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N MODIFIED)	510088
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)	510086
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	510087
STRUCTURAL CONCRETE, BARRIER SLAB	510072
STRUCTURAL CONCRETE, BOX CULVERT	510090
STRUCTURAL CONCRETE, BRIDGE	510053
STRUCTURAL CONCRETE, BRIDGE FOOTING	510051

ITEM DESCRIPTION	ITEM CODE
S	
STRUCTURAL CONCRETE, RETAINING WALL	510060
STRUCTURAL CONCRETE, SOUND WALL	510061
STRUCTURAL STEEL (BRIDGE)	550102
STRUCTURE BACKFILL	193001
STRUCTURE BACKFILL (BRIDGE)	193003
STRUCTURE BACKFILL (CRIB WALL)	193012
STRUCTURE BACKFILL (CULVERT)	193004
STRUCTURE BACKFILL (PUMPING PLANT)	192027
STRUCTURE BACKFILL (RETAINING WALL)	193013
STRUCTURE BACKFILL (SLURRY CEMENT)	193006
STRUCTURE BACKFILL (SOIL NAIL WALL)	193028
STRUCTURE BACKFILL (SOLDIER PILE WALL)	193029
STRUCTURE BACKFILL (SOUND WALL)	193014
STRUCTURE BACKFILL (TIEBACK WALL)	193026
STRUCTURE BACKFILL (TUNNEL)	193039
STRUCTURE CONCRETE (PUMPING PLANT)	510069
STRUCTURE EXCAVATION	192001
STRUCTURE EXCAVATION (BRIDGE)	192003
STRUCTURE EXCAVATION (CRIB WALL)	192036
STRUCTURE EXCAVATION (CULVERT)	192025
STRUCTURE EXCAVATION (NATURALLY OCCURRING ASBESTOS)	192009
STRUCTURE EXCAVATION (RETAINING WALL)	192037
STRUCTURE EXCAVATION (ROCK SLOPE PROTECTION)	192032
STRUCTURE EXCAVATION (ROCK)	192035
STRUCTURE EXCAVATION (SOIL NAIL WALL)	192055
STRUCTURE EXCAVATION (SOLDIER PILE WALL)	192049
STRUCTURE EXCAVATION (SOUND WALL)	192038
STRUCTURE EXCAVATION (TIEBACK WALL)	192050
STRUCTURE EXCAVATION (TYPE A)	192008
STRUCTURE EXCAVATION (TYPE D)	192020
STRUCTURE EXCAVATION (TYPE H)	192023

ITEM DESCRIPTION	ITEM CODE
S	
STRUCTURE EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)	192057
STRUCTURE EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD)	192058
STRUCTURE EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	192053
STRUCTURE EXCAVATION (TYPE Z-3) (AERIALLY DEPOSITED LEAD)	192054
SUBGRADE ENHANCEMENT GEOTEXTILE	198205
SURVEY MONUMENT	810110
SURVEY MONUMENT (TYPE A)	810111
SURVEY MONUMENT (TYPE D)	810116
SYSTEM TESTING AND DOCUMENTATION	869075
T	
TACK COAT	397005
TAPERED INLET	692101
TEMPORARY ACTIVE TREATMENT SYSTEM	074015
TEMPORARY CHECK DAM	074035
TEMPORARY CONCRETE WASHOUT (PORTABLE)	074042
TEMPORARY CONCRETE WASHOUT BIN	074043
TEMPORARY CONCRETE WASHOUT FACILITY	074032
TEMPORARY CONSTRUCTION ENTRANCE	074033
TEMPORARY CONSTRUCTION ROADWAY	074044
TEMPORARY COVER	074034
TEMPORARY CRASH CUSHION MODULE	129100
TEMPORARY CULVERT	073000
TEMPORARY DELINEATOR (CLASS 1)	128201
TEMPORARY DELINEATOR (CLASS 2)	128202
TEMPORARY DRAINAGE INLET PROTECTION	074038
TEMPORARY EROSION CONTROL BLANKET	074027
TEMPORARY FENCE	071301
TEMPORARY FENCE (TYPE BW)	071302
TEMPORARY FENCE (TYPE CL-1.8)	071322
TEMPORARY FENCE (TYPE CL-6)	071321

ITEM DESCRIPTION	ITEM CODE
T	
TEMPORARY FENCE (TYPE ESA)	071325
TEMPORARY FIBER ROLL	074028
TEMPORARY FLASHING BEACON	128660
TEMPORARY GRAVEL BAG BERM	074031
TEMPORARY HYDRAULIC MULCH	074051
TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)	074040
TEMPORARY HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX)	074039
TEMPORARY HYDROSEED	074053
TEMPORARY MULCH	074026
TEMPORARY PAVEMENT MARKER	120300
TEMPORARY PAVEMENT MARKING (PAINT)	120149
TEMPORARY PAVEMENT MARKING (TAPE)	120152
TEMPORARY RAILING (TYPE K)	129000
TEMPORARY REINFORCED SILT FENCE	071324
TEMPORARY SIGNAL SYSTEM	128601
TEMPORARY SILT FENCE	074029
TEMPORARY SOIL BINDER	074055
TEMPORARY STRAW BALE BARRIER	074036
TEMPORARY SUPPORT	072006
TEMPORARY TACKED STRAW	074054
TEMPORARY TERMINAL SECTION (TYPE K)	121161
TEMPORARY TRAFFIC SCREEN	129150
TEMPORARY TRAFFIC STRIPE	120161
TEMPORARY TRAFFIC STRIPE (PAINT)	120159
TEMPORARY TRAFFIC STRIPE (TAPE)	120151
TERMINAL ANCHOR ASSEMBLY (TYPE CA)	839569
TERMINAL ANCHOR ASSEMBLY (TYPE SFT)	839568
TERMINAL SYSTEM (TYPE CAT)	839566
TERMINAL SYSTEM (TYPE CAT) BACKUP	839567
TERMINAL SYSTEM (TYPE SRT)	839565
TESTING WELL	760012
THERMOPLASTIC CROSSWALK AND PAVEMENT MARKING	840519

ITEM DESCRIPTION	ITEM CODE
T	
THERMOPLASTIC PAVEMENT MARKING	840515
THERMOPLASTIC TRAFFIC STRIPE	840501
THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	840560
TIE BAR	406001
TIE BAR (DRILL AND BOND)	406003
TIEBACK ANCHOR	500050
TIEDOWN ANCHOR	500060
TIMBER LAGGING	575004
TIME-RELATED OVERHEAD	070018
TOPSOIL	201700
TRAFFIC CONE	120119
TRAFFIC CONTROL SURVEILLANCE	120102
TRAFFIC CONTROL SYSTEM	120100
TRAFFIC MONITORING STATION	860930
TRAFFIC MONITORING STATION (COUNT)	860925
TRAFFIC MONITORING STATION (LOCATION 1)	860931
TRAFFIC MONITORING STATION (LOCATION 2)	860932
TRAFFIC MONITORING STATION (LOCATION 3)	860933
TRAFFIC PLASTIC DRUM	120199
TRAINING	869080
TRANSITION RAILING (TYPE DTB)	839542
TRANSITION RAILING (TYPE STB)	839540
TRANSITION RAILING (TYPE WB)	839541
TRANSPLANT PALM TREE	204031
TRASH RECEPTACLE	994901
TREAT BRIDGE DECK	540102
TUBULAR HANDRAILING	833088
TURF (SOD)	204042
TWO-COMPONENT PAINT PAVEMENT MARKING	840661
TYPE II BARRICADE	120116
TYPE III BARRICADE	120120

ITEM DESCRIPTION	ITEM CODE	ITEM DESCRIPTION	ITEM CODE
U			
UNDERDRAIN MARKER	820111		
V			
VEGETATION CONTROL (MINOR CONCRETE)	832070		
W			
WATER METER	208304		
WATER POLLUTION CONTROL	074020		
WATER SUPPLY SYSTEM	760080		
WELDED STEEL PIPE CASING (BRIDGE)	703450		
WELL DEVELOPMENT	760011		
WELL SCREEN	760035		
WILD FLOWER SEEDING	204053		
WILD FLOWER SEEDING (ACRE)	204054		
WIRE MESH AND WOOD FENCE	800705		
WOOD FENCE	800701		
WORK AREA MONITORING	590301		

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
070012	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	1	3	3.00	$1,490.00	$4,470.00
		LS	2	8	8.00	$5,725.00	$45,800.00
		LS	3	11	11.00	$2,789.09	$30,680.00
		LS	4	17	17.00	$9,487.65	$161,290.00
		LS	5	5	5.00	$8,194.20	$40,971.00
		LS	6	9	9.00	$4,807.78	$43,270.00
		LS	7	8	8.00	$6,687.50	$53,500.00
		LS	8	2	2.00	$4,550.00	$9,100.00
		LS	10	5	5.00	$4,800.00	$24,000.00
		LS	11	6	6.00	$3,333.33	$20,000.00
		LS	12	7	7.00	$5,311.43	$37,180.00
	Unit Sub Total	**LS**		**81**	**81.00**	**$5,805.69**	**$470,261.00**
	Item Code 070012 Total No. of Proj.			**81**		**Total Amount**	**$470,261.00**
070013	SMALL BUSINESS UTILIZATION REPORT	EA	1	41	70.00	$253.57	$17,750.00
		EA	2	39	75.00	$250.00	$18,750.00
		EA	3	44	97.00	$250.00	$24,250.00
		EA	4	83	263.00	$250.00	$65,750.00
		EA	5	41	68.00	$250.00	$17,000.00
		EA	6	40	81.00	$250.00	$20,250.00
		EA	7	61	203.00	$245.09	$49,754.00
		EA	8	39	47.00	$250.00	$11,750.00
		EA	9	20	30.00	$250.00	$7,500.00
		EA	10	45	83.00	$250.00	$20,750.00
		EA	11	33	94.00	$250.00	$23,500.00
		EA	12	31	142.00	$250.00	$35,500.00
	Unit Sub Total	**EA**		**517**	**1,253.00**	**$249.40**	**$312,504.00**
	Item Code 070013 Total No. of Proj.			**517**		**Total Amount**	**$312,504.00**
070018	TIME-RELATED OVERHEAD	LS	3	1	1.00	$20,000.00	$20,000.00
		LS	4	6	6.00	$1,763,121.67	$10,578,730.00
		LS	6	1	1.00	$330,000.00	$330,000.00
		LS	7	2	2.00	$760,000.00	$1,520,000.00
		LS	11	4	4.00	$234,000.00	$936,000.00
		LS	12	1	1.00	$95,000.00	$95,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LS**		**15**	**15.00**	**$898,648.67**	**$13,479,730.00**
070018	TIME-RELATED OVERHEAD		WDAY	1	3	570.00	$549.07	$312,969.90
			WDAY	2	7	1,655.00	$1,374.23	$2,274,350.00
			WDAY	3	8	1,960.00	$892.35	$1,749,000.00
			WDAY	4	9	5,175.00	$1,934.75	$10,012,350.00
			WDAY	5	5	1,460.00	$2,001.01	$2,921,480.00
			WDAY	6	4	995.00	$1,657.79	$1,649,500.00
			WDAY	7	6	2,930.00	$2,563.96	$7,512,410.00
			WDAY	8	2	420.00	$2,210.43	$928,380.00
			WDAY	10	5	1,380.00	$1,354.54	$1,869,265.00
			WDAY	11	1	415.00	$2,850.00	$1,182,750.00
			WDAY	12	6	4,675.00	$2,226.06	$10,406,850.00
		Unit Sub Total	**WDAY**		**56**	**21,635.00**	**$1,886.73**	**$40,819,304.90**
	Item Code 070018	**Total No. of Proj.**			**71**		**Total Amount**	**$54,299,034.90**
071301	TEMPORARY FENCE		LF	12	1	15,100.00	$6.50	$98,150.00
		Unit Sub Total	**LF**		**1**	**15,100.00**	**$6.50**	**$98,150.00**
	Item Code 071301	**Total No. of Proj.**			**1**		**Total Amount**	**$98,150.00**
071302	TEMPORARY FENCE (TYPE BW)		LF	4	1	8,270.00	$4.25	$35,147.50
		Unit Sub Total	**LF**		**1**	**8,270.00**	**$4.25**	**$35,147.50**
	Item Code 071302	**Total No. of Proj.**			**1**		**Total Amount**	**$35,147.50**
071321	TEMPORARY FENCE (TYPE CL-6)		LF	3	1	1,520.00	$1.74	$2,644.80
			LF	4	8	40,135.00	$8.69	$348,970.00
			LF	5	1	450.00	$19.00	$8,550.00
			LF	11	1	65.00	$16.00	$1,040.00
			LF	12	4	4,920.00	$5.79	$28,470.00
		Unit Sub Total	**LF**		**15**	**47,090.00**	**$8.28**	**$389,674.80**
	Item Code 071321	**Total No. of Proj.**			**15**		**Total Amount**	**$389,674.80**
071322	TEMPORARY FENCE (TYPE CL-1.8)		M	4	1	3,510.00	$19.00	$66,690.00
			M	6	1	69.00	$14.00	$966.00
			M	7	3	2,765.00	$20.08	$55,515.00
			M	11	1	70.00	$40.00	$2,800.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M**		**6**	**6,414.00**	**$19.64**	**$125,971.00**
	Item Code 071322	**Total No. of Proj.**			**6**		**Total Amount**	**$125,971.00**
071324	TEMPORARY REINFORCED SILT FENCE		LF	1	2	820.00	$20.84	$17,090.00
			LF	4	4	29,890.00	$6.22	$185,800.00
		Unit Sub Total	**LF**		**6**	**30,710.00**	**$6.61**	**$202,890.00**
071324	TEMPORARY REINFORCED SILT FENCE		M	4	1	2,000.00	$12.00	$24,000.00
		Unit Sub Total	**M**		**1**	**2,000.00**	**$12.00**	**$24,000.00**
	Item Code 071324	**Total No. of Proj.**			**7**		**Total Amount**	**$226,890.00**
071325	TEMPORARY FENCE (TYPE ESA)		LF	1	19	7,571.00	$5.07	$38,401.00
			LF	2	6	6,070.00	$3.29	$19,969.20
			LF	3	10	37,943.00	$2.06	$78,127.80
			LF	4	17	86,150.00	$2.16	$185,970.40
			LF	5	11	11,535.00	$2.46	$28,363.00
			LF	6	13	36,890.00	$3.53	$130,129.00
			LF	7	1	1,000.00	$3.60	$3,600.00
			LF	8	1	800.00	$5.70	$4,560.00
			LF	9	3	12,210.00	$1.82	$22,260.00
			LF	10	7	8,610.00	$3.88	$33,365.00
			LF	11	3	3,020.00	$3.80	$11,471.00
			LF	12	2	1,920.00	$4.84	$9,288.00
		Unit Sub Total	**LF**		**93**	**213,719.00**	**$2.65**	**$565,504.40**
071325	TEMPORARY FENCE (TYPE ESA)		M	2	1	1,200.00	$10.00	$12,000.00
			M	3	1	260.00	$12.00	$3,120.00
			M	4	3	2,070.00	$8.38	$17,340.00
			M	6	1	340.00	$8.50	$2,890.00
			M	7	1	430.00	$17.00	$7,310.00
			M	11	2	590.00	$10.63	$6,270.00
		Unit Sub Total	**M**		**9**	**4,890.00**	**$10.01**	**$48,930.00**
	Item Code 071325	**Total No. of Proj.**			**102**		**Total Amount**	**$614,434.40**
072006	TEMPORARY SUPPORT		LS	2	3	3.00	$45,733.33	$137,200.00
			LS	3	1	1.00	$112,000.00	$112,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
072006	TEMPORARY SUPPORT	LS	4	1	1.00	$30,000.00	$30,000.00
		LS	8	1	1.00	$33,000.00	$33,000.00
		LS	10	1	1.00	$230,000.00	$230,000.00
		LS	12	2	2.00	$85,000.00	$170,000.00
	Unit Sub Total	**LS**		**9**	**9.00**	**$79,133.33**	**$712,200.00**
	Item Code 072006 Total No. of Proj.			**9**		**Total Amount**	**$712,200.00**
073000	TEMPORARY CULVERT	LF	1	1	320.00	$10.00	$3,200.00
	Unit Sub Total	**LF**		**1**	**320.00**	**$10.00**	**$3,200.00**
	Item Code 073000 Total No. of Proj.			**1**		**Total Amount**	**$3,200.00**
073004	12" TEMPORARY CULVERT	LF	4	1	780.00	$45.00	$35,100.00
	Unit Sub Total	**LF**		**1**	**780.00**	**$45.00**	**$35,100.00**
	Item Code 073004 Total No. of Proj.			**1**		**Total Amount**	**$35,100.00**
073006	18" TEMPORARY CULVERT	LF	1	1	120.00	$75.00	$9,000.00
		LF	12	1	560.00	$36.00	$20,160.00
	Unit Sub Total	**LF**		**2**	**680.00**	**$42.88**	**$29,160.00**
	Item Code 073006 Total No. of Proj.			**2**		**Total Amount**	**$29,160.00**
073008	24" TEMPORARY CULVERT	LF	4	1	13.00	$100.00	$1,300.00
		LF	12	1	780.00	$38.00	$29,640.00
	Unit Sub Total	**LF**		**2**	**793.00**	**$39.02**	**$30,940.00**
	Item Code 073008 Total No. of Proj.			**2**		**Total Amount**	**$30,940.00**
073011	36" TEMPORARY CULVERT	LF	12	1	150.00	$54.00	$8,100.00
	Unit Sub Total	**LF**		**1**	**150.00**	**$54.00**	**$8,100.00**
	Item Code 073011 Total No. of Proj.			**1**		**Total Amount**	**$8,100.00**
073026	300 MM TEMPORARY CULVERT	M	4	1	260.00	$165.00	$42,900.00
	Unit Sub Total	**M**		**1**	**260.00**	**$165.00**	**$42,900.00**
	Item Code 073026 Total No. of Proj.			**1**		**Total Amount**	**$42,900.00**
073028	450 MM TEMPORARY CULVERT	M	3	1	20.00	$250.00	$5,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
073028	450 MM TEMPORARY CULVERT		M	4	1	360.00	$175.00	$63,000.00
		Unit Sub Total	**M**		**2**	**380.00**	**$178.95**	**$68,000.00**
	Item Code 073028	**Total No. of Proj.**			**2**		**Total Amount**	**$68,000.00**
073029	600 MM TEMPORARY CULVERT		M	4	1	200.00	$215.00	$43,000.00
		Unit Sub Total	**M**		**1**	**200.00**	**$215.00**	**$43,000.00**
	Item Code 073029	**Total No. of Proj.**			**1**		**Total Amount**	**$43,000.00**
074015	TEMPORARY ACTIVE TREATMENT SYSTEM		LS	4	3	3.00	$70,333.33	$211,000.00
		Unit Sub Total	**LS**		**3**	**3.00**	**$70,333.33**	**$211,000.00**
	Item Code 074015	**Total No. of Proj.**			**3**		**Total Amount**	**$211,000.00**
074016	CONSTRUCTION SITE MANAGEMENT		LS	1	46	46.00	$27,481.82	$1,264,163.80
			LS	2	44	44.00	$4,528.75	$199,265.00
			LS	3	58	58.00	$7,343.45	$425,920.00
			LS	4	89	89.00	$11,377.18	$1,012,569.20
			LS	5	45	45.00	$6,281.89	$282,685.00
			LS	6	49	49.00	$4,939.96	$242,057.90
			LS	7	63	63.00	$9,814.43	$618,309.00
			LS	8	39	39.00	$3,627.69	$141,480.00
			LS	9	22	22.00	$2,134.66	$46,962.50
			LS	10	51	51.00	$3,590.25	$183,102.64
			LS	11	39	39.00	$9,305.56	$362,917.00
			LS	12	33	33.00	$12,066.07	$398,180.25
		Unit Sub Total	**LS**		**578**	**578.00**	**$8,957.81**	**$5,177,612.29**
	Item Code 074016	**Total No. of Proj.**			**578**		**Total Amount**	**$5,177,612.29**
074017	PREPARE WATER POLLUTION CONTROL PROGRAM		LS	1	38	38.00	$2,375.45	$90,267.00
			LS	2	29	29.00	$2,118.94	$61,449.25
			LS	3	51	51.00	$1,334.72	$68,070.50
			LS	4	66	66.00	$992.14	$65,481.00
			LS	5	37	37.00	$933.73	$34,548.00
			LS	6	34	34.00	$887.26	$30,167.00
			LS	7	53	53.00	$880.78	$46,681.50
			LS	8	27	27.00	$637.04	$17,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074017	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	9	19	19.00	$870.07	$16,531.25
		LS	10	41	41.00	$1,551.83	$63,625.00
		LS	11	27	27.00	$869.63	$23,480.00
		LS	12	22	22.00	$1,018.69	$22,411.09
	Unit Sub Total	**LS**		**444**	**444.00**	**$1,216.02**	**$539,911.59**
	Item Code 074017 Total No. of Proj.			**444**		**Total Amount**	**$539,911.59**
074018	HEALTH AND SAFETY PLAN	LS	3	1	1.00	$5,000.00	$5,000.00
		LS	4	2	2.00	$5,500.00	$11,000.00
		LS	7	1	1.00	$4,000.00	$4,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$5,000.00**	**$20,000.00**
	Item Code 074018 Total No. of Proj.			**4**		**Total Amount**	**$20,000.00**
074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	1	8	8.00	$2,118.13	$16,945.00
		LS	2	15	15.00	$1,656.67	$24,850.00
		LS	3	7	7.00	$1,942.86	$13,600.00
		LS	4	23	23.00	$4,199.13	$96,580.00
		LS	5	8	8.00	$1,568.75	$12,550.00
		LS	6	15	15.00	$1,729.20	$25,938.00
		LS	7	10	10.00	$1,964.00	$19,640.00
		LS	8	12	12.00	$2,112.50	$25,350.00
		LS	9	3	3.00	$1,433.33	$4,300.00
		LS	10	10	10.00	$2,338.30	$23,383.00
		LS	11	12	12.00	$2,045.00	$24,540.00
		LS	12	11	11.00	$4,186.36	$46,050.00
	Unit Sub Total	**LS**		**134**	**134.00**	**$2,490.49**	**$333,726.00**
	Item Code 074019 Total No. of Proj.			**134**		**Total Amount**	**$333,726.00**
074020	WATER POLLUTION CONTROL	LS	4	2	2.00	$7,000.00	$14,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$7,000.00**	**$14,000.00**
	Item Code 074020 Total No. of Proj.			**2**		**Total Amount**	**$14,000.00**
074026	TEMPORARY MULCH	M2	7	2	305,000.00	$1.13	$344,000.00
	Unit Sub Total	**M2**		**2**	**305,000.00**	**$1.13**	**$344,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074026	TEMPORARY MULCH		M3	7	1	2,400.00	$35.50	$85,200.00
		Unit Sub Total	**M3**		**1**	**2,400.00**	**$35.50**	**$85,200.00**
074026	TEMPORARY MULCH		SQYD	1	1	560.00	$6.00	$3,360.00
			SQYD	2	5	1,860.00	$6.29	$11,703.50
			SQYD	3	1	1,110.00	$4.50	$4,995.00
			SQYD	7	1	1,700.00	$2.00	$3,400.00
			SQYD	10	2	6,200.00	$2.20	$13,650.00
			SQYD	12	1	10,000.00	$1.45	$14,500.00
		Unit Sub Total	**SQYD**		**11**	**21,430.00**	**$2.41**	**$51,608.50**
	Item Code 074026	**Total No. of Proj.**			**14**		**Total Amount**	**$480,808.50**
074027	TEMPORARY EROSION CONTROL BLANKET		M2	4	1	1,000.00	$9.00	$9,000.00
			M2	7	1	410.00	$1.00	$410.00
		Unit Sub Total	**M2**		**2**	**1,410.00**	**$6.67**	**$9,410.00**
074027	TEMPORARY EROSION CONTROL BLANKET		SQYD	2	1	500.00	$5.00	$2,500.00
			SQYD	4	1	12,400.00	$4.00	$49,600.00
			SQYD	10	1	240.00	$10.00	$2,400.00
		Unit Sub Total	**SQYD**		**3**	**13,140.00**	**$4.15**	**$54,500.00**
	Item Code 074027	**Total No. of Proj.**			**5**		**Total Amount**	**$63,910.00**
074028	TEMPORARY FIBER ROLL		LF	1	22	25,921.00	$3.05	$79,003.00
			LF	2	23	31,200.00	$3.03	$94,638.10
			LF	3	12	71,060.00	$2.07	$146,817.00
			LF	4	11	24,700.00	$2.83	$69,985.40
			LF	5	5	72,770.00	$1.81	$131,912.00
			LF	6	7	25,870.00	$3.07	$79,479.00
			LF	7	6	9,530.00	$2.61	$24,847.50
			LF	8	7	18,260.00	$3.35	$61,245.00
			LF	9	11	30,160.00	$3.02	$90,945.34
			LF	10	10	38,220.00	$1.83	$69,862.00
			LF	11	8	33,240.00	$2.07	$68,808.50
			LF	12	13	212,570.00	$2.38	$505,375.00
		Unit Sub Total	**LF**		**135**	**593,501.00**	**$2.40**	**$1,422,917.84**
074028	TEMPORARY FIBER ROLL		M	2	1	1,480.00	$9.00	$13,320.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074028	TEMPORARY FIBER ROLL		M	3	2	7,710.00	$7.65	$58,990.00
			M	4	1	10,400.00	$5.75	$59,800.00
			M	6	1	1,500.00	$5.00	$7,500.00
			M	7	5	25,230.00	$7.84	$197,740.00
			M	10	1	470.00	$14.00	$6,580.00
			M	11	2	33,200.00	$7.38	$244,880.00
		Unit Sub Total	**M**		**13**	**79,990.00**	**$7.36**	**$588,810.00**
	Item Code 074028	**Total No. of Proj.**			**148**		**Total Amount**	**$2,011,727.84**
074029	TEMPORARY SILT FENCE		LF	1	11	5,527.00	$3.71	$20,510.00
			LF	2	3	2,000.00	$10.00	$20,000.00
			LF	3	9	272,700.00	$3.17	$863,447.00
			LF	4	12	27,600.00	$2.40	$66,346.00
			LF	5	5	61,460.00	$1.42	$87,382.00
			LF	6	3	65,120.00	$1.29	$84,080.00
			LF	7	2	4,210.00	$3.03	$12,756.00
			LF	8	2	10,650.00	$1.38	$14,690.00
			LF	9	1	1,000.00	$3.50	$3,500.00
			LF	10	2	13,860.00	$2.42	$33,480.00
			LF	12	4	36,410.00	$1.66	$60,566.00
		Unit Sub Total	**LF**		**54**	**500,537.00**	**$2.53**	**$1,266,757.00**
074029	TEMPORARY SILT FENCE		M	2	1	1,160.00	$13.00	$15,080.00
			M	3	1	220.00	$5.00	$1,100.00
			M	4	3	7,360.00	$6.29	$46,260.00
			M	7	4	11,690.00	$6.80	$79,490.00
			M	10	1	710.00	$18.00	$12,780.00
		Unit Sub Total	**M**		**10**	**21,140.00**	**$7.32**	**$154,710.00**
	Item Code 074029	**Total No. of Proj.**			**64**		**Total Amount**	**$1,421,467.00**
074031	TEMPORARY GRAVEL BAG BERM		LF	1	7	3,250.00	$7.11	$23,100.00
			LF	3	4	39,150.00	$3.48	$136,150.00
			LF	4	3	7,600.00	$4.21	$32,000.00
			LF	5	1	280.00	$6.00	$1,680.00
			LF	6	1	180.00	$35.00	$6,300.00
			LF	7	4	900.00	$4.33	$3,900.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074031	TEMPORARY GRAVEL BAG BERM	LF	8	4	7,850.00	$3.02	$23,700.00
		LF	11	1	380.00	$8.00	$3,040.00
		LF	12	8	8,360.00	$4.41	$36,882.50
	Unit Sub Total	**LF**		**33**	**67,950.00**	**$3.93**	**$266,752.50**
074031	TEMPORARY GRAVEL BAG BERM	M	2	1	960.00	$15.00	$14,400.00
		M	3	2	310.00	$32.26	$10,000.00
		M	4	1	200.00	$7.00	$1,400.00
		M	7	4	6,700.00	$12.10	$81,100.00
	Unit Sub Total	**M**		**8**	**8,170.00**	**$13.08**	**$106,900.00**
	Item Code 074031 Total No. of Proj.			**41**		**Total Amount**	**$373,652.50**
074032	TEMPORARY CONCRETE WASHOUT FACILITY	EA	1	1	2.00	$850.00	$1,700.00
		EA	2	1	1.00	$450.00	$450.00
		EA	3	8	23.00	$1,410.06	$32,431.30
		EA	4	4	42.00	$1,253.57	$52,650.00
		EA	5	3	18.00	$1,738.72	$31,297.00
		EA	6	7	12.00	$1,955.17	$23,462.00
		EA	7	3	17.00	$4,111.76	$69,900.00
		EA	9	3	6.00	$648.94	$3,893.61
		EA	10	2	5.00	$6,200.00	$31,000.00
		EA	11	2	10.00	$1,740.00	$17,400.00
		EA	12	2	2.00	$6,000.00	$12,000.00
	Unit Sub Total	**EA**		**36**	**138.00**	**$2,001.33**	**$276,183.91**
074032	TEMPORARY CONCRETE WASHOUT FACILITY	LS	3	2	2.00	$650.00	$1,300.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$650.00**	**$1,300.00**
	Item Code 074032 Total No. of Proj.			**38**		**Total Amount**	**$277,483.91**
074033	TEMPORARY CONSTRUCTION ENTRANCE	EA	1	3	8.00	$1,662.50	$13,300.00
		EA	2	3	17.00	$1,735.29	$29,500.00
		EA	3	11	49.00	$2,373.06	$116,280.00
		EA	4	23	89.00	$3,091.97	$275,185.00
		EA	5	10	33.00	$2,330.67	$76,912.00
		EA	6	7	41.00	$3,280.00	$134,480.00
		EA	7	7	53.00	$3,054.72	$161,900.00
		EA	8	5	11.00	$1,936.36	$21,300.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074033	TEMPORARY CONSTRUCTION ENTRANCE		EA	9	1	1.00	$1,500.00	$1,500.00
			EA	10	5	14.00	$3,257.14	$45,600.00
			EA	11	12	102.00	$1,673.49	$170,696.00
			EA	12	10	124.00	$913.34	$113,254.00
		Unit Sub Total	**EA**		**97**	**542.00**	**$2,140.05**	**$1,159,907.00**
	Item Code 074033	**Total No. of Proj.**			**97**		**Total Amount**	**$1,159,907.00**
074034	TEMPORARY COVER		M2	2	1	8,740.00	$0.40	$3,496.00
			M2	3	2	14,045.00	$1.97	$27,685.50
			M2	4	3	6,430.00	$3.60	$23,180.00
			M2	7	3	33,000.00	$2.52	$83,000.00
			M2	10	1	2,500.00	$1.40	$3,500.00
		Unit Sub Total	**M2**		**10**	**64,715.00**	**$2.18**	**$140,861.50**
074034	TEMPORARY COVER		SQFT	3	1	500.00	$1.00	$500.00
		Unit Sub Total	**SQFT**		**1**	**500.00**	**$1.00**	**$500.00**
074034	TEMPORARY COVER		SQYD	1	2	430.00	$7.07	$3,040.00
			SQYD	2	1	230.00	$2.00	$460.00
			SQYD	3	5	23,430.00	$4.13	$96,830.00
			SQYD	4	16	32,770.00	$2.58	$84,614.20
			SQYD	5	2	2,650.00	$1.89	$5,000.00
			SQYD	6	3	9,730.00	$2.00	$19,460.00
			SQYD	7	1	10.00	$30.00	$300.00
			SQYD	8	5	33,740.00	$0.96	$32,430.00
			SQYD	10	1	5,600.00	$1.20	$6,720.00
			SQYD	12	1	2,000.00	$1.00	$2,000.00
		Unit Sub Total	**SQYD**		**37**	**110,590.00**	**$2.27**	**$250,854.20**
	Item Code 074034	**Total No. of Proj.**			**48**		**Total Amount**	**$392,215.70**
074035	TEMPORARY CHECK DAM		LF	1	15	2,427.00	$11.30	$27,420.00
			LF	2	9	1,750.00	$8.33	$14,570.00
			LF	3	3	7,800.00	$3.53	$27,500.00
			LF	4	9	1,957.00	$8.20	$16,055.20
			LF	5	9	44,940.00	$1.84	$82,797.00
			LF	8	2	520.00	$3.01	$1,564.00
			LF	9	1	40.00	$11.30	$452.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074035	TEMPORARY CHECK DAM	LF	10	2	1,430.00	$8.90	$12,720.00
		LF	11	2	600.00	$2.55	$1,531.20
		LF	12	3	8,520.00	$2.98	$25,383.00
	Unit Sub Total	**LF**		**55**	**69,984.00**	**$3.00**	**$209,992.40**
074035	TEMPORARY CHECK DAM	M	2	1	170.00	$25.00	$4,250.00
		M	4	2	539.00	$17.53	$9,450.00
		M	6	1	140.00	$15.00	$2,100.00
		M	7	1	450.00	$15.00	$6,750.00
		M	11	2	800.00	$24.44	$19,550.00
	Unit Sub Total	**M**		**7**	**2,099.00**	**$20.06**	**$42,100.00**
	Item Code 074035 Total No. of Proj.			**62**		**Total Amount**	**$252,092.40**
074036	TEMPORARY STRAW BALE BARRIER	LF	1	1	20.00	$20.00	$400.00
	Unit Sub Total	**LF**		**1**	**20.00**	**$20.00**	**$400.00**
074036	TEMPORARY STRAW BALE BARRIER	M	2	1	540.00	$12.00	$6,480.00
		M	7	1	250.00	$40.00	$10,000.00
	Unit Sub Total	**M**		**2**	**790.00**	**$20.86**	**$16,480.00**
	Item Code 074036 Total No. of Proj.			**3**		**Total Amount**	**$16,880.00**
074037	MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL)	EA	2	2	15.00	$700.00	$10,500.00
		EA	3	5	29.00	$702.93	$20,385.00
		EA	4	6	42.00	$710.71	$29,850.00
		EA	5	3	13.00	$913.08	$11,870.00
		EA	7	4	41.00	$1,069.51	$43,850.00
		EA	10	3	13.00	$462.00	$6,006.00
		EA	11	4	42.00	$256.90	$10,790.00
		EA	12	3	46.00	$330.43	$15,200.00
	Unit Sub Total	**EA**		**30**	**241.00**	**$615.98**	**$148,451.00**
	Item Code 074037 Total No. of Proj.			**30**		**Total Amount**	**$148,451.00**
074038	TEMPORARY DRAINAGE INLET PROTECTION	EA	1	17	142.00	$336.25	$47,747.00
		EA	2	13	191.00	$214.85	$41,036.00
		EA	3	17	338.00	$247.02	$83,492.01
		EA	4	61	2,620.00	$176.94	$463,593.82

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074038	TEMPORARY DRAINAGE INLET PROTECTION	EA	5	13	245.00	$133.80	$32,781.00
		EA	6	20	421.00	$220.35	$92,767.00
		EA	7	15	801.00	$111.20	$89,070.00
		EA	8	6	89.00	$165.73	$14,750.00
		EA	9	8	154.00	$198.05	$30,500.00
		EA	10	8	157.00	$161.40	$25,339.80
		EA	11	14	528.00	$147.62	$77,941.00
		EA	12	23	2,086.00	$110.83	$231,196.44
	Unit Sub Total	**EA**		**215**	**7,772.00**	**$158.29**	**$1,230,214.07**
	Item Code 074038 Total No. of Proj.			**215**		**Total Amount**	**$1,230,214.07**
074039	TEMPORARY HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX)	M2	2	1	15,700.00	$0.54	$8,478.00
	Unit Sub Total	**M2**		**1**	**15,700.00**	**$0.54**	**$8,478.00**
074039	TEMPORARY HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX)	SQYD	2	2	61,400.00	$0.56	$34,490.00
		SQYD	5	1	5,000.00	$0.36	$1,800.00
	Unit Sub Total	**SQYD**		**3**	**66,400.00**	**$0.55**	**$36,290.00**
	Item Code 074039 Total No. of Proj.			**4**		**Total Amount**	**$44,768.00**
074040	TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)	M2	4	2	51,900.00	$1.09	$56,640.00
		M2	7	1	5,000.00	$1.00	$5,000.00
	Unit Sub Total	**M2**		**3**	**56,900.00**	**$1.08**	**$61,640.00**
074040	TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)	SQFT	3	1	168,000.00	$0.03	$5,040.00
	Unit Sub Total	**SQFT**		**1**	**168,000.00**	**$0.03**	**$5,040.00**
074040	TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)	SQYD	1	1	720.00	$3.00	$2,160.00
		SQYD	3	1	13,000.00	$1.00	$13,000.00
		SQYD	4	6	77,660.00	$0.95	$74,052.50
		SQYD	5	1	106,000.00	$0.69	$73,140.00
		SQYD	12	3	69,500.00	$0.89	$62,000.00
	Unit Sub Total	**SQYD**		**12**	**266,880.00**	**$0.84**	**$224,352.50**
	Item Code 074040 Total No. of Proj.			**16**		**Total Amount**	**$291,032.50**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074041	STREET SWEEPING	LS	1	14	14.00	$7,964.29	$111,500.00
		LS	2	4	4.00	$11,000.00	$44,000.00
		LS	3	17	17.00	$20,592.94	$350,080.00
		LS	4	49	49.00	$16,620.02	$814,381.00
		LS	5	7	7.00	$5,589.86	$39,129.00
		LS	6	19	19.00	$19,317.84	$367,039.00
		LS	7	22	22.00	$27,348.18	$601,660.00
		LS	8	7	7.00	$6,257.14	$43,800.00
		LS	9	4	4.00	$23,825.00	$95,300.00
		LS	10	18	18.00	$6,422.22	$115,600.00
		LS	11	16	16.00	$15,825.00	$253,200.00
		LS	12	16	16.00	$34,981.25	$559,700.00
	Unit Sub Total	**LS**		**193**	**193.00**	**$17,592.69**	**$3,395,389.00**
	Item Code 074041 Total No. of Proj.			**193**		**Total Amount**	**$3,395,389.00**
074042	TEMPORARY CONCRETE WASHOUT (PORTABLE)	EA	4	3	4.00	$1,625.00	$6,500.00
		EA	6	1	1.00	$1,200.00	$1,200.00
		EA	8	1	1.00	$500.00	$500.00
		EA	12	1	1.00	$1,500.00	$1,500.00
	Unit Sub Total	**EA**		**6**	**7.00**	**$1,385.71**	**$9,700.00**
074042	TEMPORARY CONCRETE WASHOUT (PORTABLE)	LS	1	26	26.00	$2,292.12	$59,595.00
		LS	2	30	30.00	$2,462.15	$73,864.54
		LS	3	30	30.00	$2,907.30	$87,219.00
		LS	4	29	29.00	$5,039.66	$146,150.00
		LS	5	16	16.00	$1,552.88	$24,846.00
		LS	6	22	22.00	$4,431.14	$97,485.00
		LS	7	38	38.00	$10,267.34	$390,159.00
		LS	8	16	16.00	$1,361.88	$21,790.00
		LS	9	6	6.00	$1,121.90	$6,731.37
		LS	10	23	23.00	$1,977.83	$45,490.00
		LS	11	26	26.00	$2,004.04	$52,105.00
		LS	12	17	17.00	$1,055.67	$17,946.31
	Unit Sub Total	**LS**		**279**	**279.00**	**$3,668.03**	**$1,023,381.22**
	Item Code 074042 Total No. of Proj.			**285**		**Total Amount**	**$1,033,081.22**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074043	TEMPORARY CONCRETE WASHOUT BIN	EA	4	14	235.00	$121.63	$28,584.00
		EA	8	2	4.00	$4,612.50	$18,450.00
		EA	10	1	2.00	$1,000.00	$2,000.00
		EA	12	6	152.00	$2,296.05	$349,000.00
	Unit Sub Total	**EA**		**23**	**393.00**	**$1,012.81**	**$398,034.00**
	Item Code 074043 Total No. of Proj.			**23**		**Total Amount**	**$398,034.00**
074044	TEMPORARY CONSTRUCTION ROADWAY	CY	4	1	21,000.00	$70.00	$1,470,000.00
	Unit Sub Total	**CY**		**1**	**21,000.00**	**$70.00**	**$1,470,000.00**
	Item Code 074044 Total No. of Proj.			**1**		**Total Amount**	**$1,470,000.00**
074051	TEMPORARY HYDRAULIC MULCH	M2	11	2	531,000.00	$0.40	$213,360.00
	Unit Sub Total	**M2**		**2**	**531,000.00**	**$0.40**	**$213,360.00**
074051	TEMPORARY HYDRAULIC MULCH	SQYD	3	1	22,800.00	$0.30	$6,840.00
		SQYD	10	1	34,800.00	$0.20	$6,960.00
		SQYD	11	3	61,570.00	$0.30	$18,488.00
	Unit Sub Total	**SQYD**		**5**	**119,170.00**	**$0.27**	**$32,288.00**
	Item Code 074051 Total No. of Proj.			**7**		**Total Amount**	**$245,648.00**
074053	TEMPORARY HYDROSEED	M2	10	1	45,000.00	$0.14	$6,300.00
	Unit Sub Total	**M2**		**1**	**45,000.00**	**$0.14**	**$6,300.00**
	Item Code 074053 Total No. of Proj.			**1**		**Total Amount**	**$6,300.00**
074054	TEMPORARY TACKED STRAW	M2	3	1	13,000.00	$0.40	$5,200.00
	Unit Sub Total	**M2**		**1**	**13,000.00**	**$0.40**	**$5,200.00**
074054	TEMPORARY TACKED STRAW	SQYD	2	1	450.00	$0.50	$225.00
		SQYD	10	1	3,900.00	$1.05	$4,095.00
	Unit Sub Total	**SQYD**		**2**	**4,350.00**	**$0.99**	**$4,320.00**
	Item Code 074054 Total No. of Proj.			**3**		**Total Amount**	**$9,520.00**
074055	TEMPORARY SOIL BINDER	M2	2	1	33,100.00	$0.26	$8,606.00
	Unit Sub Total	**M2**		**1**	**33,100.00**	**$0.26**	**$8,606.00**
074055	TEMPORARY SOIL BINDER	SQYD	1	1	87,800.00	$0.20	$17,560.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
074055	TEMPORARY SOIL BINDER	SQYD	2	2	104,700.00	$0.13	$13,470.00
		SQYD	8	1	19,000.00	$0.20	$3,800.00
		SQYD	10	1	25,600.00	$0.15	$3,840.00
		SQYD	12	1	312,000.00	$0.06	$18,720.00
	Unit Sub Total	**SQYD**		**6**	**549,100.00**	**$0.10**	**$57,390.00**
	Item Code 074055 Total No. of Proj.			**7**		**Total Amount**	**$65,996.00**
074056	RAIN EVENT ACTION PLAN	EA	4	4	288.00	$347.22	$100,000.00
		EA	11	1	16.00	$500.00	$8,000.00
		EA	12	1	45.00	$500.00	$22,500.00
	Unit Sub Total	**EA**		**6**	**349.00**	**$373.93**	**$130,500.00**
	Item Code 074056 Total No. of Proj.			**6**		**Total Amount**	**$130,500.00**
074057	STORM WATER ANNUAL REPORT	EA	1	3	3.00	$2,000.00	$6,000.00
		EA	2	3	3.00	$1,550.00	$4,650.00
		EA	3	3	9.00	$1,355.56	$12,200.00
		EA	4	8	14.00	$1,657.14	$23,200.00
		EA	5	1	1.00	$100.00	$100.00
		EA	6	1	2.00	$2,000.00	$4,000.00
		EA	7	3	7.00	$1,228.57	$8,600.00
		EA	11	2	6.00	$1,400.00	$8,400.00
		EA	12	2	4.00	$2,000.00	$8,000.00
	Unit Sub Total	**EA**		**26**	**49.00**	**$1,533.67**	**$75,150.00**
	Item Code 074057 Total No. of Proj.			**26**		**Total Amount**	**$75,150.00**
074058	STORM WATER SAMPLING AND ANALYSIS DAY	EA	4	4	185.00	$723.24	$133,800.00
		EA	11	1	31.00	$250.00	$7,750.00
		EA	12	1	20.00	$500.00	$10,000.00
	Unit Sub Total	**EA**		**6**	**236.00**	**$642.16**	**$151,550.00**
	Item Code 074058 Total No. of Proj.			**6**		**Total Amount**	**$151,550.00**
120090	CONSTRUCTION AREA SIGNS	LS	1	40	40.00	$7,243.50	$289,740.00
		LS	2	43	43.00	$9,924.87	$426,769.25
		LS	3	48	48.00	$6,076.72	$291,682.50
		LS	4	87	87.00	$11,705.51	$1,018,379.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
120090	CONSTRUCTION AREA SIGNS	LS	5	45	45.00	$4,561.29	$205,258.20
		LS	6	48	48.00	$5,577.31	$267,711.00
		LS	7	61	61.00	$10,450.11	$637,457.00
		LS	8	38	38.00	$6,571.58	$249,720.00
		LS	9	19	19.00	$17,439.47	$331,350.00
		LS	10	50	50.00	$5,111.50	$255,575.00
		LS	11	39	39.00	$15,062.13	$587,423.00
		LS	12	33	33.00	$31,695.60	$1,045,954.93
	Unit Sub Total	**LS**		**551**	**551.00**	**$10,176.08**	**$5,607,019.88**
	Item Code 120090 Total No. of Proj.			**551**		**Total Amount**	**$5,607,019.88**
120100	TRAFFIC CONTROL SYSTEM	LS	1	44	44.00	$67,547.43	$2,972,087.00
		LS	2	44	44.00	$76,546.00	$3,368,024.00
		LS	3	56	56.00	$57,450.41	$3,217,222.80
		LS	4	85	85.00	$90,836.31	$7,721,086.11
		LS	5	45	45.00	$52,845.84	$2,378,063.00
		LS	6	47	47.00	$90,921.94	$4,273,331.00
		LS	7	63	63.00	$117,579.10	$7,407,483.01
		LS	8	38	38.00	$65,884.01	$2,503,592.50
		LS	9	19	19.00	$75,343.02	$1,431,517.40
		LS	10	50	50.00	$60,730.64	$3,036,532.00
		LS	11	38	38.00	$71,637.04	$2,722,207.40
		LS	12	32	32.00	$120,900.79	$3,868,825.19
	Unit Sub Total	**LS**		**561**	**561.00**	**$80,035.60**	**$44,899,971.41**
	Item Code 120100 Total No. of Proj.			**561**		**Total Amount**	**$44,899,971.41**
120102	TRAFFIC CONTROL SURVEILLANCE	LS	2	2	2.00	$42,500.00	$85,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$42,500.00**	**$85,000.00**
	Item Code 120102 Total No. of Proj.			**2**		**Total Amount**	**$85,000.00**
120110	FLASHING ARROW SIGN	EA	1	1	2.00	$1,500.00	$3,000.00
		EA	2	1	6.00	$600.00	$3,600.00
		EA	7	1	12.00	$20.00	$240.00
		EA	8	1	2.00	$500.00	$1,000.00
		EA	9	1	4.00	$2,500.00	$10,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**5**	**26.00**	**$686.15**	**$17,840.00**
	Item Code 120110	**Total No. of Proj.**			**5**		**Total Amount**	**$17,840.00**
120116	TYPE II BARRICADE		EA	4	1	30.00	$75.00	$2,250.00
			EA	5	2	14.00	$30.01	$420.10
			EA	7	1	2.00	$390.00	$780.00
			EA	8	4	100.00	$36.58	$3,658.00
			EA	12	2	40.00	$391.86	$15,674.33
		Unit Sub Total	**EA**		**10**	**186.00**	**$122.49**	**$22,782.43**
	Item Code 120116	**Total No. of Proj.**			**10**		**Total Amount**	**$22,782.43**
120119	TRAFFIC CONE		EA	4	1	65.00	$23.00	$1,495.00
			EA	8	1	16.00	$50.00	$800.00
		Unit Sub Total	**EA**		**2**	**81.00**	**$28.33**	**$2,295.00**
	Item Code 120119	**Total No. of Proj.**			**2**		**Total Amount**	**$2,295.00**
120120	TYPE III BARRICADE		EA	1	4	165.00	$97.73	$16,126.00
			EA	2	2	14.00	$114.29	$1,600.00
			EA	3	4	201.00	$47.26	$9,500.00
			EA	4	8	418.00	$120.50	$50,370.00
			EA	5	3	134.00	$28.08	$3,762.80
			EA	6	5	110.00	$81.75	$8,992.00
			EA	7	5	107.00	$85.72	$9,172.00
			EA	8	3	55.00	$234.91	$12,920.00
			EA	9	2	54.00	$81.85	$4,420.00
			EA	10	1	12.00	$60.00	$720.00
			EA	11	2	18.00	$130.00	$2,340.00
			EA	12	8	144.00	$62.35	$8,978.00
		Unit Sub Total	**EA**		**47**	**1,432.00**	**$90.01**	**$128,900.80**
	Item Code 120120	**Total No. of Proj.**			**47**		**Total Amount**	**$128,900.80**
120149	TEMPORARY PAVEMENT MARKING (PAINT)		M2	2	1	7.00	$50.00	$350.00
			M2	3	1	130.00	$20.00	$2,600.00
			M2	4	2	650.00	$10.83	$7,040.00
			M2	7	1	250.00	$10.00	$2,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
120149	TEMPORARY PAVEMENT MARKING (PAINT)	M2	11	1	96.00	$20.00	$1,920.00
	Unit Sub Total	**M2**		**6**	**1,133.00**	**$12.72**	**$14,410.00**
120149	TEMPORARY PAVEMENT MARKING (PAINT)	SQFT	1	4	425.00	$11.35	$4,824.00
		SQFT	2	2	308.00	$7.63	$2,350.00
		SQFT	3	3	11,240.00	$1.25	$13,997.50
		SQFT	4	7	21,230.00	$2.86	$60,777.00
		SQFT	5	1	390.00	$6.00	$2,340.00
		SQFT	6	1	4,300.00	$0.20	$860.00
		SQFT	7	1	3,740.00	$2.50	$9,350.00
		SQFT	8	1	350.00	$2.50	$875.00
		SQFT	10	3	393.00	$3.20	$1,258.00
		SQFT	11	2	400.00	$3.41	$1,362.00
		SQFT	12	5	16,065.00	$2.12	$34,009.00
	Unit Sub Total	**SQFT**		**30**	**58,841.00**	**$2.24**	**$132,002.50**
	Item Code 120149 Total No. of Proj.			**36**		**Total Amount**	**$146,412.50**
120151	TEMPORARY TRAFFIC STRIPE (TAPE)	LF	1	3	12,130.00	$1.97	$23,840.00
		LF	2	4	150,700.00	$1.12	$168,875.00
		LF	3	2	154,700.00	$0.25	$38,675.00
		LF	4	3	13,570.00	$1.87	$25,430.00
		LF	5	1	3,170.00	$2.20	$6,974.00
		LF	6	3	17,750.00	$1.58	$28,037.50
		LF	7	1	7,650.00	$1.40	$10,710.00
		LF	8	2	11,520.00	$1.74	$20,010.00
		LF	9	2	48,900.00	$2.34	$114,570.00
		LF	10	1	5,200.00	$1.00	$5,200.00
	Unit Sub Total	**LF**		**22**	**425,290.00**	**$1.04**	**$442,321.50**
120151	TEMPORARY TRAFFIC STRIPE (TAPE)	M	7	2	4,190.00	$6.60	$27,650.00
	Unit Sub Total	**M**		**2**	**4,190.00**	**$6.60**	**$27,650.00**
	Item Code 120151 Total No. of Proj.			**24**		**Total Amount**	**$469,971.50**
120152	TEMPORARY PAVEMENT MARKING (TAPE)	M2	7	2	45.00	$35.69	$1,606.00
	Unit Sub Total	**M2**		**2**	**45.00**	**$35.69**	**$1,606.00**
120152	TEMPORARY PAVEMENT MARKING (TAPE)	SQFT	1	3	132.00	$33.18	$4,380.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
120152	TEMPORARY PAVEMENT MARKING (TAPE)	SQFT	2	2	3,500.00	$6.66	$23,320.00
		SQFT	3	1	84.00	$35.00	$2,940.00
		SQFT	4	1	24.00	$50.00	$1,200.00
		SQFT	5	2	48.00	$56.50	$2,712.00
		SQFT	6	2	260.00	$7.26	$1,887.50
		SQFT	9	2	558.00	$10.80	$6,027.00
		SQFT	10	1	47.00	$10.00	$470.00
	Unit Sub Total	**SQFT**		**14**	**4,653.00**	**$9.23**	**$42,936.50**
	Item Code 120152 Total No. of Proj.			**16**		**Total Amount**	**$44,542.50**
120159	TEMPORARY TRAFFIC STRIPE (PAINT)	LF	1	7	441,040.00	$0.05	$21,592.50
		LF	2	3	658,200.00	$0.13	$83,040.00
		LF	3	5	1,478,500.00	$0.08	$121,610.00
		LF	4	9	1,864,660.00	$0.17	$308,860.00
		LF	5	1	22,000.00	$1.00	$22,000.00
		LF	6	4	739,000.00	$0.14	$105,080.00
		LF	7	2	350,610.00	$0.16	$56,214.00
		LF	8	3	39,910.00	$0.54	$21,483.20
		LF	9	1	119,000.00	$0.15	$17,850.00
		LF	10	5	17,030.00	$0.87	$14,808.00
		LF	11	5	48,030.00	$0.32	$15,226.00
		LF	12	8	1,827,500.00	$0.27	$485,464.00
	Unit Sub Total	**LF**		**53**	**7,605,480.00**	**$0.17**	**$1,273,227.70**
120159	TEMPORARY TRAFFIC STRIPE (PAINT)	M	2	1	450.00	$3.75	$1,687.50
		M	3	1	26,900.00	$0.50	$13,450.00
		M	4	2	57,000.00	$0.77	$43,975.00
		M	6	1	50,100.00	$0.85	$42,585.00
		M	7	1	6,660.00	$1.00	$6,660.00
		M	11	2	30,830.00	$0.89	$27,421.00
	Unit Sub Total	**M**		**8**	**171,940.00**	**$0.79**	**$135,778.50**
	Item Code 120159 Total No. of Proj.			**61**		**Total Amount**	**$1,409,006.20**
120161	TEMPORARY TRAFFIC STRIPE	LF	4	1	2,550.00	$2.50	$6,375.00
	Unit Sub Total	**LF**		**1**	**2,550.00**	**$2.50**	**$6,375.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 120161 Total No. of Proj.			**1**		**Total Amount**	**$6,375.00**
120165	CHANNELIZER (SURFACE MOUNTED)	EA	1	7	1,092.00	$28.55	$31,175.00
		EA	2	9	14,790.00	$23.41	$346,295.00
		EA	3	9	1,466.00	$26.79	$39,280.00
		EA	4	15	3,463.00	$34.67	$120,059.60
		EA	5	7	461.00	$29.95	$13,809.25
		EA	6	12	1,625.00	$29.27	$47,564.00
		EA	7	12	2,039.00	$20.74	$42,284.00
		EA	8	5	734.00	$28.23	$20,720.00
		EA	9	3	730.00	$30.00	$21,900.00
		EA	10	8	714.00	$27.91	$19,926.00
		EA	11	1	46.00	$40.00	$1,840.00
		EA	12	12	4,077.00	$33.56	$136,825.00
	Unit Sub Total	**EA**		**100**	**31,237.00**	**$26.94**	**$841,677.85**
	Item Code 120165 Total No. of Proj.			**100**		**Total Amount**	**$841,677.85**
120166	CHANNELIZER (SURFACE MOUNTED) (LEFT IN PLACE)	EA	4	1	13.00	$30.00	$390.00
		EA	5	1	25.00	$25.50	$637.50
		EA	7	1	9.00	$60.00	$540.00
		EA	8	1	5.00	$45.00	$225.00
		EA	10	1	10.00	$35.00	$350.00
	Unit Sub Total	**EA**		**5**	**62.00**	**$34.56**	**$2,142.50**
	Item Code 120166 Total No. of Proj.			**5**		**Total Amount**	**$2,142.50**
120182	PORTABLE DELINEATOR	EA	2	1	140.00	$10.00	$1,400.00
		EA	5	1	72.00	$30.00	$2,160.00
		EA	8	2	259.00	$12.85	$3,329.00
	Unit Sub Total	**EA**		**4**	**471.00**	**$14.63**	**$6,889.00**
	Item Code 120182 Total No. of Proj.			**4**		**Total Amount**	**$6,889.00**
120199	TRAFFIC PLASTIC DRUM	EA	1	3	75.00	$44.67	$3,350.00
		EA	2	1	40.00	$50.00	$2,000.00
		EA	3	3	1,082.00	$40.14	$43,430.00
		EA	4	1	290.00	$60.00	$17,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
120199	TRAFFIC PLASTIC DRUM	EA	8	2	304.00	$29.89	$9,088.00
		EA	11	11	945.00	$28.88	$27,288.00
	Unit Sub Total	**EA**		**21**	**2,736.00**	**$37.48**	**$102,556.00**
	Item Code 120199 Total No. of Proj.			**21**		**Total Amount**	**$102,556.00**
120200	FLASHING BEACON (PORTABLE)	EA	1	2	16.00	$437.50	$7,000.00
		EA	5	2	6.00	$2,409.33	$14,456.00
		EA	7	1	12.00	$20.00	$240.00
		EA	8	3	11.00	$1,020.45	$11,225.00
		EA	9	2	8.00	$550.00	$4,400.00
	Unit Sub Total	**EA**		**10**	**53.00**	**$704.17**	**$37,321.00**
	Item Code 120200 Total No. of Proj.			**10**		**Total Amount**	**$37,321.00**
120300	TEMPORARY PAVEMENT MARKER	EA	1	1	400.00	$2.00	$800.00
		EA	2	2	5,860.00	$3.20	$18,740.00
		EA	3	4	22,070.00	$2.85	$62,845.00
		EA	4	9	81,885.00	$2.77	$226,726.00
		EA	6	3	4,510.00	$3.86	$17,400.00
		EA	7	1	11,200.00	$2.00	$22,400.00
		EA	8	3	8,893.00	$3.07	$27,331.00
		EA	10	2	430.00	$3.85	$1,655.00
		EA	11	5	5,470.00	$4.22	$23,063.00
		EA	12	6	79,101.00	$2.72	$214,934.00
	Unit Sub Total	**EA**		**36**	**219,819.00**	**$2.80**	**$615,894.00**
	Item Code 120300 Total No. of Proj.			**36**		**Total Amount**	**$615,894.00**
121161	TEMPORARY TERMINAL SECTION (TYPE K)	EA	2	1	3.00	$2,500.00	$7,500.00
		EA	4	1	16.00	$1,000.00	$16,000.00
		EA	7	1	6.00	$2,000.00	$12,000.00
		EA	12	1	8.00	$1,650.00	$13,200.00
	Unit Sub Total	**EA**		**4**	**33.00**	**$1,475.76**	**$48,700.00**
	Item Code 121161 Total No. of Proj.			**4**		**Total Amount**	**$48,700.00**
128201	TEMPORARY DELINEATOR (CLASS 1)	EA	3	1	640.00	$30.00	$19,200.00
	Unit Sub Total	**EA**		**1**	**640.00**	**$30.00**	**$19,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 128201 Total No. of Proj.			**1**		**Total Amount**	**$19,200.00**
128202	TEMPORARY DELINEATOR (CLASS 2)	EA	3	1	520.00	$32.00	$16,640.00
	Unit Sub Total	**EA**		**1**	**520.00**	**$32.00**	**$16,640.00**
	Item Code 128202 Total No. of Proj.			**1**		**Total Amount**	**$16,640.00**
128601	TEMPORARY SIGNAL SYSTEM	LS	1	1	1.00	$80,000.00	$80,000.00
		LS	2	2	2.00	$81,250.00	$162,500.00
		LS	4	4	4.00	$85,212.85	$340,851.38
		LS	5	2	2.00	$73,650.00	$147,300.00
		LS	6	2	2.00	$138,402.00	$276,804.00
		LS	10	3	3.00	$62,000.00	$186,000.00
	Unit Sub Total	**LS**		**14**	**14.00**	**$85,246.81**	**$1,193,455.38**
	Item Code 128601 Total No. of Proj.			**14**		**Total Amount**	**$1,193,455.38**
128650	PORTABLE CHANGEABLE MESSAGE SIGN	EA	1	20	71.00	$3,191.13	$226,570.00
		EA	2	10	31.00	$3,149.19	$97,625.00
		EA	4	13	71.00	$2,413.28	$171,343.00
		EA	8	36	102.00	$2,066.50	$210,783.00
		EA	11	39	136.00	$3,725.38	$506,651.50
	Unit Sub Total	**EA**		**118**	**411.00**	**$2,951.27**	**$1,212,972.50**
128650	PORTABLE CHANGEABLE MESSAGE SIGN	LS	1	25	25.00	$9,217.52	$230,438.00
		LS	2	34	34.00	$8,813.82	$299,670.00
		LS	3	55	55.00	$7,306.05	$401,833.00
		LS	4	69	69.00	$9,508.77	$656,105.00
		LS	5	45	45.00	$5,343.40	$240,453.00
		LS	6	47	47.00	$10,357.96	$486,824.00
		LS	8	1	1.00	$400.00	$400.00
		LS	9	18	18.00	$6,874.33	$123,738.00
		LS	10	48	48.00	$6,242.15	$299,623.00
		LS	12	28	28.00	$19,358.93	$542,050.00
	Unit Sub Total	**LS**		**370**	**370.00**	**$8,867.93**	**$3,281,134.00**
	Item Code 128650 Total No. of Proj.			**488**		**Total Amount**	**$4,494,106.50**
128660	TEMPORARY FLASHING BEACON	LS	2	1	1.00	$6,500.00	$6,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LS**		**1**	**1.00**	**$6,500.00**	**$6,500.00**
	Item Code 128660	**Total No. of Proj.**			**1**		**Total Amount**	**$6,500.00**
129000	TEMPORARY RAILING (TYPE K)		LF	1	12	11,460.00	$34.16	$391,434.00
			LF	2	8	84,070.00	$16.48	$1,385,877.60
			LF	3	8	292,920.00	$7.47	$2,188,874.00
			LF	4	15	300,380.00	$5.78	$1,737,352.00
			LF	5	6	20,880.00	$12.56	$262,178.00
			LF	6	10	184,580.00	$7.27	$1,342,500.00
			LF	7	7	9,360.00	$16.02	$149,904.00
			LF	8	4	30,940.00	$10.25	$317,064.00
			LF	9	2	5,020.00	$32.95	$165,430.00
			LF	10	7	22,510.00	$9.46	$212,850.00
			LF	11	9	52,780.00	$8.95	$472,430.00
			LF	12	11	421,600.00	$7.31	$3,082,197.50
		Unit Sub Total	**LF**		**99**	**1,436,500.00**	**$8.15**	**$11,708,091.10**
129000	TEMPORARY RAILING (TYPE K)		M	2	1	360.00	$70.00	$25,200.00
			M	3	1	4,230.00	$25.00	$105,750.00
			M	4	3	32,910.00	$17.61	$579,500.00
			M	6	1	120.00	$60.00	$7,200.00
			M	7	5	74,670.00	$34.29	$2,560,300.00
			M	10	1	2,850.00	$50.00	$142,500.00
			M	11	2	19,700.00	$16.41	$323,200.00
		Unit Sub Total	**M**		**14**	**134,840.00**	**$27.76**	**$3,743,650.00**
	Item Code 129000	**Total No. of Proj.**			**113**		**Total Amount**	**$15,451,741.10**
129100	TEMPORARY CRASH CUSHION MODULE		EA	1	4	244.00	$114.70	$27,986.00
			EA	2	6	942.00	$200.74	$189,100.00
			EA	3	7	1,633.00	$133.89	$218,646.00
			EA	4	16	2,895.00	$139.81	$404,755.00
			EA	5	4	243.00	$333.14	$80,953.00
			EA	6	11	1,036.00	$159.86	$165,620.00
			EA	7	12	1,760.00	$208.73	$367,366.00
			EA	8	2	50.00	$271.40	$13,570.00
			EA	10	8	520.00	$191.39	$99,522.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
129100	TEMPORARY CRASH CUSHION MODULE	EA	11	7	984.00	$200.22	$197,016.00
		EA	12	11	3,586.00	$144.72	$518,960.00
	Unit Sub Total	**EA**		**88**	**13,893.00**	**$164.36**	**$2,283,494.00**
	Item Code 129100 Total No. of Proj.			**88**		**Total Amount**	**$2,283,494.00**
129150	TEMPORARY TRAFFIC SCREEN	LF	3	1	13,600.00	$4.75	$64,600.00
		LF	4	2	35,820.00	$2.52	$90,200.00
		LF	5	1	530.00	$5.50	$2,915.00
		LF	7	1	800.00	$2.69	$2,152.00
		LF	10	2	16,000.00	$1.52	$24,380.00
		LF	12	10	261,310.00	$2.02	$528,585.00
	Unit Sub Total	**LF**		**17**	**328,060.00**	**$2.17**	**$712,832.00**
129150	TEMPORARY TRAFFIC SCREEN	M	2	1	220.00	$13.00	$2,860.00
		M	10	1	860.00	$20.00	$17,200.00
	Unit Sub Total	**M**		**2**	**1,080.00**	**$18.57**	**$20,060.00**
	Item Code 129150 Total No. of Proj.			**19**		**Total Amount**	**$732,892.00**
140009	ENVIRONMENTAL PROTECTION (DESERT TORTOISE)	LS	6	1	1.00	$5,500.00	$5,500.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$5,500.00**	**$5,500.00**
	Item Code 140009 Total No. of Proj.			**1**		**Total Amount**	**$5,500.00**
140010	ENVIRONMENTAL PROTECTION (MOHAVE GROUND SQUIRREL)	LS	6	1	1.00	$5,500.00	$5,500.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$5,500.00**	**$5,500.00**
	Item Code 140010 Total No. of Proj.			**1**		**Total Amount**	**$5,500.00**
141101	REMOVE YELLOW PAINTED TRAFFIC STRIPE (HAZARDOUS WASTE)	LF	4	2	4,640.00	$1.42	$6,587.00
		LF	6	1	4,450.00	$0.80	$3,560.00
		LF	7	1	93,600.00	$0.32	$29,952.00
		LF	9	1	50.00	$60.00	$3,000.00
		LF	10	2	3,130.00	$1.09	$3,415.00
		LF	11	8	357,380.00	$0.32	$116,147.50
		LF	12	2	9,210.00	$0.44	$4,010.50
	Unit Sub Total	**LF**		**17**	**472,460.00**	**$0.35**	**$166,672.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
141101	REMOVE YELLOW PAINTED TRAFFIC STRIPE (HAZARDOUS WASTE)	M	11	1	5,630.00	$1.00	$5,630.00
	Unit Sub Total	**M**		**1**	**5,630.00**	**$1.00**	**$5,630.00**
	Item Code 141101 Total No. of Proj.			**18**		**Total Amount**	**$172,302.00**
141103	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE (HAZARDOUS WASTE)	LF	1	9	49,030.00	$1.53	$75,064.00
		LF	2	5	42,140.00	$1.60	$67,559.00
		LF	3	11	304,027.00	$0.56	$170,696.52
		LF	4	37	778,568.00	$0.56	$434,964.60
		LF	5	13	771,190.00	$0.40	$305,204.00
		LF	6	4	8,010.00	$1.63	$13,053.70
		LF	7	26	955,330.00	$0.40	$382,481.50
		LF	8	11	140,320.00	$0.41	$56,916.00
		LF	10	8	178,140.00	$0.43	$76,246.60
		LF	12	15	460,000.00	$0.47	$215,539.80
	Unit Sub Total	**LF**		**139**	**3,686,755.00**	**$0.49**	**$1,797,725.72**
141103	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE (HAZARDOUS WASTE)	LS	12	1	1.00	$61,200.00	$61,200.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$61,200.00**	**$61,200.00**
141103	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE (HAZARDOUS WASTE)	M	2	1	720.00	$7.00	$5,040.00
		M	4	1	3,100.00	$3.00	$9,300.00
		M	7	2	55,140.00	$0.43	$23,532.00
	Unit Sub Total	**M**		**4**	**58,960.00**	**$0.64**	**$37,872.00**
	Item Code 141103 Total No. of Proj.			**144**		**Total Amount**	**$1,896,797.72**
141104	REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING (HAZARDOUS WASTE)	SQFT	1	2	1,310.00	$7.89	$10,340.00
		SQFT	4	3	2,260.00	$1.65	$3,724.40
		SQFT	6	2	965.00	$9.40	$9,070.00
		SQFT	7	4	4,050.00	$2.54	$10,274.00
		SQFT	8	1	100.00	$2.10	$210.00
		SQFT	10	2	4,770.00	$1.61	$7,668.90
		SQFT	12	1	11,400.00	$2.00	$22,800.00
	Unit Sub Total	**SQFT**		**15**	**24,855.00**	**$2.58**	**$64,087.30**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 141104 Total No. of Proj.			**15**		**Total Amount**	**$64,087.30**
146001	CONTRACTOR SUPPLIED BIOLOGIST (DAY)	DAY	12	1	2.00	$2,000.00	$4,000.00
	Unit Sub Total	**DAY**		**1**	**2.00**	**$2,000.00**	**$4,000.00**
	Item Code 146001 Total No. of Proj.			**1**		**Total Amount**	**$4,000.00**
146002	CONTRACTOR SUPPLIED BIOLOGIST (LS)	LS	3	1	1.00	$4,000.00	$4,000.00
		LS	6	3	3.00	$16,366.67	$49,100.00
		LS	9	1	1.00	$8,000.00	$8,000.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$12,220.00**	**$61,100.00**
	Item Code 146002 Total No. of Proj.			**5**		**Total Amount**	**$61,100.00**
146003	NATURAL RESOURCE PROTECTION PLAN	LS	3	2	2.00	$15,000.00	$30,000.00
		LS	7	1	1.00	$3,000.00	$3,000.00
		LS	9	1	1.00	$1,000.00	$1,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$8,500.00**	**$34,000.00**
	Item Code 146003 Total No. of Proj.			**4**		**Total Amount**	**$34,000.00**
146004	FISH PROTECTION	LS	7	1	1.00	$3,000.00	$3,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$3,000.00**	**$3,000.00**
	Item Code 146004 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
148005	NOISE MONITORING	LS	4	31	31.00	$1,527.03	$47,338.00
	Unit Sub Total	**LS**		**31**	**31.00**	**$1,527.03**	**$47,338.00**
	Item Code 148005 Total No. of Proj.			**31**		**Total Amount**	**$47,338.00**
150206	ABANDON CULVERT	EA	1	2	2.00	$2,250.00	$4,500.00
		EA	2	3	3.00	$1,583.33	$4,750.00
		EA	3	5	15.00	$990.40	$14,856.00
		EA	4	4	42.00	$482.74	$20,275.00
		EA	5	2	37.00	$775.41	$28,690.00
		EA	6	1	14.00	$1,200.00	$16,800.00
		EA	10	1	2.00	$950.00	$1,900.00
		EA	11	2	16.00	$920.63	$14,730.00
	Unit Sub Total	**EA**		**20**	**131.00**	**$812.98**	**$106,501.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150206	ABANDON CULVERT		LF	1	1	56.00	$39.50	$2,212.00
			LF	2	2	350.00	$37.49	$13,120.00
			LF	4	6	2,109.00	$26.34	$55,555.00
			LF	5	1	190.00	$20.00	$3,800.00
			LF	10	1	160.00	$10.00	$1,600.00
			LF	12	4	2,920.00	$20.33	$59,350.00
		Unit Sub Total	**LF**		**15**	**5,785.00**	**$23.45**	**$135,637.00**
150206	ABANDON CULVERT		M	2	1	40.00	$100.00	$4,000.00
			M	4	1	72.00	$25.00	$1,800.00
			M	7	1	7.00	$60.00	$420.00
		Unit Sub Total	**M**		**3**	**119.00**	**$52.27**	**$6,220.00**
	Item Code 150206	**Total No. of Proj.**			**38**		**Total Amount**	**$248,358.00**
150221	ABANDON INLET		EA	3	2	11.00	$540.15	$5,941.60
			EA	4	3	38.00	$794.74	$30,200.00
			EA	11	1	10.00	$765.00	$7,650.00
			EA	12	2	33.00	$522.73	$17,250.00
		Unit Sub Total	**EA**		**8**	**92.00**	**$663.50**	**$61,041.60**
	Item Code 150221	**Total No. of Proj.**			**8**		**Total Amount**	**$61,041.60**
150224	ABANDON MANHOLE		EA	3	1	2.00	$739.20	$1,478.40
			EA	4	3	9.00	$1,050.00	$9,450.00
			EA	7	1	1.00	$1,785.00	$1,785.00
		Unit Sub Total	**EA**		**5**	**12.00**	**$1,059.45**	**$12,713.40**
	Item Code 150224	**Total No. of Proj.**			**5**		**Total Amount**	**$12,713.40**
150227	ABANDON PIPELINE		EA	2	1	2.00	$500.00	$1,000.00
			EA	7	2	9.00	$1,026.11	$9,235.00
			EA	12	1	11.00	$200.00	$2,200.00
		Unit Sub Total	**EA**		**4**	**22.00**	**$565.23**	**$12,435.00**
150227	ABANDON PIPELINE		LF	1	1	150.00	$25.00	$3,750.00
			LF	6	1	200.00	$18.00	$3,600.00
		Unit Sub Total	**LF**		**2**	**350.00**	**$21.00**	**$7,350.00**
150227	ABANDON PIPELINE		M	7	1	64.00	$20.00	$1,280.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M**		**1**	**64.00**	**$20.00**	**$1,280.00**
	Item Code 150227	**Total No. of Proj.**			**7**		**Total Amount**	**$21,065.00**
150229	ABANDON WATER WELL		EA	3	1	2.00	$7,500.00	$15,000.00
			EA	4	1	5.00	$1,500.00	$7,500.00
		Unit Sub Total	**EA**		**2**	**7.00**	**$3,214.29**	**$22,500.00**
	Item Code 150229	**Total No. of Proj.**			**2**		**Total Amount**	**$22,500.00**
150305	OBLITERATE SURFACING		M2	4	1	7,000.00	$0.01	$70.00
		Unit Sub Total	**M2**		**1**	**7,000.00**	**$0.01**	**$70.00**
150305	OBLITERATE SURFACING		SQYD	3	3	6,818.00	$1.47	$10,042.00
			SQYD	10	1	5,330.00	$1.00	$5,330.00
		Unit Sub Total	**SQYD**		**4**	**12,148.00**	**$1.27**	**$15,372.00**
	Item Code 150305	**Total No. of Proj.**			**5**		**Total Amount**	**$15,442.00**
150604	REMOVE WOOD FENCE		LF	4	1	200.00	$7.00	$1,400.00
			LF	5	1	24.00	$6.00	$144.00
		Unit Sub Total	**LF**		**2**	**224.00**	**$6.89**	**$1,544.00**
150604	REMOVE WOOD FENCE		M	7	1	89.00	$32.00	$2,848.00
		Unit Sub Total	**M**		**1**	**89.00**	**$32.00**	**$2,848.00**
	Item Code 150604	**Total No. of Proj.**			**3**		**Total Amount**	**$4,392.00**
150605	REMOVE FENCE		LF	2	1	130.00	$5.00	$650.00
			LF	3	2	670.00	$8.66	$5,803.00
			LF	4	4	21,940.00	$4.28	$93,920.00
			LF	5	1	36,000.00	$0.50	$18,000.00
			LF	10	2	9,090.00	$1.47	$13,345.00
		Unit Sub Total	**LF**		**10**	**67,830.00**	**$1.94**	**$131,718.00**
150605	REMOVE FENCE		M	4	1	200.00	$18.00	$3,600.00
			M	6	1	140.00	$10.00	$1,400.00
			M	11	1	670.00	$6.60	$4,422.00
		Unit Sub Total	**M**		**3**	**1,010.00**	**$9.33**	**$9,422.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 150605 Total No. of Proj.			**13**		**Total Amount**	**$141,140.00**
150606	REMOVE FENCE (TYPE BW)	LF	4	3	1,240.00	$3.08	$3,820.00
		LF	5	2	650.00	$3.01	$1,958.00
		LF	6	1	7,180.00	$2.00	$14,360.00
		LF	8	1	180.00	$3.00	$540.00
		LF	9	1	16,800.00	$2.00	$33,600.00
		LF	10	1	12,100.00	$0.77	$9,317.00
	Unit Sub Total	**LF**		**9**	**38,150.00**	**$1.67**	**$63,595.00**
150606	REMOVE FENCE (TYPE BW)	M	6	1	14,900.00	$1.00	$14,900.00
	Unit Sub Total	**M**		**1**	**14,900.00**	**$1.00**	**$14,900.00**
	Item Code 150606 Total No. of Proj.			**10**		**Total Amount**	**$78,495.00**
150607	REMOVE FENCE (TYPE WM)	LF	1	1	510.00	$2.00	$1,020.00
		LF	4	1	370.00	$3.30	$1,221.00
		LF	6	1	1,560.00	$2.00	$3,120.00
	Unit Sub Total	**LF**		**3**	**2,440.00**	**$2.20**	**$5,361.00**
	Item Code 150607 Total No. of Proj.			**3**		**Total Amount**	**$5,361.00**
150608	REMOVE CHAIN LINK FENCE	LF	3	2	1,150.00	$4.73	$5,440.00
		LF	4	4	2,400.00	$3.81	$9,132.80
		LF	5	1	1,300.00	$5.00	$6,500.00
		LF	6	3	74.00	$37.19	$2,752.00
		LF	8	1	750.00	$2.50	$1,875.00
		LF	11	2	1,635.00	$2.28	$3,720.00
		LF	12	5	19,540.00	$5.67	$110,874.00
	Unit Sub Total	**LF**		**18**	**26,849.00**	**$5.23**	**$140,293.80**
150608	REMOVE CHAIN LINK FENCE	M	4	1	6,420.00	$6.00	$38,520.00
		M	7	4	8,100.00	$10.27	$83,160.00
	Unit Sub Total	**M**		**5**	**14,520.00**	**$8.38**	**$121,680.00**
	Item Code 150608 Total No. of Proj.			**23**		**Total Amount**	**$261,973.80**
150615	REMOVE ENTRANCE TAPER	EA	2	1	8.00	$5,000.00	$40,000.00
		EA	3	2	2.00	$235.00	$470.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**3**	**10.00**	**$4,047.00**	**$40,470.00**
	Item Code 150615	**Total No. of Proj.**			**3**		**Total Amount**	**$40,470.00**
150620	REMOVE GATE		EA	3	3	4.00	$468.75	$1,875.00
			EA	4	1	2.00	$250.00	$500.00
			EA	6	1	1.00	$400.00	$400.00
			EA	7	1	1.00	$300.00	$300.00
			EA	12	1	3.00	$100.00	$300.00
		Unit Sub Total	**EA**		**7**	**11.00**	**$306.82**	**$3,375.00**
150620	REMOVE GATE		LS	12	1	1.00	$1,000.00	$1,000.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$1,000.00**	**$1,000.00**
	Item Code 150620	**Total No. of Proj.**			**8**		**Total Amount**	**$4,375.00**
150630	REMOVE MARKER		EA	1	1	4.00	$10.00	$40.00
			EA	2	7	174.00	$33.80	$5,882.00
			EA	4	2	205.00	$5.50	$1,126.50
			EA	6	1	8.00	$5.00	$40.00
			EA	8	1	17.00	$45.00	$765.00
			EA	9	2	11.00	$7.27	$80.00
			EA	10	4	653.00	$13.00	$8,490.00
		Unit Sub Total	**EA**		**18**	**1,072.00**	**$15.32**	**$16,423.50**
	Item Code 150630	**Total No. of Proj.**			**18**		**Total Amount**	**$16,423.50**
150645	REMOVE BARRICADE		EA	11	1	62.00	$15.00	$930.00
		Unit Sub Total	**EA**		**1**	**62.00**	**$15.00**	**$930.00**
	Item Code 150645	**Total No. of Proj.**			**1**		**Total Amount**	**$930.00**
150646	REMOVE PEDESTRIAN BARRICADE		EA	4	1	4.00	$80.00	$320.00
			EA	11	1	16.00	$120.00	$1,920.00
		Unit Sub Total	**EA**		**2**	**20.00**	**$112.00**	**$2,240.00**
	Item Code 150646	**Total No. of Proj.**			**2**		**Total Amount**	**$2,240.00**
150655	REMOVE BARRIER		LF	4	1	3,800.00	$15.00	$57,000.00
			LF	7	1	4.00	$1,000.00	$4,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150655	REMOVE BARRIER		LF	10	1	16.00	$204.00	$3,264.00
		Unit Sub Total	**LF**		**3**	**3,820.00**	**$16.82**	**$64,264.00**
	Item Code 150655	**Total No. of Proj.**			**3**		**Total Amount**	**$64,264.00**
150656	REMOVE CABLE BARRIER		LF	2	1	5,150.00	$4.00	$20,600.00
		Unit Sub Total	**LF**		**1**	**5,150.00**	**$4.00**	**$20,600.00**
	Item Code 150656	**Total No. of Proj.**			**1**		**Total Amount**	**$20,600.00**
150659	REMOVE TERMINAL SECTION		EA	6	1	2.00	$250.00	$500.00
		Unit Sub Total	**EA**		**1**	**2.00**	**$250.00**	**$500.00**
	Item Code 150659	**Total No. of Proj.**			**1**		**Total Amount**	**$500.00**
150662	REMOVE METAL BEAM GUARD RAILING		LF	1	8	35,020.00	$6.02	$210,649.50
			LF	2	14	81,920.00	$5.84	$478,622.50
			LF	3	14	101,210.00	$4.44	$449,798.90
			LF	4	17	54,205.00	$9.38	$508,412.50
			LF	5	7	2,080.00	$10.43	$21,695.00
			LF	6	11	9,560.00	$9.69	$92,650.00
			LF	7	6	7,831.00	$5.85	$45,804.00
			LF	8	3	3,000.00	$3.95	$11,840.00
			LF	10	9	13,255.00	$6.02	$79,750.00
			LF	11	5	5,872.00	$9.44	$55,440.00
			LF	12	11	20,452.00	$7.43	$151,971.00
		Unit Sub Total	**LF**		**105**	**334,405.00**	**$6.30**	**$2,106,633.40**
150662	REMOVE METAL BEAM GUARD RAILING		M	2	1	120.00	$100.00	$12,000.00
			M	3	1	450.00	$10.00	$4,500.00
			M	4	3	4,260.00	$14.48	$61,680.00
			M	7	4	5,080.00	$23.32	$118,480.00
			M	10	1	340.00	$25.00	$8,500.00
			M	11	1	210.00	$25.00	$5,250.00
		Unit Sub Total	**M**		**11**	**10,460.00**	**$20.12**	**$210,410.00**
	Item Code 150662	**Total No. of Proj.**			**116**		**Total Amount**	**$2,317,043.40**
150667	REMOVE DOUBLE METAL BEAM BARRIER		LF	5	1	88.00	$20.00	$1,760.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**1**	**88.00**	**$20.00**	**$1,760.00**
	Item Code 150667	**Total No. of Proj.**			**1**		**Total Amount**	**$1,760.00**
150668	REMOVE FLARED END SECTION		EA	1	1	2.00	$500.00	$1,000.00
			EA	2	4	11.00	$187.27	$2,060.00
			EA	3	5	79.00	$186.63	$14,744.00
			EA	4	6	24.00	$383.96	$9,215.00
			EA	5	2	10.00	$268.00	$2,680.00
			EA	6	2	23.00	$513.04	$11,800.00
			EA	7	2	2.00	$492.50	$985.00
			EA	10	1	9.00	$167.00	$1,503.00
			EA	12	1	7.00	$400.00	$2,800.00
		Unit Sub Total	**EA**		**24**	**167.00**	**$280.16**	**$46,787.00**
	Item Code 150668	**Total No. of Proj.**			**24**		**Total Amount**	**$46,787.00**
150676	REMOVE CABLE RAILING		LF	12	1	960.00	$2.80	$2,688.00
		Unit Sub Total	**LF**		**1**	**960.00**	**$2.80**	**$2,688.00**
	Item Code 150676	**Total No. of Proj.**			**1**		**Total Amount**	**$2,688.00**
150685	REMOVE IRRIGATION FACILITY		LF	3	1	1,270.00	$5.00	$6,350.00
		Unit Sub Total	**LF**		**1**	**1,270.00**	**$5.00**	**$6,350.00**
150685	REMOVE IRRIGATION FACILITY		LS	4	1	1.00	$3,000.00	$3,000.00
			LS	6	2	2.00	$12,500.00	$25,000.00
			LS	12	1	1.00	$23,200.00	$23,200.00
		Unit Sub Total	**LS**		**4**	**4.00**	**$12,800.00**	**$51,200.00**
	Item Code 150685	**Total No. of Proj.**			**5**		**Total Amount**	**$57,550.00**
150686	REMOVE IRRIGATION SYSTEM		LS	2	1	1.00	$1,500.00	$1,500.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$1,500.00**	**$1,500.00**
	Item Code 150686	**Total No. of Proj.**			**1**		**Total Amount**	**$1,500.00**
150701	REMOVE YELLOW PAINTED TRAFFIC STRIPE		LF	4	1	57,800.00	$0.32	$18,496.00
			LF	11	2	80,340.00	$0.49	$39,545.00
			LF	12	1	250.00	$0.45	$112.50

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**4**	**138,390.00**	**$0.42**	**$58,153.50**
150701	REMOVE YELLOW PAINTED TRAFFIC STRIPE	M	6	2	24,640.00	$0.58	$14,385.00
		M	7	1	8,760.00	$1.58	$13,840.80
		M	10	1	1,080.00	$2.60	$2,808.00
	Unit Sub Total	**M**		**4**	**34,480.00**	**$0.90**	**$31,033.80**
	Item Code 150701 Total No. of Proj.			**8**		**Total Amount**	**$89,187.30**
150704	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE	LF	2	1	400.00	$4.25	$1,700.00
		LF	4	2	58,320.00	$0.37	$21,348.00
		LF	5	1	3,110.00	$0.60	$1,866.00
		LF	6	1	1,000.00	$6.00	$6,000.00
		LF	10	3	12,460.00	$1.04	$12,972.00
		LF	12	3	144,150.00	$0.24	$33,925.00
	Unit Sub Total	**LF**		**11**	**219,440.00**	**$0.35**	**$77,811.00**
150704	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE	M	3	1	160.00	$10.00	$1,600.00
		M	4	2	10,010.00	$1.64	$16,375.00
		M	7	3	31,026.00	$0.82	$25,321.20
		M	10	1	7,490.00	$2.60	$19,474.00
	Unit Sub Total	**M**		**7**	**48,686.00**	**$1.29**	**$62,770.20**
150704	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE	SQFT	11	1	940.00	$2.00	$1,880.00
	Unit Sub Total	**SQFT**		**1**	**940.00**	**$2.00**	**$1,880.00**
	Item Code 150704 Total No. of Proj.			**19**		**Total Amount**	**$142,461.20**
150705	REMOVE YELLOW THERMOPLASTIC PAVEMENT MARKING	SQFT	1	1	320.00	$12.00	$3,840.00
		SQFT	2	1	270.00	$15.00	$4,050.00
		SQFT	12	1	240.00	$1.50	$360.00
	Unit Sub Total	**SQFT**		**3**	**830.00**	**$9.94**	**$8,250.00**
	Item Code 150705 Total No. of Proj.			**3**		**Total Amount**	**$8,250.00**
150710	REMOVE TRAFFIC STRIPE	LF	3	2	13,260.00	$0.55	$7,320.00
		LF	4	1	2,110.00	$1.25	$2,637.50
		LF	5	1	4,560.00	$0.55	$2,508.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150710	REMOVE TRAFFIC STRIPE		LF	7	2	27,720.00	$0.74	$20,386.00
			LF	11	2	221,000.00	$0.43	$95,960.00
			LF	12	1	2,200.00	$0.70	$1,540.00
		Unit Sub Total	**LF**		**9**	**270,850.00**	**$0.48**	**$130,351.50**
150710	REMOVE TRAFFIC STRIPE		M	7	1	74,000.00	$0.40	$29,600.00
			M	11	1	15,400.00	$1.50	$23,100.00
		Unit Sub Total	**M**		**2**	**89,400.00**	**$0.59**	**$52,700.00**
150710	REMOVE TRAFFIC STRIPE		SQFT	11	1	19,300.00	$0.55	$10,615.00
		Unit Sub Total	**SQFT**		**1**	**19,300.00**	**$0.55**	**$10,615.00**
	Item Code 150710	**Total No. of Proj.**			**12**		**Total Amount**	**$193,666.50**
150711	REMOVE PAINTED TRAFFIC STRIPE		LF	2	2	9,630.00	$0.96	$9,228.00
			LF	3	1	1,240,000.00	$0.35	$434,000.00
			LF	4	6	239,860.00	$0.45	$109,011.00
			LF	5	7	253,990.00	$0.28	$69,932.00
			LF	6	7	400,720.00	$0.36	$142,345.00
			LF	7	2	107,000.00	$0.09	$10,040.00
			LF	9	4	28,180.00	$1.41	$39,746.80
			LF	10	2	10,040.00	$0.83	$8,337.10
			LF	11	15	1,406,320.00	$0.17	$234,604.50
			LF	12	8	238,990.00	$0.33	$80,053.60
		Unit Sub Total	**LF**		**54**	**3,934,730.00**	**$0.29**	**$1,137,298.00**
150711	REMOVE PAINTED TRAFFIC STRIPE		M	2	1	260.00	$4.00	$1,040.00
			M	4	2	11,640.00	$1.84	$21,460.00
			M	6	1	24,000.00	$0.55	$13,200.00
			M	7	2	23,950.00	$1.26	$30,203.00
			M	10	1	590.00	$1.70	$1,003.00
			M	11	1	7,200.00	$2.20	$15,840.00
		Unit Sub Total	**M**		**8**	**67,640.00**	**$1.22**	**$82,746.00**
150711	REMOVE PAINTED TRAFFIC STRIPE		SQFT	11	1	4,830.00	$2.00	$9,660.00
		Unit Sub Total	**SQFT**		**1**	**4,830.00**	**$2.00**	**$9,660.00**
	Item Code 150711	**Total No. of Proj.**			**63**		**Total Amount**	**$1,229,704.00**
150712	REMOVE PAINTED PAVEMENT MARKING		LF	12	1	650.00	$1.25	$812.50

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**1**	**650.00**	**$1.25**	**$812.50**
150712	REMOVE PAINTED PAVEMENT MARKING		M2	4	1	410.00	$23.00	$9,430.00
			M2	6	1	50.00	$41.00	$2,050.00
		Unit Sub Total	**M2**		**2**	**460.00**	**$24.96**	**$11,480.00**
150712	REMOVE PAINTED PAVEMENT MARKING		SQFT	2	1	130.00	$5.00	$650.00
			SQFT	4	5	6,665.00	$2.51	$16,720.00
			SQFT	6	2	3,652.00	$1.59	$5,800.00
			SQFT	9	2	3,640.00	$6.80	$24,738.00
			SQFT	12	5	3,020.00	$1.91	$5,756.20
		Unit Sub Total	**SQFT**		**15**	**17,107.00**	**$3.14**	**$53,664.20**
	Item Code 150712	**Total No. of Proj.**			**18**		**Total Amount**	**$65,956.70**
150713	REMOVE PAVEMENT MARKING		M2	4	1	4.00	$50.00	$200.00
			M2	7	2	704.00	$20.21	$14,230.00
			M2	11	1	110.00	$15.00	$1,650.00
		Unit Sub Total	**M2**		**4**	**818.00**	**$19.66**	**$16,080.00**
150713	REMOVE PAVEMENT MARKING		SQFT	2	2	1,010.00	$4.63	$4,673.00
			SQFT	3	1	260.00	$2.50	$650.00
			SQFT	6	1	44.00	$10.00	$440.00
			SQFT	7	2	1,060.00	$2.11	$2,233.00
			SQFT	8	2	7,000.00	$1.69	$11,805.00
			SQFT	10	1	130.00	$2.04	$265.20
			SQFT	11	4	1,134.00	$4.12	$4,670.00
			SQFT	12	1	770.00	$2.60	$2,002.00
		Unit Sub Total	**SQFT**		**14**	**11,408.00**	**$2.34**	**$26,738.20**
	Item Code 150713	**Total No. of Proj.**			**18**		**Total Amount**	**$42,818.20**
150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE		LF	1	11	69,580.00	$0.90	$62,769.00
			LF	2	10	119,760.00	$0.68	$81,888.00
			LF	3	11	151,932.00	$0.42	$63,950.02
			LF	4	35	777,986.00	$0.37	$289,773.40
			LF	5	18	939,300.00	$0.27	$248,923.20
			LF	6	18	100,264.00	$0.63	$63,429.60
			LF	7	21	643,700.00	$0.31	$201,835.50

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE	LF	8	14	507,620.00	$0.24	$123,786.00
		LF	10	21	331,572.00	$0.35	$114,640.70
		LF	11	7	14,060.00	$0.76	$10,745.00
		LF	12	20	1,704,940.00	$0.22	$377,249.60
	Unit Sub Total	**LF**		**186**	**5,360,714.00**	**$0.31**	**$1,638,990.02**
150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE	M	2	1	96.00	$4.00	$384.00
		M	4	3	13,770.00	$1.91	$26,275.00
		M	7	4	44,370.00	$0.96	$42,684.00
		M	10	1	6,220.00	$1.65	$10,263.00
	Unit Sub Total	**M**		**9**	**64,456.00**	**$1.24**	**$79,606.00**
150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE	SQFT	11	1	1,000.00	$0.27	$270.00
	Unit Sub Total	**SQFT**		**1**	**1,000.00**	**$0.27**	**$270.00**
	Item Code 150714 Total No. of Proj.			**196**		**Total Amount**	**$1,718,866.02**
150715	REMOVE THERMOPLASTIC PAVEMENT MARKING	LF	5	1	120.00	$4.00	$480.00
		LF	7	1	240.00	$2.50	$600.00
	Unit Sub Total	**LF**		**2**	**360.00**	**$3.00**	**$1,080.00**
150715	REMOVE THERMOPLASTIC PAVEMENT MARKING	M2	3	1	1.40	$25.00	$35.00
		M2	4	1	20.00	$100.00	$2,000.00
		M2	7	2	65.00	$33.78	$2,195.50
		M2	10	1	130.00	$25.00	$3,250.00
		M2	11	1	16.00	$33.00	$528.00
	Unit Sub Total	**M2**		**6**	**232.40**	**$34.46**	**$8,008.50**
150715	REMOVE THERMOPLASTIC PAVEMENT MARKING	SQFT	1	9	17,290.00	$3.37	$58,339.00
		SQFT	2	14	17,316.00	$2.88	$49,929.70
		SQFT	3	9	7,378.00	$2.81	$20,742.50
		SQFT	4	27	29,368.00	$2.57	$75,506.70
		SQFT	5	18	24,904.00	$1.87	$46,574.60
		SQFT	6	17	18,900.00	$2.42	$45,722.50
		SQFT	7	15	22,921.00	$1.72	$39,422.50
		SQFT	8	9	7,235.00	$1.97	$14,258.50
		SQFT	9	1	220.00	$10.50	$2,310.00
		SQFT	10	20	34,433.00	$1.86	$63,922.10
		SQFT	11	11	13,520.00	$2.22	$30,064.50

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150715	REMOVE THERMOPLASTIC PAVEMENT MARKING	SQFT	12	15	24,480.00	$1.64	$40,225.70
	Unit Sub Total	**SQFT**		**165**	**217,965.00**	**$2.23**	**$487,018.30**
	Item Code 150715 Total No. of Proj.			**173**		**Total Amount**	**$496,106.80**
150717	REMOVE TRAFFIC STRIPE AND PAVEMENT MARKING	SQFT	11	1	190.00	$2.00	$380.00
	Unit Sub Total	**SQFT**		**1**	**190.00**	**$2.00**	**$380.00**
	Item Code 150717 Total No. of Proj.			**1**		**Total Amount**	**$380.00**
150718	REMOVE THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING	SQFT	3	2	3,620.00	$3.49	$12,650.00
	Unit Sub Total	**SQFT**		**2**	**3,620.00**	**$3.49**	**$12,650.00**
	Item Code 150718 Total No. of Proj.			**2**		**Total Amount**	**$12,650.00**
150720	REMOVE CONTRAST TREATMENT	SQFT	2	2	2,009.00	$0.83	$1,677.00
		SQFT	3	2	36,440.00	$0.36	$13,254.00
		SQFT	4	2	8,416.00	$0.48	$4,038.24
		SQFT	6	1	5,890.00	$0.44	$2,591.60
		SQFT	7	2	40,454.00	$0.17	$6,918.90
		SQFT	10	1	11,264.00	$0.60	$6,758.40
		SQFT	11	3	37,286.00	$0.44	$16,542.14
	Unit Sub Total	**SQFT**		**13**	**141,759.00**	**$0.37**	**$51,780.28**
	Item Code 150720 Total No. of Proj.			**13**		**Total Amount**	**$51,780.28**
150722	REMOVE PAVEMENT MARKER	EA	1	3	1,546.00	$1.24	$1,910.00
		EA	2	5	1,897.00	$4.70	$8,911.00
		EA	3	2	343.00	$1.00	$343.00
		EA	4	45	175,877.00	$0.68	$120,170.10
		EA	5	10	42,496.00	$0.73	$30,916.00
		EA	6	11	28,750.00	$0.77	$22,265.20
		EA	7	36	397,105.00	$0.79	$315,024.90
		EA	8	21	99,452.00	$0.87	$86,677.00
		EA	9	2	1,640.00	$4.05	$6,634.00
		EA	10	15	33,538.00	$1.13	$37,768.40
		EA	11	3	31,063.00	$0.61	$19,103.00
		EA	12	20	160,728.00	$0.63	$101,555.20

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**173**	**974,435.00**	**$0.77**	**$751,277.80**
150722	REMOVE PAVEMENT MARKER		LF	6	1	20.00	$2.00	$40.00
		Unit Sub Total	**LF**		**1**	**20.00**	**$2.00**	**$40.00**
150722	REMOVE PAVEMENT MARKER		LS	8	1	1.00	$3,500.00	$3,500.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$3,500.00**	**$3,500.00**
	Item Code 150722	**Total No. of Proj.**			**175**		**Total Amount**	**$754,817.80**
150730	REMOVE CHANNELIZERS		EA	4	2	21.00	$8.81	$185.00
			EA	7	2	194.00	$8.25	$1,600.00
			EA	10	1	10.00	$50.00	$500.00
			EA	11	2	70.00	$7.57	$530.00
			EA	12	1	100.00	$10.00	$1,000.00
		Unit Sub Total	**EA**		**8**	**395.00**	**$9.66**	**$3,815.00**
	Item Code 150730	**Total No. of Proj.**			**8**		**Total Amount**	**$3,815.00**
150742	REMOVE ROADSIDE SIGN		EA	1	1	6.00	$300.00	$1,800.00
			EA	2	15	166.00	$115.83	$19,228.00
			EA	3	10	288.00	$56.58	$16,295.00
			EA	4	11	367.00	$94.73	$34,767.20
			EA	5	6	52.00	$70.90	$3,687.00
			EA	6	11	49.00	$111.27	$5,452.00
			EA	7	6	169.00	$120.27	$20,325.00
			EA	8	1	3.00	$300.00	$900.00
			EA	9	2	23.00	$78.70	$1,810.00
			EA	10	5	119.00	$66.07	$7,862.00
			EA	11	12	184.00	$96.53	$17,762.00
			EA	12	10	418.00	$126.45	$52,857.45
		Unit Sub Total	**EA**		**90**	**1,844.00**	**$99.10**	**$182,745.65**
	Item Code 150742	**Total No. of Proj.**			**90**		**Total Amount**	**$182,745.65**
150744	REMOVE ROADSIDE SIGN (WOOD POST)		EA	2	1	6.00	$250.00	$1,500.00
			EA	4	5	38.00	$108.49	$4,122.50
			EA	7	1	2.00	$100.00	$200.00
			EA	8	2	8.00	$81.25	$650.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150744	REMOVE ROADSIDE SIGN (WOOD POST)	EA	9	2	9.00	$100.00	$900.00
		EA	10	1	6.00	$100.00	$600.00
		EA	12	1	7.00	$100.00	$700.00
	Unit Sub Total	**EA**		**13**	**76.00**	**$114.11**	**$8,672.50**
	Item Code 150744 Total No. of Proj.			**13**		**Total Amount**	**$8,672.50**
150745	REMOVE ROADSIDE SIGN (METAL POST)	EA	4	3	28.00	$90.63	$2,537.50
		EA	7	2	4.00	$85.25	$341.00
		EA	12	1	3.00	$150.00	$450.00
	Unit Sub Total	**EA**		**6**	**35.00**	**$95.10**	**$3,328.50**
	Item Code 150745 Total No. of Proj.			**6**		**Total Amount**	**$3,328.50**
150747	REMOVE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD)	EA	2	1	1.00	$140.00	$140.00
		EA	3	1	4.00	$53.00	$212.00
		EA	4	3	117.00	$50.85	$5,950.00
		EA	6	1	1.00	$80.00	$80.00
		EA	7	1	2.00	$50.00	$100.00
		EA	12	4	40.00	$160.00	$6,400.00
	Unit Sub Total	**EA**		**11**	**165.00**	**$78.07**	**$12,882.00**
	Item Code 150747 Total No. of Proj.			**11**		**Total Amount**	**$12,882.00**
150748	REMOVE ROADSIDE SIGN PANEL	EA	3	1	2.00	$50.00	$100.00
		EA	4	2	6.00	$83.33	$500.00
		EA	8	1	1.00	$50.00	$50.00
		EA	10	1	1.00	$40.00	$40.00
		EA	12	2	17.00	$105.88	$1,800.00
	Unit Sub Total	**EA**		**7**	**27.00**	**$92.22**	**$2,490.00**
	Item Code 150748 Total No. of Proj.			**7**		**Total Amount**	**$2,490.00**
150760	REMOVE SIGN STRUCTURE	EA	2	2	3.00	$4,666.67	$14,000.00
		EA	3	2	4.00	$2,700.00	$10,800.00
		EA	4	4	12.00	$5,287.83	$63,454.00
		EA	6	2	7.00	$2,857.14	$20,000.00
		EA	7	10	58.00	$3,008.62	$174,500.00
		EA	8	3	3.00	$4,166.67	$12,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150760	REMOVE SIGN STRUCTURE	EA	10	1	4.00	$1,989.00	$7,956.00
		EA	11	2	6.00	$4,500.00	$27,000.00
		EA	12	6	44.00	$5,057.27	$222,520.00
	Unit Sub Total	**EA**		**32**	**141.00**	**$3,920.07**	**$552,730.00**
	Item Code 150760 Total No. of Proj.			**32**		**Total Amount**	**$552,730.00**
150761	REMOVE SIGN PANEL AND REMOVABLE SIGN PANEL FRAME	EA	8	1	2.00	$500.00	$1,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$500.00**	**$1,000.00**
	Item Code 150761 Total No. of Proj.			**1**		**Total Amount**	**$1,000.00**
150763	REMOVE SIGN PANEL	EA	4	1	1.00	$220.00	$220.00
		EA	8	1	1.00	$500.00	$500.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$360.00**	**$720.00**
	Item Code 150763 Total No. of Proj.			**2**		**Total Amount**	**$720.00**
150764	REMOVE SIGN OVERLAY	SQFT	4	1	8.00	$8.00	$64.00
	Unit Sub Total	**SQFT**		**1**	**8.00**	**$8.00**	**$64.00**
	Item Code 150764 Total No. of Proj.			**1**		**Total Amount**	**$64.00**
150767	REMOVE BRIDGE MOUNTED SIGN	EA	3	2	4.00	$2,700.00	$10,800.00
		EA	7	3	11.00	$1,779.09	$19,570.00
		EA	8	1	1.00	$5,000.00	$5,000.00
	Unit Sub Total	**EA**		**6**	**16.00**	**$2,210.63**	**$35,370.00**
	Item Code 150767 Total No. of Proj.			**6**		**Total Amount**	**$35,370.00**
150769	REMOVE ASPHALT CONCRETE	CY	4	1	20.00	$176.00	$3,520.00
		CY	7	1	6.00	$250.00	$1,500.00
		CY	8	2	847.00	$66.12	$56,007.00
	Unit Sub Total	**CY**		**4**	**873.00**	**$69.90**	**$61,027.00**
150769	REMOVE ASPHALT CONCRETE	M2	7	1	26.00	$50.00	$1,300.00
	Unit Sub Total	**M2**		**1**	**26.00**	**$50.00**	**$1,300.00**
150769	REMOVE ASPHALT CONCRETE	SQFT	5	1	740.00	$6.00	$4,440.00
		SQFT	12	1	1,100.00	$2.00	$2,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**SQFT**		**2**	**1,840.00**	**$3.61**	**$6,640.00**
150769	REMOVE ASPHALT CONCRETE		SQYD	3	1	460.00	$62.00	$28,520.00
		Unit Sub Total	**SQYD**		**1**	**460.00**	**$62.00**	**$28,520.00**
	Item Code 150769	**Total No. of Proj.**			**8**		**Total Amount**	**$97,487.00**
150771	REMOVE ASPHALT CONCRETE DIKE		LF	1	7	55,894.00	$3.06	$171,145.60
			LF	2	5	84,230.00	$3.35	$282,232.50
			LF	3	17	306,111.00	$0.77	$234,336.10
			LF	4	22	96,093.00	$2.63	$252,362.70
			LF	5	3	89,340.00	$1.04	$92,505.00
			LF	6	13	69,000.00	$1.05	$72,297.50
			LF	7	6	5,236.00	$2.66	$13,930.00
			LF	8	3	10,690.00	$2.27	$24,280.00
			LF	10	4	124,800.00	$0.29	$35,676.00
			LF	11	7	194,950.00	$0.56	$110,025.00
			LF	12	5	1,002.00	$6.50	$6,510.00
		Unit Sub Total	**LF**		**92**	**1,037,346.00**	**$1.25**	**$1,295,300.40**
150771	REMOVE ASPHALT CONCRETE DIKE		M	2	1	410.00	$10.00	$4,100.00
			M	6	1	39.00	$18.00	$702.00
			M	7	2	580.00	$6.86	$3,980.00
			M	11	1	9,400.00	$1.10	$10,340.00
		Unit Sub Total	**M**		**5**	**10,429.00**	**$1.83**	**$19,122.00**
	Item Code 150771	**Total No. of Proj.**			**97**		**Total Amount**	**$1,314,422.40**
150772	REMOVE CURB		LF	6	2	567.00	$4.20	$2,380.00
			LF	7	1	210.00	$7.00	$1,470.00
		Unit Sub Total	**LF**		**3**	**777.00**	**$4.95**	**$3,850.00**
150772	REMOVE CURB		M	10	1	54.00	$25.00	$1,350.00
		Unit Sub Total	**M**		**1**	**54.00**	**$25.00**	**$1,350.00**
	Item Code 150772	**Total No. of Proj.**			**4**		**Total Amount**	**$5,200.00**
150801	REMOVE OVERSIDE DRAIN		EA	1	2	11.00	$838.18	$9,220.00
			EA	2	2	8.00	$171.88	$1,375.00
			EA	3	1	6.00	$500.00	$3,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150801	REMOVE OVERSIDE DRAIN	EA	4	2	14.00	$382.14	$5,350.00
		EA	6	2	27.00	$138.89	$3,750.00
		EA	8	1	3.00	$500.00	$1,500.00
		EA	12	1	5.00	$700.00	$3,500.00
	Unit Sub Total	**EA**		**11**	**74.00**	**$374.26**	**$27,695.00**
	Item Code 150801 Total No. of Proj.			**11**		**Total Amount**	**$27,695.00**
150803	REMOVE DRAINAGE SYSTEM	EA	10	1	1.00	$900.00	$900.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$900.00**	**$900.00**
	Item Code 150803 Total No. of Proj.			**1**		**Total Amount**	**$900.00**
150804	REMOVE DRAINAGE FACILITY	EA	12	1	61.00	$725.00	$44,225.00
	Unit Sub Total	**EA**		**1**	**61.00**	**$725.00**	**$44,225.00**
	Item Code 150804 Total No. of Proj.			**1**		**Total Amount**	**$44,225.00**
150805	REMOVE CULVERT	EA	1	6	16.00	$586.56	$9,385.00
		EA	2	4	11.00	$1,112.46	$12,237.02
		EA	3	3	14.00	$944.71	$13,225.92
		EA	4	1	91.00	$950.00	$86,450.00
		EA	6	1	13.00	$1,200.00	$15,600.00
	Unit Sub Total	**EA**		**15**	**145.00**	**$944.12**	**$136,897.94**
150805	REMOVE CULVERT	LF	1	4	596.00	$26.38	$15,720.00
		LF	2	7	784.00	$49.10	$38,495.00
		LF	3	4	1,157.00	$13.63	$15,770.00
		LF	4	14	8,588.00	$20.59	$176,812.40
		LF	5	6	2,325.90	$25.56	$59,451.80
		LF	6	2	136.00	$38.24	$5,200.00
		LF	8	3	606.00	$24.22	$14,678.00
		LF	9	1	8.00	$20.00	$160.00
		LF	10	2	246.00	$16.42	$4,040.00
		LF	11	1	150.00	$22.30	$3,345.00
		LF	12	3	20,200.00	$9.48	$191,580.00
	Unit Sub Total	**LF**		**47**	**34,796.90**	**$15.09**	**$525,252.20**
150805	REMOVE CULVERT	M	3	1	240.00	$50.00	$12,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150805	REMOVE CULVERT		M	4	2	293.00	$107.88	$31,610.00
			M	10	1	56.00	$60.00	$3,360.00
			M	11	2	142.00	$73.78	$10,477.00
		Unit Sub Total	**M**		**6**	**731.00**	**$78.59**	**$57,447.00**
	Item Code 150805	**Total No. of Proj.**			**68**		**Total Amount**	**$719,597.14**
150806	REMOVE PIPE		EA	10	1	1.00	$300.00	$300.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$300.00**	**$300.00**
150806	REMOVE PIPE		LF	1	1	110.00	$20.00	$2,200.00
			LF	3	1	20.00	$35.00	$700.00
			LF	4	7	2,631.00	$30.41	$80,000.00
			LF	5	2	228.00	$7.50	$1,710.00
			LF	6	1	130.00	$15.00	$1,950.00
			LF	7	1	38.00	$40.00	$1,520.00
			LF	10	1	8.00	$25.00	$200.00
			LF	12	2	860.00	$22.73	$19,550.00
		Unit Sub Total	**LF**		**16**	**4,025.00**	**$26.79**	**$107,830.00**
150806	REMOVE PIPE		M	4	1	480.00	$99.00	$47,520.00
			M	7	5	6,183.00	$36.79	$227,482.00
		Unit Sub Total	**M**		**6**	**6,663.00**	**$41.27**	**$275,002.00**
	Item Code 150806	**Total No. of Proj.**			**23**		**Total Amount**	**$383,132.00**
150820	REMOVE INLET		EA	1	6	8.00	$716.25	$5,730.00
			EA	2	11	35.00	$907.45	$31,760.65
			EA	3	7	19.00	$834.24	$15,850.60
			EA	4	17	163.00	$719.67	$117,307.00
			EA	5	7	36.00	$416.39	$14,990.00
			EA	6	6	38.00	$572.37	$21,750.00
			EA	7	5	261.00	$969.08	$252,930.00
			EA	8	2	2.00	$1,100.00	$2,200.00
			EA	9	1	1.00	$75.00	$75.00
			EA	10	1	5.00	$420.00	$2,100.00
			EA	11	2	10.00	$699.00	$6,990.00
			EA	12	5	140.00	$745.50	$104,370.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**70**	**718.00**	**$802.30**	**$576,053.25**
	Item Code 150820	**Total No. of Proj.**			**70**		**Total Amount**	**$576,053.25**
150821	REMOVE HEADWALL		CY	12	1	30.00	$635.00	$19,050.00
		Unit Sub Total	**CY**		**1**	**30.00**	**$635.00**	**$19,050.00**
150821	REMOVE HEADWALL		EA	1	2	2.00	$1,075.00	$2,150.00
			EA	2	5	55.00	$417.76	$22,977.00
			EA	3	4	16.00	$800.13	$12,802.00
			EA	4	3	54.00	$371.85	$20,080.00
			EA	5	2	36.00	$517.08	$18,615.00
			EA	6	1	34.00	$15.00	$510.00
			EA	7	2	10.00	$605.50	$6,055.00
			EA	8	1	1.00	$800.00	$800.00
			EA	10	4	60.00	$517.50	$31,050.00
			EA	11	1	1.00	$648.00	$648.00
			EA	12	2	3.00	$666.67	$2,000.00
		Unit Sub Total	**EA**		**27**	**272.00**	**$432.67**	**$117,687.00**
	Item Code 150821	**Total No. of Proj.**			**28**		**Total Amount**	**$136,737.00**
150823	REMOVE DOWNDRAIN		EA	1	5	6.00	$631.67	$3,790.00
			EA	3	4	92.00	$440.22	$40,500.00
			EA	4	1	3.00	$350.00	$1,050.00
			EA	5	1	10.00	$500.00	$5,000.00
			EA	6	2	9.00	$982.22	$8,840.00
		Unit Sub Total	**EA**		**13**	**120.00**	**$493.17**	**$59,180.00**
150823	REMOVE DOWNDRAIN		LF	1	1	110.00	$22.00	$2,420.00
			LF	2	1	14.00	$50.00	$700.00
			LF	4	1	12.00	$125.00	$1,500.00
			LF	5	2	275.00	$16.36	$4,500.00
			LF	6	1	280.00	$15.25	$4,270.00
			LF	10	1	110.00	$12.00	$1,320.00
		Unit Sub Total	**LF**		**7**	**801.00**	**$18.36**	**$14,710.00**
	Item Code 150823	**Total No. of Proj.**			**20**		**Total Amount**	**$73,890.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150824	REMOVE SEWER MANHOLE		EA	4	1	5.00	$1,000.00	$5,000.00
		Unit Sub Total	**EA**		**1**	**5.00**	**$1,000.00**	**$5,000.00**
	Item Code 150824	**Total No. of Proj.**			**1**		**Total Amount**	**$5,000.00**
150825	REMOVE REINFORCED CONCRETE BOX CULVERT		LF	12	1	990.00	$17.00	$16,830.00
		Unit Sub Total	**LF**		**1**	**990.00**	**$17.00**	**$16,830.00**
	Item Code 150825	**Total No. of Proj.**			**1**		**Total Amount**	**$16,830.00**
150826	REMOVE MANHOLE		EA	4	3	7.00	$1,078.57	$7,550.00
		Unit Sub Total	**EA**		**3**	**7.00**	**$1,078.57**	**$7,550.00**
	Item Code 150826	**Total No. of Proj.**			**3**		**Total Amount**	**$7,550.00**
150827	REMOVE CATCH BASIN		EA	7	1	1.00	$500.00	$500.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$500.00**	**$500.00**
	Item Code 150827	**Total No. of Proj.**			**1**		**Total Amount**	**$500.00**
150829	REMOVE RETAINING WALL		CY	12	1	1,220.00	$64.00	$78,080.00
		Unit Sub Total	**CY**		**1**	**1,220.00**	**$64.00**	**$78,080.00**
150829	REMOVE RETAINING WALL		LF	2	1	20.00	$149.80	$2,996.00
			LF	4	1	1,010.00	$50.00	$50,500.00
		Unit Sub Total	**LF**		**2**	**1,030.00**	**$51.94**	**$53,496.00**
150829	REMOVE RETAINING WALL		LS	1	1	1.00	$12,253.00	$12,253.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$12,253.00**	**$12,253.00**
150829	REMOVE RETAINING WALL		M	7	2	164.00	$224.09	$36,750.00
		Unit Sub Total	**M**		**2**	**164.00**	**$224.09**	**$36,750.00**
150829	REMOVE RETAINING WALL		M3	4	1	560.00	$110.00	$61,600.00
		Unit Sub Total	**M3**		**1**	**560.00**	**$110.00**	**$61,600.00**
150829	REMOVE RETAINING WALL		SQFT	12	1	9,060.00	$2.00	$18,120.00
		Unit Sub Total	**SQFT**		**1**	**9,060.00**	**$2.00**	**$18,120.00**
	Item Code 150829	**Total No. of Proj.**			**8**		**Total Amount**	**$260,299.00**
150830	REMOVE RETAINING WALL (PORTION)		LF	4	1	820.00	$75.00	$61,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**1**	**820.00**	**$75.00**	**$61,500.00**
150830	REMOVE RETAINING WALL (PORTION)	LS	4	3	3.00	$8,020.67	$24,062.00
		LS	7	1	1.00	$2,500.00	$2,500.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$6,640.50**	**$26,562.00**
150830	REMOVE RETAINING WALL (PORTION)	M	7	1	1,380.00	$90.00	$124,200.00
	Unit Sub Total	**M**		**1**	**1,380.00**	**$90.00**	**$124,200.00**
	Item Code 150830	**Total No. of Proj.**		**6**		**Total Amount**	**$212,262.00**
150841	REMOVE SEWER PIPE	LF	4	1	1,420.00	$5.00	$7,100.00
	Unit Sub Total	**LF**		**1**	**1,420.00**	**$5.00**	**$7,100.00**
150841	REMOVE SEWER PIPE	M	4	1	180.00	$99.00	$17,820.00
	Unit Sub Total	**M**		**1**	**180.00**	**$99.00**	**$17,820.00**
	Item Code 150841	**Total No. of Proj.**		**2**		**Total Amount**	**$24,920.00**
150844	REMOVE SLOPE PAVING	SQFT	4	1	9,200.00	$0.50	$4,600.00
	Unit Sub Total	**SQFT**		**1**	**9,200.00**	**$0.50**	**$4,600.00**
	Item Code 150844	**Total No. of Proj.**		**1**		**Total Amount**	**$4,600.00**
150846	REMOVE CONCRETE PAVEMENT	CY	3	2	1,056.00	$44.48	$46,970.00
		CY	6	2	1,600.00	$68.05	$108,880.00
	Unit Sub Total	**CY**		**4**	**2,656.00**	**$58.68**	**$155,850.00**
150846	REMOVE CONCRETE PAVEMENT	SQYD	4	2	6,974.00	$3.04	$21,185.00
		SQYD	12	3	79,270.00	$4.92	$390,160.00
	Unit Sub Total	**SQYD**		**5**	**86,244.00**	**$4.77**	**$411,345.00**
	Item Code 150846	**Total No. of Proj.**		**9**		**Total Amount**	**$567,195.00**
150855	REMOVE PAVEMENT	CY	6	2	1,375.00	$103.39	$142,160.00
	Unit Sub Total	**CY**		**2**	**1,375.00**	**$103.39**	**$142,160.00**
	Item Code 150855	**Total No. of Proj.**		**2**		**Total Amount**	**$142,160.00**
150857	REMOVE ASPHALT CONCRETE SURFACING	CY	6	1	3,100.00	$25.00	$77,500.00
		CY	11	1	3,790.00	$45.00	$170,550.00
	Unit Sub Total	**CY**		**2**	**6,890.00**	**$36.00**	**$248,050.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
150857	REMOVE ASPHALT CONCRETE SURFACING	M2	7	1	313.00	$42.00	$13,146.00
	Unit Sub Total	**M2**		**1**	**313.00**	**$42.00**	**$13,146.00**
150857	REMOVE ASPHALT CONCRETE SURFACING	SQFT	1	1	8,102.00	$1.85	$14,988.70
		SQFT	2	7	109,814.00	$1.35	$148,720.35
		SQFT	3	11	2,618,291.00	$0.42	$1,092,491.70
		SQFT	4	6	129,649.00	$0.77	$99,239.32
		SQFT	5	4	84,803.00	$0.65	$54,776.00
		SQFT	6	2	11,518.00	$1.39	$16,005.60
		SQFT	7	2	58,235.00	$0.76	$44,100.00
		SQFT	8	2	78,280.00	$0.84	$65,456.00
		SQFT	9	3	60,788.00	$1.47	$89,593.78
		SQFT	10	1	17,482.00	$0.75	$13,111.50
		SQFT	11	2	21,650.00	$2.50	$54,100.00
	Unit Sub Total	**SQFT**		**41**	**3,198,612.00**	**$0.53**	**$1,692,582.95**
	Item Code 150857 Total No. of Proj.			**44**		**Total Amount**	**$1,953,778.95**
150859	REMOVE ASPHALT CONCRETE OVERSIDE DRAIN	EA	1	1	9.00	$200.00	$1,800.00
		EA	4	1	3.00	$300.00	$900.00
	Unit Sub Total	**EA**		**2**	**12.00**	**$225.00**	**$2,700.00**
	Item Code 150859 Total No. of Proj.			**2**		**Total Amount**	**$2,700.00**
150860	REMOVE BASE AND SURFACING	CY	3	1	9,540.00	$15.00	$143,100.00
		CY	4	2	21,330.00	$9.92	$211,500.00
		CY	5	1	680.00	$9.10	$6,188.00
		CY	10	1	2,850.00	$6.00	$17,100.00
		CY	11	1	120.00	$18.80	$2,256.00
	Unit Sub Total	**CY**		**6**	**34,520.00**	**$11.01**	**$380,144.00**
150860	REMOVE BASE AND SURFACING	M3	3	1	860.00	$10.00	$8,600.00
		M3	4	2	27,200.00	$14.94	$406,333.00
		M3	6	1	4,700.00	$3.00	$14,100.00
		M3	10	1	2,000.00	$14.00	$28,000.00
		M3	11	1	500.00	$17.00	$8,500.00
	Unit Sub Total	**M3**		**6**	**35,260.00**	**$13.20**	**$465,533.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 150860 Total No. of Proj.			**12**		**Total Amount**	**$845,677.00**
150870	REMOVE CONCRETE DECK SURFACE	CY	3	1	138.00	$345.00	$47,610.00
	Unit Sub Total	**CY**		**1**	**138.00**	**$345.00**	**$47,610.00**
150870	REMOVE CONCRETE DECK SURFACE	M2	7	1	165.00	$25.00	$4,125.00
		M2	10	1	15.00	$400.00	$6,000.00
	Unit Sub Total	**M2**		**2**	**180.00**	**$56.25**	**$10,125.00**
150870	REMOVE CONCRETE DECK SURFACE	SQFT	2	2	14,222.00	$4.15	$59,020.00
		SQFT	3	3	12,895.00	$10.94	$141,037.00
		SQFT	6	2	7,380.00	$1.15	$8,476.20
		SQFT	7	1	50,467.00	$0.20	$10,093.40
		SQFT	8	2	26,540.00	$2.43	$64,484.50
		SQFT	10	1	20,945.00	$1.65	$34,559.25
		SQFT	11	1	20,120.00	$0.20	$4,024.00
	Unit Sub Total	**SQFT**		**12**	**152,569.00**	**$2.11**	**$321,694.35**
	Item Code 150870 Total No. of Proj.			**15**		**Total Amount**	**$379,429.35**
151224	REMOVE DELINEATOR	EA	2	3	721.00	$16.19	$11,670.00
		EA	4	1	31.00	$20.00	$620.00
		EA	6	1	3.00	$5.00	$15.00
		EA	9	6	430.00	$15.63	$6,720.00
		EA	10	2	74.00	$8.31	$615.00
		EA	11	1	30.00	$3.55	$106.50
		EA	12	5	152.00	$6.60	$1,003.76
	Unit Sub Total	**EA**		**19**	**1,441.00**	**$14.40**	**$20,750.26**
	Item Code 151224 Total No. of Proj.			**19**		**Total Amount**	**$20,750.26**
151270	SALVAGE METAL BRIDGE RAILING	LF	2	2	1,118.00	$6.95	$7,771.00
		LF	3	1	361.00	$18.00	$6,498.00
		LF	12	2	2,811.00	$9.62	$27,028.00
	Unit Sub Total	**LF**		**5**	**4,290.00**	**$9.63**	**$41,297.00**
151270	SALVAGE METAL BRIDGE RAILING	M	4	1	139.00	$50.00	$6,950.00
	Unit Sub Total	**M**		**1**	**139.00**	**$50.00**	**$6,950.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 151270 Total No. of Proj.			**6**		**Total Amount**	**$48,247.00**
151272	SALVAGE METAL BEAM GUARD RAILING	LF	1	1	2,380.00	$10.68	$25,418.40
		LF	3	1	9,880.00	$5.60	$55,328.00
		LF	5	1	100.00	$2.76	$276.00
		LF	6	2	5,320.00	$3.59	$19,080.00
		LF	8	2	450.00	$6.83	$3,073.00
		LF	9	2	894.00	$15.99	$14,298.00
		LF	10	1	560.00	$13.01	$7,285.60
	Unit Sub Total	**LF**		**10**	**19,584.00**	**$6.37**	**$124,759.00**
	Item Code 151272 Total No. of Proj.			**10**		**Total Amount**	**$124,759.00**
151512	RECONSTRUCT INLET	EA	2	1	1.00	$1,284.00	$1,284.00
		EA	3	1	1.00	$2,000.00	$2,000.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$1,642.00**	**$3,284.00**
	Item Code 151512 Total No. of Proj.			**2**		**Total Amount**	**$3,284.00**
151537	RECONSTRUCT FENCE (TYPE WM)	LF	1	1	270.00	$5.00	$1,350.00
	Unit Sub Total	**LF**		**1**	**270.00**	**$5.00**	**$1,350.00**
	Item Code 151537 Total No. of Proj.			**1**		**Total Amount**	**$1,350.00**
151540	RECONSTRUCT CHAIN LINK FENCE	LF	1	1	4,550.00	$15.17	$69,023.50
		LF	4	1	130.00	$36.75	$4,777.50
		LF	6	1	14.00	$63.00	$882.00
		LF	8	1	190.00	$23.00	$4,370.00
		LF	9	1	140.00	$22.50	$3,150.00
		LF	12	2	75.00	$44.13	$3,310.00
	Unit Sub Total	**LF**		**7**	**5,099.00**	**$16.77**	**$85,513.00**
151540	RECONSTRUCT CHAIN LINK FENCE	M	3	1	3.00	$115.00	$345.00
		M	6	1	30.00	$117.00	$3,510.00
		M	7	2	133.00	$63.40	$8,432.40
	Unit Sub Total	**M**		**4**	**166.00**	**$74.02**	**$12,287.40**
	Item Code 151540 Total No. of Proj.			**11**		**Total Amount**	**$97,800.40**
151568	RECONSTRUCT THRIE BEAM BARRIER	LF	5	2	3,430.00	$19.19	$65,810.90

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
151568	RECONSTRUCT THRIE BEAM BARRIER	LF	6	1	3,960.00	$19.00	$75,240.00
	Unit Sub Total	**LF**		**3**	**7,390.00**	**$19.09**	**$141,050.90**
	Item Code 151568 Total No. of Proj.			**3**		**Total Amount**	**$141,050.90**
151570	RECONSTRUCT DOUBLE THRIE BEAM BARRIER	LF	3	1	3,700.00	$21.50	$79,550.00
		LF	4	1	380.00	$23.00	$8,740.00
		LF	5	2	1,100.00	$22.95	$25,250.00
	Unit Sub Total	**LF**		**4**	**5,180.00**	**$21.92**	**$113,540.00**
	Item Code 151570 Total No. of Proj.			**4**		**Total Amount**	**$113,540.00**
151572	RECONSTRUCT METAL BEAM GUARD RAILING	LF	1	4	50,134.00	$11.52	$577,756.00
		LF	2	10	30,850.00	$13.61	$419,875.00
		LF	3	4	23,570.00	$11.94	$281,460.00
		LF	4	2	11,613.00	$13.55	$157,315.00
		LF	5	5	10,850.00	$19.44	$210,898.40
		LF	6	4	16,510.00	$16.79	$277,270.00
		LF	8	1	1,800.00	$13.00	$23,400.00
		LF	9	1	75.00	$38.00	$2,850.00
		LF	10	2	168.00	$33.24	$5,585.00
		LF	11	1	7.00	$90.00	$630.00
		LF	12	2	250.00	$31.20	$7,800.00
	Unit Sub Total	**LF**		**36**	**145,827.00**	**$13.47**	**$1,964,839.40**
151572	RECONSTRUCT METAL BEAM GUARD RAILING	M	7	1	20.00	$51.55	$1,031.00
	Unit Sub Total	**M**		**1**	**20.00**	**$51.55**	**$1,031.00**
	Item Code 151572 Total No. of Proj.			**37**		**Total Amount**	**$1,965,870.40**
151623	RECONSTRUCT METAL BEAM GUARD RAILING (7' POST)	LF	1	3	8,730.00	$19.07	$166,506.40
	Unit Sub Total	**LF**		**3**	**8,730.00**	**$19.07**	**$166,506.40**
	Item Code 151623 Total No. of Proj.			**3**		**Total Amount**	**$166,506.40**
151625	RECONSTRUCT METAL BEAM GUARD RAILING (WOOD POST)	LF	1	4	72,320.00	$13.55	$980,235.00
		LF	3	2	11,140.00	$11.65	$129,740.00
		LF	7	1	350.00	$20.00	$7,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**7**	**83,810.00**	**$13.33**	**$1,116,975.00**
	Item Code 151625	**Total No. of Proj.**			**7**		**Total Amount**	**$1,116,975.00**
152039	RELAY ENTRANCE TAPER		EA	7	1	1.00	$830.00	$830.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$830.00**	**$830.00**
	Item Code 152039	**Total No. of Proj.**			**1**		**Total Amount**	**$830.00**
152255	RESET MAILBOX		EA	2	2	7.00	$200.00	$1,400.00
			EA	3	2	40.00	$274.00	$10,960.00
			EA	4	1	1.00	$600.00	$600.00
			EA	5	1	1.00	$275.00	$275.00
			EA	6	1	1.00	$379.00	$379.00
			EA	10	1	18.00	$350.00	$6,300.00
		Unit Sub Total	**EA**		**8**	**68.00**	**$292.85**	**$19,914.00**
	Item Code 152255	**Total No. of Proj.**			**8**		**Total Amount**	**$19,914.00**
152291	RESET GATE		EA	2	1	1.00	$1,250.00	$1,250.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$1,250.00**	**$1,250.00**
	Item Code 152291	**Total No. of Proj.**			**1**		**Total Amount**	**$1,250.00**
152299	RESET MILEPOST MARKER		EA	1	2	61.00	$55.52	$3,386.88
			EA	10	3	5.00	$53.00	$265.00
		Unit Sub Total	**EA**		**5**	**66.00**	**$55.33**	**$3,651.88**
	Item Code 152299	**Total No. of Proj.**			**5**		**Total Amount**	**$3,651.88**
152301	RESET MARKER		EA	1	5	709.00	$46.07	$32,660.40
			EA	3	1	8.00	$51.00	$408.00
			EA	4	1	18.00	$58.00	$1,044.00
			EA	8	1	6.00	$46.00	$276.00
		Unit Sub Total	**EA**		**8**	**741.00**	**$46.41**	**$34,388.40**
	Item Code 152301	**Total No. of Proj.**			**8**		**Total Amount**	**$34,388.40**
152303	RESET MARKERS AND DELINEATORS		EA	1	1	71.00	$25.00	$1,775.00
			EA	8	1	10.00	$46.00	$460.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**2**	**81.00**	**$27.59**	**$2,235.00**
	Item Code 152303	**Total No. of Proj.**			**2**		**Total Amount**	**$2,235.00**
152310	RESET BARRICADE		EA	8	1	10.00	$30.00	$300.00
		Unit Sub Total	**EA**		**1**	**10.00**	**$30.00**	**$300.00**
	Item Code 152310	**Total No. of Proj.**			**1**		**Total Amount**	**$300.00**
152316	RESET ROADSIDE SIGN (ONE POST)		EA	1	2	99.00	$138.71	$13,732.03
			EA	2	1	1.00	$300.00	$300.00
			EA	3	1	6.00	$250.00	$1,500.00
			EA	5	1	1.00	$224.00	$224.00
			EA	8	5	52.00	$140.10	$7,285.00
		Unit Sub Total	**EA**		**10**	**159.00**	**$144.91**	**$23,041.03**
	Item Code 152316	**Total No. of Proj.**			**10**		**Total Amount**	**$23,041.03**
152317	RESET ROADSIDE SIGN (TWO POST)		EA	1	1	6.00	$751.72	$4,510.32
			EA	2	1	6.00	$460.00	$2,760.00
			EA	3	1	1.00	$500.00	$500.00
			EA	5	1	1.00	$391.00	$391.00
			EA	8	3	8.00	$342.50	$2,740.00
		Unit Sub Total	**EA**		**7**	**22.00**	**$495.51**	**$10,901.32**
	Item Code 152317	**Total No. of Proj.**			**7**		**Total Amount**	**$10,901.32**
152320	RESET ROADSIDE SIGN		EA	1	2	32.00	$148.13	$4,740.00
			EA	2	7	20.00	$251.75	$5,035.00
			EA	3	6	101.00	$279.55	$28,235.00
			EA	4	3	45.00	$233.93	$10,527.00
			EA	5	1	1.00	$165.00	$165.00
			EA	6	8	104.00	$144.40	$15,018.00
			EA	10	1	5.00	$100.00	$500.00
			EA	11	6	60.00	$588.27	$35,296.00
		Unit Sub Total	**EA**		**34**	**368.00**	**$270.42**	**$99,516.00**
	Item Code 152320	**Total No. of Proj.**			**34**		**Total Amount**	**$99,516.00**
152322	RESET ROADSIDE SIGN (WOOD POST)		EA	3	1	5.00	$250.00	$1,250.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
152322	RESET ROADSIDE SIGN (WOOD POST)	EA	5	1	3.00	$200.00	$600.00
	Unit Sub Total	**EA**		**2**	**8.00**	**$231.25**	**$1,850.00**
	Item Code 152322 Total No. of Proj.			**2**		**Total Amount**	**$1,850.00**
152324	RESET ROADSIDE SIGN (METAL POST)	EA	1	1	3.00	$127.65	$382.95
		EA	10	1	1.00	$200.00	$200.00
	Unit Sub Total	**EA**		**2**	**4.00**	**$145.74**	**$582.95**
	Item Code 152324 Total No. of Proj.			**2**		**Total Amount**	**$582.95**
152351	RELOCATE HYDRANT	EA	4	1	6.00	$4,200.00	$25,200.00
	Unit Sub Total	**EA**		**1**	**6.00**	**$4,200.00**	**$25,200.00**
	Item Code 152351 Total No. of Proj.			**1**		**Total Amount**	**$25,200.00**
152370	RELOCATE MAILBOX	EA	3	2	6.00	$266.67	$1,600.00
	Unit Sub Total	**EA**		**2**	**6.00**	**$266.67**	**$1,600.00**
	Item Code 152370 Total No. of Proj.			**2**		**Total Amount**	**$1,600.00**
152379	RELOCATE FENCE	LF	4	1	160.00	$40.00	$6,400.00
	Unit Sub Total	**LF**		**1**	**160.00**	**$40.00**	**$6,400.00**
152379	RELOCATE FENCE	M	10	1	31.00	$45.00	$1,395.00
	Unit Sub Total	**M**		**1**	**31.00**	**$45.00**	**$1,395.00**
	Item Code 152379 Total No. of Proj.			**2**		**Total Amount**	**$7,795.00**
152381	RELOCATE GATE	EA	3	1	1.00	$500.00	$500.00
		EA	5	1	1.00	$940.00	$940.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$720.00**	**$1,440.00**
	Item Code 152381 Total No. of Proj.			**2**		**Total Amount**	**$1,440.00**
152386	RELOCATE ROADSIDE SIGN-ONE POST	EA	2	3	7.00	$321.43	$2,250.00
		EA	4	4	60.00	$160.00	$9,600.00
		EA	6	1	3.00	$171.00	$513.00
		EA	8	2	5.00	$190.00	$950.00
		EA	9	1	1.00	$270.00	$270.00
		EA	12	1	1.00	$100.00	$100.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**12**	**77.00**	**$177.70**	**$13,683.00**
	Item Code 152386	**Total No. of Proj.**			**12**		**Total Amount**	**$13,683.00**
152387	RELOCATE ROADSIDE SIGN-TWO POST		EA	4	4	34.00	$240.88	$8,190.00
			EA	6	2	2.00	$364.00	$728.00
			EA	12	1	1.00	$200.00	$200.00
		Unit Sub Total	**EA**		**7**	**37.00**	**$246.43**	**$9,118.00**
	Item Code 152387	**Total No. of Proj.**			**7**		**Total Amount**	**$9,118.00**
152388	RELOCATE CRASH CUSHION		EA	4	1	2.00	$1,100.00	$2,200.00
			EA	6	1	1.00	$6,000.00	$6,000.00
		Unit Sub Total	**EA**		**2**	**3.00**	**$2,733.33**	**$8,200.00**
	Item Code 152388	**Total No. of Proj.**			**2**		**Total Amount**	**$8,200.00**
152390	RELOCATE ROADSIDE SIGN		EA	2	3	8.00	$383.13	$3,065.00
			EA	3	6	47.00	$205.43	$9,655.00
			EA	4	6	29.00	$447.74	$12,984.40
			EA	5	3	62.00	$167.74	$10,400.00
			EA	6	2	6.00	$225.00	$1,350.00
			EA	7	1	13.00	$250.00	$3,250.00
			EA	10	1	7.00	$220.00	$1,540.00
			EA	11	4	16.00	$239.25	$3,828.00
			EA	12	3	5.00	$335.00	$1,675.00
		Unit Sub Total	**EA**		**29**	**193.00**	**$247.40**	**$47,747.40**
	Item Code 152390	**Total No. of Proj.**			**29**		**Total Amount**	**$47,747.40**
152391	RELOCATE ROADSIDE SIGN (METAL POST)		EA	4	2	7.00	$307.14	$2,150.00
		Unit Sub Total	**EA**		**2**	**7.00**	**$307.14**	**$2,150.00**
	Item Code 152391	**Total No. of Proj.**			**2**		**Total Amount**	**$2,150.00**
152392	RELOCATE ROADSIDE SIGN (WOOD POST)		EA	4	2	5.00	$264.00	$1,320.00
			EA	8	1	8.00	$300.00	$2,400.00
			EA	10	1	1.00	$200.00	$200.00
			EA	12	2	2.00	$185.00	$370.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**6**	**16.00**	**$268.13**	**$4,290.00**
	Item Code 152392	**Total No. of Proj.**			**6**		**Total Amount**	**$4,290.00**
152393	RELOCATE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD)		EA	4	1	8.00	$75.00	$600.00
			EA	7	1	11.00	$41.00	$451.00
		Unit Sub Total	**EA**		**2**	**19.00**	**$55.32**	**$1,051.00**
	Item Code 152393	**Total No. of Proj.**			**2**		**Total Amount**	**$1,051.00**
152394	RELOCATE SIGN STRUCTURE		EA	3	1	8.00	$7,200.00	$57,600.00
			EA	6	1	2.00	$27,500.00	$55,000.00
			EA	10	1	1.00	$9,500.00	$9,500.00
		Unit Sub Total	**EA**		**3**	**11.00**	**$11,100.00**	**$122,100.00**
	Item Code 152394	**Total No. of Proj.**			**3**		**Total Amount**	**$122,100.00**
152396	RELOCATE SIGN PANEL		EA	2	1	19.00	$25.00	$475.00
		Unit Sub Total	**EA**		**1**	**19.00**	**$25.00**	**$475.00**
	Item Code 152396	**Total No. of Proj.**			**1**		**Total Amount**	**$475.00**
152397	RELOCATE METAL BEAM GUARD RAILING		LF	2	1	140.00	$10.25	$1,435.00
		Unit Sub Total	**LF**		**1**	**140.00**	**$10.25**	**$1,435.00**
	Item Code 152397	**Total No. of Proj.**			**1**		**Total Amount**	**$1,435.00**
152398	RELOCATE SIGN STRUCTURE (BRIDGE-MOUNTED)		EA	11	1	1.00	$8,200.00	$8,200.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$8,200.00**	**$8,200.00**
	Item Code 152398	**Total No. of Proj.**			**1**		**Total Amount**	**$8,200.00**
152400	ADJUST SEWER CLEANOUT TO GRADE		EA	6	1	1.00	$500.00	$500.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$500.00**	**$500.00**
	Item Code 152400	**Total No. of Proj.**			**1**		**Total Amount**	**$500.00**
152401	ADJUST WATER METER TO GRADE		EA	8	1	30.00	$65.00	$1,950.00
		Unit Sub Total	**EA**		**1**	**30.00**	**$65.00**	**$1,950.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 152401 Total No. of Proj.			**1**		**Total Amount**	**$1,950.00**
152402	ADJUST WATER VALVE COVER TO GRADE	EA	4	1	70.00	$400.00	$28,000.00
		EA	6	2	16.00	$631.25	$10,100.00
		EA	7	1	19.00	$500.00	$9,500.00
		EA	11	1	1.00	$360.00	$360.00
		EA	12	1	2.00	$280.00	$560.00
	Unit Sub Total	**EA**		**6**	**108.00**	**$449.26**	**$48,520.00**
	Item Code 152402 Total No. of Proj.			**6**		**Total Amount**	**$48,520.00**
152403	ADJUST WATER METER BOX TO GRADE	EA	11	1	2.00	$500.00	$1,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$500.00**	**$1,000.00**
	Item Code 152403 Total No. of Proj.			**1**		**Total Amount**	**$1,000.00**
152410	RELOCATE WATER METER	EA	4	1	1.00	$850.00	$850.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$850.00**	**$850.00**
152410	RELOCATE WATER METER	LS	12	1	1.00	$2,000.00	$2,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$2,000.00**	**$2,000.00**
	Item Code 152410 Total No. of Proj.			**2**		**Total Amount**	**$2,850.00**
152423	ADJUST MONUMENT TO GRADE	EA	10	2	24.00	$500.00	$12,000.00
		EA	12	1	12.00	$280.00	$3,360.00
	Unit Sub Total	**EA**		**3**	**36.00**	**$426.67**	**$15,360.00**
	Item Code 152423 Total No. of Proj.			**3**		**Total Amount**	**$15,360.00**
152427	ADJUST FIRE HYDRANT	EA	4	1	1.00	$450.00	$450.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$450.00**	**$450.00**
	Item Code 152427 Total No. of Proj.			**1**		**Total Amount**	**$450.00**
152430	ADJUST INLET	EA	1	1	7.00	$1,350.00	$9,450.00
		EA	2	2	44.00	$1,422.73	$62,600.00
		EA	3	5	20.00	$1,088.00	$21,760.00
		EA	4	3	188.00	$1,321.69	$248,477.00
		EA	5	4	44.00	$1,767.09	$77,752.00
		EA	6	2	16.00	$1,000.00	$16,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
152430	ADJUST INLET		EA	7	4	35.00	$1,510.57	$52,870.00
			EA	12	3	7.00	$1,757.14	$12,300.00
		Unit Sub Total	**EA**		**24**	**361.00**	**$1,388.39**	**$501,209.00**
152430	ADJUST INLET		LF	4	1	4.80	$1,700.00	$8,160.00
		Unit Sub Total	**LF**		**1**	**4.80**	**$1,700.00**	**$8,160.00**
	Item Code 152430	**Total No. of Proj.**			**25**		**Total Amount**	**$509,369.00**
152438	ADJUST FRAME AND COVER TO GRADE		EA	1	3	214.00	$404.21	$86,500.00
			EA	4	6	295.00	$448.71	$132,370.00
			EA	5	3	56.00	$454.46	$25,450.00
			EA	6	2	10.00	$687.50	$6,875.00
			EA	7	2	70.00	$465.36	$32,575.00
			EA	8	1	6.00	$270.00	$1,620.00
			EA	9	2	61.00	$985.03	$60,086.58
			EA	10	4	273.00	$394.52	$107,705.00
			EA	12	1	82.00	$285.00	$23,370.00
		Unit Sub Total	**EA**		**24**	**1,067.00**	**$446.63**	**$476,551.58**
	Item Code 152438	**Total No. of Proj.**			**24**		**Total Amount**	**$476,551.58**
152439	ADJUST FRAME AND GRATE TO GRADE		EA	4	3	21.00	$342.86	$7,200.00
			EA	6	1	7.00	$2,000.00	$14,000.00
			EA	10	1	2.00	$750.00	$1,500.00
		Unit Sub Total	**EA**		**5**	**30.00**	**$756.67**	**$22,700.00**
	Item Code 152439	**Total No. of Proj.**			**5**		**Total Amount**	**$22,700.00**
152440	ADJUST MANHOLE TO GRADE		EA	2	1	1.00	$1,000.00	$1,000.00
			EA	4	1	6.00	$3,100.00	$18,600.00
			EA	5	1	2.00	$400.00	$800.00
			EA	6	2	6.00	$825.00	$4,950.00
			EA	7	1	10.00	$900.00	$9,000.00
			EA	11	2	3.00	$783.33	$2,350.00
			EA	12	2	79.00	$427.03	$33,735.00
		Unit Sub Total	**EA**		**10**	**107.00**	**$658.27**	**$70,435.00**
	Item Code 152440	**Total No. of Proj.**			**10**		**Total Amount**	**$70,435.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
152451	ADJUST WATER VALVE	EA	2	1	3.00	$400.00	$1,200.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$400.00**	**$1,200.00**
	Item Code 152451 Total No. of Proj.			**1**		**Total Amount**	**$1,200.00**
152469	ADJUST UTILITY COVER TO GRADE	EA	2	1	2.00	$175.00	$350.00
		EA	4	2	10.00	$1,100.00	$11,000.00
		EA	5	1	2.00	$268.00	$536.00
	Unit Sub Total	**EA**		**4**	**14.00**	**$849.00**	**$11,886.00**
	Item Code 152469 Total No. of Proj.			**4**		**Total Amount**	**$11,886.00**
152472	ADJUST UTILITY COVER	EA	4	1	9.00	$163.00	$1,467.00
	Unit Sub Total	**EA**		**1**	**9.00**	**$163.00**	**$1,467.00**
	Item Code 152472 Total No. of Proj.			**1**		**Total Amount**	**$1,467.00**
152500	ADJUST METAL BEAM GUARD RAILING	LF	1	1	5,930.00	$3.50	$20,755.00
		LF	2	2	12,280.00	$5.24	$64,380.00
		LF	3	1	320.00	$5.75	$1,840.00
		LF	4	1	260.00	$14.00	$3,640.00
		LF	5	2	2,130.00	$10.63	$22,650.00
		LF	6	1	760.00	$10.00	$7,600.00
		LF	9	1	1,220.00	$13.70	$16,714.00
	Unit Sub Total	**LF**		**9**	**22,900.00**	**$6.01**	**$137,579.00**
	Item Code 152500 Total No. of Proj.			**9**		**Total Amount**	**$137,579.00**
152555	ADJUST SLOTTED DRAIN TO GRADE	LF	2	1	690.00	$25.00	$17,250.00
		LF	5	1	40.00	$102.00	$4,080.00
	Unit Sub Total	**LF**		**2**	**730.00**	**$29.22**	**$21,330.00**
	Item Code 152555 Total No. of Proj.			**2**		**Total Amount**	**$21,330.00**
152604	MODIFY INLET	EA	4	2	15.00	$1,380.00	$20,700.00
		EA	7	1	6.00	$2,200.00	$13,200.00
		EA	11	2	7.00	$2,192.00	$15,344.00
	Unit Sub Total	**EA**		**5**	**28.00**	**$1,758.71**	**$49,244.00**
	Item Code 152604 Total No. of Proj.			**5**		**Total Amount**	**$49,244.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
152609	MODIFY INLET TO MANHOLE	EA	4	3	8.00	$2,025.00	$16,200.00
	Unit Sub Total	**EA**		**3**	**8.00**	**$2,025.00**	**$16,200.00**
	Item Code 152609 Total No. of Proj.			**3**		**Total Amount**	**$16,200.00**
152632	MODIFY METAL BEAM GUARD RAILING	LF	3	2	480.00	$11.50	$5,520.00
	Unit Sub Total	**LF**		**2**	**480.00**	**$11.50**	**$5,520.00**
	Item Code 152632 Total No. of Proj.			**2**		**Total Amount**	**$5,520.00**
152641	MODIFY SIGN STRUCTURE	EA	11	1	10.00	$3,100.00	$31,000.00
		EA	12	1	1.00	$3,500.00	$3,500.00
	Unit Sub Total	**EA**		**2**	**11.00**	**$3,136.36**	**$34,500.00**
	Item Code 152641 Total No. of Proj.			**2**		**Total Amount**	**$34,500.00**
152702	REMODEL MANHOLE	EA	3	1	38.00	$750.00	$28,500.00
	Unit Sub Total	**EA**		**1**	**38.00**	**$750.00**	**$28,500.00**
	Item Code 152702 Total No. of Proj.			**1**		**Total Amount**	**$28,500.00**
152703	REMODEL INLET	EA	3	1	11.00	$1,100.00	$12,100.00
	Unit Sub Total	**EA**		**1**	**11.00**	**$1,100.00**	**$12,100.00**
	Item Code 152703 Total No. of Proj.			**1**		**Total Amount**	**$12,100.00**
153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	M2	3	1	25,400.00	$1.50	$38,100.00
		M2	4	3	28,370.00	$3.20	$90,670.00
		M2	6	2	22,220.00	$3.17	$70,440.00
		M2	7	4	126,970.00	$2.96	$375,585.00
		M2	10	1	1,490.00	$10.00	$14,900.00
		M2	11	3	449,740.00	$2.76	$1,241,995.00
	Unit Sub Total	**M2**		**14**	**654,190.00**	**$2.80**	**$1,831,690.00**
153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQFT	10	1	3,790.00	$0.20	$758.00
	Unit Sub Total	**SQFT**		**1**	**3,790.00**	**$0.20**	**$758.00**
153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	1	24	657,190.00	$1.70	$1,119,405.00
		SQYD	2	28	1,382,410.00	$2.23	$3,080,159.00
		SQYD	3	25	2,527,920.00	$0.84	$2,122,519.00
		SQYD	4	36	2,669,118.00	$1.42	$3,798,654.98

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	5	23	1,072,783.00	$1.34	$1,435,908.50
		SQYD	6	24	725,520.00	$1.44	$1,047,065.00
		SQYD	7	12	1,653,470.00	$2.16	$3,564,930.00
		SQYD	8	13	1,076,180.00	$0.88	$951,462.00
		SQYD	9	9	420,770.00	$1.37	$578,489.70
		SQYD	10	25	780,570.00	$1.89	$1,475,132.40
		SQYD	11	10	732,030.00	$1.40	$1,022,786.00
		SQYD	12	11	107,736.00	$3.31	$356,413.00
	Unit Sub Total	**SQYD**		**240**	**13,805,697.00**	**$1.49**	**$20,552,924.58**
	Item Code 153103 Total No. of Proj.			**255**		**Total Amount**	**$22,385,372.58**
153112	COLD PLANE ASPHALT CONCRETE PAVEMENT (.15' MAXIMUM)	SQYD	4	1	8,970.00	$3.25	$29,152.50
	Unit Sub Total	**SQYD**		**1**	**8,970.00**	**$3.25**	**$29,152.50**
	Item Code 153112 Total No. of Proj.			**1**		**Total Amount**	**$29,152.50**
153210	REMOVE CONCRETE	CF	3	1	48.00	$90.00	$4,320.00
	Unit Sub Total	**CF**		**1**	**48.00**	**$90.00**	**$4,320.00**
153210	REMOVE CONCRETE	CY	1	1	1.60	$483.00	$772.80
		CY	2	1	40.00	$45.00	$1,800.00
		CY	3	1	2.00	$520.00	$1,040.00
		CY	4	9	2,132.90	$94.38	$201,298.00
		CY	5	3	41.00	$143.51	$5,884.00
		CY	6	9	6,225.50	$35.77	$222,709.00
		CY	7	4	184.00	$142.17	$26,160.00
		CY	8	1	36.00	$135.00	$4,860.00
		CY	9	2	65.00	$62.48	$4,061.34
		CY	10	1	7.00	$240.00	$1,680.00
		CY	11	4	572.00	$212.31	$121,440.00
		CY	12	5	416.00	$104.32	$43,396.70
	Unit Sub Total	**CY**		**41**	**9,723.00**	**$65.32**	**$635,101.84**
153210	REMOVE CONCRETE	M3	4	3	2,114.00	$94.60	$199,990.00
		M3	6	1	9.00	$350.00	$3,150.00
		M3	7	5	1,150.50	$102.79	$118,265.00
	Unit Sub Total	**M3**		**9**	**3,273.50**	**$98.18**	**$321,405.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 153210 Total No. of Proj.			**51**		**Total Amount**	**$960,826.84**
153211	REMOVE CONCRETE SIDEWALK AND DRIVEWAY	CY	8	1	80.00	$65.00	$5,200.00
	Unit Sub Total	**CY**		**1**	**80.00**	**$65.00**	**$5,200.00**
	Item Code 153211 Total No. of Proj.			**1**		**Total Amount**	**$5,200.00**
153213	REMOVE CONCRETE (STRUCTURE)	CY	7	1	0.20	$4,500.00	$900.00
	Unit Sub Total	**CY**		**1**	**0.20**	**$4,500.00**	**$900.00**
153213	REMOVE CONCRETE (STRUCTURE)	EA	8	1	1.00	$3,040.00	$3,040.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$3,040.00**	**$3,040.00**
153213	REMOVE CONCRETE (STRUCTURE)	M3	4	1	43.00	$380.00	$16,340.00
	Unit Sub Total	**M3**		**1**	**43.00**	**$380.00**	**$16,340.00**
	Item Code 153213 Total No. of Proj.			**3**		**Total Amount**	**$20,280.00**
153214	REMOVE CONCRETE CURB	LF	2	2	480.00	$6.25	$3,000.00
		LF	3	2	1,690.00	$21.72	$36,700.00
		LF	4	5	7,890.00	$4.83	$38,100.00
		LF	6	2	98.00	$13.18	$1,292.00
		LF	7	2	2,000.00	$8.60	$17,195.00
		LF	11	2	600.00	$4.26	$2,558.00
		LF	12	5	20,510.00	$3.98	$81,697.50
	Unit Sub Total	**LF**		**20**	**33,268.00**	**$5.43**	**$180,542.50**
153214	REMOVE CONCRETE CURB	M	6	1	160.00	$8.00	$1,280.00
		M	7	3	17,090.00	$7.61	$130,020.00
	Unit Sub Total	**M**		**4**	**17,250.00**	**$7.61**	**$131,300.00**
	Item Code 153214 Total No. of Proj.			**24**		**Total Amount**	**$311,842.50**
153215	REMOVE CONCRETE (CURB AND GUTTER)	CY	6	1	30.00	$100.00	$3,000.00
		CY	8	1	130.00	$100.00	$13,000.00
	Unit Sub Total	**CY**		**2**	**160.00**	**$100.00**	**$16,000.00**
153215	REMOVE CONCRETE (CURB AND GUTTER)	LF	2	3	722.00	$8.17	$5,897.12
		LF	3	1	4,470.00	$4.00	$17,880.00
		LF	4	2	3,420.00	$4.22	$14,440.00
		LF	6	1	1,030.00	$9.00	$9,270.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
153215	REMOVE CONCRETE (CURB AND GUTTER)	LF	8	1	35.00	$12.00	$420.00
	Unit Sub Total	**LF**		**8**	**9,677.00**	**$4.95**	**$47,907.12**
153215	REMOVE CONCRETE (CURB AND GUTTER)	M	7	1	1,000.00	$6.00	$6,000.00
		M	10	1	360.00	$35.00	$12,600.00
	Unit Sub Total	**M**		**2**	**1,360.00**	**$13.68**	**$18,600.00**
	Item Code 153215 Total No. of Proj.			**12**		**Total Amount**	**$82,507.12**
153216	REMOVE CONCRETE CURB AND SIDEWALK	CY	2	1	32.00	$155.00	$4,960.00
		CY	5	1	75.00	$74.00	$5,550.00
		CY	11	1	14.00	$175.00	$2,450.00
	Unit Sub Total	**CY**		**3**	**121.00**	**$107.11**	**$12,960.00**
	Item Code 153216 Total No. of Proj.			**3**		**Total Amount**	**$12,960.00**
153218	REMOVE CONCRETE SIDEWALK	CY	2	1	20.00	$90.00	$1,800.00
		CY	4	1	90.00	$70.00	$6,300.00
	Unit Sub Total	**CY**		**2**	**110.00**	**$73.64**	**$8,100.00**
153218	REMOVE CONCRETE SIDEWALK	LF	2	1	220.00	$10.00	$2,200.00
		LF	3	1	190.00	$4.00	$760.00
		LF	4	1	60.00	$15.00	$900.00
	Unit Sub Total	**LF**		**3**	**470.00**	**$8.21**	**$3,860.00**
153218	REMOVE CONCRETE SIDEWALK	M2	7	1	690.00	$15.00	$10,350.00
	Unit Sub Total	**M2**		**1**	**690.00**	**$15.00**	**$10,350.00**
153218	REMOVE CONCRETE SIDEWALK	SQFT	4	1	18,800.00	$0.65	$12,220.00
		SQFT	12	2	11,200.00	$0.84	$9,429.00
	Unit Sub Total	**SQFT**		**3**	**30,000.00**	**$0.72**	**$21,649.00**
153218	REMOVE CONCRETE SIDEWALK	SQYD	2	1	79.00	$32.15	$2,539.85
		SQYD	12	1	650.00	$10.00	$6,500.00
	Unit Sub Total	**SQYD**		**2**	**729.00**	**$12.40**	**$9,039.85**
	Item Code 153218 Total No. of Proj.			**11**		**Total Amount**	**$52,998.85**
153220	REMOVE CONCRETE (CHANNEL)	CY	11	1	16.00	$83.00	$1,328.00
		CY	12	3	1,310.00	$48.66	$63,750.00
	Unit Sub Total	**CY**		**4**	**1,326.00**	**$49.08**	**$65,078.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
153220	REMOVE CONCRETE (CHANNEL)	M	11	1	52.00	$39.00	$2,028.00
	Unit Sub Total	**M**		**1**	**52.00**	**$39.00**	**$2,028.00**
	Item Code 153220 Total No. of Proj.			**5**		**Total Amount**	**$67,106.00**
153221	REMOVE CONCRETE BARRIER	LF	2	1	79.00	$75.00	$5,925.00
		LF	3	1	150.00	$26.00	$3,900.00
		LF	4	2	1,335.00	$16.65	$22,230.00
		LF	11	1	110.00	$100.00	$11,000.00
		LF	12	5	29,220.00	$8.01	$234,170.00
	Unit Sub Total	**LF**		**10**	**30,894.00**	**$8.97**	**$277,225.00**
153221	REMOVE CONCRETE BARRIER	M	7	4	21,821.20	$19.61	$427,848.00
		M	11	1	940.00	$35.00	$32,900.00
	Unit Sub Total	**M**		**5**	**22,761.20**	**$20.24**	**$460,748.00**
	Item Code 153221 Total No. of Proj.			**15**		**Total Amount**	**$737,973.00**
153222	REMOVE CONCRETE ISLAND (PORTIONS)	CY	12	1	38.00	$75.00	$2,850.00
	Unit Sub Total	**CY**		**1**	**38.00**	**$75.00**	**$2,850.00**
153222	REMOVE CONCRETE ISLAND (PORTIONS)	SQYD	2	1	1.90	$802.63	$1,525.00
	Unit Sub Total	**SQYD**		**1**	**1.90**	**$802.63**	**$1,525.00**
	Item Code 153222 Total No. of Proj.			**2**		**Total Amount**	**$4,375.00**
153223	REMOVE UNSOUND CONCRETE	CF	1	2	562.00	$26.27	$14,765.00
		CF	2	8	3,688.00	$31.18	$114,996.25
		CF	3	11	16,645.00	$16.16	$268,902.00
		CF	4	13	12,065.00	$21.76	$262,501.25
		CF	5	5	734.00	$67.63	$49,644.00
		CF	6	3	403.00	$23.23	$9,360.80
		CF	7	14	12,581.00	$12.92	$162,597.00
		CF	8	7	1,774.00	$24.62	$43,668.00
		CF	9	3	1,042.00	$46.22	$48,157.51
		CF	10	5	1,687.00	$7.61	$12,836.75
		CF	11	6	5,375.00	$19.53	$104,990.00
		CF	12	4	646.00	$15.11	$9,761.00
	Unit Sub Total	**CF**		**81**	**57,202.00**	**$19.27**	**$1,102,179.56**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 153223 Total No. of Proj.			**81**		**Total Amount**	**$1,102,179.56**
153225	PREPARE CONCRETE BRIDGE DECK SURFACE	M2	2	1	2,295.00	$2.00	$4,590.00
		M2	4	1	1,022.00	$3.00	$3,066.00
		M2	7	1	165.00	$25.45	$4,199.25
		M2	10	1	29.00	$80.00	$2,320.00
		M2	11	1	133.00	$50.00	$6,650.00
	Unit Sub Total	**M2**		**5**	**3,644.00**	**$5.71**	**$20,825.25**
153225	PREPARE CONCRETE BRIDGE DECK SURFACE	SQFT	1	2	14,872.00	$0.45	$6,759.00
		SQFT	2	10	522,713.00	$0.19	$99,414.44
		SQFT	3	7	539,659.00	$0.17	$93,099.48
		SQFT	4	4	203,762.00	$0.41	$84,254.64
		SQFT	5	1	9,640.00	$0.22	$2,120.80
		SQFT	6	3	84,228.00	$0.37	$30,861.90
		SQFT	7	4	197,516.00	$0.15	$29,955.53
		SQFT	8	3	247,970.00	$0.18	$44,512.70
		SQFT	9	3	102,611.00	$0.19	$19,110.42
		SQFT	10	1	20,945.00	$0.30	$6,283.50
		SQFT	11	1	20,120.00	$0.08	$1,609.60
		SQFT	12	3	48,307.00	$0.44	$21,098.04
	Unit Sub Total	**SQFT**		**42**	**2,012,343.00**	**$0.22**	**$439,080.05**
	Item Code 153225 Total No. of Proj.			**47**		**Total Amount**	**$459,905.30**
153229	REMOVE CONCRETE BARRIER (TYPE K)	LF	4	2	2,370.00	$5.22	$12,360.00
		LF	7	1	120.00	$5.00	$600.00
		LF	12	1	3,610.00	$4.00	$14,440.00
	Unit Sub Total	**LF**		**4**	**6,100.00**	**$4.49**	**$27,400.00**
153229	REMOVE CONCRETE BARRIER (TYPE K)	M	4	3	1,980.00	$10.91	$21,600.00
		M	7	1	260.00	$12.00	$3,120.00
		M	11	1	180.00	$21.00	$3,780.00
	Unit Sub Total	**M**		**5**	**2,420.00**	**$11.78**	**$28,500.00**
	Item Code 153229 Total No. of Proj.			**9**		**Total Amount**	**$55,900.00**
153230	REMOVE CONCRETE BARRIER (TYPE 50)	LF	4	2	51,300.00	$10.16	$521,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**2**	**51,300.00**	**$10.16**	**$521,000.00**
153230	REMOVE CONCRETE BARRIER (TYPE 50)	M	4	1	1,280.00	$36.00	$46,080.00
	Unit Sub Total	**M**		**1**	**1,280.00**	**$36.00**	**$46,080.00**
	Item Code 153230 Total No. of Proj.			**3**		**Total Amount**	**$567,080.00**
153235	CLEAN BRIDGE DECK	M2	4	1	22,800.00	$0.50	$11,400.00
		M2	7	1	313.00	$26.00	$8,138.00
	Unit Sub Total	**M2**		**2**	**23,113.00**	**$0.85**	**$19,538.00**
153235	CLEAN BRIDGE DECK	SQFT	1	2	92,118.00	$0.26	$24,406.25
		SQFT	2	4	129,871.00	$0.36	$46,784.58
		SQFT	3	9	1,988,713.00	$0.08	$168,210.12
		SQFT	4	14	3,450,558.00	$0.14	$479,257.46
		SQFT	5	4	128,524.00	$0.24	$30,499.10
		SQFT	6	1	80,024.00	$0.17	$13,604.08
		SQFT	7	12	3,196,622.00	$0.12	$384,766.41
		SQFT	8	3	447,589.00	$0.21	$92,450.04
		SQFT	10	4	347,589.00	$0.13	$46,156.50
		SQFT	11	6	2,093,979.00	$0.13	$271,757.68
		SQFT	12	2	168,267.00	$0.17	$28,180.71
	Unit Sub Total	**SQFT**		**61**	**12,123,854.00**	**$0.13**	**$1,586,072.93**
	Item Code 153235 Total No. of Proj.			**63**		**Total Amount**	**$1,605,610.93**
153237	REMOVE CHIP SEAL	SQFT	2	1	91,673.00	$1.00	$91,673.00
		SQFT	10	1	10,685.00	$0.60	$6,411.00
	Unit Sub Total	**SQFT**		**2**	**102,358.00**	**$0.96**	**$98,084.00**
	Item Code 153237 Total No. of Proj.			**2**		**Total Amount**	**$98,084.00**
153239	REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK)	CY	4	1	490.00	$105.00	$51,450.00
		CY	6	1	63.00	$100.00	$6,300.00
		CY	12	1	12.00	$130.00	$1,560.00
	Unit Sub Total	**CY**		**3**	**565.00**	**$104.97**	**$59,310.00**
153239	REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK)	M	11	1	5,000.00	$8.00	$40,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M**		**1**	**5,000.00**	**$8.00**	**$40,000.00**
	Item Code 153239	**Total No. of Proj.**			**4**		**Total Amount**	**$99,310.00**
153246	REMOVE CONCRETE (MISCELLANEOUS)		CY	2	2	8.20	$556.10	$4,560.00
			CY	3	1	75.00	$116.00	$8,700.00
			CY	4	1	1,510.00	$27.00	$40,770.00
			CY	11	2	94.00	$237.34	$22,310.00
			CY	12	1	23.00	$80.00	$1,840.00
		Unit Sub Total	**CY**		**7**	**1,710.20**	**$45.71**	**$78,180.00**
153246	REMOVE CONCRETE (MISCELLANEOUS)		M3	7	1	5.00	$300.00	$1,500.00
		Unit Sub Total	**M3**		**1**	**5.00**	**$300.00**	**$1,500.00**
153246	REMOVE CONCRETE (MISCELLANEOUS)		SQFT	8	1	2,520.00	$1.50	$3,780.00
			SQFT	12	2	104.00	$65.25	$6,786.00
		Unit Sub Total	**SQFT**		**3**	**2,624.00**	**$4.03**	**$10,566.00**
153246	REMOVE CONCRETE (MISCELLANEOUS)		SQYD	12	1	1,340.00	$12.00	$16,080.00
		Unit Sub Total	**SQYD**		**1**	**1,340.00**	**$12.00**	**$16,080.00**
	Item Code 153246	**Total No. of Proj.**			**12**		**Total Amount**	**$106,326.00**
153250	REMOVE SOUND WALL		LS	7	1	1.00	$800.00	$800.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$800.00**	**$800.00**
153250	REMOVE SOUND WALL		M	7	1	3,680.00	$25.00	$92,000.00
		Unit Sub Total	**M**		**1**	**3,680.00**	**$25.00**	**$92,000.00**
153250	REMOVE SOUND WALL		M2	7	2	14,620.00	$26.60	$388,840.00
		Unit Sub Total	**M2**		**2**	**14,620.00**	**$26.60**	**$388,840.00**
153250	REMOVE SOUND WALL		SQFT	12	3	49,730.00	$2.18	$108,296.00
		Unit Sub Total	**SQFT**		**3**	**49,730.00**	**$2.18**	**$108,296.00**
153250	REMOVE SOUND WALL		SQYD	10	1	16.00	$479.00	$7,664.00
			SQYD	12	2	10,680.00	$23.03	$246,000.00
		Unit Sub Total	**SQYD**		**3**	**10,696.00**	**$23.72**	**$253,664.00**
	Item Code 153250	**Total No. of Proj.**			**10**		**Total Amount**	**$843,600.00**
153530	ACCESS OPENING, DECK		EA	4	1	64.00	$300.00	$19,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
153530	ACCESS OPENING, DECK	EA	7	1	8.00	$600.00	$4,800.00
	Unit Sub Total	**EA**		**2**	**72.00**	**$333.33**	**$24,000.00**
	Item Code 153530 Total No. of Proj.			**2**		**Total Amount**	**$24,000.00**
153531	ACCESS OPENING, SOFFIT	EA	3	2	14.00	$2,197.14	$30,760.00
		EA	4	1	4.00	$1,500.00	$6,000.00
		EA	7	2	17.00	$1,582.35	$26,900.00
	Unit Sub Total	**EA**		**5**	**35.00**	**$1,818.86**	**$63,660.00**
	Item Code 153531 Total No. of Proj.			**5**		**Total Amount**	**$63,660.00**
155001	PLUG CULVERT	EA	5	1	2.00	$300.00	$600.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$300.00**	**$600.00**
	Item Code 155001 Total No. of Proj.			**1**		**Total Amount**	**$600.00**
155003	CAP INLET	EA	2	1	1.00	$1,100.00	$1,100.00
		EA	4	5	28.00	$1,061.32	$29,717.00
		EA	6	3	10.00	$500.00	$5,000.00
		EA	7	4	51.00	$1,251.96	$63,850.00
		EA	11	1	5.00	$1,550.00	$7,750.00
		EA	12	4	22.00	$1,420.45	$31,250.00
	Unit Sub Total	**EA**		**18**	**117.00**	**$1,185.19**	**$138,667.00**
	Item Code 155003 Total No. of Proj.			**18**		**Total Amount**	**$138,667.00**
155006	CAP RISER	EA	11	1	5.00	$600.00	$3,000.00
	Unit Sub Total	**EA**		**1**	**5.00**	**$600.00**	**$3,000.00**
	Item Code 155006 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
155007	CAP MANHOLE	EA	4	1	2.00	$1,300.00	$2,600.00
		EA	7	1	1.00	$1,680.00	$1,680.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$1,426.67**	**$4,280.00**
	Item Code 155007 Total No. of Proj.			**2**		**Total Amount**	**$4,280.00**
155115	18" ALTERNATIVE PIPELINER	LF	3	3	1,290.00	$125.38	$161,740.00
	Unit Sub Total	**LF**		**3**	**1,290.00**	**$125.38**	**$161,740.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 155115 Total No. of Proj.			**3**		**Total Amount**	**$161,740.00**
155121	24" ALTERNATIVE PIPELINER	LF	3	3	1,065.00	$141.22	$150,400.00
	Unit Sub Total	**LF**		**3**	**1,065.00**	**$141.22**	**$150,400.00**
	Item Code 155121 Total No. of Proj.			**3**		**Total Amount**	**$150,400.00**
155210	CLEANING, INSPECTING AND PREPARING HOST PIPE	CY	6	1	49.00	$104.00	$5,096.00
	Unit Sub Total	**CY**		**1**	**49.00**	**$104.00**	**$5,096.00**
155210	CLEANING, INSPECTING AND PREPARING HOST PIPE	LF	3	1	1,550.00	$7.15	$11,082.50
		LF	7	1	2,900.00	$13.00	$37,700.00
		LF	12	1	950.00	$5.00	$4,750.00
	Unit Sub Total	**LF**		**3**	**5,400.00**	**$9.91**	**$53,532.50**
	Item Code 155210 Total No. of Proj.			**4**		**Total Amount**	**$58,628.50**
155230	CONCRETE INVERT PAVING	CY	3	1	31.00	$1,213.00	$37,603.00
		CY	6	1	22.00	$1,400.00	$30,800.00
	Unit Sub Total	**CY**		**2**	**53.00**	**$1,290.62**	**$68,403.00**
	Item Code 155230 Total No. of Proj.			**2**		**Total Amount**	**$68,403.00**
155314	18" CURED-IN-PLACE PIPELINER	LF	6	1	69.00	$154.00	$10,626.00
		LF	7	1	1,240.00	$88.00	$109,120.00
	Unit Sub Total	**LF**		**2**	**1,309.00**	**$91.48**	**$119,746.00**
	Item Code 155314 Total No. of Proj.			**2**		**Total Amount**	**$119,746.00**
155316	24" CURED-IN-PLACE PIPELINER	LF	3	2	610.00	$151.11	$92,180.00
		LF	6	1	1,400.00	$154.00	$215,600.00
		LF	7	1	1,220.00	$73.00	$89,060.00
	Unit Sub Total	**LF**		**4**	**3,230.00**	**$122.86**	**$396,840.00**
	Item Code 155316 Total No. of Proj.			**4**		**Total Amount**	**$396,840.00**
155318	30" CURED-IN-PLACE PIPELINER	LF	6	1	180.00	$185.00	$33,300.00
		LF	7	1	190.00	$173.00	$32,870.00
	Unit Sub Total	**LF**		**2**	**370.00**	**$178.84**	**$66,170.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 155318 Total No. of Proj.			**2**		**Total Amount**	**$66,170.00**
155319	36" CURED-IN-PLACE PIPELINER	LF	6	1	200.00	$220.00	$44,000.00
		LF	7	1	240.00	$184.00	$44,160.00
	Unit Sub Total	**LF**		**2**	**440.00**	**$200.36**	**$88,160.00**
	Item Code 155319 Total No. of Proj.			**2**		**Total Amount**	**$88,160.00**
155320	42" CURED-IN-PLACE PIPELINER	LF	5	1	190.00	$619.00	$117,610.00
	Unit Sub Total	**LF**		**1**	**190.00**	**$619.00**	**$117,610.00**
	Item Code 155320 Total No. of Proj.			**1**		**Total Amount**	**$117,610.00**
155321	48" CURED-IN-PLACE PIPELINER	LF	6	1	68.00	$400.00	$27,200.00
	Unit Sub Total	**LF**		**1**	**68.00**	**$400.00**	**$27,200.00**
	Item Code 155321 Total No. of Proj.			**1**		**Total Amount**	**$27,200.00**
155369	30" MACHINE SPIRAL WOUND PVC PIPELINER (EXPANDABLE DIAMETER)	LF	4	1	160.00	$400.00	$64,000.00
	Unit Sub Total	**LF**		**1**	**160.00**	**$400.00**	**$64,000.00**
	Item Code 155369 Total No. of Proj.			**1**		**Total Amount**	**$64,000.00**
156535	REMOVE BOX CULVERT	EA	10	1	1.00	$6,000.00	$6,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$6,000.00**	**$6,000.00**
156535	REMOVE BOX CULVERT	LF	2	1	170.00	$116.43	$19,793.10
	Unit Sub Total	**LF**		**1**	**170.00**	**$116.43**	**$19,793.10**
156535	REMOVE BOX CULVERT	M3	6	1	93.00	$75.00	$6,975.00
	Unit Sub Total	**M3**		**1**	**93.00**	**$75.00**	**$6,975.00**
	Item Code 156535 Total No. of Proj.			**3**		**Total Amount**	**$32,768.10**
156572	REMOVE RAILING	LS	2	1	1.00	$700.00	$700.00
		LS	3	1	1.00	$1,440.00	$1,440.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$1,070.00**	**$2,140.00**
	Item Code 156572 Total No. of Proj.			**2**		**Total Amount**	**$2,140.00**
156576	REMOVE METAL RAILING	LF	2	1	4.60	$200.00	$920.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
156576	REMOVE METAL RAILING	LF	4	1	100.00	$45.00	$4,500.00
		LF	7	1	43.00	$9.00	$387.00
	Unit Sub Total	**LF**		**3**	**147.60**	**$39.34**	**$5,807.00**
156576	REMOVE METAL RAILING	M	7	1	15.00	$26.00	$390.00
	Unit Sub Total	**M**		**1**	**15.00**	**$26.00**	**$390.00**
	Item Code 156576 Total No. of Proj.			**4**		**Total Amount**	**$6,197.00**
156577	REMOVE BARRIER RAILING	LF	11	1	24,600.00	$6.00	$147,600.00
	Unit Sub Total	**LF**		**1**	**24,600.00**	**$6.00**	**$147,600.00**
	Item Code 156577 Total No. of Proj.			**1**		**Total Amount**	**$147,600.00**
156585	REMOVE CRASH CUSHION	EA	2	2	3.00	$1,666.67	$5,000.00
		EA	3	1	9.00	$1,750.00	$15,750.00
		EA	4	2	44.00	$173.18	$7,620.00
		EA	6	1	1.00	$500.00	$500.00
		EA	7	3	52.00	$70.00	$3,640.00
		EA	12	1	1.00	$1,000.00	$1,000.00
	Unit Sub Total	**EA**		**10**	**110.00**	**$304.64**	**$33,510.00**
	Item Code 156585 Total No. of Proj.			**10**		**Total Amount**	**$33,510.00**
156590	REMOVE CRASH CUSHION (SAND FILLED)	EA	2	1	1.00	$2,840.00	$2,840.00
		EA	3	2	33.00	$380.00	$12,540.00
		EA	4	1	22.00	$60.00	$1,320.00
		EA	5	1	1.00	$3,000.00	$3,000.00
		EA	6	3	4.00	$1,475.00	$5,900.00
		EA	7	1	5.00	$300.00	$1,500.00
		EA	12	2	2.00	$2,070.00	$4,140.00
	Unit Sub Total	**EA**		**11**	**68.00**	**$459.41**	**$31,240.00**
	Item Code 156590 Total No. of Proj.			**11**		**Total Amount**	**$31,240.00**
157550	BRIDGE REMOVAL	LS	2	2	2.00	$287,500.00	$575,000.00
		LS	4	2	2.00	$125,000.00	$250,000.00
		LS	6	2	2.00	$66,000.00	$132,000.00
		LS	7	1	1.00	$320,000.00	$320,000.00
		LS	10	2	2.00	$115,500.00	$231,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
157550	BRIDGE REMOVAL	LS	11	1	1.00	$41,000.00	$41,000.00
	Unit Sub Total	**LS**		**10**	**10.00**	**$154,900.00**	**$1,549,000.00**
	Item Code 157550 Total No. of Proj.			**10**		**Total Amount**	**$1,549,000.00**
157551	BRIDGE REMOVAL, LOCATION A	LS	4	2	2.00	$107,500.00	$215,000.00
		LS	7	1	1.00	$20,000.00	$20,000.00
		LS	12	2	2.00	$168,500.00	$337,000.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$114,400.00**	**$572,000.00**
	Item Code 157551 Total No. of Proj.			**5**		**Total Amount**	**$572,000.00**
157552	BRIDGE REMOVAL, LOCATION B	LS	4	2	2.00	$95,000.00	$190,000.00
		LS	7	1	1.00	$10,000.00	$10,000.00
		LS	12	2	2.00	$198,500.00	$397,000.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$119,400.00**	**$597,000.00**
	Item Code 157552 Total No. of Proj.			**5**		**Total Amount**	**$597,000.00**
157553	BRIDGE REMOVAL, LOCATION C	LS	4	1	1.00	$140,000.00	$140,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$140,000.00**	**$140,000.00**
	Item Code 157553 Total No. of Proj.			**1**		**Total Amount**	**$140,000.00**
157554	BRIDGE REMOVAL, LOCATION D	LS	4	1	1.00	$100,000.00	$100,000.00
		LS	12	1	1.00	$71,500.00	$71,500.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$85,750.00**	**$171,500.00**
	Item Code 157554 Total No. of Proj.			**2**		**Total Amount**	**$171,500.00**
157555	BRIDGE REMOVAL, LOCATION E	LS	12	1	1.00	$116,500.00	$116,500.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$116,500.00**	**$116,500.00**
	Item Code 157555 Total No. of Proj.			**1**		**Total Amount**	**$116,500.00**
157560	BRIDGE REMOVAL (PORTION)	CY	10	1	15.00	$955.00	$14,325.00
	Unit Sub Total	**CY**		**1**	**15.00**	**$955.00**	**$14,325.00**
157560	BRIDGE REMOVAL (PORTION)	LS	1	2	2.00	$26,000.00	$52,000.00
		LS	2	3	3.00	$22,333.33	$67,000.00
		LS	3	3	3.00	$7,316.67	$21,950.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
157560	BRIDGE REMOVAL (PORTION)	LS	4	9	9.00	$30,533.33	$274,800.00
		LS	5	2	2.00	$16,000.00	$32,000.00
		LS	7	4	4.00	$43,940.00	$175,760.00
		LS	8	3	3.00	$3,966.67	$11,900.00
		LS	9	1	1.00	$6,700.00	$6,700.00
		LS	10	2	2.00	$21,750.00	$43,500.00
		LS	11	2	2.00	$32,750.00	$65,500.00
		LS	12	1	1.00	$35,000.00	$35,000.00
	Unit Sub Total	**LS**		**32**	**32.00**	**$24,565.94**	**$786,110.00**
	Item Code 157560 Total No. of Proj.			**33**		**Total Amount**	**$800,435.00**
157561	BRIDGE REMOVAL (PORTION), LOCATION A	LS	2	5	5.00	$18,520.00	$92,600.00
		LS	3	2	2.00	$44,500.00	$89,000.00
		LS	4	7	7.00	$193,036.86	$1,351,258.00
		LS	6	2	2.00	$27,500.00	$55,000.00
		LS	7	8	8.00	$56,487.50	$451,900.00
		LS	9	1	1.00	$28,000.00	$28,000.00
		LS	11	2	2.00	$3,055.00	$6,110.00
		LS	12	4	4.00	$15,625.00	$62,500.00
	Unit Sub Total	**LS**		**31**	**31.00**	**$68,915.10**	**$2,136,368.00**
	Item Code 157561 Total No. of Proj.			**31**		**Total Amount**	**$2,136,368.00**
157562	BRIDGE REMOVAL (PORTION), LOCATION B	LS	2	4	4.00	$15,675.00	$62,700.00
		LS	3	2	2.00	$17,500.00	$35,000.00
		LS	4	7	7.00	$230,875.00	$1,616,125.00
		LS	6	2	2.00	$22,500.00	$45,000.00
		LS	7	8	8.00	$14,768.75	$118,150.00
		LS	9	1	1.00	$42,000.00	$42,000.00
		LS	11	2	2.00	$4,850.00	$9,700.00
		LS	12	4	4.00	$9,100.00	$36,400.00
	Unit Sub Total	**LS**		**30**	**30.00**	**$65,502.50**	**$1,965,075.00**
	Item Code 157562 Total No. of Proj.			**30**		**Total Amount**	**$1,965,075.00**
157563	BRIDGE REMOVAL (PORTION), LOCATION C	LS	2	1	1.00	$7,900.00	$7,900.00
		LS	3	1	1.00	$5,000.00	$5,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
157563	BRIDGE REMOVAL (PORTION), LOCATION C	LS	4	1	1.00	$2,320,000.00	$2,320,000.00
		LS	6	2	2.00	$32,500.00	$65,000.00
		LS	7	4	4.00	$49,037.50	$196,150.00
		LS	12	3	3.00	$12,500.00	$37,500.00
	Unit Sub Total	**LS**		**12**	**12.00**	**$219,295.83**	**$2,631,550.00**
	Item Code 157563 Total No. of Proj.			**12**		**Total Amount**	**$2,631,550.00**
157564	BRIDGE REMOVAL (PORTION), LOCATION D	LS	2	1	1.00	$7,900.00	$7,900.00
		LS	3	1	1.00	$5,000.00	$5,000.00
		LS	4	1	1.00	$10,000.00	$10,000.00
		LS	7	4	4.00	$32,437.50	$129,750.00
		LS	12	2	2.00	$15,000.00	$30,000.00
	Unit Sub Total	**LS**		**9**	**9.00**	**$20,294.44**	**$182,650.00**
	Item Code 157564 Total No. of Proj.			**9**		**Total Amount**	**$182,650.00**
157565	BRIDGE REMOVAL (PORTION), LOCATION E	LS	3	1	1.00	$5,000.00	$5,000.00
		LS	7	3	3.00	$22,850.00	$68,550.00
		LS	12	2	2.00	$22,500.00	$45,000.00
	Unit Sub Total	**LS**		**6**	**6.00**	**$19,758.33**	**$118,550.00**
	Item Code 157565 Total No. of Proj.			**6**		**Total Amount**	**$118,550.00**
157566	BRIDGE REMOVAL (PORTION), LOCATION F	LS	3	1	1.00	$5,000.00	$5,000.00
		LS	7	3	3.00	$47,800.00	$143,400.00
		LS	12	2	2.00	$12,500.00	$25,000.00
	Unit Sub Total	**LS**		**6**	**6.00**	**$28,900.00**	**$173,400.00**
	Item Code 157566 Total No. of Proj.			**6**		**Total Amount**	**$173,400.00**
157567	BRIDGE REMOVAL (PORTION), LOCATION G	LS	3	1	1.00	$5,000.00	$5,000.00
		LS	7	2	2.00	$280,125.00	$560,250.00
		LS	12	1	1.00	$8,500.00	$8,500.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$143,437.50**	**$573,750.00**
	Item Code 157567 Total No. of Proj.			**4**		**Total Amount**	**$573,750.00**
157568	BRIDGE REMOVAL (PORTION), LOCATION H	LS	3	1	1.00	$5,000.00	$5,000.00
		LS	7	2	2.00	$43,625.00	$87,250.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LS**		**3**	**3.00**	**$30,750.00**	**$92,250.00**
	Item Code 157568 Total No. of Proj.			**3**		**Total Amount**	**$92,250.00**
157569	BRIDGE REMOVAL (PORTION), LOCATION I	LS	3	1	1.00	$5,000.00	$5,000.00
		LS	7	1	1.00	$16,000.00	$16,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$10,500.00**	**$21,000.00**
	Item Code 157569 Total No. of Proj.			**2**		**Total Amount**	**$21,000.00**
157570	BRIDGE REMOVAL (PORTION), LOCATION J	LS	3	1	1.00	$75,000.00	$75,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$75,000.00**	**$75,000.00**
	Item Code 157570 Total No. of Proj.			**1**		**Total Amount**	**$75,000.00**
157571	BRIDGE REMOVAL (PORTION), LOCATION K	LS	3	1	1.00	$85,000.00	$85,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$85,000.00**	**$85,000.00**
	Item Code 157571 Total No. of Proj.			**1**		**Total Amount**	**$85,000.00**
157572	BRIDGE REMOVAL (PORTION), LOCATION L	LS	3	1	1.00	$108,000.00	$108,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$108,000.00**	**$108,000.00**
	Item Code 157572 Total No. of Proj.			**1**		**Total Amount**	**$108,000.00**
157573	BRIDGE REMOVAL (PORTION), LOCATION M	LS	3	1	1.00	$97,000.00	$97,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$97,000.00**	**$97,000.00**
	Item Code 157573 Total No. of Proj.			**1**		**Total Amount**	**$97,000.00**
158100	SALVAGE CRASH CUSHION	EA	5	2	4.00	$1,214.50	$4,858.00
	Unit Sub Total	**EA**		**2**	**4.00**	**$1,214.50**	**$4,858.00**
	Item Code 158100 Total No. of Proj.			**2**		**Total Amount**	**$4,858.00**
158210	RESET TEMPORARY RAILING (TYPE K)	LF	8	1	420.00	$8.00	$3,360.00
	Unit Sub Total	**LF**		**1**	**420.00**	**$8.00**	**$3,360.00**
	Item Code 158210 Total No. of Proj.			**1**		**Total Amount**	**$3,360.00**
158505	SALVAGE TERMINAL SECTION	EA	2	1	3.00	$400.00	$1,200.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$400.00**	**$1,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 158505 Total No. of Proj.			**1**		**Total Amount**	**$1,200.00**
158509	SALVAGE TERMINAL SECTION (TYPE C)	EA	5	1	8.00	$250.00	$2,000.00
	Unit Sub Total	**EA**		**1**	**8.00**	**$250.00**	**$2,000.00**
	Item Code 158509 Total No. of Proj.			**1**		**Total Amount**	**$2,000.00**
159010	RECONSTRUCT METAL RAILING (BRIDGE)	LF	4	1	1,650.00	$30.00	$49,500.00
	Unit Sub Total	**LF**		**1**	**1,650.00**	**$30.00**	**$49,500.00**
159010	RECONSTRUCT METAL RAILING (BRIDGE)	LS	7	1	1.00	$2,500.00	$2,500.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$2,500.00**	**$2,500.00**
	Item Code 159010 Total No. of Proj.			**2**		**Total Amount**	**$52,000.00**
159021	RECONSTRUCT FENDER	LS	4	1	1.00	$85,000.00	$85,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$85,000.00**	**$85,000.00**
	Item Code 159021 Total No. of Proj.			**1**		**Total Amount**	**$85,000.00**
159101	RAISE BRIDGE	LS	4	2	2.00	$1,600,000.00	$3,200,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$1,600,000.00**	**$3,200,000.00**
	Item Code 159101 Total No. of Proj.			**2**		**Total Amount**	**$3,200,000.00**
160101	CLEARING AND GRUBBING	ACRE	2	1	0.30	$10,000.00	$3,000.00
		ACRE	3	2	1.30	$17,750.15	$23,075.20
	Unit Sub Total	**ACRE**		**3**	**1.60**	**$16,297.00**	**$26,075.20**
160101	CLEARING AND GRUBBING	LS	1	14	14.00	$14,564.79	$203,907.00
		LS	2	18	18.00	$25,846.94	$465,245.00
		LS	3	18	18.00	$47,881.01	$861,858.20
		LS	4	34	34.00	$25,193.00	$856,562.00
		LS	5	11	11.00	$26,838.36	$295,222.00
		LS	6	20	20.00	$26,805.15	$536,103.00
		LS	7	12	12.00	$118,891.67	$1,426,700.00
		LS	8	8	8.00	$13,750.00	$110,000.00
		LS	9	6	6.00	$7,598.17	$45,589.00
		LS	10	9	9.00	$24,786.56	$223,079.00
		LS	11	10	10.00	$28,193.20	$281,932.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
160101	CLEARING AND GRUBBING	LS	12	12	12.00	$107,475.00	$1,289,700.00
	Unit Sub Total	**LS**		**172**	**172.00**	**$38,348.24**	**$6,595,897.20**
	Item Code 160101 Total No. of Proj.			**175**		**Total Amount**	**$6,621,972.40**
160120	REMOVE TREE	EA	10	1	68.00	$550.00	$37,400.00
	Unit Sub Total	**EA**		**1**	**68.00**	**$550.00**	**$37,400.00**
	Item Code 160120 Total No. of Proj.			**1**		**Total Amount**	**$37,400.00**
160130	REMOVE BUILDING	EA	6	1	1.00	$15,000.00	$15,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$15,000.00**	**$15,000.00**
	Item Code 160130 Total No. of Proj.			**1**		**Total Amount**	**$15,000.00**
170101	DEVELOP WATER SUPPLY	LS	1	1	1.00	$500.00	$500.00
		LS	2	8	8.00	$12,437.50	$99,500.00
		LS	3	2	2.00	$6,250.00	$12,500.00
		LS	4	8	8.00	$11,168.75	$89,350.00
		LS	5	1	1.00	$100,000.00	$100,000.00
		LS	6	1	1.00	$40,500.00	$40,500.00
		LS	7	2	2.00	$45,000.00	$90,000.00
		LS	10	2	2.00	$12,000.00	$24,000.00
		LS	11	4	4.00	$47,000.00	$188,000.00
		LS	12	3	3.00	$105,000.00	$315,000.00
	Unit Sub Total	**LS**		**32**	**32.00**	**$29,979.69**	**$959,350.00**
	Item Code 170101 Total No. of Proj.			**32**		**Total Amount**	**$959,350.00**
190101	ROADWAY EXCAVATION	CY	1	16	36,988.00	$20.86	$771,585.00
		CY	2	21	154,217.00	$13.20	$2,035,634.04
		CY	3	15	225,891.00	$22.77	$5,143,987.40
		CY	4	25	329,228.00	$11.02	$3,629,061.00
		CY	5	11	1,992,259.00	$2.93	$5,833,801.00
		CY	6	22	357,801.00	$12.91	$4,618,348.50
		CY	7	9	3,131.00	$35.44	$110,960.00
		CY	8	9	50,665.00	$18.60	$942,290.00
		CY	9	8	6,553.00	$26.55	$173,988.10
		CY	10	8	167,300.00	$8.45	$1,412,862.50

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
190101	ROADWAY EXCAVATION	CY	11	11	17,664.00	$38.15	$673,797.00
		CY	12	11	703,610.00	$16.05	$11,295,315.00
	Unit Sub Total	**CY**		**166**	**4,045,307.00**	**$9.06**	**$36,641,629.54**
190101	ROADWAY EXCAVATION	M3	2	1	2,300.00	$30.00	$69,000.00
		M3	3	1	43,200.00	$15.00	$648,000.00
		M3	4	3	175,080.00	$8.76	$1,533,475.00
		M3	6	3	318,540.00	$6.16	$1,963,604.00
		M3	7	6	194,100.00	$23.27	$4,517,175.00
		M3	10	1	28,800.00	$17.00	$489,600.00
		M3	11	2	466,400.00	$8.19	$3,820,450.00
	Unit Sub Total	**M3**		**17**	**1,228,420.00**	**$10.62**	**$13,041,304.00**
	Item Code 190101 Total No. of Proj.			**183**		**Total Amount**	**$49,682,933.54**
190105	ROADWAY EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	CY	4	6	6,450.00	$141.54	$912,950.00
		CY	6	2	3,270.00	$220.70	$721,680.00
		CY	7	3	612.50	$51.09	$31,290.00
		CY	11	1	2,860.00	$122.00	$348,920.00
	Unit Sub Total	**CY**		**12**	**13,192.50**	**$152.73**	**$2,014,840.00**
190105	ROADWAY EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	M3	7	1	190.00	$135.00	$25,650.00
	Unit Sub Total	**M3**		**1**	**190.00**	**$135.00**	**$25,650.00**
	Item Code 190105 Total No. of Proj.			**13**		**Total Amount**	**$2,040,490.00**
190106	ROADWAY EXCAVATION (TYPE Z-3) (AERIALLY DEPOSITED LEAD)	CY	12	2	5,320.00	$202.27	$1,076,100.00
	Unit Sub Total	**CY**		**2**	**5,320.00**	**$202.27**	**$1,076,100.00**
190106	ROADWAY EXCAVATION (TYPE Z-3) (AERIALLY DEPOSITED LEAD)	M3	7	4	3,680.00	$151.07	$555,950.00
	Unit Sub Total	**M3**		**4**	**3,680.00**	**$151.07**	**$555,950.00**
	Item Code 190106 Total No. of Proj.			**6**		**Total Amount**	**$1,632,050.00**
190107	ROADWAY EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)	CY	3	1	270.00	$25.00	$6,750.00
		CY	4	2	3,980.00	$21.07	$83,840.00
		CY	12	7	43,394.00	$12.19	$528,910.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**CY**		**10**	**47,644.00**	**$13.00**	**$619,500.00**
190107	ROADWAY EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)		M3	7	3	18,950.00	$21.56	$408,560.00
			M3	11	1	4,160.00	$9.25	$38,480.00
		Unit Sub Total	**M3**		**4**	**23,110.00**	**$19.34**	**$447,040.00**
	Item Code 190107	**Total No. of Proj.**			**14**		**Total Amount**	**$1,066,540.00**
190108	ROADWAY EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD)		CY	11	1	2,270.00	$65.00	$147,550.00
			CY	12	2	4,430.00	$6.77	$30,000.00
		Unit Sub Total	**CY**		**3**	**6,700.00**	**$26.50**	**$177,550.00**
190108	ROADWAY EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD)		M3	7	3	14,880.00	$21.86	$325,210.00
		Unit Sub Total	**M3**		**3**	**14,880.00**	**$21.86**	**$325,210.00**
	Item Code 190108	**Total No. of Proj.**			**6**		**Total Amount**	**$502,760.00**
190109	ROADWAY EXCAVATION (NATURALLY OCCURRING ASBESTOS)		CY	2	1	2,970.00	$7.00	$20,790.00
			CY	4	1	26,500.00	$10.00	$265,000.00
			CY	10	1	1,500.00	$8.00	$12,000.00
		Unit Sub Total	**CY**		**3**	**30,970.00**	**$9.62**	**$297,790.00**
	Item Code 190109	**Total No. of Proj.**			**3**		**Total Amount**	**$297,790.00**
190110	LEAD COMPLIANCE PLAN		LS	1	41	41.00	$1,959.51	$80,340.00
			LS	2	43	43.00	$2,204.88	$94,809.88
			LS	3	53	53.00	$1,801.83	$95,497.00
			LS	4	63	63.00	$2,640.08	$166,325.00
			LS	5	31	31.00	$1,516.90	$47,024.00
			LS	6	41	41.00	$2,973.32	$121,906.00
			LS	7	54	54.00	$3,356.91	$181,273.00
			LS	8	32	32.00	$2,287.09	$73,187.00
			LS	9	15	15.00	$1,453.40	$21,801.00
			LS	10	42	42.00	$2,285.00	$95,970.00
			LS	11	30	30.00	$2,497.60	$74,928.00
			LS	12	28	28.00	$2,927.77	$81,977.50
		Unit Sub Total	**LS**		**473**	**473.00**	**$2,399.66**	**$1,135,038.38**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 190110 Total No. of Proj.			**473**		**Total Amount**	**$1,135,038.38**
190111	ADL BURIAL LOCATION REPORT	LS	3	1	1.00	$2,500.00	$2,500.00
		LS	4	3	3.00	$4,500.00	$13,500.00
		LS	11	2	2.00	$5,250.00	$10,500.00
		LS	12	5	5.00	$9,100.00	$45,500.00
	Unit Sub Total	**LS**		**11**	**11.00**	**$6,545.45**	**$72,000.00**
	Item Code 190111 Total No. of Proj.			**11**		**Total Amount**	**$72,000.00**
190113	ASBESTOS COMPLIANCE PLAN	LS	2	4	4.00	$2,725.00	$10,900.00
		LS	3	2	2.00	$2,750.00	$5,500.00
		LS	4	2	2.00	$1,525.00	$3,050.00
		LS	6	3	3.00	$1,833.33	$5,500.00
		LS	10	2	2.00	$5,500.00	$11,000.00
	Unit Sub Total	**LS**		**13**	**13.00**	**$2,765.38**	**$35,950.00**
	Item Code 190113 Total No. of Proj.			**13**		**Total Amount**	**$35,950.00**
190114	DUST CONTROL PLAN	LS	3	2	2.00	$1,250.00	$2,500.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$1,250.00**	**$2,500.00**
	Item Code 190114 Total No. of Proj.			**2**		**Total Amount**	**$2,500.00**
190115	ASBESTOS COMPLIANCE PLAN (NATURALLY OCCURING ASBESTOS)	LS	1	8	8.00	$2,977.50	$23,820.00
		LS	2	1	1.00	$1,500.00	$1,500.00
		LS	4	4	4.00	$2,500.00	$10,000.00
		LS	10	2	2.00	$2,137.50	$4,275.00
	Unit Sub Total	**LS**		**15**	**15.00**	**$2,639.67**	**$39,595.00**
	Item Code 190115 Total No. of Proj.			**15**		**Total Amount**	**$39,595.00**
190116	DUST CONTROL PLAN (NATURALLY OCCURRING ASBESTOS)	LS	1	7	7.00	$1,928.57	$13,500.00
		LS	2	1	1.00	$1,000.00	$1,000.00
		LS	4	5	5.00	$1,600.00	$8,000.00
		LS	10	2	2.00	$1,337.50	$2,675.00
	Unit Sub Total	**LS**		**15**	**15.00**	**$1,678.33**	**$25,175.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 190116 Total No. of Proj.			**15**		**Total Amount**	**$25,175.00**
190117	SAMPLING AND ANALYSIS PLAN (NATURALLY OCCURRING ASBESTOS)	LS	1	2	2.00	$6,900.00	$13,800.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$6,900.00**	**$13,800.00**
	Item Code 190117 Total No. of Proj.			**2**		**Total Amount**	**$13,800.00**
190160	ROCK EXCAVATION (CONTROLLED BLASTING)	CY	10	1	9,620.00	$125.00	$1,202,500.00
	Unit Sub Total	**CY**		**1**	**9,620.00**	**$125.00**	**$1,202,500.00**
190160	ROCK EXCAVATION (CONTROLLED BLASTING)	M3	2	1	21,000.00	$20.00	$420,000.00
	Unit Sub Total	**M3**		**1**	**21,000.00**	**$20.00**	**$420,000.00**
	Item Code 190160 Total No. of Proj.			**2**		**Total Amount**	**$1,622,500.00**
190161	ROCK EXCAVATION	CY	2	2	111,100.00	$14.03	$1,558,300.00
		CY	4	1	22.00	$250.00	$5,500.00
	Unit Sub Total	**CY**		**3**	**111,122.00**	**$14.07**	**$1,563,800.00**
190161	ROCK EXCAVATION	M3	4	1	70.00	$350.00	$24,500.00
	Unit Sub Total	**M3**		**1**	**70.00**	**$350.00**	**$24,500.00**
	Item Code 190161 Total No. of Proj.			**4**		**Total Amount**	**$1,588,300.00**
190162	STRIPPING EXCAVATION	M3	2	1	77.00	$200.00	$15,400.00
	Unit Sub Total	**M3**		**1**	**77.00**	**$200.00**	**$15,400.00**
	Item Code 190162 Total No. of Proj.			**1**		**Total Amount**	**$15,400.00**
190167	REMOVE UNSUITABLE MATERIAL	CY	7	1	102.00	$50.00	$5,100.00
	Unit Sub Total	**CY**		**1**	**102.00**	**$50.00**	**$5,100.00**
	Item Code 190167 Total No. of Proj.			**1**		**Total Amount**	**$5,100.00**
190170	DRILL HOLE (PRESPLITTING)	LF	2	1	15,000.00	$7.20	$108,000.00
		LF	10	1	48,400.00	$7.00	$338,800.00
	Unit Sub Total	**LF**		**2**	**63,400.00**	**$7.05**	**$446,800.00**
	Item Code 190170 Total No. of Proj.			**2**		**Total Amount**	**$446,800.00**
190185	SHOULDER BACKING	TON	3	1	60.00	$48.00	$2,880.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
190185	SHOULDER BACKING		TON	4	1	28.00	$125.00	$3,500.00
			TON	6	1	2,170.00	$25.00	$54,250.00
		Unit Sub Total	**TON**		**3**	**2,258.00**	**$26.85**	**$60,630.00**
	Item Code 190185	**Total No. of Proj.**			**3**		**Total Amount**	**$60,630.00**
192001	STRUCTURE EXCAVATION		CY	4	1	330.00	$50.00	$16,500.00
			CY	9	1	46.00	$40.00	$1,840.00
		Unit Sub Total	**CY**		**2**	**376.00**	**$48.78**	**$18,340.00**
192001	STRUCTURE EXCAVATION		M3	3	1	410.00	$1.00	$410.00
			M3	7	2	2,063.00	$15.54	$32,060.00
		Unit Sub Total	**M3**		**3**	**2,473.00**	**$13.13**	**$32,470.00**
	Item Code 192001	**Total No. of Proj.**			**5**		**Total Amount**	**$50,810.00**
192003	STRUCTURE EXCAVATION (BRIDGE)		CY	1	1	69.00	$380.00	$26,220.00
			CY	2	3	3,167.00	$108.74	$344,390.00
			CY	3	2	918.00	$95.42	$87,592.00
			CY	4	4	3,805.00	$34.94	$132,940.00
			CY	5	2	2,018.00	$42.72	$86,200.00
			CY	6	3	2,087.00	$47.92	$100,015.00
			CY	9	1	75.00	$100.00	$7,500.00
			CY	11	3	608.00	$63.48	$38,595.00
			CY	12	6	50,127.00	$38.84	$1,947,031.00
		Unit Sub Total	**CY**		**25**	**62,874.00**	**$44.06**	**$2,770,483.00**
192003	STRUCTURE EXCAVATION (BRIDGE)		M3	2	1	695.00	$50.00	$34,750.00
			M3	4	3	20,770.00	$110.67	$2,298,650.00
			M3	7	5	6,757.00	$60.54	$409,100.00
			M3	10	1	930.00	$35.00	$32,550.00
			M3	11	2	710.00	$56.20	$39,900.00
		Unit Sub Total	**M3**		**12**	**29,862.00**	**$94.27**	**$2,814,950.00**
	Item Code 192003	**Total No. of Proj.**			**37**		**Total Amount**	**$5,585,433.00**
192008	STRUCTURE EXCAVATION (TYPE A)		CY	12	1	420.00	$55.00	$23,100.00
		Unit Sub Total	**CY**		**1**	**420.00**	**$55.00**	**$23,100.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 192008 Total No. of Proj.			**1**		**Total Amount**	**$23,100.00**
192009	STRUCTURE EXCAVATION (NATURALLY OCCURRING ASBESTOS)	CY	4	1	445.00	$98.00	$43,610.00
	Unit Sub Total	**CY**		**1**	**445.00**	**$98.00**	**$43,610.00**
	Item Code 192009 Total No. of Proj.			**1**		**Total Amount**	**$43,610.00**
192020	STRUCTURE EXCAVATION (TYPE D)	CY	3	1	98.00	$2,000.00	$196,000.00
		CY	6	1	30.00	$217.00	$6,510.00
		CY	8	1	330.00	$43.00	$14,190.00
		CY	10	1	240.00	$48.00	$11,520.00
	Unit Sub Total	**CY**		**4**	**698.00**	**$326.96**	**$228,220.00**
192020	STRUCTURE EXCAVATION (TYPE D)	M3	2	1	440.00	$80.00	$35,200.00
		M3	11	1	125.00	$205.00	$25,625.00
	Unit Sub Total	**M3**		**2**	**565.00**	**$107.65**	**$60,825.00**
	Item Code 192020 Total No. of Proj.			**6**		**Total Amount**	**$289,045.00**
192023	STRUCTURE EXCAVATION (TYPE H)	M3	4	1	266.00	$400.00	$106,400.00
	Unit Sub Total	**M3**		**1**	**266.00**	**$400.00**	**$106,400.00**
	Item Code 192023 Total No. of Proj.			**1**		**Total Amount**	**$106,400.00**
192025	STRUCTURE EXCAVATION (CULVERT)	CY	10	1	120.00	$20.00	$2,400.00
		CY	12	1	430.00	$20.00	$8,600.00
	Unit Sub Total	**CY**		**2**	**550.00**	**$20.00**	**$11,000.00**
	Item Code 192025 Total No. of Proj.			**2**		**Total Amount**	**$11,000.00**
192027	STRUCTURE BACKFILL (PUMPING PLANT)	CY	4	1	310.00	$60.00	$18,600.00
	Unit Sub Total	**CY**		**1**	**310.00**	**$60.00**	**$18,600.00**
	Item Code 192027 Total No. of Proj.			**1**		**Total Amount**	**$18,600.00**
192032	STRUCTURE EXCAVATION (ROCK SLOPE PROTECTION)	M3	4	1	2,100.00	$17.00	$35,700.00
	Unit Sub Total	**M3**		**1**	**2,100.00**	**$17.00**	**$35,700.00**
	Item Code 192032 Total No. of Proj.			**1**		**Total Amount**	**$35,700.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
192035	STRUCTURE EXCAVATION (ROCK)	CY	4	1	21,590.00	$40.00	$863,600.00
	Unit Sub Total	**CY**		**1**	**21,590.00**	**$40.00**	**$863,600.00**
	Item Code 192035 Total No. of Proj.			**1**		**Total Amount**	**$863,600.00**
192036	STRUCTURE EXCAVATION (CRIB WALL)	CY	5	1	200.00	$48.00	$9,600.00
		CY	9	1	330.00	$56.00	$18,480.00
	Unit Sub Total	**CY**		**2**	**530.00**	**$52.98**	**$28,080.00**
192036	STRUCTURE EXCAVATION (CRIB WALL)	M3	7	1	4.00	$60.00	$240.00
	Unit Sub Total	**M3**		**1**	**4.00**	**$60.00**	**$240.00**
	Item Code 192036 Total No. of Proj.			**3**		**Total Amount**	**$28,320.00**
192037	STRUCTURE EXCAVATION (RETAINING WALL)	CY	4	7	23,321.00	$22.21	$517,994.50
		CY	5	2	3,240.00	$31.94	$103,480.00
		CY	6	4	22,882.00	$16.03	$366,816.00
		CY	8	1	11,115.00	$10.00	$111,150.00
		CY	10	1	18,104.00	$10.75	$194,618.00
		CY	11	1	845.00	$70.00	$59,150.00
		CY	12	6	46,000.00	$27.59	$1,269,289.00
	Unit Sub Total	**CY**		**22**	**125,507.00**	**$20.90**	**$2,622,497.50**
192037	STRUCTURE EXCAVATION (RETAINING WALL)	M3	4	3	20,158.00	$37.01	$746,049.00
		M3	7	5	37,014.90	$34.00	$1,258,588.77
		M3	10	1	40.00	$12.00	$480.00
	Unit Sub Total	**M3**		**9**	**57,212.90**	**$35.05**	**$2,005,117.77**
	Item Code 192037 Total No. of Proj.			**31**		**Total Amount**	**$4,627,615.27**
192038	STRUCTURE EXCAVATION (SOUND WALL)	CY	4	1	140.00	$25.00	$3,500.00
	Unit Sub Total	**CY**		**1**	**140.00**	**$25.00**	**$3,500.00**
	Item Code 192038 Total No. of Proj.			**1**		**Total Amount**	**$3,500.00**
192049	STRUCTURE EXCAVATION (SOLDIER PILE WALL)	CY	1	4	2,899.00	$30.24	$87,671.00
		CY	4	3	4,183.00	$26.80	$112,111.00
		CY	5	2	2,794.00	$180.46	$504,200.00
		CY	12	1	88.00	$45.00	$3,960.00
	Unit Sub Total	**CY**		**10**	**9,964.00**	**$71.05**	**$707,942.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 192049 Total No. of Proj.			**10**		**Total Amount**	**$707,942.00**
192050	STRUCTURE EXCAVATION (TIEBACK WALL)	CY	4	1	2,180.00	$25.00	$54,500.00
		CY	6	1	125.00	$40.00	$5,000.00
		CY	12	2	903.00	$42.45	$38,331.00
	Unit Sub Total	**CY**		**4**	**3,208.00**	**$30.50**	**$97,831.00**
	Item Code 192050 Total No. of Proj.			**4**		**Total Amount**	**$97,831.00**
192053	STRUCTURE EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	CY	4	1	210.00	$135.00	$28,350.00
		CY	7	1	4.00	$500.00	$2,000.00
		CY	11	1	285.00	$125.00	$35,625.00
	Unit Sub Total	**CY**		**3**	**499.00**	**$132.21**	**$65,975.00**
192053	STRUCTURE EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)	M3	7	1	17.00	$135.00	$2,295.00
	Unit Sub Total	**M3**		**1**	**17.00**	**$135.00**	**$2,295.00**
	Item Code 192053 Total No. of Proj.			**4**		**Total Amount**	**$68,270.00**
192054	STRUCTURE EXCAVATION (TYPE Z-3) (AERIALLY DEPOSITED LEAD)	M3	7	4	1,007.80	$280.43	$282,618.00
	Unit Sub Total	**M3**		**4**	**1,007.80**	**$280.43**	**$282,618.00**
	Item Code 192054 Total No. of Proj.			**4**		**Total Amount**	**$282,618.00**
192055	STRUCTURE EXCAVATION (SOIL NAIL WALL)	CY	4	1	2,698.00	$30.00	$80,940.00
	Unit Sub Total	**CY**		**1**	**2,698.00**	**$30.00**	**$80,940.00**
	Item Code 192055 Total No. of Proj.			**1**		**Total Amount**	**$80,940.00**
192057	STRUCTURE EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)	CY	12	2	4,922.00	$26.47	$130,280.00
	Unit Sub Total	**CY**		**2**	**4,922.00**	**$26.47**	**$130,280.00**
192057	STRUCTURE EXCAVATION (TYPE Y-1) (AERIALLY DEPOSITED LEAD)	M3	7	3	23,788.60	$31.46	$748,272.73
	Unit Sub Total	**M3**		**3**	**23,788.60**	**$31.46**	**$748,272.73**
	Item Code 192057 Total No. of Proj.			**5**		**Total Amount**	**$878,552.73**
192058	STRUCTURE EXCAVATION (TYPE Y-2) (AERIALLY DEPOSITED LEAD)	M3	7	4	22,741.00	$34.32	$780,500.20

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M3**		**4**	**22,741.00**	**$34.32**	**$780,500.20**
	Item Code 192058	**Total No. of Proj.**			**4**		**Total Amount**	**$780,500.20**
192502	SAND BEDDING		CY	5	1	180.00	$220.00	$39,600.00
		Unit Sub Total	**CY**		**1**	**180.00**	**$220.00**	**$39,600.00**
	Item Code 192502	**Total No. of Proj.**			**1**		**Total Amount**	**$39,600.00**
193001	STRUCTURE BACKFILL		CY	4	2	2,480.00	$31.85	$79,000.00
			CY	9	1	10.00	$50.00	$500.00
		Unit Sub Total	**CY**		**3**	**2,490.00**	**$31.93**	**$79,500.00**
193001	STRUCTURE BACKFILL		M3	3	1	340.00	$1.00	$340.00
			M3	7	2	657.20	$30.00	$19,716.00
		Unit Sub Total	**M3**		**3**	**997.20**	**$20.11**	**$20,056.00**
	Item Code 193001	**Total No. of Proj.**			**6**		**Total Amount**	**$99,556.00**
193003	STRUCTURE BACKFILL (BRIDGE)		CY	1	1	50.00	$70.00	$3,500.00
			CY	2	3	1,816.00	$89.14	$161,880.00
			CY	3	2	520.00	$26.35	$13,700.00
			CY	4	6	2,982.00	$84.70	$252,570.00
			CY	5	2	1,386.00	$89.44	$123,960.00
			CY	6	3	1,243.00	$47.31	$58,804.00
			CY	7	1	102.00	$50.00	$5,100.00
			CY	8	1	260.00	$69.00	$17,940.00
			CY	9	1	68.00	$85.00	$5,780.00
			CY	10	1	110.00	$90.00	$9,900.00
			CY	11	3	258.00	$95.54	$24,650.00
			CY	12	6	34,251.00	$39.35	$1,347,717.00
		Unit Sub Total	**CY**		**30**	**43,046.00**	**$47.05**	**$2,025,501.00**
193003	STRUCTURE BACKFILL (BRIDGE)		M3	2	1	730.00	$100.00	$73,000.00
			M3	4	3	9,262.00	$76.00	$703,910.00
			M3	7	5	8,230.00	$67.80	$558,014.00
			M3	10	1	1,310.00	$70.00	$91,700.00
			M3	11	2	550.00	$132.20	$72,710.00
		Unit Sub Total	**M3**		**12**	**20,082.00**	**$74.66**	**$1,499,334.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 193003 Total No. of Proj.			**42**		**Total Amount**	**$3,524,835.00**
193004	STRUCTURE BACKFILL (CULVERT)	CY	10	1	50.00	$20.00	$1,000.00
		CY	12	1	350.00	$30.00	$10,500.00
	Unit Sub Total	**CY**		**2**	**400.00**	**$28.75**	**$11,500.00**
193004	STRUCTURE BACKFILL (CULVERT)	M3	7	1	360.00	$60.00	$21,600.00
	Unit Sub Total	**M3**		**1**	**360.00**	**$60.00**	**$21,600.00**
	Item Code 193004 Total No. of Proj.			**3**		**Total Amount**	**$33,100.00**
193006	STRUCTURE BACKFILL (SLURRY CEMENT)	CY	4	1	985.00	$74.00	$72,890.00
		CY	5	1	130.00	$65.00	$8,450.00
		CY	12	1	190.00	$86.00	$16,340.00
	Unit Sub Total	**CY**		**3**	**1,305.00**	**$74.85**	**$97,680.00**
193006	STRUCTURE BACKFILL (SLURRY CEMENT)	M3	7	1	21.00	$500.00	$10,500.00
	Unit Sub Total	**M3**		**1**	**21.00**	**$500.00**	**$10,500.00**
	Item Code 193006 Total No. of Proj.			**4**		**Total Amount**	**$108,180.00**
193012	STRUCTURE BACKFILL (CRIB WALL)	CY	9	1	630.00	$34.00	$21,420.00
	Unit Sub Total	**CY**		**1**	**630.00**	**$34.00**	**$21,420.00**
193012	STRUCTURE BACKFILL (CRIB WALL)	M3	7	1	1,250.00	$35.50	$44,375.00
	Unit Sub Total	**M3**		**1**	**1,250.00**	**$35.50**	**$44,375.00**
	Item Code 193012 Total No. of Proj.			**2**		**Total Amount**	**$65,795.00**
193013	STRUCTURE BACKFILL (RETAINING WALL)	CY	4	8	20,309.00	$28.88	$586,613.40
		CY	5	2	4,205.00	$38.69	$162,700.00
		CY	6	4	12,930.00	$32.84	$424,569.00
		CY	8	1	8,500.00	$12.00	$102,000.00
		CY	10	1	10,594.00	$23.75	$251,607.50
		CY	11	1	775.00	$33.00	$25,575.00
		CY	12	6	43,571.00	$30.38	$1,323,760.00
	Unit Sub Total	**CY**		**23**	**100,884.00**	**$28.52**	**$2,876,824.90**
193013	STRUCTURE BACKFILL (RETAINING WALL)	M3	4	3	16,253.00	$63.90	$1,038,539.00
		M3	7	5	89,163.20	$33.74	$3,008,080.45
		M3	10	1	60.00	$60.00	$3,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M3**		**9**	**105,476.20**	**$38.40**	**$4,050,219.45**
	Item Code 193013 Total No. of Proj.			**32**		**Total Amount**	**$6,927,044.35**
193014	STRUCTURE BACKFILL (SOUND WALL)	CY	4	1	470.00	$40.00	$18,800.00
	Unit Sub Total	**CY**		**1**	**470.00**	**$40.00**	**$18,800.00**
	Item Code 193014 Total No. of Proj.			**1**		**Total Amount**	**$18,800.00**
193026	STRUCTURE BACKFILL (TIEBACK WALL)	CY	4	1	580.00	$40.00	$23,200.00
		CY	6	1	9.00	$100.00	$900.00
		CY	12	2	117.00	$106.54	$12,465.00
	Unit Sub Total	**CY**		**4**	**706.00**	**$51.79**	**$36,565.00**
	Item Code 193026 Total No. of Proj.			**4**		**Total Amount**	**$36,565.00**
193028	STRUCTURE BACKFILL (SOIL NAIL WALL)	CY	4	1	220.00	$50.00	$11,000.00
	Unit Sub Total	**CY**		**1**	**220.00**	**$50.00**	**$11,000.00**
	Item Code 193028 Total No. of Proj.			**1**		**Total Amount**	**$11,000.00**
193029	STRUCTURE BACKFILL (SOLDIER PILE WALL)	CY	1	4	923.00	$73.43	$67,775.00
		CY	4	2	167.00	$105.99	$17,700.00
		CY	5	2	427.00	$291.22	$124,350.00
		CY	12	1	72.00	$65.00	$4,680.00
	Unit Sub Total	**CY**		**9**	**1,589.00**	**$134.99**	**$214,505.00**
	Item Code 193029 Total No. of Proj.			**9**		**Total Amount**	**$214,505.00**
193030	PERVIOUS BACKFILL MATERIAL	CY	6	1	69.00	$20.00	$1,380.00
		CY	10	1	1,860.00	$44.80	$83,328.00
		CY	12	1	161.00	$65.00	$10,465.00
	Unit Sub Total	**CY**		**3**	**2,090.00**	**$45.54**	**$95,173.00**
193030	PERVIOUS BACKFILL MATERIAL	M3	4	2	276.00	$95.22	$26,280.00
	Unit Sub Total	**M3**		**2**	**276.00**	**$95.22**	**$26,280.00**
	Item Code 193030 Total No. of Proj.			**5**		**Total Amount**	**$121,453.00**
193031	PERVIOUS BACKFILL MATERIAL (RETAINING WALL)	CY	4	1	819.00	$135.00	$110,565.00
		CY	5	2	345.00	$43.12	$14,875.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
193031	PERVIOUS BACKFILL MATERIAL (RETAINING WALL)	CY	6	1	816.00	$80.00	$65,280.00
		CY	12	3	287.00	$185.98	$53,375.00
	Unit Sub Total	**CY**		**7**	**2,267.00**	**$107.67**	**$244,095.00**
193031	PERVIOUS BACKFILL MATERIAL (RETAINING WALL)	M3	4	2	765.00	$79.41	$60,750.00
		M3	7	2	5,076.60	$88.74	$450,476.00
	Unit Sub Total	**M3**		**4**	**5,841.60**	**$87.51**	**$511,226.00**
193031	PERVIOUS BACKFILL MATERIAL (RETAINING WALL)	TON	2	1	25.00	$50.00	$1,250.00
	Unit Sub Total	**TON**		**1**	**25.00**	**$50.00**	**$1,250.00**
	Item Code 193031 **Total No. of Proj.**			**12**		**Total Amount**	**$756,571.00**
193039	STRUCTURE BACKFILL (TUNNEL)	CY	4	1	215.00	$45.00	$9,675.00
	Unit Sub Total	**CY**		**1**	**215.00**	**$45.00**	**$9,675.00**
	Item Code 193039 **Total No. of Proj.**			**1**		**Total Amount**	**$9,675.00**
193114	SAND BACKFILL	CY	2	4	94.00	$49.70	$4,672.00
		CY	3	2	46.00	$99.13	$4,560.00
		CY	4	4	387.00	$171.55	$66,390.00
		CY	5	2	720.00	$100.07	$72,050.00
		CY	10	1	16.00	$200.00	$3,200.00
		CY	12	4	320.00	$73.75	$23,600.00
	Unit Sub Total	**CY**		**17**	**1,583.00**	**$110.22**	**$174,472.00**
193114	SAND BACKFILL	M3	2	1	7.00	$150.00	$1,050.00
		M3	3	1	19.00	$100.00	$1,900.00
		M3	4	2	80.00	$176.25	$14,100.00
		M3	7	4	177.00	$160.66	$28,436.00
		M3	11	2	78.20	$236.32	$18,480.00
	Unit Sub Total	**M3**		**10**	**361.20**	**$177.09**	**$63,966.00**
	Item Code 193114 **Total No. of Proj.**			**27**		**Total Amount**	**$238,438.00**
193116	CONCRETE BACKFILL (SOLDIER PILE WALL)	CY	1	3	795.00	$237.54	$188,841.00
		CY	4	1	42.00	$220.00	$9,240.00
		CY	5	1	92.00	$150.00	$13,800.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
193116	CONCRETE BACKFILL (SOLDIER PILE WALL)	CY	12	1	53.00	$300.00	$15,900.00
	Unit Sub Total	**CY**		**6**	**982.00**	**$231.96**	**$227,781.00**
	Item Code 193116 Total No. of Proj.			**6**		**Total Amount**	**$227,781.00**
193117	CONCRETE BACKFILL FAST SETTING	CY	4	1	10.00	$150.00	$1,500.00
	Unit Sub Total	**CY**		**1**	**10.00**	**$150.00**	**$1,500.00**
	Item Code 193117 Total No. of Proj.			**1**		**Total Amount**	**$1,500.00**
193118	CONCRETE BACKFILL	CY	4	2	2,578.00	$125.08	$322,450.00
		CY	5	1	967.00	$360.00	$348,120.00
		CY	8	1	4.00	$300.00	$1,200.00
	Unit Sub Total	**CY**		**4**	**3,549.00**	**$189.28**	**$671,770.00**
	Item Code 193118 Total No. of Proj.			**4**		**Total Amount**	**$671,770.00**
193119	LEAN CONCRETE BACKFILL	CY	1	4	644.00	$157.56	$101,471.00
		CY	4	3	2,140.00	$125.65	$268,890.00
		CY	5	2	1,145.00	$354.05	$405,385.00
	Unit Sub Total	**CY**		**9**	**3,929.00**	**$197.44**	**$775,746.00**
	Item Code 193119 Total No. of Proj.			**9**		**Total Amount**	**$775,746.00**
193120	GRAVEL BACKFILL	CY	9	1	4.00	$28.60	$114.40
	Unit Sub Total	**CY**		**1**	**4.00**	**$28.60**	**$114.40**
	Item Code 193120 Total No. of Proj.			**1**		**Total Amount**	**$114.40**
194001	DITCH EXCAVATION	CY	1	4	160.50	$58.86	$9,447.50
		CY	2	4	771.00	$21.40	$16,499.60
		CY	3	1	430.00	$60.00	$25,800.00
		CY	4	7	1,093.00	$52.09	$56,930.00
		CY	5	1	320.00	$21.00	$6,720.00
		CY	6	1	880.00	$10.00	$8,800.00
		CY	7	2	119.00	$56.24	$6,692.00
		CY	10	2	260.00	$27.50	$7,150.00
		CY	11	1	79.00	$30.00	$2,370.00
		CY	12	3	17,140.00	$11.75	$201,380.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**CY**		**26**	**21,252.50**	**$16.08**	**$341,789.10**
194001	DITCH EXCAVATION		LF	3	1	35.00	$50.00	$1,750.00
		Unit Sub Total	**LF**		**1**	**35.00**	**$50.00**	**$1,750.00**
194001	DITCH EXCAVATION		M3	4	1	400.00	$35.00	$14,000.00
			M3	6	1	50.00	$20.00	$1,000.00
			M3	7	2	740.00	$29.05	$21,500.00
		Unit Sub Total	**M3**		**4**	**1,190.00**	**$30.67**	**$36,500.00**
	Item Code 194001	**Total No. of Proj.**			**31**		**Total Amount**	**$380,039.10**
197003	CONTOUR GRADING		SQYD	4	1	1,970.00	$2.50	$4,925.00
		Unit Sub Total	**SQYD**		**1**	**1,970.00**	**$2.50**	**$4,925.00**
	Item Code 197003	**Total No. of Proj.**			**1**		**Total Amount**	**$4,925.00**
197020	EARTH RETAINING STRUCTURE		SQFT	4	1	3,600.00	$36.00	$129,600.00
		Unit Sub Total	**SQFT**		**1**	**3,600.00**	**$36.00**	**$129,600.00**
	Item Code 197020	**Total No. of Proj.**			**1**		**Total Amount**	**$129,600.00**
197021	EARTH RETAINING STRUCTURE, LOCATION A		M2	4	1	3,500.00	$400.00	$1,400,000.00
			M2	10	1	1,150.00	$500.00	$575,000.00
		Unit Sub Total	**M2**		**2**	**4,650.00**	**$424.73**	**$1,975,000.00**
	Item Code 197021	**Total No. of Proj.**			**2**		**Total Amount**	**$1,975,000.00**
197022	EARTH RETAINING STRUCTURE, LOCATION B		M2	4	1	2,450.00	$425.00	$1,041,250.00
			M2	10	1	1,080.00	$960.00	$1,036,800.00
		Unit Sub Total	**M2**		**2**	**3,530.00**	**$588.68**	**$2,078,050.00**
	Item Code 197022	**Total No. of Proj.**			**2**		**Total Amount**	**$2,078,050.00**
197023	EARTH RETAINING STRUCTURE, LOCATION C		M2	4	1	2,955.00	$400.00	$1,182,000.00
			M2	10	1	1,300.00	$500.00	$650,000.00
		Unit Sub Total	**M2**		**2**	**4,255.00**	**$430.55**	**$1,832,000.00**
	Item Code 197023	**Total No. of Proj.**			**2**		**Total Amount**	**$1,832,000.00**
197024	EARTH RETAINING STRUCTURE, LOCATION D		M2	10	1	775.00	$1,060.00	$821,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M2**		**1**	**775.00**	**$1,060.00**	**$821,500.00**
	Item Code 197024 Total No. of Proj.			**1**		**Total Amount**	**$821,500.00**
197028	EARTH RETAINING STRUCTURE, LOCATION 3	SQFT	12	1	15,100.00	$35.00	$528,500.00
	Unit Sub Total	**SQFT**		**1**	**15,100.00**	**$35.00**	**$528,500.00**
	Item Code 197028 Total No. of Proj.			**1**		**Total Amount**	**$528,500.00**
197029	EARTH RETAINING STRUCTURE, LOCATION 4	SQFT	12	1	25,100.00	$42.00	$1,054,200.00
	Unit Sub Total	**SQFT**		**1**	**25,100.00**	**$42.00**	**$1,054,200.00**
	Item Code 197029 Total No. of Proj.			**1**		**Total Amount**	**$1,054,200.00**
197030	EARTH RETAINING STRUCTURE (GUARD RAILING)	SQFT	2	2	5,326.00	$20.63	$109,900.00
	Unit Sub Total	**SQFT**		**2**	**5,326.00**	**$20.63**	**$109,900.00**
	Item Code 197030 Total No. of Proj.			**2**		**Total Amount**	**$109,900.00**
197031	EARTH RETAINING STRUCTURE (MECHANICALLY STABILIZED EARTH WALL)	M2	7	1	1,825.00	$411.00	$750,075.00
	Unit Sub Total	**M2**		**1**	**1,825.00**	**$411.00**	**$750,075.00**
197031	EARTH RETAINING STRUCTURE (MECHANICALLY STABILIZED EARTH WALL)	SQFT	12	2	80,327.00	$42.20	$3,389,983.00
	Unit Sub Total	**SQFT**		**2**	**80,327.00**	**$42.20**	**$3,389,983.00**
	Item Code 197031 Total No. of Proj.			**3**		**Total Amount**	**$4,140,058.00**
197060	SOIL NAIL ASSEMBLY	LF	4	1	23,136.00	$18.67	$431,949.12
	Unit Sub Total	**LF**		**1**	**23,136.00**	**$18.67**	**$431,949.12**
197060	SOIL NAIL ASSEMBLY	M	2	1	1,890.00	$70.00	$132,300.00
	Unit Sub Total	**M**		**1**	**1,890.00**	**$70.00**	**$132,300.00**
	Item Code 197060 Total No. of Proj.			**2**		**Total Amount**	**$564,249.12**
198001	IMPORTED BORROW	CY	1	6	446.00	$98.96	$44,135.00
		CY	2	3	1,490.00	$41.77	$62,233.20
		CY	3	9	169,250.40	$10.27	$1,738,109.00
		CY	4	7	73,015.00	$8.53	$622,656.00
		CY	5	3	1,280.00	$43.65	$55,870.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
198001	IMPORTED BORROW		CY	6	4	17,970.00	$18.79	$337,720.00
			CY	7	1	480.00	$49.00	$23,520.00
			CY	8	2	690.00	$1.00	$690.00
			CY	9	1	420.00	$35.00	$14,700.00
			CY	10	4	1,047.00	$19.17	$20,070.00
			CY	12	3	260,390.00	$3.83	$996,350.00
		Unit Sub Total	**CY**		**43**	**526,478.40**	**$7.44**	**$3,916,053.20**
198001	IMPORTED BORROW		M3	4	2	18,100.00	$0.21	$3,781.00
			M3	7	4	153,150.00	$1.27	$195,200.00
			M3	10	1	4,250.00	$0.50	$2,125.00
			M3	11	1	417,000.00	$7.00	$2,919,000.00
		Unit Sub Total	**M3**		**8**	**592,500.00**	**$5.27**	**$3,120,106.00**
198001	IMPORTED BORROW		TON	2	2	3,390.00	$33.56	$113,780.00
			TON	11	2	161.00	$92.17	$14,840.00
		Unit Sub Total	**TON**		**4**	**3,551.00**	**$36.22**	**$128,620.00**
	Item Code 198001	**Total No. of Proj.**			**55**		**Total Amount**	**$7,164,779.20**
198007	IMPORTED MATERIAL (SHOULDER BACKING)		CY	1	1	140.00	$95.00	$13,300.00
			CY	3	1	17,100.00	$35.00	$598,500.00
			CY	10	1	400.00	$40.00	$16,000.00
		Unit Sub Total	**CY**		**3**	**17,640.00**	**$35.59**	**$627,800.00**
198007	IMPORTED MATERIAL (SHOULDER BACKING)		TON	1	10	2,819.80	$42.16	$118,888.00
			TON	2	22	80,725.00	$19.00	$1,533,900.00
			TON	3	14	90,560.00	$7.26	$657,146.00
			TON	4	12	10,366.00	$34.44	$356,955.00
			TON	5	12	13,765.00	$30.65	$421,865.60
			TON	6	17	41,182.00	$19.43	$800,337.35
			TON	7	2	1,120.00	$64.48	$72,220.00
			TON	8	1	380.00	$45.00	$17,100.00
			TON	9	6	7,120.00	$45.72	$325,560.00
			TON	10	20	44,524.00	$27.01	$1,202,633.00
		Unit Sub Total	**TON**		**116**	**292,561.80**	**$18.82**	**$5,506,604.95**
198007	IMPORTED MATERIAL (SHOULDER BACKING)		TONN	2	1	80.00	$105.00	$8,400.00
			TONN	3	1	860.00	$30.00	$25,800.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
198007	IMPORTED MATERIAL (SHOULDER BACKING)	TONN	6	1	7,660.00	$16.00	$122,560.00
	Unit Sub Total	**TONN**		**3**	**8,600.00**	**$18.23**	**$156,760.00**
	Item Code 198007 Total No. of Proj.			**122**		**Total Amount**	**$6,291,164.95**
198009	IMPORTED BORROW (LIGHTWEIGHT AGGREGATE)	CY	4	1	10,900.00	$60.00	$654,000.00
	Unit Sub Total	**CY**		**1**	**10,900.00**	**$60.00**	**$654,000.00**
	Item Code 198009 Total No. of Proj.			**1**		**Total Amount**	**$654,000.00**
198021	IMPORTED ROCKY MATERIAL	CY	1	1	100.00	$85.00	$8,500.00
	Unit Sub Total	**CY**		**1**	**100.00**	**$85.00**	**$8,500.00**
198021	IMPORTED ROCKY MATERIAL	TON	1	1	36.00	$75.00	$2,700.00
	Unit Sub Total	**TON**		**1**	**36.00**	**$75.00**	**$2,700.00**
	Item Code 198021 Total No. of Proj.			**2**		**Total Amount**	**$11,200.00**
198205	SUBGRADE ENHANCEMENT GEOTEXTILE	SQYD	1	1	22.00	$25.00	$550.00
		SQYD	2	3	53,100.00	$2.70	$143,260.00
		SQYD	4	3	10,770.00	$2.52	$27,155.00
		SQYD	10	1	3,650.00	$2.15	$7,847.50
	Unit Sub Total	**SQYD**		**8**	**67,542.00**	**$2.65**	**$178,812.50**
	Item Code 198205 Total No. of Proj.			**8**		**Total Amount**	**$178,812.50**
198250	GEOSYNTHETIC REINFORCEMENT	SQYD	1	3	7,840.00	$9.25	$72,490.00
		SQYD	4	1	6,500.00	$10.00	$65,000.00
		SQYD	7	1	1,960.00	$5.50	$10,780.00
	Unit Sub Total	**SQYD**		**5**	**16,300.00**	**$9.10**	**$148,270.00**
	Item Code 198250 Total No. of Proj.			**5**		**Total Amount**	**$148,270.00**
200001	HIGHWAY PLANTING	LS	2	1	1.00	$2,240.00	$2,240.00
		LS	3	2	2.00	$84,275.50	$168,551.00
		LS	4	7	7.00	$22,849.43	$159,946.00
		LS	5	6	6.00	$10,920.33	$65,522.00
		LS	6	5	5.00	$26,374.80	$131,874.00
		LS	7	9	9.00	$78,565.56	$707,090.00
		LS	8	3	3.00	$45,533.33	$136,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
200001	HIGHWAY PLANTING		LS	10	4	4.00	$14,466.00	$57,864.00
			LS	11	7	7.00	$50,214.71	$351,503.00
			LS	12	9	9.00	$28,402.22	$255,620.00
		Unit Sub Total	**LS**		**53**	**53.00**	**$38,430.38**	**$2,036,810.00**
	Item Code 200001	**Total No. of Proj.**			**53**		**Total Amount**	**$2,036,810.00**
200002	ROADSIDE CLEARING		LS	3	3	3.00	$19,883.33	$59,650.00
			LS	4	8	8.00	$27,570.50	$220,564.00
			LS	5	4	4.00	$16,250.00	$65,000.00
			LS	6	2	2.00	$3,875.00	$7,750.00
			LS	7	3	3.00	$17,000.00	$51,000.00
			LS	10	5	5.00	$16,160.00	$80,800.00
			LS	11	4	4.00	$56,000.00	$224,000.00
			LS	12	5	5.00	$40,960.00	$204,800.00
		Unit Sub Total	**LS**		**34**	**34.00**	**$26,869.53**	**$913,564.00**
	Item Code 200002	**Total No. of Proj.**			**34**		**Total Amount**	**$913,564.00**
200052	PRUNE EXISTING PLANTS		LF	11	1	14,600.00	$5.00	$73,000.00
		Unit Sub Total	**LF**		**1**	**14,600.00**	**$5.00**	**$73,000.00**
200052	PRUNE EXISTING PLANTS		LS	3	1	1.00	$24,000.00	$24,000.00
			LS	4	2	2.00	$10,000.00	$20,000.00
			LS	6	4	4.00	$6,250.00	$25,000.00
			LS	7	1	1.00	$7,210.00	$7,210.00
			LS	11	2	2.00	$2,350.00	$4,700.00
			LS	12	1	1.00	$6,000.00	$6,000.00
		Unit Sub Total	**LS**		**11**	**11.00**	**$7,900.91**	**$86,910.00**
	Item Code 200052	**Total No. of Proj.**			**12**		**Total Amount**	**$159,910.00**
200101	IMPORTED TOPSOIL		CY	1	3	313.00	$58.63	$18,350.00
			CY	2	3	154.00	$68.57	$10,560.00
			CY	4	3	1,551.00	$54.43	$84,423.00
			CY	5	1	85.00	$50.00	$4,250.00
			CY	11	1	2,870.00	$26.00	$74,620.00
		Unit Sub Total	**CY**		**11**	**4,973.00**	**$38.65**	**$192,203.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
200101	IMPORTED TOPSOIL	M3	2	1	2,600.00	$35.00	$91,000.00
		M3	4	1	2,500.00	$48.00	$120,000.00
	Unit Sub Total	**M3**		**2**	**5,100.00**	**$41.37**	**$211,000.00**
	Item Code 200101 Total No. of Proj.			**13**		**Total Amount**	**$403,203.00**
200102	IMPORTED TOPSOIL (CY)	CY	4	1	1,370.00	$11.85	$16,234.50
	Unit Sub Total	**CY**		**1**	**1,370.00**	**$11.85**	**$16,234.50**
	Item Code 200102 Total No. of Proj.			**1**		**Total Amount**	**$16,234.50**
200110	PREPARE HOLE	EA	4	1	600.00	$12.60	$7,560.00
	Unit Sub Total	**EA**		**1**	**600.00**	**$12.60**	**$7,560.00**
	Item Code 200110 Total No. of Proj.			**1**		**Total Amount**	**$7,560.00**
200114	ROCK BLANKET	M2	7	1	450.00	$72.45	$32,602.50
	Unit Sub Total	**M2**		**1**	**450.00**	**$72.45**	**$32,602.50**
200114	ROCK BLANKET	SQYD	2	1	80.00	$60.00	$4,800.00
		SQYD	4	2	3,360.00	$94.78	$318,444.00
		SQYD	7	1	910.00	$65.00	$59,150.00
		SQYD	8	1	69.00	$100.00	$6,900.00
		SQYD	11	1	800.00	$45.00	$36,000.00
		SQYD	12	4	14,130.00	$56.72	$801,390.00
	Unit Sub Total	**SQYD**		**10**	**19,349.00**	**$63.40**	**$1,226,684.00**
	Item Code 200114 Total No. of Proj.			**11**		**Total Amount**	**$1,259,286.50**
200115	GRAVEL (MISCELLANEOUS AREAS) (SQFT)	SQFT	11	1	340.00	$5.00	$1,700.00
	Unit Sub Total	**SQFT**		**1**	**340.00**	**$5.00**	**$1,700.00**
	Item Code 200115 Total No. of Proj.			**1**		**Total Amount**	**$1,700.00**
200116	GRAVEL (MISCELLANEOUS AREAS) (SQYD)	SQYD	12	1	37.00	$50.00	$1,850.00
	Unit Sub Total	**SQYD**		**1**	**37.00**	**$50.00**	**$1,850.00**
	Item Code 200116 Total No. of Proj.			**1**		**Total Amount**	**$1,850.00**
200117	DECOMPOSED GRANITE (MISCELLANEOUS AREAS) (SQFT)	SQFT	6	1	38.00	$35.00	$1,330.00
		SQFT	11	1	2,900.00	$7.00	$20,300.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**SQFT**		**2**	**2,938.00**	**$7.36**	**$21,630.00**
	Item Code 200117 Total No. of Proj.			**2**		**Total Amount**	**$21,630.00**
200118	DECOMPOSED GRANITE (MISCELLANEOUS AREAS) (SQYD)	SQYD	4	1	820.00	$35.00	$28,700.00
		SQYD	6	1	180.00	$59.00	$10,620.00
	Unit Sub Total	**SQYD**		**2**	**1,000.00**	**$39.32**	**$39,320.00**
	Item Code 200118 Total No. of Proj.			**2**		**Total Amount**	**$39,320.00**
200120	CULTIVATE	M2	3	1	20,800.00	$1.40	$29,120.00
	Unit Sub Total	**M2**		**1**	**20,800.00**	**$1.40**	**$29,120.00**
200120	CULTIVATE	SQYD	4	1	8,610.00	$3.12	$26,863.20
		SQYD	11	1	3,400.00	$3.00	$10,200.00
	Unit Sub Total	**SQYD**		**2**	**12,010.00**	**$3.09**	**$37,063.20**
	Item Code 200120 Total No. of Proj.			**3**		**Total Amount**	**$66,183.20**
200121	CULTIVATE (SOIL AMENDMENT)	ACRE	5	1	4.90	$7,080.00	$34,692.00
	Unit Sub Total	**ACRE**		**1**	**4.90**	**$7,080.00**	**$34,692.00**
	Item Code 200121 Total No. of Proj.			**1**		**Total Amount**	**$34,692.00**
201700	TOPSOIL	CY	2	1	7.00	$50.00	$350.00
	Unit Sub Total	**CY**		**1**	**7.00**	**$50.00**	**$350.00**
	Item Code 201700 Total No. of Proj.			**1**		**Total Amount**	**$350.00**
202003	IRON SULFATE	KG	11	1	1,550.00	$2.00	$3,100.00
	Unit Sub Total	**KG**		**1**	**1,550.00**	**$2.00**	**$3,100.00**
202003	IRON SULFATE	LB	11	2	1,568.00	$1.29	$2,015.10
	Unit Sub Total	**LB**		**2**	**1,568.00**	**$1.29**	**$2,015.10**
	Item Code 202003 Total No. of Proj.			**3**		**Total Amount**	**$5,115.10**
202006	SOIL AMENDMENT	CY	3	1	33.00	$75.00	$2,475.00
		CY	4	7	2,150.00	$31.81	$68,386.00
		CY	5	2	212.00	$63.21	$13,400.00
		CY	6	1	220.00	$45.00	$9,900.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
202006	SOIL AMENDMENT		CY	10	4	958.00	$32.07	$30,727.50
			CY	12	2	580.00	$29.64	$17,190.00
		Unit Sub Total	**CY**		**17**	**4,153.00**	**$34.21**	**$142,078.50**
202006	SOIL AMENDMENT		M3	3	1	250.00	$55.00	$13,750.00
		Unit Sub Total	**M3**		**1**	**250.00**	**$55.00**	**$13,750.00**
	Item Code 202006	**Total No. of Proj.**			**18**		**Total Amount**	**$155,828.50**
202007	DUFF		HA	6	1	49.00	$2,900.00	$142,100.00
		Unit Sub Total	**HA**		**1**	**49.00**	**$2,900.00**	**$142,100.00**
202007	DUFF		SQYD	2	1	6,300.00	$4.80	$30,240.00
			SQYD	3	2	1,540.00	$8.36	$12,872.00
			SQYD	5	2	11,010.00	$0.49	$5,385.00
			SQYD	9	4	27,850.00	$1.90	$52,945.00
			SQYD	11	1	250.00	$3.00	$750.00
		Unit Sub Total	**SQYD**		**10**	**46,950.00**	**$2.18**	**$102,192.00**
	Item Code 202007	**Total No. of Proj.**			**11**		**Total Amount**	**$244,292.00**
202011	MULCH		CY	1	5	128.00	$174.10	$22,285.00
			CY	2	5	281.00	$56.37	$15,840.00
			CY	3	4	388.00	$87.08	$33,786.00
			CY	4	8	9,469.00	$29.91	$283,245.50
			CY	5	4	13,740.00	$28.33	$389,220.00
			CY	6	1	7,350.00	$26.00	$191,100.00
			CY	7	4	7,245.00	$19.40	$140,575.00
			CY	8	1	740.00	$47.00	$34,780.00
			CY	10	4	27,990.00	$23.83	$666,898.00
			CY	11	2	710.00	$48.01	$34,090.00
			CY	12	3	1,446.00	$28.53	$41,260.00
		Unit Sub Total	**CY**		**41**	**69,487.00**	**$26.67**	**$1,853,079.50**
202011	MULCH		M3	3	1	2,480.00	$50.00	$124,000.00
			M3	11	1	990.00	$55.00	$54,450.00
		Unit Sub Total	**M3**		**2**	**3,470.00**	**$51.43**	**$178,450.00**
	Item Code 202011	**Total No. of Proj.**			**43**		**Total Amount**	**$2,031,529.50**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
202030	COMMERCIAL FERTILIZER (GRANULAR)	KG	3	1	320.00	$18.00	$5,760.00
	Unit Sub Total	**KG**		**1**	**320.00**	**$18.00**	**$5,760.00**
	Item Code 202030 Total No. of Proj.			**1**		**Total Amount**	**$5,760.00**
202031	COMMERCIAL FERTILIZER (SLOW RELEASE)	KG	11	1	1,720.00	$2.00	$3,440.00
	Unit Sub Total	**KG**		**1**	**1,720.00**	**$2.00**	**$3,440.00**
202031	COMMERCIAL FERTILIZER (SLOW RELEASE)	LB	4	3	1,205.00	$2.16	$2,601.90
		LB	7	3	2,810.00	$0.87	$2,445.00
		LB	10	3	2,160.00	$1.23	$2,650.00
		LB	11	3	3,277.00	$2.55	$8,369.40
		LB	12	2	22,050.00	$1.08	$23,810.00
	Unit Sub Total	**LB**		**14**	**31,502.00**	**$1.27**	**$39,876.30**
	Item Code 202031 Total No. of Proj.			**15**		**Total Amount**	**$43,316.30**
202033	COMMERCIAL FERTILIZER (PACKET)	EA	3	2	9,820.00	$0.59	$5,803.50
		EA	4	5	43,690.00	$0.17	$7,222.80
		EA	5	3	25,720.00	$0.30	$7,758.00
		EA	6	1	13,200.00	$0.25	$3,300.00
		EA	10	2	17,370.00	$0.06	$1,119.00
		EA	11	1	29,100.00	$0.20	$5,820.00
	Unit Sub Total	**EA**		**14**	**138,900.00**	**$0.22**	**$31,023.30**
	Item Code 202033 Total No. of Proj.			**14**		**Total Amount**	**$31,023.30**
203001	EROSION CONTROL (BLANKET)	M2	3	1	1,470.00	$2.00	$2,940.00
	Unit Sub Total	**M2**		**1**	**1,470.00**	**$2.00**	**$2,940.00**
203001	EROSION CONTROL (BLANKET)	SQYD	1	2	695.00	$7.48	$5,200.00
		SQYD	3	1	410.00	$2.00	$820.00
		SQYD	9	1	990.00	$6.00	$5,940.00
	Unit Sub Total	**SQYD**		**4**	**2,095.00**	**$5.71**	**$11,960.00**
	Item Code 203001 Total No. of Proj.			**5**		**Total Amount**	**$14,900.00**
203002	EROSION CONTROL (COMPOST BLANKET)	CY	1	5	186.00	$185.73	$34,545.00
		CY	2	2	130.00	$74.32	$9,661.00
		CY	3	2	25.00	$174.00	$4,350.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
203002	EROSION CONTROL (COMPOST BLANKET)	CY	4	12	2,832.40	$62.50	$177,015.24
		CY	5	11	15,729.00	$43.22	$679,751.00
		CY	6	4	1,302.00	$70.28	$91,500.00
		CY	10	1	110.00	$135.00	$14,850.00
		CY	11	2	700.00	$30.96	$21,675.00
	Unit Sub Total	**CY**		**39**	**21,014.40**	**$49.17**	**$1,033,347.24**
	Item Code 203002 Total No. of Proj.			**39**		**Total Amount**	**$1,033,347.24**
203005	EROSION CONTROL (DRILL SEED) (ACRE)	ACRE	5	1	12.00	$1,150.00	$13,800.00
		ACRE	6	3	7.50	$1,955.00	$14,662.50
	Unit Sub Total	**ACRE**		**4**	**19.50**	**$1,459.62**	**$28,462.50**
	Item Code 203005 Total No. of Proj.			**4**		**Total Amount**	**$28,462.50**
203006	EROSION CONTROL (SEEDING) (SQFT)	SQFT	2	1	15,900.00	$0.10	$1,590.00
		SQFT	6	1	3,900.00	$0.17	$663.00
	Unit Sub Total	**SQFT**		**2**	**19,800.00**	**$0.11**	**$2,253.00**
	Item Code 203006 Total No. of Proj.			**2**		**Total Amount**	**$2,253.00**
203008	EROSION CONTROL (PUNCHED STRAW) (SQFT)	SQFT	5	1	58,800.00	$0.14	$8,232.00
		SQFT	11	1	138,000.00	$0.11	$15,180.00
	Unit Sub Total	**SQFT**		**2**	**196,800.00**	**$0.12**	**$23,412.00**
	Item Code 203008 Total No. of Proj.			**2**		**Total Amount**	**$23,412.00**
203009	EROSION CONTROL (PUNCHED STRAW) (ACRE)	ACRE	6	1	5.00	$4,200.00	$21,000.00
		ACRE	10	1	7.00	$5,100.00	$35,700.00
	Unit Sub Total	**ACRE**		**2**	**12.00**	**$4,725.00**	**$56,700.00**
	Item Code 203009 Total No. of Proj.			**2**		**Total Amount**	**$56,700.00**
203011	EROSION CONTROL (TYPE C)	SQYD	9	3	25,860.00	$1.58	$40,760.00
	Unit Sub Total	**SQYD**		**3**	**25,860.00**	**$1.58**	**$40,760.00**
	Item Code 203011 Total No. of Proj.			**3**		**Total Amount**	**$40,760.00**
203012	EROSION CONTROL (DRILL SEED)	ACRE	5	1	16.00	$1,200.00	$19,200.00
	Unit Sub Total	**ACRE**		**1**	**16.00**	**$1,200.00**	**$19,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
203012	EROSION CONTROL (DRILL SEED)	HA	6	1	15.00	$4,000.00	$60,000.00
	Unit Sub Total	**HA**		**1**	**15.00**	**$4,000.00**	**$60,000.00**
203012	EROSION CONTROL (DRILL SEED)	SQYD	3	1	226,000.00	$0.20	$45,200.00
	Unit Sub Total	**SQYD**		**1**	**226,000.00**	**$0.20**	**$45,200.00**
	Item Code 203012 Total No. of Proj.			**3**		**Total Amount**	**$124,400.00**
203016	EROSION CONTROL (TYPE D)	ACRE	4	1	13.00	$4,000.00	$52,000.00
		ACRE	6	1	4.20	$3,000.00	$12,600.00
	Unit Sub Total	**ACRE**		**2**	**17.20**	**$3,755.81**	**$64,600.00**
203016	EROSION CONTROL (TYPE D)	HA	2	1	1.60	$22,000.00	$35,200.00
		HA	3	2	9.80	$7,265.31	$71,200.00
		HA	4	2	1.70	$12,000.00	$20,400.00
		HA	6	1	34.00	$7,000.00	$238,000.00
	Unit Sub Total	**HA**		**6**	**47.10**	**$7,745.22**	**$364,800.00**
203016	EROSION CONTROL (TYPE D)	M2	4	1	88,000.00	$0.10	$8,800.00
		M2	6	2	1,090.00	$6.84	$7,454.00
		M2	7	3	8,290.00	$1.29	$10,721.00
		M2	10	1	45,000.00	$0.85	$38,250.00
		M2	11	1	1,980.00	$0.75	$1,485.00
	Unit Sub Total	**M2**		**8**	**144,360.00**	**$0.46**	**$66,710.00**
203016	EROSION CONTROL (TYPE D)	SQYD	1	9	19,080.00	$2.58	$49,225.40
		SQYD	2	1	23,400.00	$0.75	$17,550.00
		SQYD	3	3	360,980.00	$1.02	$366,944.40
		SQYD	4	2	6,660.00	$1.12	$7,444.00
		SQYD	5	1	23,100.00	$0.26	$6,006.00
		SQYD	10	2	40,800.00	$1.21	$49,540.00
		SQYD	11	1	7,050.00	$2.62	$18,471.00
		SQYD	12	1	5,600.00	$1.25	$7,000.00
	Unit Sub Total	**SQYD**		**20**	**486,670.00**	**$1.07**	**$522,180.80**
	Item Code 203016 Total No. of Proj.			**36**		**Total Amount**	**$1,018,290.80**
203017	EROSION CONTROL (HYDRAULIC MATRIX)	SQYD	11	1	1,800.00	$1.25	$2,250.00
	Unit Sub Total	**SQYD**		**1**	**1,800.00**	**$1.25**	**$2,250.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 203017	**Total No. of Proj.**			**1**		**Total Amount**	**$2,250.00**
203018	EROSION CONTROL (NETTING)		M2	4	3	28,260.00	$3.35	$94,810.00
		Unit Sub Total	**M2**		**3**	**28,260.00**	**$3.35**	**$94,810.00**
203018	EROSION CONTROL (NETTING)		SQYD	3	1	57,800.00	$6.00	$346,800.00
			SQYD	4	2	5,280.00	$3.61	$19,063.00
			SQYD	5	1	236,000.00	$2.47	$582,920.00
			SQYD	12	1	10,400.00	$2.25	$23,400.00
		Unit Sub Total	**SQYD**		**5**	**309,480.00**	**$3.14**	**$972,183.00**
	Item Code 203018	**Total No. of Proj.**			**8**		**Total Amount**	**$1,066,993.00**
203019	EROSION CONTROL (BFM)		M2	11	1	197,000.00	$0.68	$133,960.00
		Unit Sub Total	**M2**		**1**	**197,000.00**	**$0.68**	**$133,960.00**
203019	EROSION CONTROL (BFM)		SQYD	3	1	2,070.00	$2.00	$4,140.00
		Unit Sub Total	**SQYD**		**1**	**2,070.00**	**$2.00**	**$4,140.00**
	Item Code 203019	**Total No. of Proj.**			**2**		**Total Amount**	**$138,100.00**
203021	FIBER ROLLS		LF	1	1	290.00	$40.00	$11,600.00
			LF	2	1	2,920.00	$3.50	$10,220.00
			LF	3	4	89,660.00	$1.17	$105,318.00
			LF	4	27	153,161.00	$2.96	$453,037.00
			LF	5	6	118,230.00	$2.74	$324,454.00
			LF	8	1	4,300.00	$2.00	$8,600.00
			LF	10	2	4,820.00	$2.62	$12,620.20
			LF	11	4	30,900.00	$2.25	$69,670.00
		Unit Sub Total	**LF**		**46**	**404,281.00**	**$2.46**	**$995,519.20**
203021	FIBER ROLLS		M	3	1	4,130.00	$6.00	$24,780.00
			M	4	3	4,240.00	$8.59	$36,425.00
			M	11	2	10,920.00	$3.64	$39,711.00
		Unit Sub Total	**M**		**6**	**19,290.00**	**$5.23**	**$100,916.00**
	Item Code 203021	**Total No. of Proj.**			**52**		**Total Amount**	**$1,096,435.20**
203022	EROSION CONTROL HYDRAULIC MULCH (POLYMER STABILIZED FIBER MATRIX)		SQFT	12	1	19,400.00	$0.20	$3,880.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**SQFT**		**1**	**19,400.00**	**$0.20**	**$3,880.00**
	Item Code 203022	**Total No. of Proj.**			**1**		**Total Amount**	**$3,880.00**
203025	COMPOST, INCORPORATE		CY	7	1	130.00	$10.00	$1,300.00
		Unit Sub Total	**CY**		**1**	**130.00**	**$10.00**	**$1,300.00**
203025	COMPOST, INCORPORATE		M2	2	1	5,000.00	$12.00	$60,000.00
			M2	3	1	8,140.00	$3.00	$24,420.00
		Unit Sub Total	**M2**		**2**	**13,140.00**	**$6.42**	**$84,420.00**
203025	COMPOST, INCORPORATE		SQYD	2	1	48,400.00	$3.50	$169,400.00
	COMPOST (INCORPORATE)		SQYD	3	1	10,300.00	$14.00	$144,200.00
	COMPOST, INCORPORATE		SQYD	3	1	7,970.00	$3.00	$23,910.00
			SQYD	4	1	85.00	$5.20	$442.00
	COMPOST (INCORPORATE)		SQYD	4	6	38,650.00	$6.89	$266,471.90
			SQYD	6	2	16,100.00	$3.55	$57,227.00
	COMPOST, INCORPORATE		SQYD	6	3	42,700.00	$0.85	$36,424.00
	COMPOST (INCORPORATE)		SQYD	8	1	22,000.00	$2.40	$52,800.00
			SQYD	11	1	960.00	$7.00	$6,720.00
		Unit Sub Total	**SQYD**		**17**	**187,165.00**	**$4.05**	**$757,594.90**
	Item Code 203025	**Total No. of Proj.**			**20**		**Total Amount**	**$843,314.90**
203026	MOVE-IN/MOVE-OUT (EROSION CONTROL)		EA	3	4	38.00	$468.42	$17,800.00
			EA	4	14	60.00	$612.73	$36,763.50
			EA	5	6	22.00	$508.64	$11,190.00
			EA	6	5	37.00	$433.57	$16,042.00
			EA	7	1	6.00	$424.00	$2,544.00
			EA	10	7	39.00	$539.74	$21,050.00
			EA	11	4	17.00	$380.29	$6,465.00
			EA	12	4	26.00	$353.85	$9,200.00
		Unit Sub Total	**EA**		**45**	**245.00**	**$494.10**	**$121,054.50**
	Item Code 203026	**Total No. of Proj.**			**45**		**Total Amount**	**$121,054.50**
203027	EROSION CONTROL (BONDED FIBER MATRIX) (SQFT)		SQFT	8	2	43,800.00	$0.16	$6,816.00
			SQFT	11	1	96,600.00	$0.10	$9,660.00
			SQFT	12	1	216,000.00	$0.06	$12,960.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**SQFT**		**4**	**356,400.00**	**$0.08**	**$29,436.00**
	Item Code 203027 Total No. of Proj.			**4**		**Total Amount**	**$29,436.00**
203029	EROSION CONTROL (POLYMER STABILIZED FIBER MATRIX) (SQFT)	SQFT	1	1	20,300.00	$0.30	$6,090.00
		SQFT	11	1	239,000.00	$0.12	$28,680.00
	Unit Sub Total	**SQFT**		**2**	**259,300.00**	**$0.13**	**$34,770.00**
	Item Code 203029 Total No. of Proj.			**2**		**Total Amount**	**$34,770.00**
203030	EROSION CONTROL (POLYMER STABILIZED FIBER MATRIX) (ACRE)	ACRE	5	1	1.00	$4,700.00	$4,700.00
	Unit Sub Total	**ACRE**		**1**	**1.00**	**$4,700.00**	**$4,700.00**
	Item Code 203030 Total No. of Proj.			**1**		**Total Amount**	**$4,700.00**
203031	EROSION CONTROL (HYDROSEED) (SQFT)	ACRE	4	1	20.00	$3,700.00	$74,000.00
	Unit Sub Total	**ACRE**		**1**	**20.00**	**$3,700.00**	**$74,000.00**
203031	EROSION CONTROL (HYDROSEED) (SQFT)	SQFT	1	5	60,160.00	$0.36	$21,495.00
		SQFT	2	3	67,400.00	$0.17	$11,391.00
		SQFT	3	3	283,800.00	$0.30	$83,805.00
		SQFT	4	20	1,121,830.00	$0.14	$157,145.50
		SQFT	5	3	67,400.00	$0.13	$8,983.00
		SQFT	6	3	290,200.00	$0.08	$22,720.00
		SQFT	7	2	15,570.00	$0.44	$6,835.50
		SQFT	8	1	194,000.00	$0.03	$5,820.00
		SQFT	10	3	30,200.00	$1.15	$34,805.00
		SQFT	11	3	219,200.00	$0.19	$42,214.00
		SQFT	12	3	1,282,500.00	$0.04	$55,788.00
	Unit Sub Total	**SQFT**		**49**	**3,632,260.00**	**$0.12**	**$451,002.00**
	Item Code 203031 Total No. of Proj.			**50**		**Total Amount**	**$525,002.00**
203032	EROSION CONTROL (HYDROSEED) (ACRE)	ACRE	1	1	16.00	$5,100.00	$81,600.00
		ACRE	2	10	44.80	$4,916.38	$220,254.00
		ACRE	3	2	1.30	$5,288.46	$6,875.00
		ACRE	4	4	27.00	$5,445.38	$147,025.20
		ACRE	5	2	25.00	$1,688.40	$42,210.00
		ACRE	6	2	41.30	$2,741.53	$113,225.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
203032	EROSION CONTROL (HYDROSEED) (ACRE)	ACRE	10	1	12.00	$2,448.00	$29,376.00
	Unit Sub Total	**ACRE**		**22**	**167.40**	**$3,826.55**	**$640,565.20**
	Item Code 203032 Total No. of Proj.			**22**		**Total Amount**	**$640,565.20**
203033	ROLLED EROSION CONTROL PRODUCT (BLANKET)	SQFT	1	1	40.00	$15.00	$600.00
		SQFT	3	1	45.00	$5.00	$225.00
		SQFT	6	1	7,600.00	$0.50	$3,800.00
	Unit Sub Total	**SQFT**		**3**	**7,685.00**	**$0.60**	**$4,625.00**
	Item Code 203033 Total No. of Proj.			**3**		**Total Amount**	**$4,625.00**
203034	ROLLED EROSION CONTROL PRODUCT (NETTING)	SQFT	3	4	178,290.00	$0.67	$119,274.00
		SQFT	4	18	431,470.00	$0.54	$231,173.50
		SQFT	5	1	22,300.00	$0.37	$8,251.00
		SQFT	6	2	103,020.00	$0.35	$36,210.00
		SQFT	11	1	61,100.00	$0.30	$18,330.00
	Unit Sub Total	**SQFT**		**26**	**796,180.00**	**$0.52**	**$413,238.50**
	Item Code 203034 Total No. of Proj.			**26**		**Total Amount**	**$413,238.50**
203038	ROLLED EROSION CONTROL PRODUCT (JUTE MESH)	M2	11	1	13,620.00	$9.00	$122,580.00
	Unit Sub Total	**M2**		**1**	**13,620.00**	**$9.00**	**$122,580.00**
203038	ROLLED EROSION CONTROL PRODUCT (JUTE MESH)	SQFT	5	1	20,500.00	$0.30	$6,150.00
		SQFT	11	1	25,500.00	$0.30	$7,650.00
	Unit Sub Total	**SQFT**		**2**	**46,000.00**	**$0.30**	**$13,800.00**
	Item Code 203038 Total No. of Proj.			**3**		**Total Amount**	**$136,380.00**
203039	ROLLED EROSION CONTROL PRODUCT (TRM)	SQFT	3	1	1,810.00	$4.65	$8,416.50
	Unit Sub Total	**SQFT**		**1**	**1,810.00**	**$4.65**	**$8,416.50**
	Item Code 203039 Total No. of Proj.			**1**		**Total Amount**	**$8,416.50**
203070	ROCK STAIN	SQFT	3	1	139,000.00	$0.20	$27,800.00
	Unit Sub Total	**SQFT**		**1**	**139,000.00**	**$0.20**	**$27,800.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 203070	**Total No. of Proj.**			**1**		**Total Amount**	**$27,800.00**
203561	JUTE MESH		SQYD	5	1	5,100.00	$1.70	$8,670.00
		Unit Sub Total	**SQYD**		**1**	**5,100.00**	**$1.70**	**$8,670.00**
	Item Code 203561	**Total No. of Proj.**			**1**		**Total Amount**	**$8,670.00**
204001	PLANT (GROUP A)		EA	7	1	4,300.00	$1.00	$4,300.00
			EA	10	1	1,020.00	$7.00	$7,140.00
		Unit Sub Total	**EA**		**2**	**5,320.00**	**$2.15**	**$11,440.00**
	Item Code 204001	**Total No. of Proj.**			**2**		**Total Amount**	**$11,440.00**
204002	PLANT (GROUP B)		EA	10	1	220.00	$19.00	$4,180.00
		Unit Sub Total	**EA**		**1**	**220.00**	**$19.00**	**$4,180.00**
	Item Code 204002	**Total No. of Proj.**			**1**		**Total Amount**	**$4,180.00**
204006	PLANT (GROUP F)		EA	3	1	42,700.00	$0.95	$40,565.00
			EA	11	3	299,300.00	$0.48	$143,190.00
			EA	12	2	196,400.00	$0.29	$56,909.00
		Unit Sub Total	**EA**		**6**	**538,400.00**	**$0.45**	**$240,664.00**
	Item Code 204006	**Total No. of Proj.**			**6**		**Total Amount**	**$240,664.00**
204007	PLANT (GROUP G)		EA	11	1	260.00	$0.60	$156.00
		Unit Sub Total	**EA**		**1**	**260.00**	**$0.60**	**$156.00**
	Item Code 204007	**Total No. of Proj.**			**1**		**Total Amount**	**$156.00**
204008	PLANT (GROUP H)		EA	10	1	43,900.00	$0.29	$12,731.00
			EA	11	4	229,620.00	$0.25	$58,042.25
			EA	12	2	117,500.00	$0.28	$33,183.00
		Unit Sub Total	**EA**		**7**	**391,020.00**	**$0.27**	**$103,956.25**
	Item Code 204008	**Total No. of Proj.**			**7**		**Total Amount**	**$103,956.25**
204009	PLANT (GROUP I)		EA	3	1	890.00	$20.00	$17,800.00
			EA	5	2	4,850.00	$2.60	$12,619.50
		Unit Sub Total	**EA**		**3**	**5,740.00**	**$5.30**	**$30,419.50**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 204009	**Total No. of Proj.**			**3**		**Total Amount**	**$30,419.50**
204010	PLANT (GROUP O)		EA	5	1	1,750.00	$12.50	$21,875.00
		Unit Sub Total	**EA**		**1**	**1,750.00**	**$12.50**	**$21,875.00**
	Item Code 204010	**Total No. of Proj.**			**1**		**Total Amount**	**$21,875.00**
204011	PLANT (GROUP K)		EA	5	1	53.00	$180.00	$9,540.00
			EA	7	1	43.00	$200.00	$8,600.00
			EA	12	1	3.00	$850.00	$2,550.00
		Unit Sub Total	**EA**		**3**	**99.00**	**$208.99**	**$20,690.00**
	Item Code 204011	**Total No. of Proj.**			**3**		**Total Amount**	**$20,690.00**
204013	PLANT (GROUP M)		EA	4	7	19,154.00	$4.42	$84,681.00
			EA	5	1	880.00	$7.75	$6,820.00
			EA	6	2	2,750.00	$5.30	$14,580.00
			EA	7	1	10,500.00	$0.50	$5,250.00
		Unit Sub Total	**EA**		**11**	**33,284.00**	**$3.34**	**$111,331.00**
	Item Code 204013	**Total No. of Proj.**			**11**		**Total Amount**	**$111,331.00**
204017	PLANT (GROUP W)		EA	4	3	634.00	$7.91	$5,014.80
			EA	5	1	10.00	$20.00	$200.00
			EA	7	1	820.00	$11.00	$9,020.00
			EA	11	2	1,600.00	$2.63	$4,200.00
		Unit Sub Total	**EA**		**7**	**3,064.00**	**$6.02**	**$18,434.80**
	Item Code 204017	**Total No. of Proj.**			**7**		**Total Amount**	**$18,434.80**
204021	PLANT (GROUP U)		EA	4	1	180.00	$70.00	$12,600.00
		Unit Sub Total	**EA**		**1**	**180.00**	**$70.00**	**$12,600.00**
	Item Code 204021	**Total No. of Proj.**			**1**		**Total Amount**	**$12,600.00**
204031	TRANSPLANT PALM TREE		EA	11	2	6.00	$1,516.67	$9,100.00
			EA	12	1	1.00	$1,950.00	$1,950.00
		Unit Sub Total	**EA**		**3**	**7.00**	**$1,578.57**	**$11,050.00**
204031	TRANSPLANT PALM TREE		LS	12	2	2.00	$6,781.00	$13,562.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LS**		**2**	**2.00**	**$6,781.00**	**$13,562.00**
	Item Code 204031	**Total No. of Proj.**			**5**		**Total Amount**	**$24,612.00**
204035	PLANT (GROUP A)		EA	3	1	7,790.00	$8.00	$62,320.00
			EA	4	4	16,960.00	$9.93	$168,469.90
			EA	5	3	16,180.00	$4.93	$79,780.00
			EA	6	1	9,810.00	$6.00	$58,860.00
			EA	7	2	4,390.00	$5.82	$25,570.00
			EA	10	3	15,460.00	$5.44	$84,060.00
			EA	11	1	12,400.00	$7.75	$96,100.00
			EA	12	3	33,700.00	$4.40	$148,370.00
		Unit Sub Total	**EA**		**18**	**116,690.00**	**$6.20**	**$723,529.90**
	Item Code 204035	**Total No. of Proj.**			**18**		**Total Amount**	**$723,529.90**
204036	PLANT (GROUP B)		EA	3	1	130.00	$30.00	$3,900.00
			EA	4	4	2,346.00	$17.29	$40,571.80
			EA	5	2	600.00	$16.93	$10,160.00
			EA	6	1	380.00	$25.00	$9,500.00
			EA	7	2	770.00	$17.09	$13,160.00
			EA	10	1	710.00	$12.00	$8,520.00
			EA	11	1	270.00	$15.00	$4,050.00
			EA	12	2	300.00	$12.08	$3,622.50
		Unit Sub Total	**EA**		**14**	**5,506.00**	**$16.98**	**$93,484.30**
	Item Code 204036	**Total No. of Proj.**			**14**		**Total Amount**	**$93,484.30**
204038	PLANT (GROUP U)		EA	4	3	2,850.00	$51.64	$147,184.20
			EA	5	2	290.00	$71.72	$20,800.00
			EA	7	3	438.00	$80.82	$35,400.00
			EA	11	1	740.00	$105.00	$77,700.00
			EA	12	3	1,058.00	$69.76	$73,810.00
		Unit Sub Total	**EA**		**12**	**5,376.00**	**$66.01**	**$354,894.20**
	Item Code 204038	**Total No. of Proj.**			**12**		**Total Amount**	**$354,894.20**
204042	TURF (SOD)		SQFT	11	1	30,000.00	$1.20	$36,000.00
		Unit Sub Total	**SQFT**		**1**	**30,000.00**	**$1.20**	**$36,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
204042	TURF (SOD)	SQYD	2	1	230.00	$10.25	$2,357.50
	Unit Sub Total	**SQYD**		**1**	**230.00**	**$10.25**	**$2,357.50**
	Item Code 204042 Total No. of Proj.			**2**		**Total Amount**	**$38,357.50**
204051	SEEDING	KG	4	1	2.00	$1,250.00	$2,500.00
	Unit Sub Total	**KG**		**1**	**2.00**	**$1,250.00**	**$2,500.00**
204051	SEEDING	SQYD	4	1	8,610.00	$0.47	$4,046.70
	Unit Sub Total	**SQYD**		**1**	**8,610.00**	**$0.47**	**$4,046.70**
	Item Code 204051 Total No. of Proj.			**2**		**Total Amount**	**$6,546.70**
204053	WILD FLOWER SEEDING	ACRE	6	1	8.10	$3,250.00	$26,325.00
	Unit Sub Total	**ACRE**		**1**	**8.10**	**$3,250.00**	**$26,325.00**
	Item Code 204053 Total No. of Proj.			**1**		**Total Amount**	**$26,325.00**
204054	WILD FLOWER SEEDING (ACRE)	ACRE	8	1	3.00	$1,310.00	$3,930.00
	Unit Sub Total	**ACRE**		**1**	**3.00**	**$1,310.00**	**$3,930.00**
	Item Code 204054 Total No. of Proj.			**1**		**Total Amount**	**$3,930.00**
204096	MAINTAIN EXISTING PLANTED AREAS	LS	4	5	5.00	$6,870.00	$34,350.00
		LS	6	2	2.00	$4,660.00	$9,320.00
		LS	7	5	5.00	$12,156.00	$60,780.00
		LS	10	4	4.00	$7,250.00	$29,000.00
		LS	11	3	3.00	$14,000.00	$42,000.00
		LS	12	10	10.00	$30,955.50	$309,555.00
	Unit Sub Total	**LS**		**29**	**29.00**	**$16,724.31**	**$485,005.00**
	Item Code 204096 Total No. of Proj.			**29**		**Total Amount**	**$485,005.00**
204099	PLANT ESTABLISHMENT WORK	LS	3	3	3.00	$64,128.33	$192,385.00
		LS	4	13	13.00	$49,078.43	$638,019.65
		LS	5	8	8.00	$36,812.38	$294,499.00
		LS	6	7	7.00	$12,005.57	$84,039.00
		LS	7	12	12.00	$28,699.17	$344,390.00
		LS	8	3	3.00	$7,776.67	$23,330.00
		LS	10	8	8.00	$54,243.75	$433,950.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
204099	PLANT ESTABLISHMENT WORK	LS	11	11	11.00	$30,166.45	$331,831.00
		LS	12	12	12.00	$32,199.50	$386,394.00
	Unit Sub Total	**LS**		**77**	**77.00**	**$35,439.45**	**$2,728,837.65**
	Item Code 204099 Total No. of Proj.			**77**		**Total Amount**	**$2,728,837.65**
205051	FOLIAGE PROTECTOR	EA	3	1	530.00	$55.00	$29,150.00
		EA	4	2	880.00	$26.65	$23,450.00
		EA	5	1	1,210.00	$20.00	$24,200.00
		EA	12	1	1,120.00	$15.00	$16,800.00
	Unit Sub Total	**EA**		**5**	**3,740.00**	**$25.03**	**$93,600.00**
	Item Code 205051 Total No. of Proj.			**5**		**Total Amount**	**$93,600.00**
205061	ROOT PROTECTOR	EA	5	3	14,760.00	$6.29	$92,840.00
	Unit Sub Total	**EA**		**3**	**14,760.00**	**$6.29**	**$92,840.00**
	Item Code 205061 Total No. of Proj.			**3**		**Total Amount**	**$92,840.00**
205062	ROOT BARRIER	LF	2	1	160.00	$8.00	$1,280.00
		LF	4	1	300.00	$7.00	$2,100.00
	Unit Sub Total	**LF**		**2**	**460.00**	**$7.35**	**$3,380.00**
	Item Code 205062 Total No. of Proj.			**2**		**Total Amount**	**$3,380.00**
206401	MAINTAIN EXISTING IRRIGATION FACILITIES	LS	3	1	1.00	$6,260.00	$6,260.00
		LS	4	2	2.00	$1,500.00	$3,000.00
		LS	5	2	2.00	$5,750.00	$11,500.00
		LS	6	4	4.00	$2,437.50	$9,750.00
		LS	7	5	5.00	$2,783.00	$13,915.00
		LS	8	1	1.00	$1,000.00	$1,000.00
		LS	10	3	3.00	$7,006.67	$21,020.00
		LS	11	1	1.00	$10,000.00	$10,000.00
		LS	12	10	10.00	$15,780.00	$157,800.00
	Unit Sub Total	**LS**		**29**	**29.00**	**$8,077.41**	**$234,245.00**
	Item Code 206401 Total No. of Proj.			**29**		**Total Amount**	**$234,245.00**
206560	CONTROL AND NEUTRAL CONDUCTORS	LF	10	1	158,000.00	$0.20	$31,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**1**	**158,000.00**	**$0.20**	**$31,600.00**
206560	CONTROL AND NEUTRAL CONDUCTORS		LS	3	2	2.00	$7,902.50	$15,805.00
			LS	4	4	4.00	$26,008.25	$104,033.00
			LS	5	2	2.00	$37,500.00	$75,000.00
			LS	6	1	1.00	$12,500.00	$12,500.00
			LS	7	3	3.00	$11,333.33	$34,000.00
			LS	10	1	1.00	$19,000.00	$19,000.00
			LS	11	4	4.00	$15,475.00	$61,900.00
			LS	12	2	2.00	$44,000.00	$88,000.00
		Unit Sub Total	**LS**		**19**	**19.00**	**$21,591.47**	**$410,238.00**
	Item Code 206560	**Total No. of Proj.**			**20**		**Total Amount**	**$441,838.00**
206601	3/4" ELECTRIC REMOTE CONTROL VALVE		EA	4	1	16.00	$193.87	$3,101.92
			EA	7	2	10.00	$265.00	$2,650.00
		Unit Sub Total	**EA**		**3**	**26.00**	**$221.23**	**$5,751.92**
	Item Code 206601	**Total No. of Proj.**			**3**		**Total Amount**	**$5,751.92**
206602	1" ELECTRIC REMOTE CONTROL VALVE		EA	3	1	7.00	$375.00	$2,625.00
			EA	4	4	101.00	$255.94	$25,849.71
			EA	5	2	64.00	$206.25	$13,200.00
			EA	6	1	5.00	$300.00	$1,500.00
			EA	7	3	37.00	$402.70	$14,900.00
			EA	10	2	20.00	$348.00	$6,960.00
			EA	11	2	70.00	$164.00	$11,480.00
			EA	12	2	28.00	$208.36	$5,834.00
		Unit Sub Total	**EA**		**17**	**332.00**	**$248.04**	**$82,348.71**
	Item Code 206602	**Total No. of Proj.**			**17**		**Total Amount**	**$82,348.71**
206603	1 1/4" ELECTRIC REMOTE CONTROL VALVE		EA	4	2	49.00	$234.48	$11,489.68
			EA	7	1	4.00	$300.00	$1,200.00
		Unit Sub Total	**EA**		**3**	**53.00**	**$239.43**	**$12,689.68**
	Item Code 206603	**Total No. of Proj.**			**3**		**Total Amount**	**$12,689.68**
206604	1 1/2" ELECTRIC REMOTE CONTROL VALVE		EA	4	3	46.00	$301.09	$13,850.00
			EA	5	2	55.00	$271.45	$14,930.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
206604	1 1/2" ELECTRIC REMOTE CONTROL VALVE	EA	6	1	1.00	$310.00	$310.00
		EA	7	2	22.00	$325.00	$7,150.00
		EA	10	2	24.00	$433.33	$10,400.00
		EA	11	2	255.00	$205.88	$52,500.00
		EA	12	2	55.00	$238.09	$13,095.00
	Unit Sub Total	**EA**		**14**	**458.00**	**$245.05**	**$112,235.00**
	Item Code 206604 Total No. of Proj.			**14**		**Total Amount**	**$112,235.00**
206605	2" ELECTRIC REMOTE CONTROL VALVE	EA	4	3	11.00	$357.33	$3,930.58
		EA	5	2	31.00	$309.68	$9,600.00
		EA	6	1	31.00	$330.00	$10,230.00
		EA	7	2	13.00	$359.62	$4,675.00
		EA	10	2	28.00	$562.68	$15,755.00
		EA	12	2	113.00	$281.11	$31,765.00
	Unit Sub Total	**EA**		**12**	**227.00**	**$334.61**	**$75,955.58**
	Item Code 206605 Total No. of Proj.			**12**		**Total Amount**	**$75,955.58**
206606	2 1/2" ELECTRIC REMOTE CONTROL VALVE	EA	7	1	1.00	$450.00	$450.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$450.00**	**$450.00**
	Item Code 206606 Total No. of Proj.			**1**		**Total Amount**	**$450.00**
206607	3" ELECTRIC REMOTE CONTROL VALVE	EA	4	1	4.00	$324.20	$1,296.80
		EA	10	1	29.00	$650.00	$18,850.00
	Unit Sub Total	**EA**		**2**	**33.00**	**$610.51**	**$20,146.80**
	Item Code 206607 Total No. of Proj.			**2**		**Total Amount**	**$20,146.80**
206611	25 MM ELECTRIC REMOTE CONTROL VALVE	EA	3	1	15.00	$400.00	$6,000.00
		EA	11	1	19.00	$250.00	$4,750.00
	Unit Sub Total	**EA**		**2**	**34.00**	**$316.18**	**$10,750.00**
	Item Code 206611 Total No. of Proj.			**2**		**Total Amount**	**$10,750.00**
206613	40 MM ELECTRIC REMOTE CONTROL VALVE	EA	3	1	23.00	$510.00	$11,730.00
		EA	11	1	92.00	$300.00	$27,600.00
	Unit Sub Total	**EA**		**2**	**115.00**	**$342.00**	**$39,330.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 206613 Total No. of Proj.			**2**		**Total Amount**	**$39,330.00**
206614	50 MM ELECTRIC REMOTE CONTROL VALVE	EA	3	1	28.00	$600.00	$16,800.00
	Unit Sub Total	**EA**		**1**	**28.00**	**$600.00**	**$16,800.00**
	Item Code 206614 Total No. of Proj.			**1**		**Total Amount**	**$16,800.00**
206616	75 MM ELECTRIC REMOTE CONTROL VALVE	EA	3	1	37.00	$660.00	$24,420.00
	Unit Sub Total	**EA**		**1**	**37.00**	**$660.00**	**$24,420.00**
	Item Code 206616 Total No. of Proj.			**1**		**Total Amount**	**$24,420.00**
206749	8 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	EA	4	2	2.00	$1,959.46	$3,918.92
		EA	5	1	1.00	$1,500.00	$1,500.00
	Unit Sub Total	**EA**		**3**	**3.00**	**$1,806.31**	**$5,418.92**
	Item Code 206749 Total No. of Proj.			**3**		**Total Amount**	**$5,418.92**
206751	12 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	EA	3	1	2.00	$8,120.00	$16,240.00
		EA	4	1	3.00	$1,200.00	$3,600.00
		EA	5	2	2.00	$1,042.50	$2,085.00
		EA	7	1	1.00	$2,000.00	$2,000.00
	Unit Sub Total	**EA**		**5**	**8.00**	**$2,990.63**	**$23,925.00**
	Item Code 206751 Total No. of Proj.			**5**		**Total Amount**	**$23,925.00**
206752	18 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	EA	5	1	1.00	$1,000.00	$1,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,000.00**	**$1,000.00**
	Item Code 206752 Total No. of Proj.			**1**		**Total Amount**	**$1,000.00**
206753	24 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	EA	3	1	3.00	$11,900.00	$35,700.00
		EA	4	2	2.00	$2,235.47	$4,470.94
		EA	5	1	1.00	$1,000.00	$1,000.00
		EA	7	1	1.00	$3,000.00	$3,000.00
		EA	12	1	3.00	$11,000.00	$33,000.00
	Unit Sub Total	**EA**		**6**	**10.00**	**$7,717.09**	**$77,170.94**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 206753 Total No. of Proj.			**6**		**Total Amount**	**$77,170.94**
206756	16 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	EA	3	1	1.00	$9,400.00	$9,400.00
		EA	4	2	5.00	$1,691.47	$8,457.33
	Unit Sub Total	**EA**		**3**	**6.00**	**$2,976.22**	**$17,857.33**
	Item Code 206756 Total No. of Proj.			**3**		**Total Amount**	**$17,857.33**
206929	IRRIGATION CONTROLLER (BATTERY)	EA	3	1	4.00	$210.00	$840.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$210.00**	**$840.00**
	Item Code 206929 Total No. of Proj.			**1**		**Total Amount**	**$840.00**
208000	IRRIGATION SYSTEM	LS	2	3	3.00	$8,150.00	$24,450.00
		LS	3	2	2.00	$62,162.50	$124,325.00
		LS	4	4	4.00	$51,050.00	$204,200.00
		LS	5	6	6.00	$11,990.00	$71,940.00
		LS	6	5	5.00	$31,039.00	$155,195.00
		LS	7	9	9.00	$154,027.00	$1,386,243.00
		LS	8	1	1.00	$175,000.00	$175,000.00
		LS	10	4	4.00	$46,591.35	$186,365.40
		LS	11	7	7.00	$147,256.43	$1,030,795.00
		LS	12	11	11.00	$52,402.55	$576,428.00
	Unit Sub Total	**LS**		**52**	**52.00**	**$75,671.95**	**$3,934,941.40**
	Item Code 208000 Total No. of Proj.			**52**		**Total Amount**	**$3,934,941.40**
208003	1" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	4	1	100.00	$10.00	$1,000.00
	Unit Sub Total	**LF**		**1**	**100.00**	**$10.00**	**$1,000.00**
	Item Code 208003 Total No. of Proj.			**1**		**Total Amount**	**$1,000.00**
208006	2" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	11	1	410.00	$23.00	$9,430.00
	Unit Sub Total	**LF**		**1**	**410.00**	**$23.00**	**$9,430.00**
	Item Code 208006 Total No. of Proj.			**1**		**Total Amount**	**$9,430.00**
208007	2 1/2" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	4	1	240.00	$30.00	$7,200.00
	Unit Sub Total	**LF**		**1**	**240.00**	**$30.00**	**$7,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208007 Total No. of Proj.			**1**		**Total Amount**	**$7,200.00**
208008	3" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	4	1	230.00	$37.50	$8,625.00
		LF	7	1	20.00	$100.00	$2,000.00
		LF	10	1	30.00	$20.00	$600.00
		LF	12	2	420.00	$24.88	$10,450.00
	Unit Sub Total	**LF**		**5**	**700.00**	**$30.96**	**$21,675.00**
	Item Code 208008 Total No. of Proj.			**5**		**Total Amount**	**$21,675.00**
208009	4" GALVANIZED STEEL PIPE (SUPPLY LINE)	LF	10	1	470.00	$25.00	$11,750.00
		LF	11	1	410.00	$80.00	$32,800.00
	Unit Sub Total	**LF**		**2**	**880.00**	**$50.63**	**$44,550.00**
	Item Code 208009 Total No. of Proj.			**2**		**Total Amount**	**$44,550.00**
208017	20 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	M	3	1	83.00	$75.00	$6,225.00
	Unit Sub Total	**M**		**1**	**83.00**	**$75.00**	**$6,225.00**
	Item Code 208017 Total No. of Proj.			**1**		**Total Amount**	**$6,225.00**
208018	25 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	M	3	1	38.00	$90.00	$3,420.00
	Unit Sub Total	**M**		**1**	**38.00**	**$90.00**	**$3,420.00**
	Item Code 208018 Total No. of Proj.			**1**		**Total Amount**	**$3,420.00**
208019	32 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	M	3	1	39.00	$115.00	$4,485.00
	Unit Sub Total	**M**		**1**	**39.00**	**$115.00**	**$4,485.00**
	Item Code 208019 Total No. of Proj.			**1**		**Total Amount**	**$4,485.00**
208020	40 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	M	3	1	21.00	$130.00	$2,730.00
	Unit Sub Total	**M**		**1**	**21.00**	**$130.00**	**$2,730.00**
	Item Code 208020 Total No. of Proj.			**1**		**Total Amount**	**$2,730.00**
208021	50 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	M	3	1	38.00	$165.00	$6,270.00
	Unit Sub Total	**M**		**1**	**38.00**	**$165.00**	**$6,270.00**
	Item Code 208021 Total No. of Proj.			**1**		**Total Amount**	**$6,270.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208022	65 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	M	3	1	8.00	$200.00	$1,600.00
	Unit Sub Total	**M**		**1**	**8.00**	**$200.00**	**$1,600.00**
	Item Code 208022 Total No. of Proj.			**1**		**Total Amount**	**$1,600.00**
208023	75 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	M	3	1	19.00	$225.00	$4,275.00
	Unit Sub Total	**M**		**1**	**19.00**	**$225.00**	**$4,275.00**
	Item Code 208023 Total No. of Proj.			**1**		**Total Amount**	**$4,275.00**
208024	100 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	M	3	1	19.00	$300.00	$5,700.00
	Unit Sub Total	**M**		**1**	**19.00**	**$300.00**	**$5,700.00**
	Item Code 208024 Total No. of Proj.			**1**		**Total Amount**	**$5,700.00**
208028	3" SUPPLY LINE (BRIDGE)	LF	5	2	1,575.00	$73.23	$115,345.00
		LF	11	1	210.00	$120.00	$25,200.00
		LF	12	1	212.00	$60.00	$12,720.00
	Unit Sub Total	**LF**		**4**	**1,997.00**	**$76.75**	**$153,265.00**
	Item Code 208028 Total No. of Proj.			**4**		**Total Amount**	**$153,265.00**
208036	NPS 2 SUPPLY LINE (BRIDGE)	M	7	2	168.00	$312.86	$52,560.00
	Unit Sub Total	**M**		**2**	**168.00**	**$312.86**	**$52,560.00**
	Item Code 208036 Total No. of Proj.			**2**		**Total Amount**	**$52,560.00**
208037	NPS 2.5 SUPPLY LINE (BRIDGE)	M	7	2	159.00	$288.40	$45,855.00
	Unit Sub Total	**M**		**2**	**159.00**	**$288.40**	**$45,855.00**
	Item Code 208037 Total No. of Proj.			**2**		**Total Amount**	**$45,855.00**
208038	NPS 3 SUPPLY LINE (BRIDGE)	M	4	1	104.00	$150.00	$15,600.00
		M	7	2	136.00	$318.24	$43,280.00
		M	11	1	210.00	$250.00	$52,500.00
	Unit Sub Total	**M**		**4**	**450.00**	**$247.51**	**$111,380.00**
	Item Code 208038 Total No. of Proj.			**4**		**Total Amount**	**$111,380.00**
208039	NPS 4 SUPPLY LINE (BRIDGE)	M	7	1	41.00	$470.00	$19,270.00
	Unit Sub Total	**M**		**1**	**41.00**	**$470.00**	**$19,270.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208039 Total No. of Proj.			**1**		**Total Amount**	**$19,270.00**
208040	NPS 6 SUPPLY LINE (BRIDGE)	M	7	1	52.00	$275.00	$14,300.00
	Unit Sub Total	**M**		**1**	**52.00**	**$275.00**	**$14,300.00**
	Item Code 208040 Total No. of Proj.			**1**		**Total Amount**	**$14,300.00**
208042	2" GALVANIZED STEEL PIPE (SUPPLY LINE ON BRIDGE)	LF	6	1	330.00	$45.00	$14,850.00
	Unit Sub Total	**LF**		**1**	**330.00**	**$45.00**	**$14,850.00**
	Item Code 208042 Total No. of Proj.			**1**		**Total Amount**	**$14,850.00**
208211	1/2" PLASTIC PIPE (IRRIGATION LINE)	LF	7	1	27,095.00	$1.24	$33,597.80
	Unit Sub Total	**LF**		**1**	**27,095.00**	**$1.24**	**$33,597.80**
	Item Code 208211 Total No. of Proj.			**1**		**Total Amount**	**$33,597.80**
208213	3/4" PLASTIC PIPE (IRRIGATION LINE)	LF	3	1	5,760.00	$0.50	$2,880.00
		LF	5	1	51,027.00	$0.80	$40,821.60
	Unit Sub Total	**LF**		**2**	**56,787.00**	**$0.77**	**$43,701.60**
	Item Code 208213 Total No. of Proj.			**2**		**Total Amount**	**$43,701.60**
208249	20 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	3	1	6,296.00	$3.50	$22,036.00
	Unit Sub Total	**M**		**1**	**6,296.00**	**$3.50**	**$22,036.00**
	Item Code 208249 Total No. of Proj.			**1**		**Total Amount**	**$22,036.00**
208250	25 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	3	1	2,303.00	$3.80	$8,751.40
		M	11	1	9,865.00	$6.58	$64,911.70
	Unit Sub Total	**M**		**2**	**12,168.00**	**$6.05**	**$73,663.10**
	Item Code 208250 Total No. of Proj.			**2**		**Total Amount**	**$73,663.10**
208251	32 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	3	1	2,845.00	$4.00	$11,380.00
		M	11	1	3,000.00	$6.80	$20,400.00
	Unit Sub Total	**M**		**2**	**5,845.00**	**$5.44**	**$31,780.00**
	Item Code 208251 Total No. of Proj.			**2**		**Total Amount**	**$31,780.00**
208252	40 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	3	1	1,801.00	$4.75	$8,554.75

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208252	40 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	11	1	810.00	$7.50	$6,075.00
	Unit Sub Total	**M**		**2**	**2,611.00**	**$5.60**	**$14,629.75**
	Item Code 208252 Total No. of Proj.			**2**		**Total Amount**	**$14,629.75**
208253	50 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	3	1	5,010.00	$5.20	$26,052.00
		M	11	1	966.00	$9.50	$9,177.00
	Unit Sub Total	**M**		**2**	**5,976.00**	**$5.90**	**$35,229.00**
	Item Code 208253 Total No. of Proj.			**2**		**Total Amount**	**$35,229.00**
208254	65 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	3	1	1,010.00	$5.50	$5,555.00
		M	11	1	125.00	$10.00	$1,250.00
	Unit Sub Total	**M**		**2**	**1,135.00**	**$6.00**	**$6,805.00**
	Item Code 208254 Total No. of Proj.			**2**		**Total Amount**	**$6,805.00**
208255	75 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	3	1	1,588.00	$6.20	$9,845.60
		M	11	1	3,870.00	$11.00	$42,570.00
	Unit Sub Total	**M**		**2**	**5,458.00**	**$9.60**	**$52,415.60**
	Item Code 208255 Total No. of Proj.			**2**		**Total Amount**	**$52,415.60**
208256	100 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	3	1	3,126.00	$6.80	$21,256.80
	Unit Sub Total	**M**		**1**	**3,126.00**	**$6.80**	**$21,256.80**
	Item Code 208256 Total No. of Proj.			**1**		**Total Amount**	**$21,256.80**
208262	3/4" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	3	1	1,772.00	$6.00	$10,632.00
		LF	4	5	155,531.00	$1.61	$249,849.75
		LF	5	1	29,108.00	$1.50	$43,662.00
		LF	6	1	6,745.00	$1.25	$8,431.25
		LF	7	3	32,958.00	$1.95	$64,291.00
		LF	10	4	116,857.00	$1.10	$128,200.75
		LF	12	2	62,734.00	$1.67	$104,675.55
	Unit Sub Total	**LF**		**17**	**405,705.00**	**$1.50**	**$609,742.30**
	Item Code 208262 Total No. of Proj.			**17**		**Total Amount**	**$609,742.30**
208263	1" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	3	1	756.00	$6.35	$4,800.60
		LF	4	4	34,361.00	$1.55	$53,184.96

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208263	1" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	5	2	50,775.00	$1.87	$94,932.50
		LF	6	1	8,505.00	$1.55	$13,182.75
		LF	7	3	18,576.00	$3.20	$59,367.25
		LF	10	4	21,485.00	$1.58	$33,923.00
		LF	11	2	4,761.00	$5.91	$28,134.00
		LF	12	2	21,529.00	$1.88	$40,568.70
	Unit Sub Total	**LF**		**19**	**160,748.00**	**$2.04**	**$328,093.76**
	Item Code 208263 Total No. of Proj.			**19**		**Total Amount**	**$328,093.76**
208264	1 1/4" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	4	4	26,462.00	$1.65	$43,752.20
		LF	5	1	2,459.00	$1.50	$3,688.50
		LF	6	1	3,605.00	$1.70	$6,128.50
		LF	7	3	2,485.00	$2.43	$6,046.50
		LF	10	4	10,718.00	$1.92	$20,604.00
		LF	11	1	1,513.00	$6.00	$9,078.00
		LF	12	2	6,723.00	$1.91	$12,852.70
	Unit Sub Total	**LF**		**16**	**53,965.00**	**$1.89**	**$102,150.40**
	Item Code 208264 Total No. of Proj.			**16**		**Total Amount**	**$102,150.40**
208265	1 1/2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	4	4	11,545.00	$1.75	$20,224.90
		LF	5	2	15,871.00	$2.19	$34,779.00
		LF	6	1	2,175.00	$1.95	$4,241.25
		LF	7	3	4,305.00	$5.86	$25,225.00
		LF	10	4	14,878.00	$1.94	$28,876.25
		LF	11	2	1,067.00	$6.88	$7,345.00
		LF	12	2	13,753.00	$2.07	$28,426.50
	Unit Sub Total	**LF**		**18**	**63,594.00**	**$2.34**	**$149,117.90**
	Item Code 208265 Total No. of Proj.			**18**		**Total Amount**	**$149,117.90**
208266	2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	4	5	15,259.00	$3.92	$59,837.60
		LF	5	2	13,400.00	$2.53	$33,937.50
		LF	6	1	4,070.00	$2.20	$8,954.00
		LF	7	2	4,260.00	$6.73	$28,680.00
		LF	10	4	21,512.00	$2.56	$54,971.55
		LF	11	1	1,248.00	$7.00	$8,736.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208266	2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	12	2	21,598.00	$2.65	$57,131.50
	Unit Sub Total	**LF**		**17**	**81,347.00**	**$3.10**	**$252,248.15**
	Item Code 208266 Total No. of Proj.			**17**		**Total Amount**	**$252,248.15**
208267	2 1/2" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	4	2	15,025.00	$4.13	$62,020.00
		LF	5	1	9,840.00	$3.00	$29,520.00
		LF	6	1	10,630.00	$2.45	$26,043.50
		LF	10	3	14,999.00	$2.46	$36,855.00
		LF	11	1	867.00	$8.00	$6,936.00
		LF	12	1	809.00	$4.00	$3,236.00
	Unit Sub Total	**LF**		**9**	**52,170.00**	**$3.16**	**$164,610.50**
	Item Code 208267 Total No. of Proj.			**9**		**Total Amount**	**$164,610.50**
208268	3" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	4	1	2,170.00	$4.16	$9,027.20
		LF	6	1	1,730.00	$3.00	$5,190.00
		LF	10	2	17,594.00	$3.00	$52,782.00
		LF	11	2	450.00	$5.00	$2,250.00
		LF	12	1	150.00	$10.00	$1,500.00
	Unit Sub Total	**LF**		**7**	**22,094.00**	**$3.20**	**$70,749.20**
	Item Code 208268 Total No. of Proj.			**7**		**Total Amount**	**$70,749.20**
208270	4" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	2	1	3,430.00	$26.63	$91,340.90
		LF	5	1	7,580.00	$3.25	$24,635.00
		LF	10	1	3,794.00	$4.00	$15,176.00
		LF	11	1	3,470.00	$6.00	$20,820.00
	Unit Sub Total	**LF**		**4**	**18,274.00**	**$8.32**	**$151,971.90**
	Item Code 208270 Total No. of Proj.			**4**		**Total Amount**	**$151,971.90**
208276	2" PLASTIC PIPE (PR 315) (SUPPLY LINE)	EA	3	1	317.00	$9.50	$3,011.50
	Unit Sub Total	**EA**		**1**	**317.00**	**$9.50**	**$3,011.50**
208276	2" PLASTIC PIPE (PR 315) (SUPPLY LINE)	LF	5	1	978.00	$3.10	$3,031.80
		LF	7	2	6,488.00	$3.08	$19,974.00
		LF	11	1	80.00	$20.00	$1,600.00
	Unit Sub Total	**LF**		**4**	**7,546.00**	**$3.26**	**$24,605.80**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208276 Total No. of Proj.			**5**		**Total Amount**	**$27,617.30**
208277	2 1/2" PLASTIC PIPE (PR 315) (SUPPLY LINE)	LF	5	1	1,855.00	$3.40	$6,307.00
		LF	6	1	260.00	$4.00	$1,040.00
		LF	11	1	70.00	$15.00	$1,050.00
	Unit Sub Total	**LF**		**3**	**2,185.00**	**$3.84**	**$8,397.00**
	Item Code 208277 Total No. of Proj.			**3**		**Total Amount**	**$8,397.00**
208278	3" PLASTIC PIPE (PR 315) (SUPPLY LINE)	LF	4	1	320.00	$4.81	$1,539.20
		LF	5	1	11,399.00	$3.00	$34,197.00
		LF	7	2	5,003.00	$3.56	$17,825.75
		LF	10	1	567.00	$5.00	$2,835.00
		LF	11	1	2,254.00	$15.00	$33,810.00
		LF	12	1	5,780.00	$3.95	$22,831.00
	Unit Sub Total	**LF**		**7**	**25,323.00**	**$4.46**	**$113,037.95**
	Item Code 208278 Total No. of Proj.			**7**		**Total Amount**	**$113,037.95**
208279	4" PLASTIC PIPE (PR 315) (SUPPLY LINE)	LF	11	1	190.00	$15.00	$2,850.00
	Unit Sub Total	**LF**		**1**	**190.00**	**$15.00**	**$2,850.00**
	Item Code 208279 Total No. of Proj.			**1**		**Total Amount**	**$2,850.00**
208280	6" PLASTIC PIPE (PR 315) (SUPPLY LINE)	LF	11	1	140.00	$25.00	$3,500.00
	Unit Sub Total	**LF**		**1**	**140.00**	**$25.00**	**$3,500.00**
	Item Code 208280 Total No. of Proj.			**1**		**Total Amount**	**$3,500.00**
208281	6" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	11	1	3,050.00	$9.00	$27,450.00
	Unit Sub Total	**LF**		**1**	**3,050.00**	**$9.00**	**$27,450.00**
	Item Code 208281 Total No. of Proj.			**1**		**Total Amount**	**$27,450.00**
208282	8" PLASTIC PIPE (PR 200) (SUPPLY LINE)	LF	4	1	18.00	$200.00	$3,600.00
	Unit Sub Total	**LF**		**1**	**18.00**	**$200.00**	**$3,600.00**
	Item Code 208282 Total No. of Proj.			**1**		**Total Amount**	**$3,600.00**
208301	IRRIGATION CONTROLLER ENCLOSURE CABINET	EA	4	2	16.00	$1,139.56	$18,233.00
		EA	5	1	3.00	$1,500.00	$4,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208301	IRRIGATION CONTROLLER ENCLOSURE CABINET	EA	7	1	1.00	$2,000.00	$2,000.00
		EA	12	1	2.00	$2,250.00	$4,500.00
	Unit Sub Total	**EA**		**5**	**22.00**	**$1,328.77**	**$29,233.00**
	Item Code 208301 Total No. of Proj.			**5**		**Total Amount**	**$29,233.00**
208304	WATER METER	EA	2	3	3.00	$5,269.90	$15,809.70
		EA	4	5	10.00	$53,232.27	$532,322.65
		EA	8	1	3.00	$5,000.00	$15,000.00
		EA	10	1	1.00	$14,500.00	$14,500.00
		EA	11	2	3.00	$21,666.67	$65,000.00
	Unit Sub Total	**EA**		**12**	**20.00**	**$32,131.62**	**$642,632.35**
	Item Code 208304 Total No. of Proj.			**12**		**Total Amount**	**$642,632.35**
208310	IRRIGATION SLEEVE	LF	2	1	340.00	$15.00	$5,100.00
		LF	4	6	3,030.00	$16.71	$50,641.30
		LF	10	2	600.00	$6.73	$4,040.00
		LF	11	1	140.00	$23.40	$3,276.00
	Unit Sub Total	**LF**		**10**	**4,110.00**	**$15.34**	**$63,057.30**
208310	IRRIGATION SLEEVE	M	7	1	300.00	$21.20	$6,360.00
	Unit Sub Total	**M**		**1**	**300.00**	**$21.20**	**$6,360.00**
	Item Code 208310 Total No. of Proj.			**11**		**Total Amount**	**$69,417.30**
208420	BACKFLOW PREVENTER ASSEMBLY	EA	7	1	2.00	$1,250.00	$2,500.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$1,250.00**	**$2,500.00**
	Item Code 208420 Total No. of Proj.			**1**		**Total Amount**	**$2,500.00**
208421	BACKFLOW PREVENTER ASSEMBLY ENCLOSURE	EA	2	1	1.00	$3,828.38	$3,828.38
		EA	3	1	1.00	$2,235.00	$2,235.00
		EA	4	4	11.00	$1,701.40	$18,715.40
		EA	5	2	4.00	$687.50	$2,750.00
		EA	7	2	4.00	$1,325.00	$5,300.00
		EA	10	1	2.00	$1,375.00	$2,750.00
	Unit Sub Total	**EA**		**11**	**23.00**	**$1,546.90**	**$35,578.78**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208421 Total No. of Proj.			**11**		**Total Amount**	**$35,578.78**
208425	1 1/2" BACKFLOW PREVENTER ASSEMBLY	EA	4	1	2.00	$1,500.00	$3,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$1,500.00**	**$3,000.00**
	Item Code 208425 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
208426	2" BACKFLOW PREVENTER ASSEMBLY	EA	4	3	6.00	$3,746.96	$22,481.78
		EA	5	2	2.00	$3,450.00	$6,900.00
		EA	10	1	1.00	$1,245.00	$1,245.00
	Unit Sub Total	**EA**		**6**	**9.00**	**$3,402.98**	**$30,626.78**
	Item Code 208426 Total No. of Proj.			**6**		**Total Amount**	**$30,626.78**
208428	3" BACKFLOW PREVENTER ASSEMBLY	EA	7	1	2.00	$1,750.00	$3,500.00
		EA	10	1	1.00	$2,994.00	$2,994.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$2,164.67**	**$6,494.00**
	Item Code 208428 Total No. of Proj.			**2**		**Total Amount**	**$6,494.00**
208430	4" BACKFLOW PREVENTER ASSEMBLY	EA	2	1	1.00	$6,836.75	$6,836.75
	Unit Sub Total	**EA**		**1**	**1.00**	**$6,836.75**	**$6,836.75**
	Item Code 208430 Total No. of Proj.			**1**		**Total Amount**	**$6,836.75**
208435	50 MM BACKFLOW PREVENTER ASSEMBLY	EA	3	1	3.00	$2,800.00	$8,400.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$2,800.00**	**$8,400.00**
	Item Code 208435 Total No. of Proj.			**1**		**Total Amount**	**$8,400.00**
208439	BACKFLOW PREVENTER ASSEMBLY BLANKET	EA	3	1	6.00	$550.00	$3,300.00
	Unit Sub Total	**EA**		**1**	**6.00**	**$550.00**	**$3,300.00**
	Item Code 208439 Total No. of Proj.			**1**		**Total Amount**	**$3,300.00**
208461	SPRINKLER (TYPE A-1)	EA	5	1	140.00	$35.00	$4,900.00
		EA	6	1	97.00	$30.00	$2,910.00
		EA	12	2	113.00	$16.53	$1,868.00
	Unit Sub Total	**EA**		**4**	**350.00**	**$27.65**	**$9,678.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208461 Total No. of Proj.			**4**		**Total Amount**	**$9,678.00**
208462	SPRINKLER (TYPE A-2)	EA	12	2	81.00	$37.62	$3,047.00
	Unit Sub Total	**EA**		**2**	**81.00**	**$37.62**	**$3,047.00**
	Item Code 208462 Total No. of Proj.			**2**		**Total Amount**	**$3,047.00**
208463	SPRINKLER (TYPE A-3)	EA	6	1	350.00	$7.00	$2,450.00
		EA	12	2	236.00	$16.15	$3,812.00
	Unit Sub Total	**EA**		**3**	**586.00**	**$10.69**	**$6,262.00**
	Item Code 208463 Total No. of Proj.			**3**		**Total Amount**	**$6,262.00**
208464	SPRINKLER (TYPE A-4)	EA	12	1	92.00	$35.00	$3,220.00
	Unit Sub Total	**EA**		**1**	**92.00**	**$35.00**	**$3,220.00**
	Item Code 208464 Total No. of Proj.			**1**		**Total Amount**	**$3,220.00**
208465	SPRINKLER (TYPE A-5)	EA	3	1	294.00	$55.00	$16,170.00
		EA	4	1	110.00	$51.16	$5,627.60
		EA	5	2	167.00	$41.44	$6,920.00
		EA	11	2	734.00	$22.39	$16,436.00
		EA	12	2	440.00	$18.32	$8,060.00
	Unit Sub Total	**EA**		**8**	**1,745.00**	**$30.49**	**$53,213.60**
	Item Code 208465 Total No. of Proj.			**8**		**Total Amount**	**$53,213.60**
208466	SPRINKLER (TYPE A-6)	EA	3	1	130.00	$60.00	$7,800.00
		EA	4	2	281.00	$67.95	$19,093.60
		EA	7	1	7.00	$50.00	$350.00
		EA	11	3	9.00	$62.22	$560.00
		EA	12	2	310.00	$37.03	$11,480.00
	Unit Sub Total	**EA**		**9**	**737.00**	**$53.30**	**$39,283.60**
	Item Code 208466 Total No. of Proj.			**9**		**Total Amount**	**$39,283.60**
208467	SPRINKLER (TYPE A-7)	EA	3	1	160.00	$60.00	$9,600.00
		EA	11	2	293.00	$25.43	$7,450.00
		EA	12	2	185.00	$33.24	$6,150.00
	Unit Sub Total	**EA**		**5**	**638.00**	**$36.36**	**$23,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208467 Total No. of Proj.			**5**		**Total Amount**	**$23,200.00**
208468	SPRINKLER (TYPE A-8)	EA	3	1	352.00	$55.00	$19,360.00
		EA	11	3	58.00	$83.97	$4,870.00
		EA	12	2	164.00	$41.59	$6,820.00
	Unit Sub Total	**EA**		**6**	**574.00**	**$54.09**	**$31,050.00**
	Item Code 208468 Total No. of Proj.			**6**		**Total Amount**	**$31,050.00**
208471	SPRINKLER (TYPE B-1)	EA	3	1	9.00	$35.00	$315.00
		EA	5	1	23.00	$15.00	$345.00
		EA	6	1	38.00	$22.75	$864.50
		EA	10	2	255.00	$25.27	$6,444.00
		EA	11	1	40.00	$25.00	$1,000.00
	Unit Sub Total	**EA**		**6**	**365.00**	**$24.57**	**$8,968.50**
	Item Code 208471 Total No. of Proj.			**6**		**Total Amount**	**$8,968.50**
208472	SPRINKLER (TYPE B-2)	EA	3	1	69.00	$35.00	$2,415.00
		EA	4	1	360.00	$30.00	$10,800.00
		EA	5	1	670.00	$20.00	$13,400.00
		EA	6	1	140.00	$25.00	$3,500.00
		EA	10	2	306.00	$22.52	$6,890.00
	Unit Sub Total	**EA**		**6**	**1,545.00**	**$23.95**	**$37,005.00**
	Item Code 208472 Total No. of Proj.			**6**		**Total Amount**	**$37,005.00**
208473	SPRINKLER (TYPE B-3)	EA	7	1	70.00	$20.00	$1,400.00
		EA	12	1	184.00	$45.00	$8,280.00
	Unit Sub Total	**EA**		**2**	**254.00**	**$38.11**	**$9,680.00**
	Item Code 208473 Total No. of Proj.			**2**		**Total Amount**	**$9,680.00**
208474	SPRINKLER (TYPE B-4)	EA	3	1	4.00	$35.00	$140.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$35.00**	**$140.00**
	Item Code 208474 Total No. of Proj.			**1**		**Total Amount**	**$140.00**
208475	SPRINKLER (TYPE B-5)	EA	10	1	1,000.00	$11.00	$11,000.00
	Unit Sub Total	**EA**		**1**	**1,000.00**	**$11.00**	**$11,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208475	**Total No. of Proj.**			**1**		**Total Amount**	**$11,000.00**
208476	SPRINKLER (TYPE B-6)		EA	10	1	450.00	$20.00	$9,000.00
		Unit Sub Total	**EA**		**1**	**450.00**	**$20.00**	**$9,000.00**
	Item Code 208476	**Total No. of Proj.**			**1**		**Total Amount**	**$9,000.00**
208480	SPRINKLER (TYPE C-2 MOD)		EA	4	1	840.00	$11.00	$9,240.00
			EA	11	2	930.00	$17.38	$16,165.00
			EA	12	1	1,109.00	$18.00	$19,962.00
		Unit Sub Total	**EA**		**4**	**2,879.00**	**$15.76**	**$45,367.00**
	Item Code 208480	**Total No. of Proj.**			**4**		**Total Amount**	**$45,367.00**
208481	SPRINKLER (TYPE C-1)		EA	3	1	139.00	$27.00	$3,753.00
		Unit Sub Total	**EA**		**1**	**139.00**	**$27.00**	**$3,753.00**
	Item Code 208481	**Total No. of Proj.**			**1**		**Total Amount**	**$3,753.00**
208482	SPRINKLER (TYPE C-2)		EA	3	2	268.00	$37.01	$9,920.00
			EA	4	4	8,930.00	$11.48	$102,517.80
			EA	5	1	4,680.00	$14.00	$65,520.00
			EA	7	3	4,900.00	$17.09	$83,720.00
			EA	10	2	1,860.00	$19.97	$37,150.00
			EA	12	1	310.00	$6.00	$1,860.00
		Unit Sub Total	**EA**		**13**	**20,948.00**	**$14.35**	**$300,687.80**
	Item Code 208482	**Total No. of Proj.**			**13**		**Total Amount**	**$300,687.80**
208483	SPRINKLER (TYPE C-3)		EA	5	1	3,700.00	$10.00	$37,000.00
			EA	6	1	400.00	$26.00	$10,400.00
			EA	10	2	3,200.00	$5.19	$16,619.00
			EA	12	3	1,372.00	$8.95	$12,281.50
		Unit Sub Total	**EA**		**7**	**8,672.00**	**$8.80**	**$76,300.50**
	Item Code 208483	**Total No. of Proj.**			**7**		**Total Amount**	**$76,300.50**
208491	50 MM GATE VALVE		EA	11	1	35.00	$150.00	$5,250.00
		Unit Sub Total	**EA**		**1**	**35.00**	**$150.00**	**$5,250.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208491 Total No. of Proj.			**1**		**Total Amount**	**$5,250.00**
208493	75 MM GATE VALVE	EA	3	1	3.00	$450.00	$1,350.00
		EA	11	1	5.00	$400.00	$2,000.00
	Unit Sub Total	**EA**		**2**	**8.00**	**$418.75**	**$3,350.00**
	Item Code 208493 Total No. of Proj.			**2**		**Total Amount**	**$3,350.00**
208509	25 MM WYE STRAINER	EA	3	1	10.00	$550.00	$5,500.00
	Unit Sub Total	**EA**		**1**	**10.00**	**$550.00**	**$5,500.00**
	Item Code 208509 Total No. of Proj.			**1**		**Total Amount**	**$5,500.00**
208511	40 MM WYE STRAINER	EA	3	1	4.00	$800.00	$3,200.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$800.00**	**$3,200.00**
	Item Code 208511 Total No. of Proj.			**1**		**Total Amount**	**$3,200.00**
208512	50 MM WYE STRAINER	EA	3	1	8.00	$1,200.00	$9,600.00
	Unit Sub Total	**EA**		**1**	**8.00**	**$1,200.00**	**$9,600.00**
	Item Code 208512 Total No. of Proj.			**1**		**Total Amount**	**$9,600.00**
208517	20 MM QUICK COUPLING VALVE	EA	3	1	17.00	$175.00	$2,975.00
	Unit Sub Total	**EA**		**1**	**17.00**	**$175.00**	**$2,975.00**
	Item Code 208517 Total No. of Proj.			**1**		**Total Amount**	**$2,975.00**
208526	SPRINKLER (TYPE D-1)	EA	3	1	1,180.00	$30.00	$35,400.00
		EA	4	2	1,740.00	$11.57	$20,130.00
		EA	5	1	3,620.00	$5.00	$18,100.00
	Unit Sub Total	**EA**		**4**	**6,540.00**	**$11.26**	**$73,630.00**
	Item Code 208526 Total No. of Proj.			**4**		**Total Amount**	**$73,630.00**
208527	SPRINKLER (TYPE D-2)	EA	4	1	100.00	$10.50	$1,050.00
		EA	12	1	980.00	$6.50	$6,370.00
	Unit Sub Total	**EA**		**2**	**1,080.00**	**$6.87**	**$7,420.00**
	Item Code 208527 Total No. of Proj.			**2**		**Total Amount**	**$7,420.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208528	SPRINKLER (TYPE D-3)	LF	4	1	8,200.00	$2.00	$16,400.00
	Unit Sub Total	**LF**		**1**	**8,200.00**	**$2.00**	**$16,400.00**
	Item Code 208528 Total No. of Proj.			**1**		**Total Amount**	**$16,400.00**
208560	FILTER ASSEMBLY UNIT	EA	5	1	15.00	$330.00	$4,950.00
		EA	6	1	4.00	$650.00	$2,600.00
		EA	7	1	2.00	$150.00	$300.00
		EA	10	1	1.00	$200.00	$200.00
		EA	12	1	3.00	$225.00	$675.00
	Unit Sub Total	**EA**		**5**	**25.00**	**$349.00**	**$8,725.00**
	Item Code 208560 Total No. of Proj.			**5**		**Total Amount**	**$8,725.00**
208562	CAM COUPLER ASSEMBLY	EA	3	1	4.00	$750.00	$3,000.00
		EA	4	2	2.00	$752.50	$1,505.00
		EA	5	2	16.00	$390.63	$6,250.00
		EA	10	2	30.00	$218.33	$6,550.00
		EA	12	1	5.00	$500.00	$2,500.00
	Unit Sub Total	**EA**		**8**	**57.00**	**$347.46**	**$19,805.00**
	Item Code 208562 Total No. of Proj.			**8**		**Total Amount**	**$19,805.00**
208565	REPLACE VALVE BOX COVER	EA	11	2	104.00	$22.88	$2,380.00
	Unit Sub Total	**EA**		**2**	**104.00**	**$22.88**	**$2,380.00**
	Item Code 208565 Total No. of Proj.			**2**		**Total Amount**	**$2,380.00**
208572	1" GATE VALVE	EA	4	1	1.00	$120.00	$120.00
		EA	7	1	4.00	$400.00	$1,600.00
	Unit Sub Total	**EA**		**2**	**5.00**	**$344.00**	**$1,720.00**
	Item Code 208572 Total No. of Proj.			**2**		**Total Amount**	**$1,720.00**
208573	1 1/4" GATE VALVE	EA	10	1	1.00	$60.00	$60.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$60.00**	**$60.00**
	Item Code 208573 Total No. of Proj.			**1**		**Total Amount**	**$60.00**
208574	1 1/2" GATE VALVE	EA	4	2	13.00	$164.86	$2,143.12
		EA	7	1	2.00	$250.00	$500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208574	1 1/2" GATE VALVE		EA	10	1	3.00	$100.00	$300.00
		Unit Sub Total	**EA**		**4**	**18.00**	**$163.51**	**$2,943.12**
	Item Code 208574	**Total No. of Proj.**			**4**		**Total Amount**	**$2,943.12**
208575	2" GATE VALVE		EA	4	4	44.00	$228.34	$10,047.00
			EA	5	1	4.00	$275.00	$1,100.00
			EA	6	1	6.00	$245.00	$1,470.00
			EA	7	1	4.00	$275.00	$1,100.00
			EA	10	2	2.00	$151.00	$302.00
			EA	11	1	5.00	$400.00	$2,000.00
			EA	12	2	2.00	$250.00	$500.00
		Unit Sub Total	**EA**		**12**	**67.00**	**$246.55**	**$16,519.00**
	Item Code 208575	**Total No. of Proj.**			**12**		**Total Amount**	**$16,519.00**
208576	2 1/2" GATE VALVE		EA	4	1	39.00	$450.00	$17,550.00
			EA	7	1	1.00	$350.00	$350.00
		Unit Sub Total	**EA**		**2**	**40.00**	**$447.50**	**$17,900.00**
	Item Code 208576	**Total No. of Proj.**			**2**		**Total Amount**	**$17,900.00**
208588	3" GATE VALVE		EA	4	1	4.00	$497.13	$1,988.52
			EA	5	1	14.00	$375.00	$5,250.00
			EA	10	2	6.00	$357.50	$2,145.00
			EA	11	3	20.00	$742.50	$14,850.00
			EA	12	1	5.00	$365.00	$1,825.00
		Unit Sub Total	**EA**		**8**	**49.00**	**$531.81**	**$26,058.52**
	Item Code 208588	**Total No. of Proj.**			**8**		**Total Amount**	**$26,058.52**
208589	4" GATE VALVE		EA	5	1	18.00	$375.00	$6,750.00
			EA	10	1	6.00	$675.00	$4,050.00
			EA	11	1	3.00	$700.00	$2,100.00
		Unit Sub Total	**EA**		**3**	**27.00**	**$477.78**	**$12,900.00**
	Item Code 208589	**Total No. of Proj.**			**3**		**Total Amount**	**$12,900.00**
208590	6" GATE VALVE		EA	11	1	5.00	$1,050.00	$5,250.00
			EA	12	1	3.00	$1,850.00	$5,550.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**2**	**8.00**	**$1,350.00**	**$10,800.00**
	Item Code 208590 Total No. of Proj.			**2**		**Total Amount**	**$10,800.00**
208595	1" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	4	1	4,850.00	$5.25	$25,462.50
		LF	5	1	16,198.00	$1.50	$24,297.00
	Unit Sub Total	**LF**		**2**	**21,048.00**	**$2.36**	**$49,759.50**
	Item Code 208595 Total No. of Proj.			**2**		**Total Amount**	**$49,759.50**
208597	1 1/2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	5	1	416.00	$1.75	$728.00
	Unit Sub Total	**LF**		**1**	**416.00**	**$1.75**	**$728.00**
	Item Code 208597 Total No. of Proj.			**1**		**Total Amount**	**$728.00**
208598	2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	4	1	100.00	$6.30	$630.00
		LF	10	1	70.00	$15.00	$1,050.00
	Unit Sub Total	**LF**		**2**	**170.00**	**$9.88**	**$1,680.00**
	Item Code 208598 Total No. of Proj.			**2**		**Total Amount**	**$1,680.00**
208618	1" MANUAL CONTROL VALVE	EA	4	1	5.00	$173.25	$866.25
	Unit Sub Total	**EA**		**1**	**5.00**	**$173.25**	**$866.25**
	Item Code 208618 Total No. of Proj.			**1**		**Total Amount**	**$866.25**
208626	1" WYE STRAINER	EA	4	4	33.00	$168.88	$5,573.05
		EA	10	1	5.00	$100.00	$500.00
	Unit Sub Total	**EA**		**5**	**38.00**	**$159.82**	**$6,073.05**
	Item Code 208626 Total No. of Proj.			**5**		**Total Amount**	**$6,073.05**
208627	1 1/4" WYE STRAINER	EA	4	2	7.00	$232.78	$1,629.44
	Unit Sub Total	**EA**		**2**	**7.00**	**$232.78**	**$1,629.44**
	Item Code 208627 Total No. of Proj.			**2**		**Total Amount**	**$1,629.44**
208628	1 1/2" WYE STRAINER	EA	4	4	36.00	$236.40	$8,510.54
		EA	10	2	7.00	$146.43	$1,025.00
	Unit Sub Total	**EA**		**6**	**43.00**	**$221.76**	**$9,535.54**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208628	**Total No. of Proj.**			**6**		**Total Amount**	**$9,535.54**
208630	2" WYE STRAINER		EA	3	1	4.00	$450.00	$1,800.00
			EA	4	1	1.00	$400.00	$400.00
			EA	5	1	1.00	$230.00	$230.00
			EA	10	1	17.00	$150.00	$2,550.00
		Unit Sub Total	**EA**		**4**	**23.00**	**$216.52**	**$4,980.00**
	Item Code 208630	**Total No. of Proj.**			**4**		**Total Amount**	**$4,980.00**
208633	1" PRESSURE RELIEF VALVE		EA	7	1	7.00	$200.00	$1,400.00
		Unit Sub Total	**EA**		**1**	**7.00**	**$200.00**	**$1,400.00**
	Item Code 208633	**Total No. of Proj.**			**1**		**Total Amount**	**$1,400.00**
208634	3" WYE STRAINER		EA	10	1	8.00	$250.00	$2,000.00
		Unit Sub Total	**EA**		**1**	**8.00**	**$250.00**	**$2,000.00**
	Item Code 208634	**Total No. of Proj.**			**1**		**Total Amount**	**$2,000.00**
208645	3/4" QUICK COUPLING VALVE		EA	4	4	78.00	$178.72	$13,940.35
			EA	10	1	2.00	$200.00	$400.00
		Unit Sub Total	**EA**		**5**	**80.00**	**$179.25**	**$14,340.35**
	Item Code 208645	**Total No. of Proj.**			**5**		**Total Amount**	**$14,340.35**
208670	CHECK VALVE		EA	4	2	26.00	$45.46	$1,182.00
			EA	6	1	39.00	$24.50	$955.50
		Unit Sub Total	**EA**		**3**	**65.00**	**$32.88**	**$2,137.50**
	Item Code 208670	**Total No. of Proj.**			**3**		**Total Amount**	**$2,137.50**
208683	BALL VALVE		EA	3	2	19.00	$138.95	$2,640.00
			EA	4	3	25.00	$108.00	$2,700.00
			EA	5	1	16.00	$150.00	$2,400.00
			EA	7	3	43.00	$211.63	$9,100.00
			EA	11	1	2.00	$100.00	$200.00
			EA	12	2	31.00	$235.48	$7,300.00
		Unit Sub Total	**EA**		**12**	**136.00**	**$178.97**	**$24,340.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 208683 Total No. of Proj.			**12**		**Total Amount**	**$24,340.00**
208708	6" CONDUIT	LF	1	1	50.00	$60.00	$3,000.00
		LF	3	1	67.00	$37.00	$2,479.00
	Unit Sub Total	**LF**		**2**	**117.00**	**$46.83**	**$5,479.00**
	Item Code 208708 Total No. of Proj.			**2**		**Total Amount**	**$5,479.00**
208709	8" CONDUIT	LF	3	1	40.00	$40.00	$1,600.00
	Unit Sub Total	**LF**		**1**	**40.00**	**$40.00**	**$1,600.00**
	Item Code 208709 Total No. of Proj.			**1**		**Total Amount**	**$1,600.00**
208731	200 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	M	3	1	110.00	$30.00	$3,300.00
		M	4	2	778.00	$154.37	$120,100.00
		M	7	2	90.00	$239.44	$21,549.60
		M	11	1	450.00	$90.00	$40,500.00
	Unit Sub Total	**M**		**6**	**1,428.00**	**$129.87**	**$185,449.60**
	Item Code 208731 Total No. of Proj.			**6**		**Total Amount**	**$185,449.60**
208732	250 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	M	3	1	59.00	$150.00	$8,850.00
		M	7	2	81.00	$205.93	$16,680.00
		M	11	1	330.00	$150.00	$49,500.00
	Unit Sub Total	**M**		**4**	**470.00**	**$159.64**	**$75,030.00**
	Item Code 208732 Total No. of Proj.			**4**		**Total Amount**	**$75,030.00**
208733	300 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	M	3	1	8.00	$50.00	$400.00
	Unit Sub Total	**M**		**1**	**8.00**	**$50.00**	**$400.00**
	Item Code 208733 Total No. of Proj.			**1**		**Total Amount**	**$400.00**
208738	8" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	LF	1	1	30.00	$35.00	$1,050.00
		LF	4	4	1,867.00	$31.86	$59,477.00
		LF	5	1	490.00	$37.00	$18,130.00
		LF	11	3	1,240.00	$35.80	$44,390.00
		LF	12	2	870.00	$49.24	$42,840.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**11**	**4,497.00**	**$36.89**	**$165,887.00**
	Item Code 208738 Total No. of Proj.			**11**		**Total Amount**	**$165,887.00**
208739	10" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	LF	4	1	1,040.00	$27.00	$28,080.00
		LF	5	1	255.00	$48.00	$12,240.00
		LF	12	3	1,320.00	$32.94	$43,480.00
	Unit Sub Total	**LF**		**5**	**2,615.00**	**$32.05**	**$83,800.00**
	Item Code 208739 Total No. of Proj.			**5**		**Total Amount**	**$83,800.00**
208740	12" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	LF	6	1	250.00	$41.00	$10,250.00
		LF	11	1	110.00	$45.00	$4,950.00
		LF	12	1	1,180.00	$70.00	$82,600.00
	Unit Sub Total	**LF**		**3**	**1,540.00**	**$63.51**	**$97,800.00**
	Item Code 208740 Total No. of Proj.			**3**		**Total Amount**	**$97,800.00**
208745	150 MM BITUMINOUS COATED STEEL PIPE CONDUIT (1.63 MM THICK)	M	10	1	16.00	$350.00	$5,600.00
	Unit Sub Total	**M**		**1**	**16.00**	**$350.00**	**$5,600.00**
	Item Code 208745 Total No. of Proj.			**1**		**Total Amount**	**$5,600.00**
208746	200 MM BITUMINOUS COATED STEEL PIPE CONDUIT (1.63 MM THICK)	M	10	1	36.00	$477.00	$17,172.00
	Unit Sub Total	**M**		**1**	**36.00**	**$477.00**	**$17,172.00**
	Item Code 208746 Total No. of Proj.			**1**		**Total Amount**	**$17,172.00**
208756	6" CORRUGATED STEEL PIPE CONDUIT (.064" THICK)	LF	2	1	82.00	$75.00	$6,150.00
	Unit Sub Total	**LF**		**1**	**82.00**	**$75.00**	**$6,150.00**
	Item Code 208756 Total No. of Proj.			**1**		**Total Amount**	**$6,150.00**
208770	1 1/4" GALVANIZED STEEL PIPE (CONDUIT)	LF	12	1	220.00	$15.00	$3,300.00
	Unit Sub Total	**LF**		**1**	**220.00**	**$15.00**	**$3,300.00**
	Item Code 208770 Total No. of Proj.			**1**		**Total Amount**	**$3,300.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208798	200 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	M	6	1	18.00	$100.00	$1,800.00
		M	7	3	102.00	$456.80	$46,593.60
	Unit Sub Total	**M**		**4**	**120.00**	**$403.28**	**$48,393.60**
	Item Code 208798 Total No. of Proj.			**4**		**Total Amount**	**$48,393.60**
208799	250 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	M	3	1	41.00	$500.00	$20,500.00
	Unit Sub Total	**M**		**1**	**41.00**	**$500.00**	**$20,500.00**
	Item Code 208799 Total No. of Proj.			**1**		**Total Amount**	**$20,500.00**
208800	300 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	M	3	1	32.00	$950.00	$30,400.00
	Unit Sub Total	**M**		**1**	**32.00**	**$950.00**	**$30,400.00**
	Item Code 208800 Total No. of Proj.			**1**		**Total Amount**	**$30,400.00**
208805	6" WELDED STEEL PIPE CONDUIT (.250" THICK)	LF	4	1	24.00	$400.00	$9,600.00
		LF	7	1	165.00	$121.00	$19,965.00
	Unit Sub Total	**LF**		**2**	**189.00**	**$156.43**	**$29,565.00**
	Item Code 208805 Total No. of Proj.			**2**		**Total Amount**	**$29,565.00**
208808	8" WELDED STEEL PIPE CONDUIT (.250" THICK)	LF	4	2	124.00	$192.58	$23,880.00
		LF	6	1	280.00	$105.00	$29,400.00
		LF	7	2	230.00	$121.65	$27,980.00
		LF	11	3	85.00	$191.76	$16,300.00
		LF	12	2	94.00	$564.47	$53,060.00
	Unit Sub Total	**LF**		**10**	**813.00**	**$185.26**	**$150,620.00**
	Item Code 208808 Total No. of Proj.			**10**		**Total Amount**	**$150,620.00**
208809	10" WELDED STEEL PIPE CONDUIT (.250" THICK)	LF	10	1	390.00	$72.42	$28,243.80
		LF	11	1	50.00	$145.00	$7,250.00
		LF	12	2	110.00	$132.73	$14,600.00
	Unit Sub Total	**LF**		**4**	**550.00**	**$91.08**	**$50,093.80**
	Item Code 208809 Total No. of Proj.			**4**		**Total Amount**	**$50,093.80**
208812	12" WELDED STEEL PIPE CONDUIT (.250" THICK)	LF	8	1	520.00	$160.00	$83,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
208812	12" WELDED STEEL PIPE CONDUIT (.250" THICK)	LF	10	2	855.00	$34.44	$29,450.00
	Unit Sub Total	**LF**		**3**	**1,375.00**	**$81.93**	**$112,650.00**
	Item Code 208812 Total No. of Proj.			**3**		**Total Amount**	**$112,650.00**
208905	EXTEND 6" CONDUIT	LF	4	1	45.00	$120.00	$5,400.00
		LF	12	2	190.00	$55.00	$10,450.00
	Unit Sub Total	**LF**		**3**	**235.00**	**$67.45**	**$15,850.00**
	Item Code 208905 Total No. of Proj.			**3**		**Total Amount**	**$15,850.00**
208906	EXTEND 8" CONDUIT	LF	3	1	65.00	$40.00	$2,600.00
		LF	4	2	48.00	$131.67	$6,320.00
		LF	6	3	630.00	$77.43	$48,780.00
		LF	11	1	220.00	$335.00	$73,700.00
		LF	12	3	192.00	$58.23	$11,180.00
	Unit Sub Total	**LF**		**10**	**1,155.00**	**$123.45**	**$142,580.00**
	Item Code 208906 Total No. of Proj.			**10**		**Total Amount**	**$142,580.00**
208907	EXTEND 10" CONDUIT	LF	11	1	14.00	$87.75	$1,228.50
		LF	12	1	140.00	$97.00	$13,580.00
	Unit Sub Total	**LF**		**2**	**154.00**	**$96.16**	**$14,808.50**
	Item Code 208907 Total No. of Proj.			**2**		**Total Amount**	**$14,808.50**
208908	EXTEND 150 MM CONDUIT	M	7	1	1.20	$550.00	$660.00
	Unit Sub Total	**M**		**1**	**1.20**	**$550.00**	**$660.00**
	Item Code 208908 Total No. of Proj.			**1**		**Total Amount**	**$660.00**
208910	EXTEND 250 MM CONDUIT	M	11	1	60.00	$180.00	$10,800.00
	Unit Sub Total	**M**		**1**	**60.00**	**$180.00**	**$10,800.00**
	Item Code 208910 Total No. of Proj.			**1**		**Total Amount**	**$10,800.00**
209202	RECYCLED WATER WARNING SIGNS	LS	5	1	1.00	$275.00	$275.00
		LS	11	2	2.00	$2,500.00	$5,000.00
		LS	12	1	1.00	$2,500.00	$2,500.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$1,943.75**	**$7,775.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 209202 Total No. of Proj.			**4**		**Total Amount**	**$7,775.00**
209503	BOOSTER PUMP SYSTEM	EA	3	1	6.00	$23,400.00	$140,400.00
		EA	10	1	2.00	$15,800.00	$31,600.00
	Unit Sub Total	**EA**		**2**	**8.00**	**$21,500.00**	**$172,000.00**
	Item Code 209503 Total No. of Proj.			**2**		**Total Amount**	**$172,000.00**
220101	FINISHING ROADWAY	LS	2	2	2.00	$3,000.00	$6,000.00
		LS	3	1	1.00	$12,000.00	$12,000.00
		LS	5	1	1.00	$9,000.00	$9,000.00
		LS	9	1	1.00	$10,000.00	$10,000.00
		LS	11	1	1.00	$20,300.00	$20,300.00
		LS	12	2	2.00	$12,750.00	$25,500.00
	Unit Sub Total	**LS**		**8**	**8.00**	**$10,350.00**	**$82,800.00**
	Item Code 220101 Total No. of Proj.			**8**		**Total Amount**	**$82,800.00**
240100	LIME	TON	12	2	1,650.00	$185.47	$306,020.00
	Unit Sub Total	**TON**		**2**	**1,650.00**	**$185.47**	**$306,020.00**
240100	LIME	TONN	4	1	3,680.00	$150.00	$552,000.00
	Unit Sub Total	**TONN**		**1**	**3,680.00**	**$150.00**	**$552,000.00**
	Item Code 240100 Total No. of Proj.			**3**		**Total Amount**	**$858,020.00**
240105	LIME STABILIZED SOIL	SQYD	12	2	95,200.00	$2.29	$217,850.00
	Unit Sub Total	**SQYD**		**2**	**95,200.00**	**$2.29**	**$217,850.00**
	Item Code 240105 Total No. of Proj.			**2**		**Total Amount**	**$217,850.00**
250101	CLASS 1 AGGREGATE SUBBASE	CY	5	2	160,600.00	$19.12	$3,070,430.00
		CY	8	1	8.00	$156.00	$1,248.00
	Unit Sub Total	**CY**		**3**	**160,608.00**	**$19.13**	**$3,071,678.00**
	Item Code 250101 Total No. of Proj.			**3**		**Total Amount**	**$3,071,678.00**
250201	CLASS 2 AGGREGATE SUBBASE	CY	1	1	390.00	$30.00	$11,700.00
		CY	3	1	600.00	$37.00	$22,200.00
		CY	6	1	90,300.00	$16.20	$1,462,860.00
		CY	8	1	210.00	$85.00	$17,850.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
250201	CLASS 2 AGGREGATE SUBBASE		CY	12	7	36,493.00	$24.65	$899,650.00
		Unit Sub Total	**CY**		**11**	**127,993.00**	**$18.86**	**$2,414,260.00**
	Item Code 250201	**Total No. of Proj.**			**11**		**Total Amount**	**$2,414,260.00**
250301	CLASS 3 AGGREGATE SUBBASE		CY	4	1	20.00	$95.00	$1,900.00
		Unit Sub Total	**CY**		**1**	**20.00**	**$95.00**	**$1,900.00**
	Item Code 250301	**Total No. of Proj.**			**1**		**Total Amount**	**$1,900.00**
250401	CLASS 4 AGGREGATE SUBBASE		CY	4	11	74,812.30	$17.32	$1,295,623.70
			CY	10	1	14,400.00	$11.30	$162,720.00
		Unit Sub Total	**CY**		**12**	**89,212.30**	**$16.35**	**$1,458,343.70**
250401	CLASS 4 AGGREGATE SUBBASE		M3	4	2	15,120.00	$25.62	$387,400.00
			M3	11	2	45,900.00	$19.72	$905,100.00
		Unit Sub Total	**M3**		**4**	**61,020.00**	**$21.18**	**$1,292,500.00**
	Item Code 250401	**Total No. of Proj.**			**16**		**Total Amount**	**$2,750,843.70**
260201	CLASS 2 AGGREGATE BASE		CY	1	17	9,940.00	$51.10	$507,950.00
			CY	2	18	97,255.00	$29.71	$2,889,164.80
			CY	3	14	134,910.00	$29.38	$3,964,108.00
			CY	4	12	16,326.00	$55.19	$901,036.00
			CY	5	11	24,311.00	$42.39	$1,030,644.00
			CY	6	14	90,525.00	$25.47	$2,306,020.00
			CY	8	8	10,551.00	$50.14	$529,060.00
			CY	9	6	4,294.00	$43.49	$186,762.34
			CY	10	7	10,233.00	$30.76	$314,746.00
			CY	11	7	18,444.00	$35.50	$654,763.50
			CY	12	7	54,042.00	$27.14	$1,466,710.00
		Unit Sub Total	**CY**		**121**	**470,831.00**	**$31.33**	**$14,750,964.64**
260201	CLASS 2 AGGREGATE BASE		M3	2	1	1,900.00	$65.00	$123,500.00
			M3	3	1	16,500.00	$40.00	$660,000.00
			M3	6	3	133,810.00	$31.28	$4,185,150.00
			M3	7	1	6.00	$170.00	$1,020.00
			M3	10	1	17,200.00	$39.00	$670,800.00
			M3	11	2	44,350.00	$43.48	$1,928,250.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M3**		**9**	**213,766.00**	**$35.41**	**$7,568,720.00**
	Item Code 260201	**Total No. of Proj.**			**130**		**Total Amount**	**$22,319,684.64**
260210	AGGREGATE BASE (APPROACH SLAB)		CY	1	1	1.00	$250.00	$250.00
			CY	2	4	111.00	$140.45	$15,590.00
			CY	3	4	109.00	$226.24	$24,660.00
			CY	4	4	191.00	$116.42	$22,237.00
			CY	6	3	73.00	$232.67	$16,985.00
			CY	7	1	36.00	$350.00	$12,600.00
			CY	8	1	133.00	$544.00	$72,352.00
			CY	9	1	9.00	$500.00	$4,500.00
			CY	10	2	19.00	$363.55	$6,907.50
			CY	11	5	103.00	$330.29	$34,020.00
			CY	12	4	81.00	$327.72	$26,545.00
		Unit Sub Total	**CY**		**30**	**866.00**	**$273.26**	**$236,646.50**
260210	AGGREGATE BASE (APPROACH SLAB)		M3	7	3	105.00	$228.34	$23,976.00
		Unit Sub Total	**M3**		**3**	**105.00**	**$228.34**	**$23,976.00**
	Item Code 260210	**Total No. of Proj.**			**33**		**Total Amount**	**$260,622.50**
260301	CLASS 3 AGGREGATE BASE		CY	4	13	64,727.00	$32.40	$2,097,117.00
			CY	7	3	43.00	$143.86	$6,186.00
			CY	10	1	19,100.00	$28.15	$537,665.00
			CY	12	1	4,750.00	$20.00	$95,000.00
		Unit Sub Total	**CY**		**18**	**88,620.00**	**$30.87**	**$2,735,968.00**
260301	CLASS 3 AGGREGATE BASE		M3	4	2	19,970.00	$35.35	$705,990.00
			M3	7	5	84,940.00	$33.10	$2,811,800.00
		Unit Sub Total	**M3**		**7**	**104,910.00**	**$33.53**	**$3,517,790.00**
	Item Code 260301	**Total No. of Proj.**			**25**		**Total Amount**	**$6,253,758.00**
270001	CEMENT TREATED BASE (ROAD-MIXED, CLASS A)		CY	11	1	230.00	$440.00	$101,200.00
		Unit Sub Total	**CY**		**1**	**230.00**	**$440.00**	**$101,200.00**
	Item Code 270001	**Total No. of Proj.**			**1**		**Total Amount**	**$101,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
270011	CEMENT TREATED BASE (PLANT-MIXED, CLASS A)	M3	11	1	5,480.00	$60.00	$328,800.00
	Unit Sub Total	**M3**		**1**	**5,480.00**	**$60.00**	**$328,800.00**
	Item Code 270011 Total No. of Proj.			**1**		**Total Amount**	**$328,800.00**
270065	ASPHALTIC EMULSION (CURING SEAL)	TON	12	2	82.00	$559.63	$45,890.00
	Unit Sub Total	**TON**		**2**	**82.00**	**$559.63**	**$45,890.00**
	Item Code 270065 Total No. of Proj.			**2**		**Total Amount**	**$45,890.00**
280000	LEAN CONCRETE BASE	CY	3	1	1,010.00	$160.00	$161,600.00
		CY	4	5	30,340.00	$125.47	$3,806,650.00
		CY	5	2	48,390.00	$74.47	$3,603,740.00
		CY	6	1	210.00	$190.00	$39,900.00
		CY	7	1	11.00	$254.00	$2,794.00
		CY	8	2	9,540.00	$82.92	$791,100.00
		CY	12	3	21,330.00	$101.38	$2,162,500.00
	Unit Sub Total	**CY**		**15**	**110,831.00**	**$95.35**	**$10,568,284.00**
280000	LEAN CONCRETE BASE	M3	7	5	52,400.00	$99.18	$5,196,893.00
	Unit Sub Total	**M3**		**5**	**52,400.00**	**$99.18**	**$5,196,893.00**
	Item Code 280000 Total No. of Proj.			**20**		**Total Amount**	**$15,765,177.00**
290201	ASPHALT TREATED PERMEABLE BASE	CY	4	3	2,320.00	$130.78	$303,400.00
		CY	6	1	600.00	$175.00	$105,000.00
		CY	12	1	1,260.00	$133.00	$167,580.00
	Unit Sub Total	**CY**		**5**	**4,180.00**	**$137.79**	**$575,980.00**
	Item Code 290201 Total No. of Proj.			**5**		**Total Amount**	**$575,980.00**
290301	CEMENT TREATED PERMEABLE BASE	CY	2	1	13.00	$400.00	$5,200.00
	Unit Sub Total	**CY**		**1**	**13.00**	**$400.00**	**$5,200.00**
	Item Code 290301 Total No. of Proj.			**1**		**Total Amount**	**$5,200.00**
365001	SAND COVER	TON	1	3	1,090.00	$103.79	$113,130.00
		TON	2	2	770.00	$132.27	$101,850.00
		TON	3	2	710.00	$28.29	$20,082.50
		TON	4	2	190.00	$132.89	$25,250.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
365001	SAND COVER	TON	5	1	190.00	$30.00	$5,700.00
		TON	6	6	2,125.00	$22.22	$47,215.00
		TON	7	1	4.20	$52.00	$218.40
		TON	8	1	170.00	$125.00	$21,250.00
		TON	9	6	3,160.00	$53.66	$169,575.00
		TON	10	2	580.00	$19.04	$11,042.50
		TON	11	2	2,490.00	$49.91	$124,282.00
	Unit Sub Total	**TON**		**28**	**11,479.20**	**$55.72**	**$639,595.40**
	Item Code 365001 Total No. of Proj.			**28**		**Total Amount**	**$639,595.40**
370120	ASPHALT-RUBBER BINDER	TON	1	2	1,060.00	$720.28	$763,500.00
		TON	2	1	1,010.00	$880.00	$888,800.00
		TON	4	4	1,322.00	$1,170.78	$1,547,768.00
		TON	7	1	21.00	$566.00	$11,886.00
		TON	11	1	1,710.00	$915.00	$1,564,650.00
	Unit Sub Total	**TON**		**9**	**5,123.00**	**$932.38**	**$4,776,604.00**
	Item Code 370120 Total No. of Proj.			**9**		**Total Amount**	**$4,776,604.00**
370125	ASPHALT BINDER (POLYMER MODIFIED)	TON	6	1	260.00	$1.00	$260.00
	Unit Sub Total	**TON**		**1**	**260.00**	**$1.00**	**$260.00**
	Item Code 370125 Total No. of Proj.			**1**		**Total Amount**	**$260.00**
373900	ASPHALTIC EMULSION	TON	2	2	311.00	$522.75	$162,575.00
		TON	3	1	13.00	$400.00	$5,200.00
		TON	4	1	14.00	$1,053.00	$14,742.00
		TON	6	1	3.50	$800.00	$2,800.00
	Unit Sub Total	**TON**		**5**	**341.50**	**$542.66**	**$185,317.00**
	Item Code 373900 Total No. of Proj.			**5**		**Total Amount**	**$185,317.00**
374002	ASPHALTIC EMULSION (FOG SEAL COAT)	TON	1	4	262.00	$672.04	$176,075.00
		TON	2	5	265.00	$764.53	$202,600.00
		TON	3	10	185.00	$518.89	$95,994.92
		TON	4	3	21.50	$951.00	$20,446.50
		TON	5	13	145.00	$675.23	$97,908.20
		TON	6	8	406.00	$362.14	$147,027.10

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
374002	ASPHALTIC EMULSION (FOG SEAL COAT)	TON	7	1	0.70	$715.14	$500.60
		TON	8	7	345.00	$858.06	$296,030.00
		TON	9	7	401.00	$591.18	$237,065.00
		TON	10	4	109.00	$495.64	$54,025.00
		TON	11	14	570.00	$617.24	$351,829.00
	Unit Sub Total	**TON**		**76**	**2,710.20**	**$619.70**	**$1,679,501.32**
374002	ASPHALTIC EMULSION (FOG SEAL COAT)	TONN	7	1	0.20	$14,000.00	$2,800.00
		TONN	11	3	80.20	$861.60	$69,100.00
	Unit Sub Total	**TONN**		**4**	**80.40**	**$894.28**	**$71,900.00**
	Item Code 374002 Total No. of Proj.			**80**		**Total Amount**	**$1,751,401.32**
374206	SEAL RANDOM CRACKS	LNMI	4	1	2.50	$8,980.00	$22,450.00
		LNMI	8	1	12.00	$5,500.00	$66,000.00
	Unit Sub Total	**LNMI**		**2**	**14.50**	**$6,100.00**	**$88,450.00**
	Item Code 374206 Total No. of Proj.			**2**		**Total Amount**	**$88,450.00**
374207	CRACK TREATMENT	LNKM	7	2	27.10	$3,856.09	$104,500.00
	Unit Sub Total	**LNKM**		**2**	**27.10**	**$3,856.09**	**$104,500.00**
374207	CRACK TREATMENT	LNMI	2	1	5.00	$4,000.00	$20,000.00
		LNMI	3	8	204.00	$3,444.25	$702,626.00
		LNMI	4	12	103.50	$3,890.74	$402,691.50
		LNMI	5	2	19.00	$1,352.63	$25,699.96
		LNMI	6	4	79.00	$3,246.58	$256,480.00
		LNMI	7	4	34.70	$2,269.74	$78,760.00
		LNMI	8	2	71.00	$3,302.82	$234,500.00
		LNMI	9	2	14.40	$1,534.72	$22,100.00
		LNMI	10	4	178.00	$4,140.73	$737,050.00
	Unit Sub Total	**LNMI**		**39**	**708.60**	**$3,499.73**	**$2,479,907.46**
374207	CRACK TREATMENT	LS	12	1	1.00	$800.00	$800.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$800.00**	**$800.00**
	Item Code 374207 Total No. of Proj.			**42**		**Total Amount**	**$2,585,207.46**
374492	ASPHALTIC EMULSION (POLYMER MODIFIED)	TON	1	1	270.00	$728.00	$196,560.00
		TON	3	2	520.00	$823.65	$428,299.20

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
374492	ASPHALTIC EMULSION (POLYMER MODIFIED)	TON	5	1	180.00	$766.00	$137,880.00
		TON	8	1	160.00	$425.00	$68,000.00
		TON	9	1	340.00	$490.00	$166,600.00
		TON	10	2	490.00	$485.31	$237,800.00
		TON	11	1	660.00	$1,175.00	$775,500.00
	Unit Sub Total	**TON**		**9**	**2,620.00**	**$767.42**	**$2,010,639.20**
	Item Code 374492 Total No. of Proj.			**9**		**Total Amount**	**$2,010,639.20**
375001	SCREENINGS	TON	4	1	300.00	$98.00	$29,400.00
	Unit Sub Total	**TON**		**1**	**300.00**	**$98.00**	**$29,400.00**
	Item Code 375001 Total No. of Proj.			**1**		**Total Amount**	**$29,400.00**
375021	SCREENINGS (MEDIUM FINE)	TON	1	1	2,270.00	$51.00	$115,770.00
	Unit Sub Total	**TON**		**1**	**2,270.00**	**$51.00**	**$115,770.00**
	Item Code 375021 Total No. of Proj.			**1**		**Total Amount**	**$115,770.00**
375022	SCREENINGS (MEDIUM)	TON	3	2	4,370.00	$23.27	$101,694.50
		TON	5	1	1,550.00	$27.00	$41,850.00
		TON	8	1	1,240.00	$20.00	$24,800.00
		TON	9	1	3,020.00	$30.00	$90,600.00
		TON	10	2	4,300.00	$30.83	$132,576.00
		TON	11	1	6,880.00	$8.75	$60,200.00
	Unit Sub Total	**TON**		**8**	**21,360.00**	**$21.15**	**$451,720.50**
	Item Code 375022 Total No. of Proj.			**8**		**Total Amount**	**$451,720.50**
375023	SCREENINGS (COARSE)	TON	4	1	70.00	$108.00	$7,560.00
	Unit Sub Total	**TON**		**1**	**70.00**	**$108.00**	**$7,560.00**
	Item Code 375023 Total No. of Proj.			**1**		**Total Amount**	**$7,560.00**
375030	SCREENINGS (HOT-APPLIED)	TON	1	2	6,670.00	$63.70	$424,900.00
		TON	2	2	8,830.00	$70.14	$619,297.00
		TON	4	3	9,805.00	$68.01	$666,862.50
		TON	6	3	9,630.00	$66.60	$641,340.00
		TON	7	1	28.00	$412.00	$11,536.00
		TON	9	4	16,620.00	$49.60	$824,427.50

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
375030	SCREENINGS (HOT-APPLIED)		TON	11	1	14,900.00	$122.75	$1,828,975.00
		Unit Sub Total	**TON**		**16**	**66,483.00**	**$75.47**	**$5,017,338.00**
	Item Code 375030	**Total No. of Proj.**			**16**		**Total Amount**	**$5,017,338.00**
377501	SLURRY SEAL		TON	5	1	15.00	$2,785.00	$41,775.00
			TON	6	2	735.40	$248.93	$183,060.00
			TON	7	2	7,430.00	$168.23	$1,249,955.20
			TON	8	4	18,998.00	$140.19	$2,663,277.40
			TON	11	2	1,347.00	$199.58	$268,840.00
			TON	12	2	280.00	$451.43	$126,400.00
		Unit Sub Total	**TON**		**13**	**28,805.40**	**$157.38**	**$4,533,307.60**
	Item Code 377501	**Total No. of Proj.**			**13**		**Total Amount**	**$4,533,307.60**
378000	MICRO-SURFACING		TON	3	1	3,420.00	$139.00	$475,380.00
			TON	5	4	9,630.00	$162.79	$1,567,710.00
			TON	11	1	7,370.00	$150.00	$1,105,500.00
		Unit Sub Total	**TON**		**6**	**20,420.00**	**$154.19**	**$3,148,590.00**
	Item Code 378000	**Total No. of Proj.**			**6**		**Total Amount**	**$3,148,590.00**
390095	REPLACE ASPHALT CONCRETE SURFACING		CY	1	4	5,770.00	$213.82	$1,233,740.00
			CY	2	11	5,956.00	$216.48	$1,289,370.00
			CY	3	16	19,197.00	$171.11	$3,284,862.50
			CY	4	7	13,390.00	$177.17	$2,372,360.00
			CY	6	5	226.80	$547.10	$124,082.00
			CY	7	6	348.90	$466.79	$162,862.00
			CY	8	13	21,171.00	$226.57	$4,796,690.40
			CY	10	1	2,760.00	$145.00	$400,200.00
			CY	11	1	6.50	$330.00	$2,145.00
		Unit Sub Total	**CY**		**64**	**68,826.20**	**$198.56**	**$13,666,311.90**
390095	REPLACE ASPHALT CONCRETE SURFACING		M3	3	1	19.00	$400.00	$7,600.00
		Unit Sub Total	**M3**		**1**	**19.00**	**$400.00**	**$7,600.00**
	Item Code 390095	**Total No. of Proj.**			**65**		**Total Amount**	**$13,673,911.90**
390126	RUBBERIZED ASPHALT CONCRETE (TYPE G)		TON	12	1	29.00	$140.00	$4,060.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**TON**		**1**	**29.00**	**$140.00**	**$4,060.00**
	Item Code 390126	**Total No. of Proj.**			**1**		**Total Amount**	**$4,060.00**
390129	HOT MIX ASPHALT (TYPE C)		TON	8	1	9,930.00	$115.00	$1,141,950.00
			TON	11	3	2,070.00	$139.60	$288,970.00
		Unit Sub Total	**TON**		**4**	**12,000.00**	**$119.24**	**$1,430,920.00**
390129	HOT MIX ASPHALT (TYPE C)		TONN	11	1	1,340.00	$94.00	$125,960.00
		Unit Sub Total	**TONN**		**1**	**1,340.00**	**$94.00**	**$125,960.00**
	Item Code 390129	**Total No. of Proj.**			**5**		**Total Amount**	**$1,556,880.00**
390130	HOT MIX ASPHALT		TON	3	2	30,990.00	$62.49	$1,936,563.30
			TON	8	1	3.40	$570.00	$1,938.00
		Unit Sub Total	**TON**		**3**	**30,993.40**	**$62.55**	**$1,938,501.30**
	Item Code 390130	**Total No. of Proj.**			**3**		**Total Amount**	**$1,938,501.30**
390131	HOT MIX ASPHALT		TON	2	12	615,400.00	$75.54	$46,487,950.00
			TON	3	5	530,500.00	$57.14	$30,312,300.00
			TON	4	5	209,000.00	$66.33	$13,863,000.00
			TON	5	3	157,700.00	$66.90	$10,550,300.00
			TON	6	5	300,100.00	$56.75	$17,029,600.00
			TON	7	2	39,600.00	$70.52	$2,792,625.00
			TON	9	1	26,900.00	$94.00	$2,528,600.00
			TON	10	4	119,400.00	$62.54	$7,467,730.00
			TON	12	3	148,900.00	$67.18	$10,002,800.00
		Unit Sub Total	**TON**		**40**	**2,147,500.00**	**$65.67**	**$141,034,905.00**
390131	HOT MIX ASPHALT		TONN	3	1	26,400.00	$67.00	$1,768,800.00
			TONN	4	2	101,700.00	$76.58	$7,788,000.00
			TONN	6	1	160,000.00	$62.50	$10,000,000.00
			TONN	10	1	11,700.00	$69.00	$807,300.00
			TONN	11	2	79,100.00	$80.26	$6,348,800.00
		Unit Sub Total	**TONN**		**7**	**378,900.00**	**$70.50**	**$26,712,900.00**
	Item Code 390131	**Total No. of Proj.**			**47**		**Total Amount**	**$167,747,805.00**
390132	HOT MIX ASPHALT (TYPE A)		TON	1	25	65,138.00	$92.06	$5,996,443.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
390132	HOT MIX ASPHALT (TYPE A)		TON	2	15	48,318.00	$94.69	$4,575,020.00
			TON	3	17	111,542.40	$53.17	$5,930,620.92
			TON	4	39	66,851.00	$87.10	$5,822,457.40
			TON	5	24	126,913.70	$71.96	$9,132,182.30
			TON	6	25	104,964.00	$74.25	$7,793,500.00
			TON	8	10	10,125.00	$96.06	$972,630.00
			TON	9	10	15,010.00	$114.31	$1,715,860.00
			TON	10	12	19,705.00	$91.33	$1,799,664.50
			TON	11	8	33,828.00	$82.94	$2,805,836.00
			TON	12	9	28,768.00	$67.82	$1,951,052.00
		Unit Sub Total	**TON**		**194**	**631,163.10**	**$76.83**	**$48,495,266.12**
390132	HOT MIX ASPHALT (TYPE A)		TONN	2	1	4,100.00	$125.00	$512,500.00
			TONN	4	1	520.00	$131.00	$68,120.00
			TONN	6	2	1,140.00	$133.95	$152,700.00
		Unit Sub Total	**TONN**		**4**	**5,760.00**	**$127.31**	**$733,320.00**
	Item Code 390132	**Total No. of Proj.**			**198**		**Total Amount**	**$49,228,586.12**
390133	HOT MIX ASPHALT (TYPE B)		TON	2	2	844.00	$139.93	$118,105.00
			TON	3	2	8,675.00	$56.80	$492,750.00
			TON	5	1	1,100.00	$124.00	$136,400.00
			TON	7	4	192.00	$177.58	$34,095.00
			TON	8	1	10.00	$118.00	$1,180.00
			TON	9	1	170.00	$210.00	$35,700.00
			TON	10	9	26,379.00	$68.45	$1,805,668.20
			TON	12	1	34.00	$60.00	$2,040.00
		Unit Sub Total	**TON**		**21**	**37,404.00**	**$70.20**	**$2,625,938.20**
390133	HOT MIX ASPHALT (TYPE B)		TONN	7	5	31,300.00	$88.11	$2,757,898.00
		Unit Sub Total	**TONN**		**5**	**31,300.00**	**$88.11**	**$2,757,898.00**
	Item Code 390133	**Total No. of Proj.**			**26**		**Total Amount**	**$5,383,836.20**
390134	HOT MIX ASPHALT (OPEN GRADED)		TON	1	4	7,730.00	$114.40	$884,300.00
			TON	2	2	4,080.00	$88.16	$359,700.00
			TON	3	8	8,740.00	$76.11	$665,235.00
			TON	4	4	106,100.00	$79.80	$8,466,305.00
			TON	5	4	16,676.00	$93.74	$1,563,128.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
390134	HOT MIX ASPHALT (OPEN GRADED)	TON	9	3	18,150.00	$119.35	$2,166,270.00
		TON	12	4	5,570.00	$77.37	$430,925.00
	Unit Sub Total	**TON**		**29**	**167,046.00**	**$87.02**	**$14,535,863.00**
	Item Code 390134 Total No. of Proj.			**29**		**Total Amount**	**$14,535,863.00**
390135	HOT MIX ASPHALT (LEVELING)	TON	4	2	725.00	$102.23	$74,120.00
	Unit Sub Total	**TON**		**2**	**725.00**	**$102.23**	**$74,120.00**
	Item Code 390135 Total No. of Proj.			**2**		**Total Amount**	**$74,120.00**
390136	MINOR HOT MIX ASPHALT	TON	1	3	217.50	$191.28	$41,602.80
		TON	2	9	1,904.00	$162.66	$309,699.00
		TON	3	7	594.70	$134.30	$79,866.40
		TON	4	9	712.20	$211.56	$150,672.00
		TON	5	2	58.00	$269.60	$15,637.00
		TON	6	5	338.60	$138.02	$46,732.00
		TON	7	3	50.50	$344.95	$17,420.00
		TON	8	4	220.00	$203.55	$44,780.00
		TON	9	3	370.00	$166.97	$61,780.00
		TON	10	2	118.00	$157.20	$18,550.00
		TON	11	9	5,422.60	$87.81	$476,140.00
	Unit Sub Total	**TON**		**56**	**10,006.10**	**$126.21**	**$1,262,879.20**
390136	MINOR HOT MIX ASPHALT	TONN	11	2	900.00	$83.67	$75,300.00
	Unit Sub Total	**TONN**		**2**	**900.00**	**$83.67**	**$75,300.00**
	Item Code 390136 Total No. of Proj.			**58**		**Total Amount**	**$1,338,179.20**
390137	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	TON	1	2	41,770.00	$107.01	$4,469,910.00
		TON	3	1	7,090.00	$82.00	$581,380.00
		TON	4	3	20,510.00	$104.56	$2,144,440.00
		TON	5	2	9,570.00	$88.19	$843,945.00
		TON	6	1	4,940.00	$85.00	$419,900.00
		TON	7	7	37,570.00	$89.39	$3,358,455.00
		TON	8	4	20,150.00	$93.26	$1,879,150.00
		TON	10	9	65,700.00	$85.31	$5,604,986.70
		TON	12	6	13,598.00	$83.20	$1,131,300.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**TON**		**35**	**220,898.00**	**$92.50**	**$20,433,466.70**
390137	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	TONN	7	1	4,290.00	$100.00	$429,000.00
	Unit Sub Total	**TONN**		**1**	**4,290.00**	**$100.00**	**$429,000.00**
	Item Code 390137 Total No. of Proj.			**36**		**Total Amount**	**$20,862,466.70**
390138	RUBBERIZED HOT MIX ASPHALT (OPEN GRADED)	TON	2	1	8,700.00	$77.00	$669,900.00
		TON	3	4	20,280.00	$66.46	$1,347,800.00
		TON	8	3	87,900.00	$79.80	$7,014,075.00
		TON	12	2	60,307.00	$75.45	$4,550,365.00
	Unit Sub Total	**TON**		**10**	**177,187.00**	**$76.65**	**$13,582,140.00**
390138	RUBBERIZED HOT MIX ASPHALT (OPEN GRADED)	TONN	3	1	3,050.00	$100.00	$305,000.00
	Unit Sub Total	**TONN**		**1**	**3,050.00**	**$100.00**	**$305,000.00**
	Item Code 390138 Total No. of Proj.			**11**		**Total Amount**	**$13,887,140.00**
390139	RUBBERIZED HOT MIX ASPHALT (OPEN GRADED HIGH BINDER)	TON	2	1	9,040.00	$80.00	$723,200.00
		TON	6	1	18,000.00	$82.00	$1,476,000.00
	Unit Sub Total	**TON**		**2**	**27,040.00**	**$81.33**	**$2,199,200.00**
	Item Code 390139 Total No. of Proj.			**2**		**Total Amount**	**$2,199,200.00**
390140	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	TON	4	6	347,500.00	$84.73	$29,443,840.00
		TON	5	1	24,800.00	$92.00	$2,281,600.00
		TON	6	9	202,500.00	$85.41	$17,295,325.00
		TON	7	3	156,800.00	$76.23	$11,953,580.00
		TON	8	3	82,800.00	$84.02	$6,956,795.00
		TON	10	7	98,700.00	$83.76	$8,267,550.00
		TON	11	2	58,200.00	$81.06	$4,717,600.00
	Unit Sub Total	**TON**		**31**	**971,300.00**	**$83.31**	**$80,916,290.00**
390140	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	TONN	7	1	13,500.00	$94.95	$1,281,825.00
		TONN	11	1	57,100.00	$82.00	$4,682,200.00
	Unit Sub Total	**TONN**		**2**	**70,600.00**	**$84.48**	**$5,964,025.00**
	Item Code 390140 Total No. of Proj.			**33**		**Total Amount**	**$86,880,315.00**
390141	HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED)	TON	3	1	25,700.00	$88.00	$2,261,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
390141	HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED)	TON	4	2	17,180.00	$105.95	$1,820,240.00
		TON	5	1	25,700.00	$131.00	$3,366,700.00
	Unit Sub Total	**TON**		**4**	**68,580.00**	**$108.61**	**$7,448,540.00**
	Item Code 390141 Total No. of Proj.			**4**		**Total Amount**	**$7,448,540.00**
390142	HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED)	TON	3	1	14,800.00	$105.00	$1,554,000.00
		TON	6	1	21,400.00	$85.00	$1,819,000.00
	Unit Sub Total	**TON**		**2**	**36,200.00**	**$93.18**	**$3,373,000.00**
	Item Code 390142 Total No. of Proj.			**2**		**Total Amount**	**$3,373,000.00**
390149	ASPHALTIC EMULSION MEMBRANE (BONDED WEARING COURSE)	TON	1	1	190.00	$750.00	$142,500.00
		TON	3	1	245.00	$1,200.00	$294,000.00
		TON	4	1	40.00	$525.00	$21,000.00
	Unit Sub Total	**TON**		**3**	**475.00**	**$963.16**	**$457,500.00**
	Item Code 390149 Total No. of Proj.			**3**		**Total Amount**	**$457,500.00**
390151	ASPHALTIC EMULSION MEMBRANE (BONDED WEARING COURSE)	TON	1	1	350.00	$767.00	$268,450.00
		TON	3	1	430.00	$1,200.00	$516,000.00
		TON	4	2	321.00	$729.05	$234,025.00
		TON	5	1	460.00	$870.00	$400,200.00
		TON	6	1	370.00	$550.00	$203,500.00
		TON	7	2	440.00	$588.75	$259,050.00
		TON	8	1	230.00	$738.00	$169,740.00
		TON	10	1	140.00	$810.00	$113,400.00
	Unit Sub Total	**TON**		**10**	**2,741.00**	**$789.63**	**$2,164,365.00**
	Item Code 390151 Total No. of Proj.			**10**		**Total Amount**	**$2,164,365.00**
390156	RUBBERIZED HOT MIX ASPHALT (BONDED WEARING COURSE-GAP GRADED)	TON	4	1	2,560.00	$110.00	$281,600.00
		TON	7	2	22,840.00	$101.28	$2,313,200.00
		TON	8	1	16,500.00	$97.50	$1,608,750.00
		TON	10	1	19,600.00	$95.00	$1,862,000.00
	Unit Sub Total	**TON**		**5**	**61,500.00**	**$98.63**	**$6,065,550.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 390156 Total No. of Proj.			**5**		**Total Amount**	**$6,065,550.00**
390158	HOT MIX ASPHALT (BONDED WEARING COURSE-OPEN GRADED)	TON	1	2	24,800.00	$118.45	$2,937,600.00
	Unit Sub Total	**TON**		**2**	**24,800.00**	**$118.45**	**$2,937,600.00**
	Item Code 390158 Total No. of Proj.			**2**		**Total Amount**	**$2,937,600.00**
391005	PAVING ASPHALT (BINDER-PAVEMENT REINFORCING FABRIC)	TON	3	1	1.30	$1.00	$1.30
		TON	4	2	19.40	$677.32	$13,140.00
	Unit Sub Total	**TON**		**3**	**20.70**	**$634.85**	**$13,141.30**
	Item Code 391005 Total No. of Proj.			**3**		**Total Amount**	**$13,141.30**
391007	PAVING ASPHALT (BINDER, GEOSYNTHETIC PAVEMENT INTERLAYER)	TON	1	4	1.00	$9,025.00	$9,025.00
		TON	3	1	9.00	$400.00	$3,600.00
		TON	9	2	600.00	$587.08	$352,250.00
	Unit Sub Total	**TON**		**7**	**610.00**	**$598.16**	**$364,875.00**
391007	PAVING ASPHALT (BINDER, GEOSYNTHETIC PAVEMENT INTERLAYER)	TONN	3	1	1.70	$700.00	$1,190.00
		TONN	11	1	2.60	$4,100.00	$10,660.00
	Unit Sub Total	**TONN**		**2**	**4.30**	**$2,755.81**	**$11,850.00**
	Item Code 391007 Total No. of Proj.			**9**		**Total Amount**	**$376,725.00**
391031	PAVING ASPHALT (BINDER-PAVEMENT REINFORCING FABRIC)	TON	4	1	3.00	$1,000.00	$3,000.00
	Unit Sub Total	**TON**		**1**	**3.00**	**$1,000.00**	**$3,000.00**
	Item Code 391031 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
393001	PAVEMENT REINFORCING FABRIC	SQYD	4	2	7,380.00	$1.30	$9,580.00
		SQYD	12	1	1,040.00	$2.85	$2,964.00
	Unit Sub Total	**SQYD**		**3**	**8,420.00**	**$1.49**	**$12,544.00**
	Item Code 393001 Total No. of Proj.			**3**		**Total Amount**	**$12,544.00**
393003	GEOSYNTHETIC PAVEMENT INTERLAYER	M2	3	1	1,470.00	$4.00	$5,880.00
		M2	7	4	22,540.00	$1.71	$38,458.00
		M2	11	1	1,680.00	$4.00	$6,720.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M2**		**6**	**25,690.00**	**$1.99**	**$51,058.00**
393003	GEOSYNTHETIC PAVEMENT INTERLAYER	SQYD	1	7	4,486.00	$4.17	$18,697.00
		SQYD	3	3	9,280.00	$2.55	$23,640.60
		SQYD	4	1	207,000.00	$0.79	$163,530.00
		SQYD	7	1	308,000.00	$0.77	$237,160.00
		SQYD	9	2	437,000.00	$0.67	$294,560.00
	Unit Sub Total	**SQYD**		**14**	**965,766.00**	**$0.76**	**$737,587.60**
	Item Code 393003 Total No. of Proj.			**20**		**Total Amount**	**$788,645.60**
394002	PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA)	SQFT	1	1	330.00	$6.00	$1,980.00
	Unit Sub Total	**SQFT**		**1**	**330.00**	**$6.00**	**$1,980.00**
394002	PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA)	SQYD	3	1	42.00	$200.00	$8,400.00
	Unit Sub Total	**SQYD**		**1**	**42.00**	**$200.00**	**$8,400.00**
	Item Code 394002 Total No. of Proj.			**2**		**Total Amount**	**$10,380.00**
394040	PLACE ASPHALT CONCRETE DIKE (TYPE A)	LF	1	1	3,540.00	$2.00	$7,080.00
		LF	4	2	1,740.00	$3.35	$5,827.50
	Unit Sub Total	**LF**		**3**	**5,280.00**	**$2.44**	**$12,907.50**
394040	PLACE ASPHALT CONCRETE DIKE (TYPE A)	M	2	1	410.00	$10.00	$4,100.00
	Unit Sub Total	**M**		**1**	**410.00**	**$10.00**	**$4,100.00**
	Item Code 394040 Total No. of Proj.			**4**		**Total Amount**	**$17,007.50**
394044	PLACE ASPHALT CONCRETE DIKE (TYPE C)	LF	4	1	180.00	$5.00	$900.00
		LF	10	2	1,085.00	$0.82	$890.50
	Unit Sub Total	**LF**		**3**	**1,265.00**	**$1.42**	**$1,790.50**
	Item Code 394044 Total No. of Proj.			**3**		**Total Amount**	**$1,790.50**
394046	PLACE ASPHALT CONCRETE DIKE (TYPE D)	LF	8	1	540.00	$7.60	$4,104.00
		LF	12	1	33.00	$20.00	$660.00
	Unit Sub Total	**LF**		**2**	**573.00**	**$8.31**	**$4,764.00**
	Item Code 394046 Total No. of Proj.			**2**		**Total Amount**	**$4,764.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
394048	PLACE ASPHALT CONCRETE DIKE (TYPE E)	LF	10	1	76,100.00	$0.72	$54,792.00
	Unit Sub Total	**LF**		**1**	**76,100.00**	**$0.72**	**$54,792.00**
	Item Code 394048 Total No. of Proj.			**1**		**Total Amount**	**$54,792.00**
394049	PLACE ASPHALT CONCRETE DIKE (TYPE F)	LF	4	2	760.00	$7.76	$5,900.00
		LF	5	1	100.00	$35.00	$3,500.00
		LF	8	1	900.00	$4.50	$4,050.00
		LF	10	1	1,430.00	$0.85	$1,215.50
	Unit Sub Total	**LF**		**5**	**3,190.00**	**$4.60**	**$14,665.50**
	Item Code 394049 Total No. of Proj.			**5**		**Total Amount**	**$14,665.50**
394050	RUMBLE STRIP	STA	1	1	720.00	$30.00	$21,600.00
		STA	2	4	3,790.00	$11.78	$44,650.00
		STA	3	6	8,329.00	$12.23	$101,870.00
		STA	4	1	24.00	$150.00	$3,600.00
		STA	5	7	4,580.00	$23.25	$106,464.00
		STA	6	6	5,713.00	$17.68	$100,996.00
		STA	8	1	130.00	$35.00	$4,550.00
		STA	9	5	1,173.00	$28.43	$33,350.00
		STA	10	2	500.00	$18.82	$9,410.40
		STA	11	2	1,671.60	$20.18	$33,740.00
	Unit Sub Total	**STA**		**35**	**26,630.60**	**$17.28**	**$460,230.40**
	Item Code 394050 Total No. of Proj.			**35**		**Total Amount**	**$460,230.40**
394051	SHOULDER RUMBLE STRIP (HMA,ROLLED-IN INDENTATIONS)	STA	11	1	890.00	$15.00	$13,350.00
	Unit Sub Total	**STA**		**1**	**890.00**	**$15.00**	**$13,350.00**
	Item Code 394051 Total No. of Proj.			**1**		**Total Amount**	**$13,350.00**
394053	SHOULDER RUMBLE STRIP (HMA,GROUND-IN INDENTATIONS)	LF	2	1	150.00	$35.00	$5,250.00
		LF	4	1	26,400.00	$0.12	$3,168.00
		LF	8	1	880.00	$7.50	$6,600.00
	Unit Sub Total	**LF**		**3**	**27,430.00**	**$0.55**	**$15,018.00**
394053	SHOULDER RUMBLE STRIP (HMA,GROUND-IN INDENTATIONS)	STA	1	1	1,330.00	$18.00	$23,940.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
394053	SHOULDER RUMBLE STRIP (HMA,GROUND-IN INDENTATIONS)	STA	2	3	3,570.00	$19.91	$71,070.00
		STA	3	2	1,329.00	$9.48	$12,592.50
		STA	4	1	90.00	$75.00	$6,750.00
		STA	6	1	450.00	$56.00	$25,200.00
		STA	9	1	140.00	$62.00	$8,680.00
		STA	10	1	1,170.00	$37.00	$43,290.00
	Unit Sub Total	**STA**		**10**	**8,079.00**	**$23.71**	**$191,522.50**
	Item Code 394053 Total No. of Proj.			**13**		**Total Amount**	**$206,540.50**
394054	SHOULDER RUMBLE STRIP (AC, GROUND-IN INDENTATIONS)	LF	2	1	380.00	$7.75	$2,945.00
	Unit Sub Total	**LF**		**1**	**380.00**	**$7.75**	**$2,945.00**
394054	SHOULDER RUMBLE STRIP (AC, GROUND-IN INDENTATIONS)	STA	1	1	420.00	$49.00	$20,580.00
		STA	6	1	300.00	$10.00	$3,000.00
		STA	10	1	240.00	$75.00	$18,000.00
	Unit Sub Total	**STA**		**3**	**960.00**	**$43.31**	**$41,580.00**
	Item Code 394054 Total No. of Proj.			**4**		**Total Amount**	**$44,525.00**
394060	DATA CORE	EA	12	1	3.00	$1,750.00	$5,250.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$1,750.00**	**$5,250.00**
394060	DATA CORE	LS	1	9	9.00	$2,133.33	$19,200.00
		LS	2	17	17.00	$3,538.24	$60,150.00
		LS	3	11	11.00	$21,136.36	$232,500.00
		LS	4	25	25.00	$4,728.72	$118,218.00
		LS	5	17	17.00	$4,687.59	$79,689.00
		LS	6	19	19.00	$6,338.16	$120,425.00
		LS	7	15	15.00	$5,053.33	$75,800.00
		LS	8	9	9.00	$5,611.11	$50,500.00
		LS	9	4	4.00	$6,100.00	$24,400.00
		LS	10	22	22.00	$3,298.86	$72,575.00
		LS	11	6	6.00	$5,616.67	$33,700.00
		LS	12	9	9.00	$4,727.78	$42,550.00
	Unit Sub Total	**LS**		**163**	**163.00**	**$5,703.72**	**$929,707.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 394060	**Total No. of Proj.**			**164**		**Total Amount**	**$934,957.00**
394070	HOT MIX ASPHALT DIKE		LF	11	1	770.00	$5.00	$3,850.00
		Unit Sub Total	**LF**		**1**	**770.00**	**$5.00**	**$3,850.00**
	Item Code 394070	**Total No. of Proj.**			**1**		**Total Amount**	**$3,850.00**
394071	PLACE HOT MIX ASPHALT DIKE		LF	4	2	13,410.00	$1.94	$25,976.00
			LF	11	11	204,000.00	$1.01	$205,024.10
		Unit Sub Total	**LF**		**13**	**217,410.00**	**$1.06**	**$231,000.10**
394071	PLACE HOT MIX ASPHALT DIKE		M	11	3	15,760.00	$3.69	$58,151.00
		Unit Sub Total	**M**		**3**	**15,760.00**	**$3.69**	**$58,151.00**
	Item Code 394071	**Total No. of Proj.**			**16**		**Total Amount**	**$289,151.10**
394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)		LF	1	3	1,069.00	$12.94	$13,829.00
			LF	2	6	5,592.00	$2.00	$11,199.76
			LF	3	10	72,012.00	$1.14	$82,085.70
			LF	4	8	10,335.00	$3.03	$31,360.00
			LF	5	5	61,200.00	$1.53	$93,887.40
			LF	6	3	5,855.00	$3.15	$18,425.00
			LF	7	2	301.00	$9.54	$2,872.00
			LF	12	3	810.00	$9.14	$7,403.00
		Unit Sub Total	**LF**		**40**	**157,174.00**	**$1.66**	**$261,061.86**
394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)		M	3	1	98.00	$5.00	$490.00
			M	4	1	30.00	$6.00	$180.00
			M	7	2	660.00	$14.67	$9,680.00
		Unit Sub Total	**M**		**4**	**788.00**	**$13.13**	**$10,350.00**
	Item Code 394073	**Total No. of Proj.**			**44**		**Total Amount**	**$271,411.86**
394074	PLACE HOT MIX ASPHALT DIKE (TYPE C)		LF	1	4	1,346.00	$11.71	$15,766.00
			LF	2	3	2,150.00	$3.45	$7,422.00
			LF	3	8	8,761.00	$1.65	$14,487.54
			LF	4	10	14,307.00	$8.91	$127,483.30
			LF	5	6	2,095.00	$1.46	$3,063.00
			LF	6	7	1,850.00	$3.58	$6,615.80
			LF	7	2	2,210.00	$6.27	$13,860.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
394074	PLACE HOT MIX ASPHALT DIKE (TYPE C)	LF	8	2	120.00	$3.62	$434.00
		LF	10	4	1,230.00	$5.30	$6,514.10
		LF	12	6	2,485.00	$3.65	$9,059.00
	Unit Sub Total	**LF**		**52**	**36,554.00**	**$5.60**	**$204,704.74**
394074	PLACE HOT MIX ASPHALT DIKE (TYPE C)	M	4	1	94.00	$6.00	$564.00
		M	7	3	650.00	$10.08	$6,552.80
		M	10	1	80.00	$10.00	$800.00
	Unit Sub Total	**M**		**5**	**824.00**	**$9.61**	**$7,916.80**
	Item Code 394074 Total No. of Proj.			**57**		**Total Amount**	**$212,621.54**
394075	PLACE HOT MIX ASPHALT DIKE (TYPE D)	LF	2	3	30,160.00	$1.02	$30,658.50
		LF	3	4	18,863.00	$1.29	$24,395.40
		LF	4	2	34,920.00	$0.96	$33,668.00
		LF	5	1	630.00	$0.75	$472.50
		LF	7	1	190.00	$7.00	$1,330.00
		LF	8	1	140.00	$25.00	$3,500.00
		LF	12	3	3,488.00	$2.97	$10,359.40
	Unit Sub Total	**LF**		**15**	**88,391.00**	**$1.18**	**$104,383.80**
394075	PLACE HOT MIX ASPHALT DIKE (TYPE D)	M	3	1	530.00	$5.00	$2,650.00
		M	7	1	690.00	$9.30	$6,417.00
	Unit Sub Total	**M**		**2**	**1,220.00**	**$7.43**	**$9,067.00**
	Item Code 394075 Total No. of Proj.			**17**		**Total Amount**	**$113,450.80**
394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)	LF	1	2	19,550.00	$1.73	$33,775.00
		LF	2	4	6,100.00	$2.84	$17,306.50
		LF	3	8	125,595.00	$1.21	$151,800.10
		LF	4	8	31,460.00	$1.87	$58,864.00
		LF	5	6	95,060.00	$0.91	$86,310.00
		LF	6	13	150,680.00	$1.17	$175,574.60
		LF	9	1	9,950.00	$1.90	$18,905.00
		LF	10	5	59,240.00	$0.83	$49,062.60
		LF	12	4	16,720.00	$2.12	$35,508.00
	Unit Sub Total	**LF**		**51**	**514,355.00**	**$1.22**	**$627,105.80**
394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)	M	4	2	2,182.00	$8.22	$17,940.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)	M	6	1	2,940.00	$3.00	$8,820.00
		M	7	3	2,250.00	$8.26	$18,590.00
		M	10	1	280.00	$10.00	$2,800.00
	Unit Sub Total	**M**		**7**	**7,652.00**	**$6.29**	**$48,150.00**
	Item Code 394076 Total No. of Proj.			**58**		**Total Amount**	**$675,255.80**
394077	PLACE HOT MIX ASPHALT DIKE (TYPE F)	LF	1	6	34,027.00	$3.18	$108,057.50
		LF	2	5	48,665.00	$1.80	$87,764.75
		LF	3	8	52,080.00	$1.25	$65,217.30
		LF	4	10	16,561.00	$2.29	$37,965.00
		LF	5	8	5,683.00	$2.02	$11,482.50
		LF	6	9	5,745.00	$2.82	$16,217.20
		LF	7	4	2,340.00	$6.12	$14,310.00
		LF	8	2	9,900.00	$1.60	$15,824.00
		LF	9	1	140.00	$54.50	$7,630.00
		LF	10	6	5,602.00	$2.77	$15,491.10
		LF	12	8	14,545.00	$2.72	$39,604.50
	Unit Sub Total	**LF**		**67**	**195,288.00**	**$2.15**	**$419,563.85**
394077	PLACE HOT MIX ASPHALT DIKE (TYPE F)	M	3	1	88.00	$5.00	$440.00
		M	4	1	160.00	$6.00	$960.00
		M	7	4	3,150.00	$9.89	$31,167.00
		M	10	1	16.00	$10.00	$160.00
	Unit Sub Total	**M**		**7**	**3,414.00**	**$9.59**	**$32,727.00**
	Item Code 394077 Total No. of Proj.			**74**		**Total Amount**	**$452,290.85**
394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	LF	10	1	1.00	$400.00	$400.00
	Unit Sub Total	**LF**		**1**	**1.00**	**$400.00**	**$400.00**
394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	M2	3	1	3,410.00	$10.00	$34,100.00
		M2	4	2	600.00	$26.02	$15,610.00
		M2	6	2	2,156.00	$16.73	$36,060.00
		M2	7	2	434.00	$57.77	$25,074.00
		M2	10	1	320.00	$15.00	$4,800.00
		M2	11	1	2,520.00	$10.00	$25,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M2**		**9**	**9,440.00**	**$14.92**	**$140,844.00**
394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	SQFT	6	1	1,040.00	$7.00	$7,280.00
		SQFT	12	1	460.00	$8.00	$3,680.00
	Unit Sub Total	**SQFT**		**2**	**1,500.00**	**$7.31**	**$10,960.00**
394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	SQYD	1	13	11,298.50	$10.68	$120,617.82
		SQYD	2	14	2,881.00	$39.97	$115,143.50
		SQYD	3	9	17,104.00	$13.42	$229,617.20
		SQYD	4	9	11,074.00	$23.36	$258,692.00
		SQYD	5	8	3,041.00	$24.24	$73,712.00
		SQYD	6	13	2,353.00	$28.49	$67,039.00
		SQYD	8	1	21.00	$110.00	$2,310.00
		SQYD	9	1	2,010.00	$52.30	$105,123.00
		SQYD	10	5	3,188.00	$20.62	$65,731.00
		SQYD	11	4	155.40	$83.49	$12,975.00
		SQYD	12	5	4,777.00	$10.90	$52,085.00
	Unit Sub Total	**SQYD**		**82**	**57,902.90**	**$19.05**	**$1,103,045.52**
	Item Code 394090 Total No. of Proj.			**94**		**Total Amount**	**$1,255,249.52**
394095	ROADSIDE PAVING (MISCELLANEOUS AREAS)	M2	3	1	215.00	$120.00	$25,800.00
	Unit Sub Total	**M2**		**1**	**215.00**	**$120.00**	**$25,800.00**
394095	ROADSIDE PAVING (MISCELLANEOUS AREAS)	SQYD	7	1	240.00	$50.00	$12,000.00
		SQYD	11	1	440.00	$47.00	$20,680.00
		SQYD	12	1	560.00	$49.00	$27,440.00
	Unit Sub Total	**SQYD**		**3**	**1,240.00**	**$48.48**	**$60,120.00**
	Item Code 394095 Total No. of Proj.			**4**		**Total Amount**	**$85,920.00**
395000	LIQUID ASPHALT (PRIME COAT)	TON	4	2	0.80	$925.00	$740.00
		TON	8	2	12.00	$1,450.00	$17,400.00
		TON	12	1	3.00	$900.00	$2,700.00
	Unit Sub Total	**TON**		**5**	**15.80**	**$1,318.99**	**$20,840.00**
	Item Code 395000 Total No. of Proj.			**5**		**Total Amount**	**$20,840.00**
397001	ASPHALTIC EMULSION (PAINT BINDER)	TON	3	2	312.00	$16.35	$5,100.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
397001	ASPHALTIC EMULSION (PAINT BINDER)	TON	4	2	1.30	$1,107.69	$1,440.00
	Unit Sub Total	**TON**		**4**	**313.30**	**$20.87**	**$6,540.00**
	Item Code 397001 Total No. of Proj.			**4**		**Total Amount**	**$6,540.00**
397005	TACK COAT	TON	1	18	366.30	$598.67	$219,294.00
		TON	2	26	2,007.10	$388.67	$780,105.00
		TON	3	19	1,831.80	$566.35	$1,037,445.00
		TON	4	28	2,160.80	$581.36	$1,256,212.80
		TON	5	27	895.10	$260.02	$232,740.10
		TON	6	26	1,209.00	$272.89	$329,928.50
		TON	7	10	614.00	$595.90	$365,885.00
		TON	8	12	764.00	$639.29	$488,418.00
		TON	9	9	390.00	$437.12	$170,475.00
		TON	10	24	1,316.20	$236.90	$311,813.60
		TON	11	12	173.30	$685.77	$118,844.19
		TON	12	14	388.00	$574.50	$222,905.00
	Unit Sub Total	**TON**		**225**	**12,115.60**	**$456.77**	**$5,534,066.19**
397005	TACK COAT	TONN	2	1	4.50	$1,800.00	$8,100.00
		TONN	3	1	91.00	$1.00	$91.00
		TONN	4	2	355.00	$256.94	$91,215.00
		TONN	6	2	680.00	$211.76	$144,000.00
		TONN	7	4	114.40	$807.29	$92,354.00
		TONN	10	1	9.00	$900.00	$8,100.00
		TONN	11	3	221.00	$809.95	$179,000.00
	Unit Sub Total	**TONN**		**14**	**1,474.90**	**$354.51**	**$522,860.00**
	Item Code 397005 Total No. of Proj.			**239**		**Total Amount**	**$6,056,926.19**
397100	COLD FOAM IN-PLACE RECYCLING	SQYD	2	2	390,600.00	$3.16	$1,235,846.00
		SQYD	4	1	31,900.00	$4.00	$127,600.00
	Unit Sub Total	**SQYD**		**3**	**422,500.00**	**$3.23**	**$1,363,446.00**
	Item Code 397100 Total No. of Proj.			**3**		**Total Amount**	**$1,363,446.00**
397200	STABILIZING AGENT (FOAMED ASPHALT)	TON	2	2	7,810.00	$512.56	$4,003,120.00
		TON	4	1	730.00	$555.00	$405,150.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**TON**		**3**	**8,540.00**	**$516.19**	**$4,408,270.00**
	Item Code 397200 Total No. of Proj.			**3**		**Total Amount**	**$4,408,270.00**
397205	STABILIZING AGENT (CEMENTITIOUS MATERIAL)	TON	2	2	4,660.00	$131.34	$612,040.00
		TON	4	1	420.00	$123.00	$51,660.00
	Unit Sub Total	**TON**		**3**	**5,080.00**	**$130.65**	**$663,700.00**
	Item Code 397205 Total No. of Proj.			**3**		**Total Amount**	**$663,700.00**
400050	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT	CY	3	1	32,100.00	$150.00	$4,815,000.00
		CY	4	1	1,820.00	$310.00	$564,200.00
		CY	6	1	60,500.00	$152.65	$9,235,325.00
	Unit Sub Total	**CY**		**3**	**94,420.00**	**$154.78**	**$14,614,525.00**
400050	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT	M3	11	1	33,900.00	$235.00	$7,966,500.00
	Unit Sub Total	**M3**		**1**	**33,900.00**	**$235.00**	**$7,966,500.00**
	Item Code 400050 Total No. of Proj.			**4**		**Total Amount**	**$22,581,025.00**
400061	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE A)	M	11	1	24.00	$9.00	$216.00
	Unit Sub Total	**M**		**1**	**24.00**	**$9.00**	**$216.00**
	Item Code 400061 Total No. of Proj.			**1**		**Total Amount**	**$216.00**
400063	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE C)	LF	4	1	530.00	$180.00	$95,400.00
	Unit Sub Total	**LF**		**1**	**530.00**	**$180.00**	**$95,400.00**
	Item Code 400063 Total No. of Proj.			**1**		**Total Amount**	**$95,400.00**
400064	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE D)	LF	6	1	120.00	$35.25	$4,230.00
	Unit Sub Total	**LF**		**1**	**120.00**	**$35.25**	**$4,230.00**
400064	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE D)	M	11	1	24.00	$53.00	$1,272.00
	Unit Sub Total	**M**		**1**	**24.00**	**$53.00**	**$1,272.00**
	Item Code 400064 Total No. of Proj.			**2**		**Total Amount**	**$5,502.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
400065	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE E)	LF	4	1	60.00	$30.00	$1,800.00
		LF	6	1	200.00	$40.27	$8,054.00
	Unit Sub Total	**LF**		**2**	**260.00**	**$37.90**	**$9,854.00**
400065	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (TERMINAL JOINT, TYPE E)	M	11	1	47.00	$55.00	$2,585.00
	Unit Sub Total	**M**		**1**	**47.00**	**$55.00**	**$2,585.00**
	Item Code 400065	**Total No. of Proj.**		**3**		**Total Amount**	**$12,439.00**
400075	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (PAVEMENT ANCHOR)	EA	3	1	15.00	$9,000.00	$135,000.00
	Unit Sub Total	**EA**		**1**	**15.00**	**$9,000.00**	**$135,000.00**
400075	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (PAVEMENT ANCHOR)	LF	4	1	240.00	$110.00	$26,400.00
		LF	6	1	400.00	$201.38	$80,552.00
	Unit Sub Total	**LF**		**2**	**640.00**	**$167.11**	**$106,952.00**
400075	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (PAVEMENT ANCHOR)	M	11	1	93.60	$442.50	$41,418.00
	Unit Sub Total	**M**		**1**	**93.60**	**$442.50**	**$41,418.00**
	Item Code 400075	**Total No. of Proj.**		**4**		**Total Amount**	**$283,370.00**
400080	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (WIDE FLANGE BEAM TERMINAL)	M	11	1	47.00	$2,620.00	$123,140.00
	Unit Sub Total	**M**		**1**	**47.00**	**$2,620.00**	**$123,140.00**
	Item Code 400080	**Total No. of Proj.**		**1**		**Total Amount**	**$123,140.00**
400090	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (EXPANSION JOINT, TYPE AN)	LF	6	1	310.00	$125.00	$38,750.00
	Unit Sub Total	**LF**		**1**	**310.00**	**$125.00**	**$38,750.00**
400090	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (EXPANSION JOINT, TYPE AN)	M	11	1	47.00	$330.00	$15,510.00
	Unit Sub Total	**M**		**1**	**47.00**	**$330.00**	**$15,510.00**
	Item Code 400090	**Total No. of Proj.**		**2**		**Total Amount**	**$54,260.00**
400092	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (EXPANSION JOINT, TYPE WF)	LF	6	1	84.00	$201.00	$16,884.00
	Unit Sub Total	**LF**		**1**	**84.00**	**$201.00**	**$16,884.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
400092	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT (EXPANSION JOINT, TYPE WF)	M	11	1	47.00	$330.00	$15,510.00
	Unit Sub Total	**M**		**1**	**47.00**	**$330.00**	**$15,510.00**
	Item Code 400092 Total No. of Proj.			**2**		**Total Amount**	**$32,394.00**
401000	CONCRETE PAVEMENT	CY	3	2	173,320.00	$115.65	$20,044,000.00
		CY	4	1	930.00	$170.00	$158,100.00
		CY	8	1	290.00	$264.00	$76,560.00
	Unit Sub Total	**CY**		**4**	**174,540.00**	**$116.18**	**$20,278,660.00**
401000	CONCRETE PAVEMENT	M3	4	2	31,849.00	$215.10	$6,850,850.00
		M3	7	1	41,200.00	$178.00	$7,333,600.00
	Unit Sub Total	**M3**		**3**	**73,049.00**	**$194.18**	**$14,184,450.00**
	Item Code 401000 Total No. of Proj.			**7**		**Total Amount**	**$34,463,110.00**
401050	JOINTED PLAIN CONCRETE PAVEMENT	CY	3	1	3,710.00	$150.00	$556,500.00
		CY	4	3	34,460.00	$153.48	$5,288,910.00
		CY	6	3	1,690.00	$230.47	$389,500.00
		CY	8	1	17,400.00	$105.00	$1,827,000.00
		CY	12	5	89,020.00	$127.39	$11,340,100.00
	Unit Sub Total	**CY**		**13**	**146,280.00**	**$132.64**	**$19,402,010.00**
401050	JOINTED PLAIN CONCRETE PAVEMENT	M3	7	2	46,400.00	$174.41	$8,092,800.00
	Unit Sub Total	**M3**		**2**	**46,400.00**	**$174.41**	**$8,092,800.00**
	Item Code 401050 Total No. of Proj.			**15**		**Total Amount**	**$27,494,810.00**
401066	CONCRETE PAVEMENT (RAMP TERMINI)	CY	8	1	360.00	$182.00	$65,520.00
		CY	12	1	300.00	$220.00	$66,000.00
	Unit Sub Total	**CY**		**2**	**660.00**	**$199.27**	**$131,520.00**
401066	CONCRETE PAVEMENT (RAMP TERMINI)	M3	7	2	1,360.00	$218.05	$296,550.00
	Unit Sub Total	**M3**		**2**	**1,360.00**	**$218.05**	**$296,550.00**
	Item Code 401066 Total No. of Proj.			**4**		**Total Amount**	**$428,070.00**
401081	SHOULDER RUMBLE STRIP (CONCRETE PAVEMENT, ROLLED-IN INDENTATIONS)	STA	6	1	1,120.00	$5.00	$5,600.00
	Unit Sub Total	**STA**		**1**	**1,120.00**	**$5.00**	**$5,600.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 401081 Total No. of Proj.			**1**		**Total Amount**	**$5,600.00**
401082	SHOULDER RUMBLE STRIP (PCC, GROUND-IN INDENTATIONS)	STA	1	1	1,330.00	$34.00	$45,220.00
		STA	11	1	85.00	$116.00	$9,860.00
	Unit Sub Total	**STA**		**2**	**1,415.00**	**$38.93**	**$55,080.00**
	Item Code 401082 Total No. of Proj.			**2**		**Total Amount**	**$55,080.00**
401083	SHOULDER RUMBLE STRIP (CONCRETE PAVEMENT, GROUND-IN INDENTATIONS)	STA	3	1	41.00	$280.00	$11,480.00
	SHOULDER RUMBLE STRIP (CONCRETE PAVEMENT, GROUND-IN	STA	3	1	1,900.00	$55.00	$104,500.00
	Unit Sub Total	**STA**		**2**	**1,941.00**	**$59.75**	**$115,980.00**
	Item Code 401083 Total No. of Proj.			**2**		**Total Amount**	**$115,980.00**
401100	REPLACE CONCRETE PAVEMENT	CY	3	1	7,660.00	$80.00	$612,800.00
	Unit Sub Total	**CY**		**1**	**7,660.00**	**$80.00**	**$612,800.00**
	Item Code 401100 Total No. of Proj.			**1**		**Total Amount**	**$612,800.00**
401102	CONCRETE PAVEMENT (WEIGH-IN-MOTION)	CY	4	1	220.00	$800.00	$176,000.00
	Unit Sub Total	**CY**		**1**	**220.00**	**$800.00**	**$176,000.00**
	Item Code 401102 Total No. of Proj.			**1**		**Total Amount**	**$176,000.00**
401108	REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)	CY	1	1	28,000.00	$235.00	$6,580,000.00
		CY	3	6	20,728.00	$324.31	$6,722,350.00
		CY	4	4	2,650.00	$393.01	$1,041,480.00
		CY	5	1	670.00	$360.00	$241,200.00
		CY	6	2	4,043.00	$260.95	$1,055,020.00
		CY	7	4	59,240.00	$367.21	$21,753,630.00
		CY	8	4	972.00	$599.90	$583,100.00
		CY	10	4	36,490.00	$301.63	$11,006,400.00
		CY	11	4	2,190.00	$644.73	$1,411,950.00
		CY	12	2	1,870.00	$527.70	$986,800.00
	Unit Sub Total	**CY**		**32**	**156,853.00**	**$327.58**	**$51,381,930.00**
401108	REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)	M3	7	2	24,800.00	$411.97	$10,216,800.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M3**		**2**	**24,800.00**	**$411.97**	**$10,216,800.00**
	Item Code 401108	**Total No. of Proj.**			**34**		**Total Amount**	**$61,598,730.00**
404092	SEAL PAVEMENT JOINT		LF	1	1	88,500.00	$2.15	$190,275.00
			LF	3	5	793,080.00	$1.57	$1,247,650.00
			LF	4	3	54,760.00	$4.44	$243,049.00
			LF	6	2	4,560.00	$4.14	$18,870.00
			LF	7	3	64,090.00	$2.54	$162,571.00
			LF	8	2	65,460.00	$0.81	$52,960.00
			LF	11	1	9,320.00	$3.00	$27,960.00
			LF	12	5	334,740.00	$1.61	$537,458.00
		Unit Sub Total	**LF**		**22**	**1,414,510.00**	**$1.75**	**$2,480,793.00**
404092	SEAL PAVEMENT JOINT		M	4	1	58,000.00	$3.75	$217,500.00
			M	7	3	109,100.00	$10.72	$1,169,448.00
			M	11	1	60,500.00	$3.60	$217,800.00
		Unit Sub Total	**M**		**5**	**227,600.00**	**$7.05**	**$1,604,748.00**
	Item Code 404092	**Total No. of Proj.**			**27**		**Total Amount**	**$4,085,541.00**
404093	SEAL ISOLATION JOINT		LF	3	1	15,600.00	$1.45	$22,620.00
			LF	4	2	17,560.00	$2.31	$40,571.00
			LF	6	1	2,080.00	$5.00	$10,400.00
			LF	7	2	7,060.00	$10.92	$77,110.00
			LF	8	1	26,000.00	$4.00	$104,000.00
			LF	12	4	41,740.00	$5.77	$240,964.00
		Unit Sub Total	**LF**		**11**	**110,040.00**	**$4.50**	**$495,665.00**
	Item Code 404093	**Total No. of Proj.**			**11**		**Total Amount**	**$495,665.00**
404094	SEAL LONGITUDINAL ISOLATION JOINT		LF	3	1	95.00	$6.00	$570.00
			LF	4	1	16,100.00	$2.00	$32,200.00
			LF	6	1	224,000.00	$1.45	$324,800.00
			LF	7	1	8,700.00	$4.00	$34,800.00
			LF	12	1	31,100.00	$4.50	$139,950.00
		Unit Sub Total	**LF**		**5**	**279,995.00**	**$1.90**	**$532,320.00**
404094	SEAL LONGITUDINAL ISOLATION JOINT		M	7	3	77,150.00	$26.71	$2,060,450.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M**		**3**	**77,150.00**	**$26.71**	**$2,060,450.00**
	Item Code 404094	**Total No. of Proj.**			**8**		**Total Amount**	**$2,592,770.00**
405030	PORTLAND CEMENT CONCRETE BASE		M3	11	1	380.00	$196.00	$74,480.00
		Unit Sub Total	**M3**		**1**	**380.00**	**$196.00**	**$74,480.00**
	Item Code 405030	**Total No. of Proj.**			**1**		**Total Amount**	**$74,480.00**
406001	TIE BAR		EA	7	3	91,690.00	$16.57	$1,519,263.00
		Unit Sub Total	**EA**		**3**	**91,690.00**	**$16.57**	**$1,519,263.00**
	Item Code 406001	**Total No. of Proj.**			**3**		**Total Amount**	**$1,519,263.00**
406003	TIE BAR (DRILL AND BOND)		EA	7	2	3,822.00	$12.82	$48,997.50
		Unit Sub Total	**EA**		**2**	**3,822.00**	**$12.82**	**$48,997.50**
	Item Code 406003	**Total No. of Proj.**			**2**		**Total Amount**	**$48,997.50**
406050	DOWEL BAR (DRILL AND BOND)		EA	6	1	3,100.00	$13.10	$40,610.00
			EA	7	2	63,000.00	$13.13	$826,875.00
			EA	8	1	1,440.00	$12.00	$17,280.00
			EA	11	2	2,540.00	$21.59	$54,840.00
			EA	12	1	2,200.00	$16.00	$35,200.00
		Unit Sub Total	**EA**		**7**	**72,280.00**	**$13.49**	**$974,805.00**
406050	DOWEL BAR (DRILL AND BOND)		LF	10	2	92,260.00	$6.28	$579,600.00
		Unit Sub Total	**LF**		**2**	**92,260.00**	**$6.28**	**$579,600.00**
	Item Code 406050	**Total No. of Proj.**			**9**		**Total Amount**	**$1,554,405.00**
406100	DOWEL BAR RETROFIT		EA	3	1	61,600.00	$38.00	$2,340,800.00
		Unit Sub Total	**EA**		**1**	**61,600.00**	**$38.00**	**$2,340,800.00**
	Item Code 406100	**Total No. of Proj.**			**1**		**Total Amount**	**$2,340,800.00**
410101	DRILL HOLE (SUBSEALING)		EA	11	1	2,680.00	$6.00	$16,080.00
		Unit Sub Total	**EA**		**1**	**2,680.00**	**$6.00**	**$16,080.00**
	Item Code 410101	**Total No. of Proj.**			**1**		**Total Amount**	**$16,080.00**
410105	GROUT (SUBSEALING)		TON	11	1	580.00	$267.00	$154,860.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**TON**		**1**	**580.00**	**$267.00**	**$154,860.00**
	Item Code 410105 Total No. of Proj.			**1**		**Total Amount**	**$154,860.00**
413111	REPAIR SPALLED JOINTS	M2	7	3	2,241.00	$631.64	$1,415,500.00
	Unit Sub Total	**M2**		**3**	**2,241.00**	**$631.64**	**$1,415,500.00**
413111	REPAIR SPALLED JOINTS	SQYD	7	1	8.00	$1,000.00	$8,000.00
		SQYD	11	2	675.00	$522.22	$352,500.00
		SQYD	12	1	140.00	$780.00	$109,200.00
	Unit Sub Total	**SQYD**		**4**	**823.00**	**$570.72**	**$469,700.00**
	Item Code 413111 Total No. of Proj.			**7**		**Total Amount**	**$1,885,200.00**
413115	SEAL JOINT (EXISTING CONCRETE PAVEMENT)	LF	3	1	121,000.00	$1.00	$121,000.00
		LF	7	2	2,418,000.00	$1.36	$3,289,800.00
		LF	11	4	548,900.00	$1.48	$810,175.00
	Unit Sub Total	**LF**		**7**	**3,087,900.00**	**$1.37**	**$4,220,975.00**
413115	SEAL JOINT (EXISTING CONCRETE PAVEMENT)	M	7	2	167,600.00	$6.74	$1,129,187.00
	Unit Sub Total	**M**		**2**	**167,600.00**	**$6.74**	**$1,129,187.00**
	Item Code 413115 Total No. of Proj.			**9**		**Total Amount**	**$5,350,162.00**
414091	SEAL LONGITUDINAL JOINT	LF	3	1	4,120.00	$7.30	$30,076.00
	Unit Sub Total	**LF**		**1**	**4,120.00**	**$7.30**	**$30,076.00**
	Item Code 414091 Total No. of Proj.			**1**		**Total Amount**	**$30,076.00**
415101	CRACK EXISTING CONCRETE PAVEMENT	SQYD	2	1	58,500.00	$2.00	$117,000.00
		SQYD	4	1	202,000.00	$0.50	$101,000.00
	Unit Sub Total	**SQYD**		**2**	**260,500.00**	**$0.84**	**$218,000.00**
	Item Code 415101 Total No. of Proj.			**2**		**Total Amount**	**$218,000.00**
420201	GRIND EXISTING CONCRETE PAVEMENT	M2	7	3	410,600.00	$3.99	$1,638,620.00
	Unit Sub Total	**M2**		**3**	**410,600.00**	**$3.99**	**$1,638,620.00**
420201	GRIND EXISTING CONCRETE PAVEMENT	SQYD	1	1	354,900.00	$4.00	$1,419,600.00
		SQYD	2	1	53.00	$1.00	$53.00
		SQYD	3	6	887,610.00	$3.56	$3,159,420.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
420201	GRIND EXISTING CONCRETE PAVEMENT	SQYD	4	2	308,240.00	$3.36	$1,035,400.00
		SQYD	6	2	151,580.00	$3.74	$567,470.00
		SQYD	7	7	3,226,180.00	$3.29	$10,625,056.00
		SQYD	8	2	613,700.00	$3.22	$1,977,055.00
		SQYD	10	2	638,810.00	$3.80	$2,424,730.00
		SQYD	11	4	1,514,800.00	$3.61	$5,473,440.00
		SQYD	12	4	909,900.00	$3.12	$2,841,150.00
	Unit Sub Total	**SQYD**		**31**	**8,605,773.00**	**$3.43**	**$29,523,374.00**
	Item Code 420201 Total No. of Proj.			**34**		**Total Amount**	**$31,161,994.00**
490503	FURNISH STEEL PILING (HP 10 X 42)	LF	12	1	1,476.00	$21.00	$30,996.00
	Unit Sub Total	**LF**		**1**	**1,476.00**	**$21.00**	**$30,996.00**
	Item Code 490503 Total No. of Proj.			**1**		**Total Amount**	**$30,996.00**
490504	DRIVE STEEL PILE (HP 10 X 42)	EA	12	1	44.00	$1,400.00	$61,600.00
	Unit Sub Total	**EA**		**1**	**44.00**	**$1,400.00**	**$61,600.00**
	Item Code 490504 Total No. of Proj.			**1**		**Total Amount**	**$61,600.00**
490508	FURNISH STEEL PILING (HP 10 X 57)	LF	2	1	655.00	$25.00	$16,375.00
	Unit Sub Total	**LF**		**1**	**655.00**	**$25.00**	**$16,375.00**
	Item Code 490508 Total No. of Proj.			**1**		**Total Amount**	**$16,375.00**
490509	DRIVE STEEL PILE (HP 10 X 57)	EA	2	1	16.00	$1,850.00	$29,600.00
	Unit Sub Total	**EA**		**1**	**16.00**	**$1,850.00**	**$29,600.00**
	Item Code 490509 Total No. of Proj.			**1**		**Total Amount**	**$29,600.00**
490528	FURNISH STEEL PILING (HP 14 X 89)	LF	12	2	887.00	$48.26	$42,804.00
	Unit Sub Total	**LF**		**2**	**887.00**	**$48.26**	**$42,804.00**
	Item Code 490528 Total No. of Proj.			**2**		**Total Amount**	**$42,804.00**
490529	DRIVE STEEL PILE (HP 14 X 89)	EA	12	1	20.00	$2,040.00	$40,800.00
	Unit Sub Total	**EA**		**1**	**20.00**	**$2,040.00**	**$40,800.00**
	Item Code 490529 Total No. of Proj.			**1**		**Total Amount**	**$40,800.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
490538	FURNISH STEEL PILING (HP 14 X 117)	LF	12	2	6,207.00	$51.26	$318,180.00
	Unit Sub Total	**LF**		**2**	**6,207.00**	**$51.26**	**$318,180.00**
	Item Code 490538 Total No. of Proj.			**2**		**Total Amount**	**$318,180.00**
490539	DRIVE STEEL PILE (HP 14 X 117)	EA	12	1	116.00	$600.00	$69,600.00
	Unit Sub Total	**EA**		**1**	**116.00**	**$600.00**	**$69,600.00**
	Item Code 490539 Total No. of Proj.			**1**		**Total Amount**	**$69,600.00**
490566	FURNISH STEEL PILING (HP 360 X 132)	M	4	1	9,201.00	$150.00	$1,380,150.00
		M	7	1	1,874.00	$115.00	$215,510.00
	Unit Sub Total	**M**		**2**	**11,075.00**	**$144.08**	**$1,595,660.00**
	Item Code 490566 Total No. of Proj.			**2**		**Total Amount**	**$1,595,660.00**
490567	DRIVE STEEL PILE (HP 360 X 132)	EA	4	1	760.00	$900.00	$684,000.00
		EA	7	1	115.00	$1,800.00	$207,000.00
	Unit Sub Total	**EA**		**2**	**875.00**	**$1,018.29**	**$891,000.00**
	Item Code 490567 Total No. of Proj.			**2**		**Total Amount**	**$891,000.00**
490601	16" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	5	1	551.00	$130.00	$71,630.00
		LF	6	1	2,895.00	$50.00	$144,750.00
		LF	10	1	130.00	$62.22	$8,088.60
		LF	12	2	15,181.00	$32.17	$488,387.00
	Unit Sub Total	**LF**		**5**	**18,757.00**	**$38.00**	**$712,855.60**
	Item Code 490601 Total No. of Proj.			**5**		**Total Amount**	**$712,855.60**
490603	24" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	4	1	1,922.00	$130.00	$249,860.00
		LF	6	3	3,522.00	$79.97	$281,671.00
		LF	11	2	121.00	$321.82	$38,940.00
		LF	12	3	9,248.00	$48.90	$452,222.00
	Unit Sub Total	**LF**		**9**	**14,813.00**	**$69.04**	**$1,022,693.00**
	Item Code 490603 Total No. of Proj.			**9**		**Total Amount**	**$1,022,693.00**
490604	30" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	4	1	8,900.00	$130.00	$1,157,000.00
		LF	12	1	2,494.00	$70.00	$174,580.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**2**	**11,394.00**	**$116.87**	**$1,331,580.00**
	Item Code 490604 Total No. of Proj.			**2**		**Total Amount**	**$1,331,580.00**
490605	36" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	6	1	166.00	$207.00	$34,362.00
		LF	11	1	11.00	$400.00	$4,400.00
	Unit Sub Total	**LF**		**2**	**177.00**	**$218.99**	**$38,762.00**
	Item Code 490605 Total No. of Proj.			**2**		**Total Amount**	**$38,762.00**
490607	48" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	11	1	642.00	$450.00	$288,900.00
	Unit Sub Total	**LF**		**1**	**642.00**	**$450.00**	**$288,900.00**
	Item Code 490607 Total No. of Proj.			**1**		**Total Amount**	**$288,900.00**
490615	18" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	12	3	9,116.00	$35.80	$326,350.00
	Unit Sub Total	**LF**		**3**	**9,116.00**	**$35.80**	**$326,350.00**
	Item Code 490615 Total No. of Proj.			**3**		**Total Amount**	**$326,350.00**
490622	120" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	5	1	1,769.00	$1,800.00	$3,184,200.00
	Unit Sub Total	**LF**		**1**	**1,769.00**	**$1,800.00**	**$3,184,200.00**
	Item Code 490622 Total No. of Proj.			**1**		**Total Amount**	**$3,184,200.00**
490655	400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	M	7	3	11,114.20	$140.33	$1,559,669.00
	Unit Sub Total	**M**		**3**	**11,114.20**	**$140.33**	**$1,559,669.00**
	Item Code 490655 Total No. of Proj.			**3**		**Total Amount**	**$1,559,669.00**
490656	450 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	M	4	1	317.00	$500.00	$158,500.00
	Unit Sub Total	**M**		**1**	**317.00**	**$500.00**	**$158,500.00**
	Item Code 490656 Total No. of Proj.			**1**		**Total Amount**	**$158,500.00**
490657	600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	M	2	1	414.00	$325.00	$134,550.00
		M	4	1	418.00	$550.00	$229,900.00
		M	7	3	4,378.60	$238.50	$1,044,293.00
		M	10	1	1,170.00	$250.00	$292,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**6**	**6,380.60**	**$266.63**	**$1,701,243.00**
	Item Code 490657 Total No. of Proj.			**6**		**Total Amount**	**$1,701,243.00**
490658	750 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	M	4	1	2,578.00	$400.00	$1,031,200.00
		M	11	1	63.00	$395.00	$24,885.00
	Unit Sub Total	**M**		**2**	**2,641.00**	**$399.88**	**$1,056,085.00**
	Item Code 490658 Total No. of Proj.			**2**		**Total Amount**	**$1,056,085.00**
490663	1.5 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	7	1	65.00	$1,100.00	$71,500.00
	Unit Sub Total	**M**		**1**	**65.00**	**$1,100.00**	**$71,500.00**
	Item Code 490663 Total No. of Proj.			**1**		**Total Amount**	**$71,500.00**
490669	2.1 M CAST-IN-DRILLED-HOLE CONCRETE PILING	M	10	1	330.00	$2,200.00	$726,000.00
	Unit Sub Total	**M**		**1**	**330.00**	**$2,200.00**	**$726,000.00**
	Item Code 490669 Total No. of Proj.			**1**		**Total Amount**	**$726,000.00**
490675	900 MM CAST-IN-DRILLED-HOLE CONCRETE PILING	M	4	1	211.00	$650.00	$137,150.00
	Unit Sub Total	**M**		**1**	**211.00**	**$650.00**	**$137,150.00**
	Item Code 490675 Total No. of Proj.			**1**		**Total Amount**	**$137,150.00**
490683	24" CAST-IN-DRILLED-HOLE CONCRETE PILING (ROCK SOCKET)	LF	6	1	60.00	$149.00	$8,940.00
	Unit Sub Total	**LF**		**1**	**60.00**	**$149.00**	**$8,940.00**
	Item Code 490683 Total No. of Proj.			**1**		**Total Amount**	**$8,940.00**
490700	FURNISH PILING (CLASS 900) (ALTERNATIVE W)	M	7	1	233.00	$168.00	$39,144.00
	Unit Sub Total	**M**		**1**	**233.00**	**$168.00**	**$39,144.00**
	Item Code 490700 Total No. of Proj.			**1**		**Total Amount**	**$39,144.00**
490701	DRIVE PILE (CLASS 900) (ALTERNATIVE W)	EA	7	1	21.00	$1,961.00	$41,181.00
	Unit Sub Total	**EA**		**1**	**21.00**	**$1,961.00**	**$41,181.00**
	Item Code 490701 Total No. of Proj.			**1**		**Total Amount**	**$41,181.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
490736	FURNISH PILING (CLASS 90)		LF	12	1	805.00	$15.00	$12,075.00
		Unit Sub Total	**LF**		**1**	**805.00**	**$15.00**	**$12,075.00**
	Item Code 490736	**Total No. of Proj.**			**1**		**Total Amount**	**$12,075.00**
490737	DRIVE PILE (CLASS 90)		EA	12	1	17.00	$2,500.00	$42,500.00
		Unit Sub Total	**EA**		**1**	**17.00**	**$2,500.00**	**$42,500.00**
	Item Code 490737	**Total No. of Proj.**			**1**		**Total Amount**	**$42,500.00**
490738	FURNISH PILING (CLASS 140)		LF	4	1	600.00	$65.00	$39,000.00
		Unit Sub Total	**LF**		**1**	**600.00**	**$65.00**	**$39,000.00**
	Item Code 490738	**Total No. of Proj.**			**1**		**Total Amount**	**$39,000.00**
490739	DRIVE PILE (CLASS 140)		EA	4	1	8.00	$2,000.00	$16,000.00
		Unit Sub Total	**EA**		**1**	**8.00**	**$2,000.00**	**$16,000.00**
	Item Code 490739	**Total No. of Proj.**			**1**		**Total Amount**	**$16,000.00**
490746	FURNISH PILING (CLASS 140) (ALTERNATIVE W)		LF	3	1	3,258.00	$40.00	$130,320.00
			LF	4	1	13,656.00	$35.00	$477,960.00
			LF	5	1	5,558.00	$45.00	$250,110.00
		Unit Sub Total	**LF**		**3**	**22,472.00**	**$38.20**	**$858,390.00**
	Item Code 490746	**Total No. of Proj.**			**3**		**Total Amount**	**$858,390.00**
490747	DRIVE PILE (CLASS 140) (ALTERNATIVE W)		EA	3	1	58.00	$1,000.00	$58,000.00
			EA	4	1	323.00	$700.00	$226,100.00
			EA	5	1	79.00	$1,600.00	$126,400.00
		Unit Sub Total	**EA**		**3**	**460.00**	**$892.39**	**$410,500.00**
	Item Code 490747	**Total No. of Proj.**			**3**		**Total Amount**	**$410,500.00**
490751	FURNISH PILE (CLASS 200)		LF	12	1	1,547.00	$25.00	$38,675.00
		Unit Sub Total	**LF**		**1**	**1,547.00**	**$25.00**	**$38,675.00**
	Item Code 490751	**Total No. of Proj.**			**1**		**Total Amount**	**$38,675.00**
490752	DRIVE PILING (CLASS 200)		EA	12	1	32.00	$2,500.00	$80,000.00
		Unit Sub Total	**EA**		**1**	**32.00**	**$2,500.00**	**$80,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 490752 Total No. of Proj.			**1**		**Total Amount**	**$80,000.00**
490753	FURNISH PILING (CLASS 625)	M	7	1	609.00	$55.00	$33,495.00
	Unit Sub Total	**M**		**1**	**609.00**	**$55.00**	**$33,495.00**
	Item Code 490753 Total No. of Proj.			**1**		**Total Amount**	**$33,495.00**
490754	DRIVE PILE (CLASS 625)	EA	7	1	40.00	$3,100.00	$124,000.00
	Unit Sub Total	**EA**		**1**	**40.00**	**$3,100.00**	**$124,000.00**
	Item Code 490754 Total No. of Proj.			**1**		**Total Amount**	**$124,000.00**
490772	FURNISH PILING (CLASS 625) (ALTERNATIVE W)	M	7	2	721.00	$151.55	$109,271.00
	Unit Sub Total	**M**		**2**	**721.00**	**$151.55**	**$109,271.00**
	Item Code 490772 Total No. of Proj.			**2**		**Total Amount**	**$109,271.00**
490773	DRIVE PILE (CLASS 625) (ALTERNATIVE W)	EA	7	2	52.00	$1,191.38	$61,952.00
	Unit Sub Total	**EA**		**2**	**52.00**	**$1,191.38**	**$61,952.00**
	Item Code 490773 Total No. of Proj.			**2**		**Total Amount**	**$61,952.00**
490780	FURNISH PILING (CLASS 200)	LF	12	1	3,372.00	$18.00	$60,696.00
	Unit Sub Total	**LF**		**1**	**3,372.00**	**$18.00**	**$60,696.00**
	Item Code 490780 Total No. of Proj.			**1**		**Total Amount**	**$60,696.00**
490781	DRIVE PILE (CLASS 200)	EA	12	1	83.00	$1,500.00	$124,500.00
	Unit Sub Total	**EA**		**1**	**83.00**	**$1,500.00**	**$124,500.00**
	Item Code 490781 Total No. of Proj.			**1**		**Total Amount**	**$124,500.00**
490782	FURNISH PILING (CLASS 200) (ALTERNATIVE W)	LF	4	1	18,303.00	$46.00	$841,938.00
		LF	12	1	78,526.00	$45.00	$3,533,670.00
	Unit Sub Total	**LF**		**2**	**96,829.00**	**$45.19**	**$4,375,608.00**
	Item Code 490782 Total No. of Proj.			**2**		**Total Amount**	**$4,375,608.00**
490783	DRIVE PILE (CLASS 200) (ALTERNATIVE W)	EA	4	1	186.00	$1,500.00	$279,000.00
		EA	12	1	1,355.00	$1,300.00	$1,761,500.00
	Unit Sub Total	**EA**		**2**	**1,541.00**	**$1,324.14**	**$2,040,500.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 490783 Total No. of Proj.			**2**		**Total Amount**	**$2,040,500.00**
490801	STEEL SHEET PILING	SQFT	4	1	35,900.00	$25.00	$897,500.00
	Unit Sub Total	**SQFT**		**1**	**35,900.00**	**$25.00**	**$897,500.00**
	Item Code 490801 Total No. of Proj.			**1**		**Total Amount**	**$897,500.00**
491012	FURNISH PILING (CLASS 400) (ALTERNATIVE W)	M	7	2	11,287.00	$139.52	$1,574,736.10
	Unit Sub Total	**M**		**2**	**11,287.00**	**$139.52**	**$1,574,736.10**
	Item Code 491012 Total No. of Proj.			**2**		**Total Amount**	**$1,574,736.10**
491013	DRIVE PILE (CLASS 400) (ALTERNATIVE W)	EA	7	2	791.00	$987.69	$781,264.00
	Unit Sub Total	**EA**		**2**	**791.00**	**$987.69**	**$781,264.00**
	Item Code 491013 Total No. of Proj.			**2**		**Total Amount**	**$781,264.00**
495115	FURNISH 24" CAST-IN-STEEL SHELL CONCRETE PILING	LF	2	1	785.00	$10.00	$7,850.00
		LF	12	1	2,717.00	$85.00	$230,945.00
	Unit Sub Total	**LF**		**2**	**3,502.00**	**$68.19**	**$238,795.00**
	Item Code 495115 Total No. of Proj.			**2**		**Total Amount**	**$238,795.00**
495116	DRIVE 24" CAST-IN-STEEL SHELL CONCRETE PILE	EA	2	1	12.00	$22,000.00	$264,000.00
		EA	12	1	30.00	$9,500.00	$285,000.00
	Unit Sub Total	**EA**		**2**	**42.00**	**$13,071.43**	**$549,000.00**
	Item Code 495116 Total No. of Proj.			**2**		**Total Amount**	**$549,000.00**
495149	FURNISH 48" CAST-IN-STEEL SHELL CONCRETE PILING	LF	12	1	10,209.00	$255.00	$2,603,295.00
	Unit Sub Total	**LF**		**1**	**10,209.00**	**$255.00**	**$2,603,295.00**
	Item Code 495149 Total No. of Proj.			**1**		**Total Amount**	**$2,603,295.00**
495150	DRIVE 48" CAST-IN-STEEL SHELL CONCRETE PILE	EA	12	1	108.00	$18,925.00	$2,043,900.00
	Unit Sub Total	**EA**		**1**	**108.00**	**$18,925.00**	**$2,043,900.00**
	Item Code 495150 Total No. of Proj.			**1**		**Total Amount**	**$2,043,900.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
498009	16" CAST-IN-DRILLED-HOLE CONCRETE PILING (BARRIER)	LF	12	1	13,430.00	$35.00	$470,050.00
	Unit Sub Total	**LF**		**1**	**13,430.00**	**$35.00**	**$470,050.00**
	Item Code 498009 Total No. of Proj.			**1**		**Total Amount**	**$470,050.00**
498016	16" CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	LF	4	1	3,130.00	$45.00	$140,850.00
		LF	12	4	22,830.00	$36.70	$837,820.00
	Unit Sub Total	**LF**		**5**	**25,960.00**	**$37.70**	**$978,670.00**
	Item Code 498016 Total No. of Proj.			**5**		**Total Amount**	**$978,670.00**
498022	24" CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	LF	12	3	1,565.00	$47.17	$73,820.00
	Unit Sub Total	**LF**		**3**	**1,565.00**	**$47.17**	**$73,820.00**
	Item Code 498022 Total No. of Proj.			**3**		**Total Amount**	**$73,820.00**
498027	400 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	M	3	1	907.00	$165.00	$149,655.00
		M	4	1	3,030.00	$140.00	$424,200.00
		M	7	2	7,622.00	$123.63	$942,290.00
	Unit Sub Total	**M**		**4**	**11,559.00**	**$131.17**	**$1,516,145.00**
	Item Code 498027 Total No. of Proj.			**4**		**Total Amount**	**$1,516,145.00**
498030	600 MM CAST-IN-DRILLED-HOLE CONCRETE PILING (SOUND WALL)	M	7	2	173.00	$323.06	$55,890.00
	Unit Sub Total	**M**		**2**	**173.00**	**$323.06**	**$55,890.00**
	Item Code 498030 Total No. of Proj.			**2**		**Total Amount**	**$55,890.00**
500001	PRESTRESSING CAST-IN-PLACE CONCRETE	LS	3	1	1.00	$25,000.00	$25,000.00
		LS	4	3	3.00	$269,666.67	$809,000.00
		LS	5	2	2.00	$187,500.00	$375,000.00
		LS	6	1	1.00	$100,000.00	$100,000.00
		LS	7	2	2.00	$561,250.00	$1,122,500.00
		LS	10	1	1.00	$444,000.00	$444,000.00
		LS	11	3	3.00	$93,966.67	$281,900.00
		LS	12	4	4.00	$968,750.00	$3,875,000.00
	Unit Sub Total	**LS**		**17**	**17.00**	**$413,670.59**	**$7,032,400.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 500001 Total No. of Proj.			**17**		**Total Amount**	**$7,032,400.00**
500010	PRESTRESSING	LS	3	2	2.00	$238,350.00	$476,700.00
		LS	7	1	1.00	$43,500.00	$43,500.00
		LS	12	1	1.00	$15,000.00	$15,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$133,800.00**	**$535,200.00**
	Item Code 500010 Total No. of Proj.			**4**		**Total Amount**	**$535,200.00**
500050	TIEBACK ANCHOR	EA	1	4	268.00	$4,443.86	$1,190,954.00
		EA	4	1	340.00	$1,500.00	$510,000.00
		EA	5	2	295.00	$5,986.10	$1,765,900.00
		EA	6	1	34.00	$2,000.00	$68,000.00
		EA	12	3	152.00	$1,969.74	$299,400.00
	Unit Sub Total	**EA**		**11**	**1,089.00**	**$3,520.89**	**$3,834,254.00**
	Item Code 500050 Total No. of Proj.			**11**		**Total Amount**	**$3,834,254.00**
500060	TIEDOWN ANCHOR	EA	2	1	24.00	$2,800.00	$67,200.00
		EA	7	1	33.00	$4,200.00	$138,600.00
	Unit Sub Total	**EA**		**2**	**57.00**	**$3,610.53**	**$205,800.00**
	Item Code 500060 Total No. of Proj.			**2**		**Total Amount**	**$205,800.00**
510000	SEAL COURSE CONCRETE	CY	3	1	223.00	$1,000.00	$223,000.00
		CY	12	1	81.00	$125.00	$10,125.00
	Unit Sub Total	**CY**		**2**	**304.00**	**$766.86**	**$233,125.00**
	Item Code 510000 Total No. of Proj.			**2**		**Total Amount**	**$233,125.00**
510050	STRUCTURAL CONCRETE	CY	2	2	141.00	$787.58	$111,049.00
		CY	4	1	7.00	$1,545.00	$10,815.00
		CY	6	1	16.00	$350.00	$5,600.00
		CY	9	1	122.00	$975.00	$118,950.00
	Unit Sub Total	**CY**		**5**	**286.00**	**$861.59**	**$246,414.00**
	Item Code 510050 Total No. of Proj.			**5**		**Total Amount**	**$246,414.00**
510051	STRUCTURAL CONCRETE, BRIDGE FOOTING	CY	2	2	415.00	$661.45	$274,500.00
		CY	3	2	200.00	$319.66	$63,932.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
510051	STRUCTURAL CONCRETE, BRIDGE FOOTING	CY	4	3	1,109.00	$272.90	$302,650.00
		CY	5	2	298.00	$355.54	$105,950.00
		CY	6	2	241.00	$369.92	$89,150.00
		CY	8	1	33.00	$950.00	$31,350.00
		CY	9	1	58.00	$680.00	$39,440.00
		CY	11	2	21.00	$735.71	$15,450.00
		CY	12	5	13,964.00	$157.69	$2,201,955.00
	Unit Sub Total	**CY**		**20**	**16,339.00**	**$191.22**	**$3,124,377.00**
510051	STRUCTURAL CONCRETE, BRIDGE FOOTING	M3	2	1	510.00	$725.00	$369,750.00
		M3	4	3	5,379.00	$354.86	$1,908,800.00
		M3	7	4	2,933.00	$338.86	$993,864.00
		M3	10	1	300.00	$200.00	$60,000.00
		M3	11	2	238.00	$386.72	$92,040.00
	Unit Sub Total	**M3**		**11**	**9,360.00**	**$365.86**	**$3,424,454.00**
	Item Code 510051 Total No. of Proj.			**31**		**Total Amount**	**$6,548,831.00**
510053	STRUCTURAL CONCRETE, BRIDGE	CF	4	1	39.00	$600.00	$23,400.00
	Unit Sub Total	**CF**		**1**	**39.00**	**$600.00**	**$23,400.00**
510053	STRUCTURAL CONCRETE, BRIDGE	CY	2	6	1,878.00	$755.57	$1,418,960.00
		CY	3	7	10,100.00	$678.97	$6,857,590.00
		CY	4	11	9,280.00	$754.18	$6,998,782.50
		CY	5	3	9,606.00	$527.23	$5,064,600.00
		CY	6	3	2,920.00	$514.94	$1,503,632.00
		CY	7	5	43.50	$1,001.72	$43,575.00
		CY	8	2	84.00	$1,095.24	$92,000.00
		CY	9	1	4.00	$555.00	$2,220.00
		CY	10	2	290.00	$491.31	$142,480.00
		CY	11	5	1,255.50	$456.51	$573,150.00
		CY	12	7	57,058.00	$502.55	$28,674,590.00
	Unit Sub Total	**CY**		**52**	**92,519.00**	**$555.25**	**$51,371,579.50**
510053	STRUCTURAL CONCRETE, BRIDGE	M3	2	1	2,970.00	$1,210.00	$3,593,700.00
		M3	4	3	39,835.00	$821.39	$32,720,250.00
		M3	7	5	25,079.00	$680.44	$17,064,780.00
		M3	10	1	7,540.00	$480.00	$3,619,200.00
		M3	11	2	2,008.00	$639.04	$1,283,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M3**		**12**	**77,432.00**	**$752.67**	**$58,281,130.00**
	Item Code 510053 Total No. of Proj.			**65**		**Total Amount**	**$109,676,109.50**
510060	STRUCTURAL CONCRETE, RETAINING WALL	CY	1	4	596.00	$660.71	$393,786.00
		CY	4	9	10,477.00	$364.92	$3,823,264.00
		CY	5	3	1,520.00	$472.41	$718,064.00
		CY	6	3	4,396.00	$394.61	$1,734,708.00
		CY	8	1	3,205.00	$300.00	$961,500.00
		CY	10	1	6,072.00	$410.00	$2,489,520.00
		CY	11	1	415.00	$385.00	$159,775.00
		CY	12	6	15,009.00	$315.61	$4,736,970.00
	Unit Sub Total	**CY**		**28**	**41,690.00**	**$360.22**	**$15,017,587.00**
510060	STRUCTURAL CONCRETE, RETAINING WALL	M3	4	3	5,328.00	$538.59	$2,869,600.00
		M3	7	5	26,842.50	$382.93	$10,278,880.00
		M3	10	1	35.00	$500.00	$17,500.00
	Unit Sub Total	**M3**		**9**	**32,205.50**	**$408.81**	**$13,165,980.00**
	Item Code 510060 Total No. of Proj.			**37**		**Total Amount**	**$28,183,567.00**
510061	STRUCTURAL CONCRETE, SOUND WALL	M3	4	1	304.00	$700.00	$212,800.00
	Unit Sub Total	**M3**		**1**	**304.00**	**$700.00**	**$212,800.00**
	Item Code 510061 Total No. of Proj.			**1**		**Total Amount**	**$212,800.00**
510069	STRUCTURE CONCRETE (PUMPING PLANT)	CY	4	1	300.00	$860.00	$258,000.00
	Unit Sub Total	**CY**		**1**	**300.00**	**$860.00**	**$258,000.00**
	Item Code 510069 Total No. of Proj.			**1**		**Total Amount**	**$258,000.00**
510072	STRUCTURAL CONCRETE, BARRIER SLAB	CY	1	3	270.00	$697.04	$188,200.00
		CY	4	2	155.00	$407.74	$63,200.00
		CY	5	2	632.00	$538.61	$340,400.00
		CY	12	4	6,366.00	$353.33	$2,249,330.00
	Unit Sub Total	**CY**		**11**	**7,423.00**	**$382.75**	**$2,841,130.00**
510072	STRUCTURAL CONCRETE, BARRIER SLAB	M3	4	1	2,910.00	$330.00	$960,300.00
		M3	7	2	426.00	$502.54	$214,082.00
		M3	10	1	925.00	$320.00	$296,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M3**		**4**	**4,261.00**	**$345.08**	**$1,470,382.00**
	Item Code 510072	**Total No. of Proj.**			**15**		**Total Amount**	**$4,311,512.00**
510080	STRUCTURAL CONCRETE, APPROACH SLAB		M3	4	1	56.00	$800.00	$44,800.00
		Unit Sub Total	**M3**		**1**	**56.00**	**$800.00**	**$44,800.00**
	Item Code 510080	**Total No. of Proj.**			**1**		**Total Amount**	**$44,800.00**
510085	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE EQ)		CY	3	1	28.00	$1,000.00	$28,000.00
		Unit Sub Total	**CY**		**1**	**28.00**	**$1,000.00**	**$28,000.00**
510085	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE EQ)		M3	2	1	21.00	$800.00	$16,800.00
			M3	4	1	22.00	$1,100.00	$24,200.00
			M3	7	1	6.00	$2,100.00	$12,600.00
		Unit Sub Total	**M3**		**3**	**49.00**	**$1,093.88**	**$53,600.00**
	Item Code 510085	**Total No. of Proj.**			**4**		**Total Amount**	**$81,600.00**
510086	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)		CY	2	2	234.00	$785.98	$183,920.00
			CY	4	2	651.00	$500.00	$325,500.00
			CY	5	1	218.00	$750.00	$163,500.00
			CY	6	1	356.00	$450.00	$160,200.00
			CY	11	1	170.00	$500.00	$85,000.00
			CY	12	5	2,175.00	$518.96	$1,128,730.00
		Unit Sub Total	**CY**		**12**	**3,804.00**	**$538.08**	**$2,046,850.00**
510086	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)		M3	4	1	264.00	$800.00	$211,200.00
			M3	7	3	950.00	$740.61	$703,577.00
			M3	10	1	120.00	$650.00	$78,000.00
			M3	11	1	135.00	$710.00	$95,850.00
		Unit Sub Total	**M3**		**6**	**1,469.00**	**$741.07**	**$1,088,627.00**
	Item Code 510086	**Total No. of Proj.**			**18**		**Total Amount**	**$3,135,477.00**
510087	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)		CY	2	4	1,113.00	$927.17	$1,031,945.00
			CY	3	4	1,075.00	$630.23	$677,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
510087	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	CY	4	4	1,909.00	$819.02	$1,563,510.00
		CY	6	3	721.00	$795.67	$573,678.00
		CY	7	1	355.00	$950.00	$337,250.00
		CY	8	1	1,317.00	$640.00	$842,880.00
		CY	9	1	86.00	$1,150.00	$98,900.00
		CY	10	2	185.00	$994.57	$183,995.00
		CY	11	5	846.00	$990.35	$837,840.00
		CY	12	4	390.00	$901.08	$351,420.00
	Unit Sub Total	**CY**		**29**	**7,997.00**	**$812.67**	**$6,498,918.00**
510087	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	M3	7	3	1,028.00	$1,036.09	$1,065,103.00
	Unit Sub Total	**M3**		**3**	**1,028.00**	**$1,036.09**	**$1,065,103.00**
	Item Code 510087 Total No. of Proj.			**32**		**Total Amount**	**$7,564,021.00**
510088	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N MODIFIED)	CY	6	1	90.00	$500.00	$45,000.00
	Unit Sub Total	**CY**		**1**	**90.00**	**$500.00**	**$45,000.00**
510088	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N MODIFIED)	M3	7	2	468.00	$716.57	$335,356.00
	Unit Sub Total	**M3**		**2**	**468.00**	**$716.57**	**$335,356.00**
	Item Code 510088 Total No. of Proj.			**3**		**Total Amount**	**$380,356.00**
510090	STRUCTURAL CONCRETE, BOX CULVERT	CY	6	1	48.00	$1,615.00	$77,520.00
		CY	8	1	10.20	$1,000.00	$10,200.00
		CY	12	2	2,062.00	$661.44	$1,363,890.00
	Unit Sub Total	**CY**		**4**	**2,120.20**	**$684.66**	**$1,451,610.00**
	Item Code 510090 Total No. of Proj.			**4**		**Total Amount**	**$1,451,610.00**
510129	CLASS 2 CONCRETE (BOX CULVERT)	M3	4	1	930.00	$700.00	$651,000.00
	Unit Sub Total	**M3**		**1**	**930.00**	**$700.00**	**$651,000.00**
	Item Code 510129 Total No. of Proj.			**1**		**Total Amount**	**$651,000.00**
510135	CLASS 2 CONCRETE (HEADWALL)	M3	4	1	290.00	$650.00	$188,500.00
	Unit Sub Total	**M3**		**1**	**290.00**	**$650.00**	**$188,500.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 510135 Total No. of Proj.			**1**		**Total Amount**	**$188,500.00**
510138	CLASS 2 CONCRETE (WINGWALLS)	CY	4	1	160.00	$795.75	$127,320.00
	Unit Sub Total	**CY**		**1**	**160.00**	**$795.75**	**$127,320.00**
510138	CLASS 2 CONCRETE (WINGWALLS)	M3	3	1	60.00	$1,000.00	$60,000.00
	Unit Sub Total	**M3**		**1**	**60.00**	**$1,000.00**	**$60,000.00**
	Item Code 510138 Total No. of Proj.			**2**		**Total Amount**	**$187,320.00**
510217	CLASS 3 CONCRETE	CY	4	2	109.00	$337.54	$36,792.00
	Unit Sub Total	**CY**		**2**	**109.00**	**$337.54**	**$36,792.00**
	Item Code 510217 Total No. of Proj.			**2**		**Total Amount**	**$36,792.00**
510220	CLASS 3 CONCRETE (BACKFILL)	CY	1	1	125.00	$287.00	$35,875.00
	Unit Sub Total	**CY**		**1**	**125.00**	**$287.00**	**$35,875.00**
	Item Code 510220 Total No. of Proj.			**1**		**Total Amount**	**$35,875.00**
510314	CLASS 4 CONCRETE (BACKFILL)	M3	3	1	11.00	$200.00	$2,200.00
	Unit Sub Total	**M3**		**1**	**11.00**	**$200.00**	**$2,200.00**
	Item Code 510314 Total No. of Proj.			**1**		**Total Amount**	**$2,200.00**
510409	CLASS 1 CONCRETE (MINOR STRUCTURE)	CY	10	1	40.00	$725.00	$29,000.00
	Unit Sub Total	**CY**		**1**	**40.00**	**$725.00**	**$29,000.00**
	Item Code 510409 Total No. of Proj.			**1**		**Total Amount**	**$29,000.00**
510413	CLASS 1 CONCRETE (BOX CULVERT)	CY	5	2	1,265.00	$546.79	$691,685.00
		CY	10	1	18.00	$1,015.00	$18,270.00
		CY	12	1	380.00	$600.00	$228,000.00
	Unit Sub Total	**CY**		**4**	**1,663.00**	**$564.01**	**$937,955.00**
510413	CLASS 1 CONCRETE (BOX CULVERT)	M3	6	1	235.00	$690.00	$162,150.00
		M3	7	1	232.70	$450.00	$104,715.00
	Unit Sub Total	**M3**		**2**	**467.70**	**$570.59**	**$266,865.00**
	Item Code 510413 Total No. of Proj.			**6**		**Total Amount**	**$1,204,820.00**
510501	MINOR CONCRETE	CY	3	1	12.00	$450.00	$5,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**CY**		**1**	**12.00**	**$450.00**	**$5,400.00**
	Item Code 510501 Total No. of Proj.			**1**		**Total Amount**	**$5,400.00**
510502	MINOR CONCRETE (MINOR STRUCTURE)	CF	8	1	620.00	$80.00	$49,600.00
	Unit Sub Total	**CF**		**1**	**620.00**	**$80.00**	**$49,600.00**
510502	MINOR CONCRETE (MINOR STRUCTURE)	CY	1	10	327.40	$1,877.52	$614,699.68
		CY	2	16	403.30	$1,142.17	$460,635.82
		CY	3	15	824.50	$940.32	$775,290.60
		CY	4	29	1,088.00	$1,290.62	$1,404,192.27
		CY	5	11	423.00	$1,407.55	$595,392.60
		CY	6	10	208.30	$1,347.24	$280,630.00
		CY	7	4	232.10	$1,209.99	$280,838.20
		CY	8	6	90.50	$1,072.13	$97,028.00
		CY	9	3	13.20	$360.52	$4,758.88
		CY	10	6	232.60	$608.10	$141,444.00
		CY	11	7	172.50	$1,394.78	$240,600.00
		CY	12	8	2,052.40	$928.72	$1,906,110.00
	Unit Sub Total	**CY**		**125**	**6,067.80**	**$1,120.94**	**$6,801,620.05**
510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	2	1	6.60	$1,500.00	$9,900.00
		M3	3	1	29.10	$2,000.00	$58,200.00
		M3	4	3	790.00	$955.63	$754,950.00
		M3	6	3	61.30	$1,695.01	$103,904.00
		M3	7	5	1,440.80	$1,512.92	$2,179,820.00
		M3	10	1	54.00	$1,000.00	$54,000.00
		M3	11	2	192.00	$1,875.00	$360,000.00
	Unit Sub Total	**M3**		**16**	**2,573.80**	**$1,367.93**	**$3,520,774.00**
	Item Code 510502 Total No. of Proj.			**142**		**Total Amount**	**$10,371,994.05**
510509	MINOR CONCRETE (MEDIAN PAVING)	CY	4	1	37.00	$440.00	$16,280.00
	Unit Sub Total	**CY**		**1**	**37.00**	**$440.00**	**$16,280.00**
	Item Code 510509 Total No. of Proj.			**1**		**Total Amount**	**$16,280.00**
510510	MINOR CONCRETE (INVERT PAVING)	CY	1	1	1.20	$880.00	$1,056.00
		CY	3	1	18.00	$3,000.00	$54,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
510510	MINOR CONCRETE (INVERT PAVING)	CY	5	1	110.00	$260.00	$28,600.00
	Unit Sub Total	**CY**		**3**	**129.20**	**$647.49**	**$83,656.00**
	Item Code 510510 Total No. of Proj.			**3**		**Total Amount**	**$83,656.00**
510520	MINOR CONCRETE (CONCRETE DRAIN)	M3	7	1	150.00	$715.00	$107,250.00
	Unit Sub Total	**M3**		**1**	**150.00**	**$715.00**	**$107,250.00**
	Item Code 510520 Total No. of Proj.			**1**		**Total Amount**	**$107,250.00**
510524	MINOR CONCRETE (SOUND WALL)	CY	4	1	313.00	$500.00	$156,500.00
		CY	12	5	1,021.00	$459.76	$469,410.00
	Unit Sub Total	**CY**		**6**	**1,334.00**	**$469.20**	**$625,910.00**
510524	MINOR CONCRETE (SOUND WALL)	M3	3	1	80.00	$2,000.00	$160,000.00
		M3	7	3	2,120.40	$339.16	$719,160.00
	Unit Sub Total	**M3**		**4**	**2,200.40**	**$399.55**	**$879,160.00**
	Item Code 510524 Total No. of Proj.			**10**		**Total Amount**	**$1,505,070.00**
510526	MINOR CONCRETE (BACKFILL)	CY	2	5	263.90	$114.12	$30,117.50
		CY	3	1	23.00	$215.04	$4,945.92
		CY	4	9	2,086.00	$126.50	$263,878.00
		CY	5	3	84.50	$169.28	$14,304.00
		CY	6	3	206.00	$171.17	$35,260.00
		CY	8	1	22.00	$146.00	$3,212.00
		CY	10	1	16.00	$122.00	$1,952.00
		CY	12	1	2,710.00	$75.00	$203,250.00
	Unit Sub Total	**CY**		**24**	**5,411.40**	**$102.92**	**$556,919.42**
510526	MINOR CONCRETE (BACKFILL)	M3	4	1	140.00	$200.00	$28,000.00
		M3	6	2	134.00	$136.27	$18,260.00
		M3	7	1	90.00	$305.00	$27,450.00
		M3	10	1	72.00	$85.00	$6,120.00
	Unit Sub Total	**M3**		**5**	**436.00**	**$183.10**	**$79,830.00**
	Item Code 510526 Total No. of Proj.			**29**		**Total Amount**	**$636,749.42**
510700	MINOR CONCRETE (PILE CAP)	M3	7	1	7.00	$690.00	$4,830.00
	Unit Sub Total	**M3**		**1**	**7.00**	**$690.00**	**$4,830.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 510700	**Total No. of Proj.**			**1**		**Total Amount**	**$4,830.00**
510800	PAVING NOTCH EXTENSION		CF	2	2	345.00	$240.13	$82,845.00
			CF	3	1	114.00	$275.00	$31,350.00
			CF	4	3	1,169.00	$100.73	$117,754.00
			CF	6	3	611.00	$134.67	$82,284.00
			CF	7	1	162.00	$90.00	$14,580.00
			CF	9	1	81.00	$110.00	$8,910.00
			CF	11	4	295.00	$173.97	$51,320.00
			CF	12	2	194.00	$175.57	$34,060.00
		Unit Sub Total	**CF**		**17**	**2,971.00**	**$142.41**	**$423,103.00**
510800	PAVING NOTCH EXTENSION		CY	3	1	3.70	$2,500.00	$9,250.00
			CY	8	1	22.00	$2,477.00	$54,494.00
			CY	10	1	2.00	$1,600.00	$3,200.00
			CY	11	1	13.00	$2,200.00	$28,600.00
		Unit Sub Total	**CY**		**4**	**40.70**	**$2,347.52**	**$95,544.00**
510800	PAVING NOTCH EXTENSION		M3	7	3	25.00	$3,276.00	$81,900.00
		Unit Sub Total	**M3**		**3**	**25.00**	**$3,276.00**	**$81,900.00**
	Item Code 510800	**Total No. of Proj.**			**24**		**Total Amount**	**$600,547.00**
510805	DIAPHRAGM BOLSTER		EA	3	1	8.00	$1,500.00	$12,000.00
		Unit Sub Total	**EA**		**1**	**8.00**	**$1,500.00**	**$12,000.00**
	Item Code 510805	**Total No. of Proj.**			**1**		**Total Amount**	**$12,000.00**
511035	ARCHITECTURAL TREATMENT		M2	4	1	1,969.00	$15.00	$29,535.00
		Unit Sub Total	**M2**		**1**	**1,969.00**	**$15.00**	**$29,535.00**
511035	ARCHITECTURAL TREATMENT		SQFT	12	2	10,119.00	$16.60	$168,006.00
		Unit Sub Total	**SQFT**		**2**	**10,119.00**	**$16.60**	**$168,006.00**
	Item Code 511035	**Total No. of Proj.**			**3**		**Total Amount**	**$197,541.00**
511047	ANTI-GRAFFITI COATING		SQFT	4	1	124,000.00	$1.00	$124,000.00
			SQFT	6	1	24,900.00	$0.60	$14,940.00
		Unit Sub Total	**SQFT**		**2**	**148,900.00**	**$0.93**	**$138,940.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 511047	**Total No. of Proj.**			**2**		**Total Amount**	**$138,940.00**
511064	FRACTURED RIB TEXTURE		M2	4	1	2,354.00	$90.00	$211,860.00
			M2	7	4	36,174.60	$19.13	$692,100.70
		Unit Sub Total	**M2**		**5**	**38,528.60**	**$23.46**	**$903,960.70**
511064	FRACTURED RIB TEXTURE		SQFT	12	3	93,639.00	$4.76	$445,362.90
		Unit Sub Total	**SQFT**		**3**	**93,639.00**	**$4.76**	**$445,362.90**
	Item Code 511064	**Total No. of Proj.**			**8**		**Total Amount**	**$1,349,323.60**
511070	RIPPED TEXTURE (REINFORCING BAR)		SQFT	5	1	6,642.00	$7.00	$46,494.00
		Unit Sub Total	**SQFT**		**1**	**6,642.00**	**$7.00**	**$46,494.00**
	Item Code 511070	**Total No. of Proj.**			**1**		**Total Amount**	**$46,494.00**
511106	DRILL AND BOND DOWEL		EA	12	1	600.00	$20.00	$12,000.00
		Unit Sub Total	**EA**		**1**	**600.00**	**$20.00**	**$12,000.00**
511106	DRILL AND BOND DOWEL		LF	1	2	347.00	$23.86	$8,281.00
			LF	2	4	1,213.00	$27.46	$33,315.00
			LF	3	1	858.00	$40.00	$34,320.00
			LF	4	7	58,989.00	$29.89	$1,763,213.00
			LF	5	1	153.00	$33.00	$5,049.00
			LF	6	1	556.00	$20.00	$11,120.00
			LF	7	1	339.00	$20.00	$6,780.00
			LF	8	1	124.00	$62.00	$7,688.00
			LF	9	1	192.00	$40.00	$7,680.00
			LF	11	2	636.00	$28.97	$18,424.00
			LF	12	4	1,435.00	$20.32	$29,161.00
		Unit Sub Total	**LF**		**25**	**64,842.00**	**$29.69**	**$1,925,031.00**
511106	DRILL AND BOND DOWEL		M	7	5	3,212.00	$61.99	$199,104.00
		Unit Sub Total	**M**		**5**	**3,212.00**	**$61.99**	**$199,104.00**
	Item Code 511106	**Total No. of Proj.**			**31**		**Total Amount**	**$2,136,135.00**
511110	DRILL AND BOND DOWEL (CHEMICAL ADHESIVE)		EA	4	1	1,460.00	$60.00	$87,600.00
			EA	5	1	2,080.00	$50.00	$104,000.00
			EA	7	3	4,037.00	$12.80	$51,692.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
511110	DRILL AND BOND DOWEL (CHEMICAL ADHESIVE)	EA	11	1	465.00	$28.00	$13,020.00
		EA	12	1	34.00	$28.00	$952.00
	Unit Sub Total	**EA**		**7**	**8,076.00**	**$31.86**	**$257,264.00**
	Item Code 511110 Total No. of Proj.			**7**		**Total Amount**	**$257,264.00**
511118	CLEAN EXPANSION JOINT	LF	1	2	185.00	$21.22	$3,926.00
		LF	2	7	4,459.00	$25.75	$114,799.00
		LF	3	13	11,710.00	$14.12	$165,329.20
		LF	4	14	44,540.00	$12.91	$574,968.50
		LF	5	4	1,481.00	$15.87	$23,496.20
		LF	6	3	1,661.00	$16.14	$26,810.00
		LF	7	13	34,464.00	$12.32	$424,459.00
		LF	8	5	3,798.00	$8.80	$33,417.00
		LF	9	2	420.00	$15.91	$6,681.00
		LF	10	5	3,119.00	$11.27	$35,156.00
		LF	11	6	6,867.00	$7.92	$54,358.00
		LF	12	4	2,678.00	$13.17	$35,269.00
	Unit Sub Total	**LF**		**78**	**115,382.00**	**$12.99**	**$1,498,668.90**
511118	CLEAN EXPANSION JOINT	M	7	2	585.00	$26.02	$15,220.00
	Unit Sub Total	**M**		**2**	**585.00**	**$26.02**	**$15,220.00**
	Item Code 511118 Total No. of Proj.			**80**		**Total Amount**	**$1,513,888.90**
511123	CONCRETE (RAPID SETTING)	CF	3	1	48.00	$150.00	$7,200.00
	Unit Sub Total	**CF**		**1**	**48.00**	**$150.00**	**$7,200.00**
	Item Code 511123 Total No. of Proj.			**1**		**Total Amount**	**$7,200.00**
511124	RAPID SETTING CONCRETE (PATCH)	CF	1	2	562.00	$26.27	$14,765.00
		CF	2	8	3,688.00	$29.48	$108,739.00
		CF	3	11	16,645.00	$18.64	$310,326.00
		CF	4	13	11,858.00	$16.17	$191,732.00
		CF	5	5	734.00	$71.06	$52,158.45
		CF	6	3	403.00	$39.13	$15,770.00
		CF	7	14	12,573.00	$14.33	$180,189.00
		CF	8	7	1,774.00	$24.94	$44,242.00
		CF	9	3	1,042.00	$85.06	$88,629.25

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
511124	RAPID SETTING CONCRETE (PATCH)	CF	10	5	1,687.00	$6.76	$11,407.00
		CF	11	7	5,436.00	$19.12	$103,928.00
		CF	12	4	646.00	$29.16	$18,839.50
	Unit Sub Total	**CF**		**82**	**57,048.00**	**$20.00**	**$1,140,725.20**
	Item Code 511124 Total No. of Proj.			**82**		**Total Amount**	**$1,140,725.20**
511125	CLOSE ACCESS, DECK	EA	7	1	8.00	$550.00	$4,400.00
	Unit Sub Total	**EA**		**1**	**8.00**	**$550.00**	**$4,400.00**
	Item Code 511125 Total No. of Proj.			**1**		**Total Amount**	**$4,400.00**
511130	INJECT CRACK (EPOXY)	LF	3	1	3.00	$300.00	$900.00
		LF	8	2	541.00	$48.56	$26,270.00
	Unit Sub Total	**LF**		**3**	**544.00**	**$49.94**	**$27,170.00**
	Item Code 511130 Total No. of Proj.			**3**		**Total Amount**	**$27,170.00**
512202	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (30'-40')	EA	2	2	34.00	$4,264.71	$145,000.00
	Unit Sub Total	**EA**		**2**	**34.00**	**$4,264.71**	**$145,000.00**
	Item Code 512202 Total No. of Proj.			**2**		**Total Amount**	**$145,000.00**
512203	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (40'-50')	EA	2	1	16.00	$4,400.00	$70,400.00
	Unit Sub Total	**EA**		**1**	**16.00**	**$4,400.00**	**$70,400.00**
	Item Code 512203 Total No. of Proj.			**1**		**Total Amount**	**$70,400.00**
512204	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (50'-60')	EA	2	2	17.00	$5,717.65	$97,200.00
		EA	6	1	8.00	$4,000.00	$32,000.00
	Unit Sub Total	**EA**		**3**	**25.00**	**$5,168.00**	**$129,200.00**
	Item Code 512204 Total No. of Proj.			**3**		**Total Amount**	**$129,200.00**
512205	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (60'-70')	EA	2	2	13.00	$5,938.46	$77,200.00
	Unit Sub Total	**EA**		**2**	**13.00**	**$5,938.46**	**$77,200.00**
	Item Code 512205 Total No. of Proj.			**2**		**Total Amount**	**$77,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
512230	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (10 M - 15 M)	EA	7	1	2.00	$9,000.00	$18,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$9,000.00**	**$18,000.00**
	Item Code 512230 Total No. of Proj.			**1**		**Total Amount**	**$18,000.00**
512231	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (15 M - 20 M)	EA	7	1	2.00	$20,520.00	$41,040.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$20,520.00**	**$41,040.00**
	Item Code 512231 Total No. of Proj.			**1**		**Total Amount**	**$41,040.00**
512232	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (20 M - 25 M)	EA	7	2	13.00	$11,021.54	$143,280.00
	Unit Sub Total	**EA**		**2**	**13.00**	**$11,021.54**	**$143,280.00**
	Item Code 512232 Total No. of Proj.			**2**		**Total Amount**	**$143,280.00**
512233	FURNISH PRECAST PRESTRESSED CONCRETE GIRDER (25 M - 30 M)	EA	7	2	27.00	$12,379.33	$334,242.00
	Unit Sub Total	**EA**		**2**	**27.00**	**$12,379.33**	**$334,242.00**
	Item Code 512233 Total No. of Proj.			**2**		**Total Amount**	**$334,242.00**
512240	FURNISH PRECAST PRESTRESSED CONCRETE BOX GIRDER (20 M - 25 M)	EA	7	1	2.00	$18,195.00	$36,390.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$18,195.00**	**$36,390.00**
	Item Code 512240 Total No. of Proj.			**1**		**Total Amount**	**$36,390.00**
512278	FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (90'-100')	EA	3	1	8.00	$26,000.00	$208,000.00
	Unit Sub Total	**EA**		**1**	**8.00**	**$26,000.00**	**$208,000.00**
	Item Code 512278 Total No. of Proj.			**1**		**Total Amount**	**$208,000.00**
512279	FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (100'-110')	EA	3	1	96.00	$23,000.00	$2,208,000.00
	Unit Sub Total	**EA**		**1**	**96.00**	**$23,000.00**	**$2,208,000.00**
	Item Code 512279 Total No. of Proj.			**1**		**Total Amount**	**$2,208,000.00**
512280	FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (110'-120')	EA	3	1	4.00	$25,000.00	$100,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**1**	**4.00**	**$25,000.00**	**$100,000.00**
	Item Code 512280 Total No. of Proj.			**1**		**Total Amount**	**$100,000.00**
512282	FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (130'-140')	EA	12	1	4.00	$38,000.00	$152,000.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$38,000.00**	**$152,000.00**
	Item Code 512282 Total No. of Proj.			**1**		**Total Amount**	**$152,000.00**
512283	FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (140'-150')	EA	12	1	4.00	$38,250.00	$153,000.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$38,250.00**	**$153,000.00**
	Item Code 512283 Total No. of Proj.			**1**		**Total Amount**	**$153,000.00**
512288	FURNISH PRECAST PRESTRESSED CONCRETE BULB-TEE GIRDER (40'-50')	EA	3	1	24.00	$11,000.00	$264,000.00
	Unit Sub Total	**EA**		**1**	**24.00**	**$11,000.00**	**$264,000.00**
	Item Code 512288 Total No. of Proj.			**1**		**Total Amount**	**$264,000.00**
512351	FURNISH PRECAST PRESTRESSED CONCRETE SLAB (TYPE SI)	SQFT	6	1	3,000.00	$20.00	$60,000.00
	Unit Sub Total	**SQFT**		**1**	**3,000.00**	**$20.00**	**$60,000.00**
	Item Code 512351 Total No. of Proj.			**1**		**Total Amount**	**$60,000.00**
512500	ERECT PRECAST PRESTRESSED CONCRETE GIRDER	EA	2	2	80.00	$960.00	$76,800.00
		EA	3	1	132.00	$1,000.00	$132,000.00
		EA	6	1	8.00	$1,500.00	$12,000.00
		EA	7	3	44.00	$1,807.91	$79,548.00
		EA	12	2	28.00	$4,778.57	$133,800.00
	Unit Sub Total	**EA**		**9**	**292.00**	**$1,486.81**	**$434,148.00**
	Item Code 512500 Total No. of Proj.			**9**		**Total Amount**	**$434,148.00**
512502	ERECT PRECAST PRESTRESSED CONCRETE BOX GIRDER	EA	7	1	2.00	$774.00	$1,548.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$774.00**	**$1,548.00**
	Item Code 512502 Total No. of Proj.			**1**		**Total Amount**	**$1,548.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
512510	ERECT PRECAST PRESTRESSED CONCRETE DECK UNIT	EA	6	1	20.00	$700.00	$14,000.00
	Unit Sub Total	**EA**		**1**	**20.00**	**$700.00**	**$14,000.00**
	Item Code 512510 Total No. of Proj.			**1**		**Total Amount**	**$14,000.00**
513501	CONCRETE CLOSURE WALL	M2	7	1	397.00	$350.00	$138,950.00
	Unit Sub Total	**M2**		**1**	**397.00**	**$350.00**	**$138,950.00**
	Item Code 513501 Total No. of Proj.			**1**		**Total Amount**	**$138,950.00**
513551	RETAINING WALL STEM (TYPE 6)	SQFT	4	2	2,800.00	$40.00	$112,000.00
		SQFT	6	1	427.00	$15.00	$6,405.00
		SQFT	12	1	620.00	$20.00	$12,400.00
	Unit Sub Total	**SQFT**		**4**	**3,847.00**	**$34.00**	**$130,805.00**
	Item Code 513551 Total No. of Proj.			**4**		**Total Amount**	**$130,805.00**
513601	REINFORCED CONCRETE CRIB WALL (TYPE A)	M2	7	1	170.00	$607.50	$103,275.00
	Unit Sub Total	**M2**		**1**	**170.00**	**$607.50**	**$103,275.00**
513601	REINFORCED CONCRETE CRIB WALL (TYPE A)	SQFT	9	1	2,160.00	$84.00	$181,440.00
	Unit Sub Total	**SQFT**		**1**	**2,160.00**	**$84.00**	**$181,440.00**
	Item Code 513601 Total No. of Proj.			**2**		**Total Amount**	**$284,715.00**
513602	REINFORCED CONCRETE CRIB WALL (TYPE B)	M2	7	1	75.00	$672.00	$50,400.00
	Unit Sub Total	**M2**		**1**	**75.00**	**$672.00**	**$50,400.00**
513602	REINFORCED CONCRETE CRIB WALL (TYPE B)	SQFT	5	1	520.00	$100.00	$52,000.00
	Unit Sub Total	**SQFT**		**1**	**520.00**	**$100.00**	**$52,000.00**
	Item Code 513602 Total No. of Proj.			**2**		**Total Amount**	**$102,400.00**
513603	REINFORCED CONCRETE CRIB WALL (TYPE C)	M2	7	1	180.00	$789.00	$142,020.00
	Unit Sub Total	**M2**		**1**	**180.00**	**$789.00**	**$142,020.00**
	Item Code 513603 Total No. of Proj.			**1**		**Total Amount**	**$142,020.00**
515020	REFINISH BRIDGE DECK	M2	7	3	641.00	$330.64	$211,940.00
	Unit Sub Total	**M2**		**3**	**641.00**	**$330.64**	**$211,940.00**
515020	REFINISH BRIDGE DECK	SQFT	5	1	1,541.00	$8.00	$12,328.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
515020	REFINISH BRIDGE DECK	SQFT	6	1	149.00	$70.00	$10,430.00
		SQFT	7	1	3,050.00	$3.00	$9,150.00
		SQFT	8	1	63.00	$53.00	$3,339.00
	Unit Sub Total	**SQFT**		**4**	**4,803.00**	**$7.34**	**$35,247.00**
	Item Code 515020 Total No. of Proj.			**7**		**Total Amount**	**$247,187.00**
515028	REPAIR SPALLED SURFACE AREA	SQFT	2	1	163.00	$107.00	$17,441.00
		SQFT	3	1	23.00	$150.00	$3,450.00
		SQFT	4	4	1,020.00	$46.86	$47,800.00
		SQFT	7	4	925.00	$102.95	$95,232.00
	Unit Sub Total	**SQFT**		**10**	**2,131.00**	**$76.92**	**$163,923.00**
	Item Code 515028 Total No. of Proj.			**10**		**Total Amount**	**$163,923.00**
515041	FURNISH POLYESTER CONCRETE OVERLAY	CF	1	2	2,370.00	$78.50	$186,046.00
		CF	2	10	37,244.00	$69.38	$2,584,136.00
		CF	3	7	43,225.00	$58.79	$2,541,173.50
		CF	4	4	15,032.00	$61.79	$928,757.96
		CF	5	1	450.00	$70.00	$31,500.00
		CF	6	3	5,232.00	$82.29	$430,546.00
		CF	7	4	19,289.00	$53.89	$1,039,567.00
		CF	8	4	20,855.00	$58.70	$1,224,110.30
		CF	9	3	9,480.00	$57.11	$541,417.63
		CF	10	1	1,570.00	$78.00	$122,460.00
		CF	11	2	2,030.00	$68.28	$138,600.00
		CF	12	3	3,160.00	$72.40	$228,769.25
	Unit Sub Total	**CF**		**44**	**159,937.00**	**$62.51**	**$9,997,083.64**
515041	FURNISH POLYESTER CONCRETE OVERLAY	M3	2	1	44.00	$2,050.00	$90,200.00
		M3	4	1	6.00	$3,000.00	$18,000.00
		M3	7	1	6.00	$3,286.00	$19,716.00
		M3	10	1	0.80	$4,500.00	$3,600.00
		M3	11	1	6.00	$3,500.00	$21,000.00
	Unit Sub Total	**M3**		**5**	**62.80**	**$2,428.60**	**$152,516.00**
	Item Code 515041 Total No. of Proj.			**49**		**Total Amount**	**$10,149,599.64**
515042	PLACE POLYESTER CONCRETE OVERLAY	M2	2	1	2,295.00	$15.00	$34,425.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
515042	PLACE POLYESTER CONCRETE OVERLAY	M2	4	1	280.00	$20.00	$5,600.00
		M2	7	1	165.00	$84.80	$13,992.00
		M2	10	1	29.00	$1,000.00	$29,000.00
		M2	11	1	133.00	$80.00	$10,640.00
	Unit Sub Total	**M2**		**5**	**2,902.00**	**$32.27**	**$93,657.00**
515042	PLACE POLYESTER CONCRETE OVERLAY	SQFT	1	2	14,872.00	$1.59	$23,645.50
		SQFT	2	10	490,232.00	$0.99	$486,252.75
		SQFT	3	7	539,659.00	$0.91	$493,230.50
		SQFT	4	4	203,762.00	$1.15	$234,776.32
		SQFT	5	1	5,900.00	$2.25	$13,275.00
		SQFT	6	3	74,340.00	$1.24	$92,456.00
		SQFT	7	4	196,316.00	$1.73	$339,344.70
		SQFT	8	4	250,603.00	$0.43	$108,913.70
		SQFT	9	3	102,611.00	$1.19	$122,330.90
		SQFT	10	1	20,945.00	$1.00	$20,945.00
		SQFT	11	1	20,120.00	$0.70	$14,084.00
		SQFT	12	3	48,307.00	$2.25	$108,532.60
	Unit Sub Total	**SQFT**		**43**	**1,967,667.00**	**$1.05**	**$2,057,786.97**
	Item Code 515042 Total No. of Proj.			**48**		**Total Amount**	**$2,151,443.97**
515061	CORE CONCRETE (2")	LF	4	1	3,456.00	$35.00	$120,960.00
	Unit Sub Total	**LF**		**1**	**3,456.00**	**$35.00**	**$120,960.00**
	Item Code 515061 Total No. of Proj.			**1**		**Total Amount**	**$120,960.00**
515064	CORE CONCRETE (5")	LF	4	2	705.00	$108.51	$76,500.00
	Unit Sub Total	**LF**		**2**	**705.00**	**$108.51**	**$76,500.00**
	Item Code 515064 Total No. of Proj.			**2**		**Total Amount**	**$76,500.00**
515065	CORE CONCRETE (6")	LF	3	1	122.00	$250.00	$30,500.00
	Unit Sub Total	**LF**		**1**	**122.00**	**$250.00**	**$30,500.00**
	Item Code 515065 Total No. of Proj.			**1**		**Total Amount**	**$30,500.00**
515072	CORE CONCRETE (0 - 50 MM)	M	7	3	30.00	$145.00	$4,350.00
	Unit Sub Total	**M**		**3**	**30.00**	**$145.00**	**$4,350.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 515072 Total No. of Proj.			**3**		**Total Amount**	**$4,350.00**
515073	CORE CONCRETE (51 MM - 100 MM)	M	7	1	3.00	$200.00	$600.00
	Unit Sub Total	**M**		**1**	**3.00**	**$200.00**	**$600.00**
	Item Code 515073 Total No. of Proj.			**1**		**Total Amount**	**$600.00**
515074	CORE CONCRETE (101 MM - 150 MM)	M	7	1	141.00	$160.00	$22,560.00
	Unit Sub Total	**M**		**1**	**141.00**	**$160.00**	**$22,560.00**
	Item Code 515074 Total No. of Proj.			**1**		**Total Amount**	**$22,560.00**
515077	CORE CONCRETE (251 MM - 300 MM)	M	7	1	1.00	$500.00	$500.00
	Unit Sub Total	**M**		**1**	**1.00**	**$500.00**	**$500.00**
	Item Code 515077 Total No. of Proj.			**1**		**Total Amount**	**$500.00**
515157	CORE CONCRETE (1 1/8")	LF	4	1	370.00	$45.00	$16,650.00
	Unit Sub Total	**LF**		**1**	**370.00**	**$45.00**	**$16,650.00**
	Item Code 515157 Total No. of Proj.			**1**		**Total Amount**	**$16,650.00**
515160	CORE CONCRETE (1 1/2")	LF	4	1	113.00	$100.00	$11,300.00
	Unit Sub Total	**LF**		**1**	**113.00**	**$100.00**	**$11,300.00**
	Item Code 515160 Total No. of Proj.			**1**		**Total Amount**	**$11,300.00**
517961	SOUND WALL (BARRIER) (MASONRY BLOCK)	SQFT	12	2	104,884.00	$15.86	$1,663,104.00
	Unit Sub Total	**SQFT**		**2**	**104,884.00**	**$15.86**	**$1,663,104.00**
	Item Code 517961 Total No. of Proj.			**2**		**Total Amount**	**$1,663,104.00**
518002	SOUND WALL (MASONRY BLOCK)	M2	3	1	2,410.00	$150.00	$361,500.00
		M2	4	1	3,144.00	$142.00	$446,448.00
		M2	7	4	49,112.00	$145.17	$7,129,345.64
		M2	10	1	230.00	$200.00	$46,000.00
	Unit Sub Total	**M2**		**7**	**54,896.00**	**$145.43**	**$7,983,293.64**
518002	SOUND WALL (MASONRY BLOCK)	SQFT	4	1	46,838.00	$15.00	$702,570.00
		SQFT	10	1	1,206.00	$21.40	$25,808.40
		SQFT	12	7	281,132.00	$13.30	$3,739,035.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**SQFT**		**9**	**329,176.00**	**$13.57**	**$4,467,413.40**
	Item Code 518002	**Total No. of Proj.**			**16**		**Total Amount**	**$12,450,707.04**
518040	REPLACE BEARING PAD		EA	4	1	12.00	$3,575.00	$42,900.00
			EA	7	1	9.00	$4,800.00	$43,200.00
			EA	10	1	8.00	$3,310.00	$26,480.00
			EA	12	1	1.00	$10,000.00	$10,000.00
		Unit Sub Total	**EA**		**4**	**30.00**	**$4,086.00**	**$122,580.00**
	Item Code 518040	**Total No. of Proj.**			**4**		**Total Amount**	**$122,580.00**
518042	REPLACE BEARING		EA	4	1	24.00	$4,000.00	$96,000.00
		Unit Sub Total	**EA**		**1**	**24.00**	**$4,000.00**	**$96,000.00**
	Item Code 518042	**Total No. of Proj.**			**1**		**Total Amount**	**$96,000.00**
518050	PTFE BEARING		EA	10	1	16.00	$4,100.00	$65,600.00
			EA	12	2	33.00	$4,448.64	$146,805.00
		Unit Sub Total	**EA**		**3**	**49.00**	**$4,334.80**	**$212,405.00**
	Item Code 518050	**Total No. of Proj.**			**3**		**Total Amount**	**$212,405.00**
518051	PTFE SPHERICAL BEARING		EA	3	1	24.00	$7,000.00	$168,000.00
			EA	4	1	10.00	$9,000.00	$90,000.00
			EA	5	1	18.00	$6,000.00	$108,000.00
			EA	7	1	20.00	$7,000.00	$140,000.00
			EA	10	1	8.00	$7,800.00	$62,400.00
			EA	12	1	15.00	$8,140.00	$122,100.00
		Unit Sub Total	**EA**		**6**	**95.00**	**$7,268.42**	**$690,500.00**
	Item Code 518051	**Total No. of Proj.**			**6**		**Total Amount**	**$690,500.00**
518201	MASONRY BLOCK WALL		M2	7	1	919.00	$75.00	$68,925.00
		Unit Sub Total	**M2**		**1**	**919.00**	**$75.00**	**$68,925.00**
518201	MASONRY BLOCK WALL		SQFT	6	1	780.00	$16.50	$12,870.00
		Unit Sub Total	**SQFT**		**1**	**780.00**	**$16.50**	**$12,870.00**
	Item Code 518201	**Total No. of Proj.**			**2**		**Total Amount**	**$81,795.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
519050	EXPANSION DAM		CF	3	1	760.00	$155.00	$117,800.00
		Unit Sub Total	**CF**		**1**	**760.00**	**$155.00**	**$117,800.00**
	Item Code 519050	**Total No. of Proj.**			**1**		**Total Amount**	**$117,800.00**
519078	SNOWPLOW DEFLECTOR		EA	3	1	392.00	$250.00	$98,000.00
		Unit Sub Total	**EA**		**1**	**392.00**	**$250.00**	**$98,000.00**
	Item Code 519078	**Total No. of Proj.**			**1**		**Total Amount**	**$98,000.00**
519081	JOINT SEAL (MR 1/2")		LF	2	3	496.00	$21.18	$10,504.00
			LF	3	6	1,953.00	$15.52	$30,314.00
			LF	4	13	29,428.00	$19.02	$559,733.15
			LF	5	2	247.00	$21.01	$5,190.04
			LF	6	3	2,451.00	$17.88	$43,835.00
			LF	7	8	8,580.00	$16.67	$143,068.00
			LF	8	4	1,230.00	$26.98	$33,186.00
			LF	10	4	1,349.00	$18.76	$25,307.25
			LF	11	6	2,899.00	$15.58	$45,161.00
			LF	12	3	586.00	$29.06	$17,031.00
		Unit Sub Total	**LF**		**52**	**49,219.00**	**$18.56**	**$913,329.44**
	Item Code 519081	**Total No. of Proj.**			**52**		**Total Amount**	**$913,329.44**
519088	JOINT SEAL (MR 1")		LF	2	7	3,261.00	$40.13	$130,876.00
			LF	3	7	2,607.00	$28.52	$74,339.00
			LF	4	14	10,463.00	$24.06	$251,790.65
			LF	5	3	1,023.00	$34.33	$35,122.10
			LF	6	2	336.00	$34.59	$11,623.50
			LF	7	12	11,172.00	$17.63	$197,010.50
			LF	8	4	1,709.00	$24.77	$42,336.00
			LF	9	1	201.00	$46.00	$9,246.00
			LF	10	4	1,206.00	$20.01	$24,134.06
			LF	11	6	1,074.00	$42.44	$45,578.00
			LF	12	6	1,520.00	$31.83	$48,389.00
		Unit Sub Total	**LF**		**66**	**34,572.00**	**$25.18**	**$870,444.81**
	Item Code 519088	**Total No. of Proj.**			**66**		**Total Amount**	**$870,444.81**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
519091	JOINT SEAL (MR 1 1/2")	LF	2	3	1,131.00	$44.02	$49,791.00
		LF	3	8	5,027.00	$41.52	$208,727.50
		LF	4	12	4,366.00	$40.44	$176,558.00
		LF	6	2	345.00	$65.03	$22,437.00
		LF	7	10	5,874.00	$33.65	$197,682.00
		LF	8	2	451.00	$76.29	$34,408.00
		LF	9	2	143.00	$32.17	$4,601.00
		LF	10	4	469.00	$44.49	$20,865.94
		LF	11	5	2,051.00	$28.10	$57,636.00
		LF	12	5	1,173.00	$45.36	$53,202.00
	Unit Sub Total	**LF**		**53**	**21,030.00**	**$39.27**	**$825,908.44**
	Item Code 519091 Total No. of Proj.			**53**		**Total Amount**	**$825,908.44**
519092	JOINT SEAL ASSEMBLY (MR 2 1/2")	LF	4	1	155.00	$170.25	$26,388.75
		LF	7	2	111.00	$276.44	$30,685.00
		LF	12	2	304.00	$351.38	$106,820.00
	Unit Sub Total	**LF**		**5**	**570.00**	**$287.53**	**$163,893.75**
	Item Code 519092 Total No. of Proj.			**5**		**Total Amount**	**$163,893.75**
519093	JOINT SEAL ASSEMBLY (MR 3")	LF	3	2	401.00	$190.59	$76,425.00
		LF	11	1	80.00	$100.00	$8,000.00
		LF	12	2	318.00	$266.70	$84,810.00
	Unit Sub Total	**LF**		**5**	**799.00**	**$211.81**	**$169,235.00**
	Item Code 519093 Total No. of Proj.			**5**		**Total Amount**	**$169,235.00**
519094	JOINT SEAL ASSEMBLY (MR 3 1/2")	LF	4	1	208.00	$185.40	$38,563.20
		LF	7	1	128.00	$125.00	$16,000.00
		LF	12	1	147.00	$360.00	$52,920.00
	Unit Sub Total	**LF**		**3**	**483.00**	**$222.53**	**$107,483.20**
	Item Code 519094 Total No. of Proj.			**3**		**Total Amount**	**$107,483.20**
519095	JOINT SEAL ASSEMBLY (MR 4")	LF	3	1	178.00	$225.00	$40,050.00
		LF	8	1	39.00	$130.00	$5,070.00
		LF	11	1	52.00	$100.00	$5,200.00
	Unit Sub Total	**LF**		**3**	**269.00**	**$187.06**	**$50,320.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 519095	**Total No. of Proj.**			**3**		**Total Amount**	**$50,320.00**
519097	JOINT SEAL ASSEMBLY (MR 5")		LF	12	2	82.00	$669.63	$54,910.00
		Unit Sub Total	**LF**		**2**	**82.00**	**$669.63**	**$54,910.00**
	Item Code 519097	**Total No. of Proj.**			**2**		**Total Amount**	**$54,910.00**
519098	JOINT SEAL ASSEMBLY (MR 5 1/2")		LF	3	1	42.00	$100.00	$4,200.00
			LF	12	1	59.00	$755.00	$44,545.00
		Unit Sub Total	**LF**		**2**	**101.00**	**$482.62**	**$48,745.00**
	Item Code 519098	**Total No. of Proj.**			**2**		**Total Amount**	**$48,745.00**
519099	JOINT SEAL ASSEMBLY (MR 6")		LF	3	1	42.00	$100.00	$4,200.00
			LF	5	1	182.00	$930.00	$169,260.00
			LF	12	2	392.00	$777.27	$304,690.00
		Unit Sub Total	**LF**		**4**	**616.00**	**$776.22**	**$478,150.00**
	Item Code 519099	**Total No. of Proj.**			**4**		**Total Amount**	**$478,150.00**
519100	JOINT SEAL (MR 2")		LF	1	1	72.00	$60.00	$4,320.00
			LF	2	3	368.00	$72.54	$26,694.00
			LF	3	8	1,285.00	$61.09	$78,495.00
			LF	4	7	1,869.00	$62.03	$115,937.50
			LF	5	1	75.00	$60.00	$4,500.00
			LF	7	5	4,136.00	$51.49	$212,963.00
			LF	8	2	357.00	$45.97	$16,410.00
			LF	9	2	178.00	$37.15	$6,612.50
			LF	10	2	200.00	$57.42	$11,484.00
			LF	11	4	531.00	$59.01	$31,334.00
			LF	12	3	690.00	$78.84	$54,396.50
		Unit Sub Total	**LF**		**38**	**9,761.00**	**$57.69**	**$563,146.50**
	Item Code 519100	**Total No. of Proj.**			**38**		**Total Amount**	**$563,146.50**
519102	JOINT SEAL (TYPE AL)		LF	4	2	3,978.00	$40.00	$159,120.00
			LF	7	3	1,043.00	$20.00	$20,859.50
			LF	8	1	1,548.00	$11.00	$17,028.00
		Unit Sub Total	**LF**		**6**	**6,569.00**	**$29.99**	**$197,007.50**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
519102	JOINT SEAL (TYPE AL)	M	7	2	81.00	$109.94	$8,905.30
	Unit Sub Total	**M**		**2**	**81.00**	**$109.94**	**$8,905.30**
	Item Code 519102 Total No. of Proj.			**8**		**Total Amount**	**$205,912.80**
519109	JOINT SEAL ASSEMBLY (MR 6 1/2")	LF	12	1	59.00	$1,115.00	$65,785.00
	Unit Sub Total	**LF**		**1**	**59.00**	**$1,115.00**	**$65,785.00**
	Item Code 519109 Total No. of Proj.			**1**		**Total Amount**	**$65,785.00**
519118	JOINT SEAL ASSEMBLY (MR 9")	LF	2	1	39.00	$2,000.00	$78,000.00
		LF	12	1	60.00	$1,375.00	$82,500.00
	Unit Sub Total	**LF**		**2**	**99.00**	**$1,621.21**	**$160,500.00**
	Item Code 519118 Total No. of Proj.			**2**		**Total Amount**	**$160,500.00**
519124	JOINT SEAL ASSEMBLY (MR 60 MM)	M	11	1	26.00	$1,000.00	$26,000.00
	Unit Sub Total	**M**		**1**	**26.00**	**$1,000.00**	**$26,000.00**
	Item Code 519124 Total No. of Proj.			**1**		**Total Amount**	**$26,000.00**
519125	JOINT SEAL ASSEMBLY (MR 70 MM)	M	4	1	61.00	$750.00	$45,750.00
	Unit Sub Total	**M**		**1**	**61.00**	**$750.00**	**$45,750.00**
	Item Code 519125 Total No. of Proj.			**1**		**Total Amount**	**$45,750.00**
519127	JOINT SEAL ASSEMBLY (MR 90 MM)	M	2	1	25.00	$300.00	$7,500.00
	Unit Sub Total	**M**		**1**	**25.00**	**$300.00**	**$7,500.00**
	Item Code 519127 Total No. of Proj.			**1**		**Total Amount**	**$7,500.00**
519128	JOINT SEAL ASSEMBLY (MR 100 MM)	M	4	1	12.00	$270.00	$3,240.00
	Unit Sub Total	**M**		**1**	**12.00**	**$270.00**	**$3,240.00**
	Item Code 519128 Total No. of Proj.			**1**		**Total Amount**	**$3,240.00**
519129	JOINT SEAL ASSEMBLY (MR 101 MM - 160 MM)	M	7	1	69.00	$2,250.00	$155,250.00
		M	10	1	50.00	$1,700.00	$85,000.00
	Unit Sub Total	**M**		**2**	**119.00**	**$2,018.91**	**$240,250.00**
	Item Code 519129 Total No. of Proj.			**2**		**Total Amount**	**$240,250.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
519130	JOINT SEAL ASSEMBLY (MR 161 MM - 240 MM)	M	10	1	25.00	$2,900.00	$72,500.00
	Unit Sub Total	**M**		**1**	**25.00**	**$2,900.00**	**$72,500.00**
	Item Code 519130 Total No. of Proj.			**1**		**Total Amount**	**$72,500.00**
519131	JOINT SEAL ASSEMBLY (MR 241 MM - 320 MM)	M	7	1	35.00	$5,750.00	$201,250.00
	Unit Sub Total	**M**		**1**	**35.00**	**$5,750.00**	**$201,250.00**
	Item Code 519131 Total No. of Proj.			**1**		**Total Amount**	**$201,250.00**
519133	JOINT SEAL (ASPHALTIC PLUG)	LF	3	1	1,323.00	$20.00	$26,460.00
		LF	4	3	253.00	$105.72	$26,746.00
		LF	5	1	190.00	$93.00	$17,670.00
		LF	10	2	644.00	$87.83	$56,560.00
	Unit Sub Total	**LF**		**7**	**2,410.00**	**$52.88**	**$127,436.00**
	Item Code 519133 Total No. of Proj.			**7**		**Total Amount**	**$127,436.00**
519142	JOINT SEAL (MR 40 MM)	M	7	2	67.00	$301.85	$20,224.00
		M	11	1	26.00	$350.00	$9,100.00
	Unit Sub Total	**M**		**3**	**93.00**	**$315.31**	**$29,324.00**
	Item Code 519142 Total No. of Proj.			**3**		**Total Amount**	**$29,324.00**
519144	JOINT SEAL (MR 50 MM)	M	4	1	64.00	$200.00	$12,800.00
		M	7	2	70.00	$356.18	$24,932.50
	Unit Sub Total	**M**		**3**	**134.00**	**$281.59**	**$37,732.50**
	Item Code 519144 Total No. of Proj.			**3**		**Total Amount**	**$37,732.50**
520101	BAR REINFORCING STEEL	KG	3	1	2,029.00	$1.00	$2,029.00
		KG	7	1	27,844.00	$1.70	$47,334.80
	Unit Sub Total	**KG**		**2**	**29,873.00**	**$1.65**	**$49,363.80**
520101	BAR REINFORCING STEEL	LB	1	1	1,000.00	$2.00	$2,000.00
		LB	2	2	9,028.00	$1.33	$12,012.00
		LB	4	2	20,200.00	$1.05	$21,290.00
		LB	6	2	2,280.00	$2.14	$4,876.00
		LB	8	1	410.00	$1.35	$553.50
		LB	10	1	300.00	$11.00	$3,300.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
520101	BAR REINFORCING STEEL	LB	11	1	40.00	$6.00	$240.00
		LB	12	1	1,272.00	$1.20	$1,526.40
	Unit Sub Total	**LB**		**11**	**34,530.00**	**$1.33**	**$45,797.90**
	Item Code 520101 Total No. of Proj.			**13**		**Total Amount**	**$95,161.70**
520102	BAR REINFORCING STEEL (BRIDGE)	KG	2	1	579,100.00	$2.30	$1,331,930.00
		KG	4	3	7,909,896.00	$1.68	$13,303,547.60
		KG	7	5	4,863,470.00	$1.56	$7,608,746.50
		KG	10	1	1,487,000.00	$1.25	$1,858,750.00
		KG	11	2	317,950.00	$1.69	$536,425.00
	Unit Sub Total	**KG**		**12**	**15,157,416.00**	**$1.63**	**$24,639,399.10**
520102	BAR REINFORCING STEEL (BRIDGE)	LB	1	1	11,414.00	$2.00	$22,828.00
		LB	2	3	601,169.00	$0.91	$544,732.10
		LB	3	3	3,281,109.00	$0.73	$2,387,779.88
		LB	4	9	3,433,615.00	$0.90	$3,082,087.30
		LB	5	4	4,208,418.00	$0.66	$2,766,403.40
		LB	6	3	872,453.00	$0.91	$791,762.40
		LB	7	3	5,037.00	$1.56	$7,860.00
		LB	8	1	19,800.00	$0.98	$19,404.00
		LB	10	2	35,183.00	$1.01	$35,443.26
		LB	11	4	364,402.00	$0.79	$288,435.50
		LB	12	7	19,115,677.00	$0.59	$11,297,800.90
	Unit Sub Total	**LB**		**40**	**31,948,277.00**	**$0.66**	**$21,244,536.74**
	Item Code 520102 Total No. of Proj.			**52**		**Total Amount**	**$45,883,935.84**
520103	BAR REINFORCING STEEL (RETAINING WALL)	KG	2	1	13,300.00	$2.00	$26,600.00
		KG	4	3	385,436.00	$1.83	$705,848.00
		KG	7	5	1,785,559.90	$1.60	$2,857,332.91
		KG	10	1	3,200.00	$2.52	$8,064.00
	Unit Sub Total	**KG**		**10**	**2,187,495.90**	**$1.64**	**$3,597,844.91**
520103	BAR REINFORCING STEEL (RETAINING WALL)	LB	1	4	272,469.00	$0.84	$229,291.00
		LB	4	9	1,600,264.00	$0.90	$1,443,991.90
		LB	5	3	209,990.00	$0.76	$159,310.00
		LB	6	4	532,303.00	$1.01	$539,596.60
		LB	8	1	198,650.00	$1.00	$198,650.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
520103	BAR REINFORCING STEEL (RETAINING WALL)	LB	10	1	492,173.00	$1.00	$492,173.00
		LB	11	1	33,400.00	$1.05	$35,070.00
		LB	12	7	1,660,990.00	$0.75	$1,244,188.85
	Unit Sub Total	**LB**		**30**	**5,000,239.00**	**$0.87**	**$4,342,271.35**
	Item Code 520103 Total No. of Proj.			**40**		**Total Amount**	**$7,940,116.26**
520105	BAR REINFORCING STEEL (SOUND WALL)	KG	4	1	25,200.00	$1.00	$25,200.00
	Unit Sub Total	**KG**		**1**	**25,200.00**	**$1.00**	**$25,200.00**
520105	BAR REINFORCING STEEL (SOUND WALL)	LB	4	1	8,072.00	$3.00	$24,216.00
		LB	12	1	52,400.00	$0.93	$48,732.00
	Unit Sub Total	**LB**		**2**	**60,472.00**	**$1.21**	**$72,948.00**
	Item Code 520105 Total No. of Proj.			**3**		**Total Amount**	**$98,148.00**
520106	BAR REINFORCING STEEL (EPOXY COATED)	LB	3	1	433,767.00	$0.70	$303,636.90
		LB	5	1	117,223.00	$1.30	$152,389.90
	Unit Sub Total	**LB**		**2**	**550,990.00**	**$0.83**	**$456,026.80**
	Item Code 520106 Total No. of Proj.			**2**		**Total Amount**	**$456,026.80**
520107	BAR REINFORCING STEEL (BOX CULVERT)	KG	4	1	116,000.00	$1.65	$191,400.00
		KG	6	1	48,210.00	$1.00	$48,210.00
		KG	7	3	45,025.80	$1.63	$73,477.78
	Unit Sub Total	**KG**		**5**	**209,235.80**	**$1.50**	**$313,087.78**
520107	BAR REINFORCING STEEL (BOX CULVERT)	LB	4	1	2,910.00	$2.00	$5,820.00
		LB	5	2	239,153.00	$0.85	$204,153.00
		LB	6	1	8,384.00	$0.70	$5,868.80
		LB	8	1	1,782.00	$1.36	$2,423.52
		LB	10	1	2,896.00	$1.30	$3,764.80
		LB	12	3	381,466.00	$0.67	$254,802.80
	Unit Sub Total	**LB**		**9**	**636,591.00**	**$0.75**	**$476,832.92**
	Item Code 520107 Total No. of Proj.			**14**		**Total Amount**	**$789,920.70**
520109	BAR REINFORCING STEEL (TUNNEL)	LB	4	1	6,330,000.00	$0.40	$2,532,000.00
	Unit Sub Total	**LB**		**1**	**6,330,000.00**	**$0.40**	**$2,532,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 520109 Total No. of Proj.			**1**		**Total Amount**	**$2,532,000.00**
520110	BAR REINFORCING STEEL (EPOXY COATED) (BRIDGE)	KG	2	1	200,000.00	$1.70	$340,000.00
	Unit Sub Total	**KG**		**1**	**200,000.00**	**$1.70**	**$340,000.00**
520110	BAR REINFORCING STEEL (EPOXY COATED) (BRIDGE)	LB	2	1	10,556.00	$1.50	$15,834.00
		LB	4	1	266,000.00	$1.40	$372,400.00
		LB	6	1	27,850.00	$1.10	$30,635.00
		LB	8	1	3,590.00	$1.58	$5,672.20
		LB	9	2	33,816.00	$1.61	$54,525.60
	Unit Sub Total	**LB**		**6**	**341,812.00**	**$1.40**	**$479,066.80**
	Item Code 520110 Total No. of Proj.			**7**		**Total Amount**	**$819,066.80**
520120	HEADED BAR REINFORCEMENT	EA	2	2	1,996.00	$15.13	$30,196.00
		EA	4	1	224.00	$75.00	$16,800.00
		EA	5	1	404.00	$5.00	$2,020.00
		EA	7	4	5,590.00	$24.11	$134,747.20
		EA	11	1	230.00	$30.00	$6,900.00
		EA	12	3	32,139.00	$7.15	$229,946.00
	Unit Sub Total	**EA**		**12**	**40,583.00**	**$10.36**	**$420,609.20**
	Item Code 520120 Total No. of Proj.			**12**		**Total Amount**	**$420,609.20**
530100	SHOTCRETE	CY	4	2	2,525.00	$316.63	$799,500.00
		CY	6	2	908.00	$322.14	$292,500.00
		CY	11	1	50.00	$1,410.00	$70,500.00
		CY	12	3	361.00	$440.61	$159,060.00
	Unit Sub Total	**CY**		**8**	**3,844.00**	**$343.80**	**$1,321,560.00**
530100	SHOTCRETE	M3	2	1	129.00	$600.00	$77,400.00
	Unit Sub Total	**M3**		**1**	**129.00**	**$600.00**	**$77,400.00**
	Item Code 530100 Total No. of Proj.			**9**		**Total Amount**	**$1,398,960.00**
540100	DECK SEAL	SQFT	2	1	42,850.00	$1.20	$51,420.00
		SQFT	5	1	7,917.00	$2.50	$19,792.50
		SQFT	8	1	424.00	$5.00	$2,120.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**SQFT**		**3**	**51,191.00**	**$1.43**	**$73,332.50**
	Item Code 540100 Total No. of Proj.			**3**		**Total Amount**	**$73,332.50**
540101	ASPHALT MEMBRANE WATERPROOFING	M2	7	1	79.00	$68.25	$5,391.75
		M2	11	1	29.00	$170.00	$4,930.00
	Unit Sub Total	**M2**		**2**	**108.00**	**$95.57**	**$10,321.75**
540101	ASPHALT MEMBRANE WATERPROOFING	SQFT	4	2	10,190.00	$6.59	$67,180.00
		SQFT	12	2	2,914.00	$8.20	$23,902.40
	Unit Sub Total	**SQFT**		**4**	**13,104.00**	**$6.95**	**$91,082.40**
	Item Code 540101 Total No. of Proj.			**6**		**Total Amount**	**$101,404.15**
540102	TREAT BRIDGE DECK	M2	4	1	22,800.00	$0.50	$11,400.00
	Unit Sub Total	**M2**		**1**	**22,800.00**	**$0.50**	**$11,400.00**
540102	TREAT BRIDGE DECK	SQFT	1	2	92,118.00	$0.30	$27,805.58
		SQFT	2	4	129,871.00	$0.40	$52,266.94
		SQFT	3	9	1,988,713.00	$0.10	$197,828.05
		SQFT	4	14	3,371,658.00	$0.15	$520,616.20
		SQFT	5	3	42,810.00	$0.50	$21,427.10
		SQFT	6	1	80,024.00	$0.17	$13,604.08
		SQFT	7	12	3,196,702.00	$0.18	$563,195.55
		SQFT	8	3	447,589.00	$0.17	$75,673.04
		SQFT	10	4	347,589.00	$0.12	$42,337.89
		SQFT	11	6	2,093,979.00	$0.13	$267,544.30
		SQFT	12	2	168,267.00	$0.20	$34,126.23
	Unit Sub Total	**SQFT**		**60**	**11,959,320.00**	**$0.15**	**$1,816,424.96**
	Item Code 540102 Total No. of Proj.			**61**		**Total Amount**	**$1,827,824.96**
540108	FURNISH BRIDGE DECK TREATMENT MATERIAL	GAL	1	2	1,025.00	$47.79	$48,986.00
		GAL	2	4	1,449.00	$60.49	$87,650.00
		GAL	3	9	22,019.00	$57.49	$1,265,945.00
		GAL	4	14	39,386.00	$56.59	$2,228,888.94
		GAL	5	2	439.00	$77.23	$33,903.00
		GAL	6	1	896.00	$55.00	$49,280.00
		GAL	7	12	37,333.00	$45.86	$1,712,254.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
540108	FURNISH BRIDGE DECK TREATMENT MATERIAL	GAL	8	3	5,516.00	$49.85	$274,973.00
		GAL	10	4	3,874.00	$54.68	$211,830.68
		GAL	11	6	26,227.00	$47.48	$1,245,204.00
		GAL	12	2	2,103.00	$48.75	$102,516.00
	Unit Sub Total	**GAL**		**59**	**140,267.00**	**$51.77**	**$7,261,430.62**
540108	FURNISH BRIDGE DECK TREATMENT MATERIAL	L	4	1	10,400.00	$20.50	$213,200.00
	Unit Sub Total	**L**		**1**	**10,400.00**	**$20.50**	**$213,200.00**
	Item Code 540108 Total No. of Proj.			**60**		**Total Amount**	**$7,474,630.62**
540109	FURNISH BRIDGE DECK TREATMENT MATERIAL (LOW ODOR)	GAL	5	1	57.00	$124.49	$7,095.93
	Unit Sub Total	**GAL**		**1**	**57.00**	**$124.49**	**$7,095.93**
	Item Code 540109 Total No. of Proj.			**1**		**Total Amount**	**$7,095.93**
550102	STRUCTURAL STEEL (BRIDGE)	LB	2	2	674.00	$29.67	$19,995.00
		LB	3	1	5,720.00	$10.00	$57,200.00
		LB	7	2	4,560.00	$61.67	$281,220.00
		LB	8	1	3,600.00	$9.00	$32,400.00
		LB	10	1	450.00	$22.78	$10,251.00
		LB	11	1	15,315.00	$14.90	$228,193.50
		LB	12	1	2,210.00	$14.00	$30,940.00
	Unit Sub Total	**LB**		**9**	**32,529.00**	**$20.30**	**$660,199.50**
	Item Code 550102 Total No. of Proj.			**9**		**Total Amount**	**$660,199.50**
550110	COLUMN CASING	KG	7	1	26,790.00	$13.00	$348,270.00
		KG	11	1	18,600.00	$6.00	$111,600.00
	Unit Sub Total	**KG**		**2**	**45,390.00**	**$10.13**	**$459,870.00**
550110	COLUMN CASING	LB	4	1	84,500.00	$9.00	$760,500.00
		LB	12	2	236,200.00	$3.99	$941,430.00
	Unit Sub Total	**LB**		**3**	**320,700.00**	**$5.31**	**$1,701,930.00**
	Item Code 550110 Total No. of Proj.			**5**		**Total Amount**	**$2,161,800.00**
550203	FURNISH STRUCTURAL STEEL (BRIDGE)	KG	4	1	27,840.00	$3.00	$83,520.00
		KG	7	3	1,661,500.00	$3.64	$6,042,163.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**KG**		**4**	**1,689,340.00**	**$3.63**	**$6,125,683.00**
550203	FURNISH STRUCTURAL STEEL (BRIDGE)	LB	4	2	4,420,000.00	$1.54	$6,785,200.00
		LB	12	1	2,785.00	$2.50	$6,962.50
	Unit Sub Total	**LB**		**3**	**4,422,785.00**	**$1.54**	**$6,792,162.50**
	Item Code 550203 Total No. of Proj.			**7**		**Total Amount**	**$12,917,845.50**
550204	ERECT STRUCTURAL STEEL (BRIDGE)	KG	4	1	27,840.00	$2.00	$55,680.00
		KG	7	3	1,661,500.00	$0.47	$787,976.00
	Unit Sub Total	**KG**		**4**	**1,689,340.00**	**$0.50**	**$843,656.00**
550204	ERECT STRUCTURAL STEEL (BRIDGE)	LB	4	2	4,420,000.00	$0.94	$4,170,000.00
		LB	12	1	2,785.00	$9.00	$25,065.00
	Unit Sub Total	**LB**		**3**	**4,422,785.00**	**$0.95**	**$4,195,065.00**
	Item Code 550204 Total No. of Proj.			**7**		**Total Amount**	**$5,038,721.00**
560203	FURNISH SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	LB	2	1	9,390.00	$3.85	$36,151.50
		LB	3	2	13,810.00	$4.22	$58,284.50
		LB	4	1	7,200.00	$4.00	$28,800.00
		LB	7	1	16,799.00	$4.00	$67,196.00
		LB	8	1	1,330.00	$7.00	$9,310.00
		LB	11	1	3,700.00	$4.00	$14,800.00
		LB	12	1	5,227.00	$3.50	$18,294.50
	Unit Sub Total	**LB**		**8**	**57,456.00**	**$4.05**	**$232,836.50**
	Item Code 560203 Total No. of Proj.			**8**		**Total Amount**	**$232,836.50**
560204	INSTALL SIGN STRUCTURE (BRIDGE MOUNTED WITH WALKWAY)	LB	2	1	9,390.00	$2.00	$18,780.00
		LB	3	2	13,810.00	$2.18	$30,130.25
		LB	4	1	7,200.00	$2.00	$14,400.00
		LB	7	1	16,799.00	$1.50	$25,198.50
		LB	8	1	1,330.00	$3.00	$3,990.00
		LB	11	1	3,700.00	$2.00	$7,400.00
		LB	12	1	5,227.00	$2.90	$15,158.30
	Unit Sub Total	**LB**		**8**	**57,456.00**	**$2.00**	**$115,057.05**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 560204 Total No. of Proj.			**8**		**Total Amount**	**$115,057.05**
560208	FURNISH SIGN STRUCTURE (TUBULAR)	LB	6	2	27,143.00	$3.25	$88,214.75
	Unit Sub Total	**LB**		**2**	**27,143.00**	**$3.25**	**$88,214.75**
	Item Code 560208 Total No. of Proj.			**2**		**Total Amount**	**$88,214.75**
560209	INSTALL SIGN STRUCTURE (TUBULAR)	LB	6	2	27,143.00	$0.37	$10,035.75
	Unit Sub Total	**LB**		**2**	**27,143.00**	**$0.37**	**$10,035.75**
	Item Code 560209 Total No. of Proj.			**2**		**Total Amount**	**$10,035.75**
560213	FURNISH SIGN STRUCTURE (LIGHTWEIGHT)	KG	7	1	3,880.00	$7.00	$27,160.00
		KG	11	1	79,222.00	$1.50	$118,833.00
	Unit Sub Total	**KG**		**2**	**83,102.00**	**$1.76**	**$145,993.00**
560213	FURNISH SIGN STRUCTURE (LIGHTWEIGHT)	LB	3	1	3,452.00	$5.60	$19,331.20
		LB	4	3	44,525.00	$4.17	$185,785.10
		LB	11	1	7,704.00	$4.00	$30,816.00
		LB	12	1	489.00	$8.00	$3,912.00
	Unit Sub Total	**LB**		**6**	**56,170.00**	**$4.27**	**$239,844.30**
	Item Code 560213 Total No. of Proj.			**8**		**Total Amount**	**$385,837.30**
560214	INSTALL SIGN STRUCTURE (LIGHTWEIGHT)	KG	7	1	3,880.00	$0.85	$3,298.00
		KG	11	1	79,222.00	$0.27	$21,389.94
	Unit Sub Total	**KG**		**2**	**83,102.00**	**$0.30**	**$24,687.94**
560214	INSTALL SIGN STRUCTURE (LIGHTWEIGHT)	LB	3	1	3,452.00	$1.00	$3,452.00
		LB	4	3	44,525.00	$0.48	$21,563.49
		LB	11	1	7,704.00	$1.50	$11,556.00
		LB	12	1	489.00	$4.00	$1,956.00
	Unit Sub Total	**LB**		**6**	**56,170.00**	**$0.69**	**$38,527.49**
	Item Code 560214 Total No. of Proj.			**8**		**Total Amount**	**$63,215.43**
560218	FURNISH SIGN STRUCTURE (TRUSS)	KG	4	2	104,501.00	$10.01	$1,046,365.00
		KG	7	5	827,726.00	$6.81	$5,635,525.85
		KG	11	2	80,746.00	$2.66	$214,619.90
	Unit Sub Total	**KG**		**9**	**1,012,973.00**	**$6.81**	**$6,896,510.75**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
560218	FURNISH SIGN STRUCTURE (TRUSS)	LB	2	2	210,773.00	$2.98	$627,129.00
		LB	3	4	333,381.00	$3.55	$1,183,683.95
		LB	4	2	210,830.00	$2.76	$581,047.20
		LB	5	2	71,078.00	$2.84	$202,117.00
		LB	6	2	124,340.00	$2.07	$257,380.00
		LB	7	7	153,761.00	$3.07	$472,037.05
		LB	8	3	189,223.00	$2.28	$430,594.00
		LB	10	2	125,762.00	$3.96	$498,101.20
		LB	12	6	1,427,076.00	$2.44	$3,482,990.40
	Unit Sub Total	**LB**		**30**	**2,846,224.00**	**$2.72**	**$7,735,079.80**
	Item Code 560218 Total No. of Proj.			**39**		**Total Amount**	**$14,631,590.55**
560219	INSTALL SIGN STRUCTURE (TRUSS)	KG	4	2	104,501.00	$0.64	$67,276.00
		KG	7	5	827,726.00	$0.44	$366,486.30
		KG	11	1	79,113.00	$0.09	$7,120.17
	Unit Sub Total	**KG**		**8**	**1,011,340.00**	**$0.44**	**$440,882.47**
560219	INSTALL SIGN STRUCTURE (TRUSS)	LB	2	2	210,773.00	$0.22	$45,787.60
		LB	3	4	332,786.00	$0.26	$86,919.79
		LB	4	2	210,830.00	$0.38	$80,621.00
		LB	5	2	71,078.00	$0.37	$26,610.00
		LB	6	2	124,340.00	$0.21	$26,608.00
		LB	7	7	153,761.00	$0.35	$53,675.75
		LB	8	3	189,223.00	$0.36	$67,181.75
		LB	10	2	125,762.00	$0.69	$86,288.30
		LB	12	6	1,427,076.00	$0.26	$376,401.30
	Unit Sub Total	**LB**		**30**	**2,845,629.00**	**$0.30**	**$850,093.49**
	Item Code 560219 Total No. of Proj.			**38**		**Total Amount**	**$1,290,975.96**
560232	FURNISH FORMED PANEL SIGN (ROADSIDE)	M2	4	1	1.00	$95.00	$95.00
	Unit Sub Total	**M2**		**1**	**1.00**	**$95.00**	**$95.00**
560232	FURNISH FORMED PANEL SIGN (ROADSIDE)	SQFT	5	1	19.00	$22.00	$418.00
	Unit Sub Total	**SQFT**		**1**	**19.00**	**$22.00**	**$418.00**
	Item Code 560232 Total No. of Proj.			**2**		**Total Amount**	**$513.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
560233	FURNISH FORMED PANEL SIGN (OVERHEAD)	M2	4	1	175.00	$95.00	$16,625.00
		M2	7	5	2,047.00	$115.90	$237,250.00
	Unit Sub Total	**M2**		**6**	**2,222.00**	**$114.26**	**$253,875.00**
560233	FURNISH FORMED PANEL SIGN (OVERHEAD)	SQFT	2	1	1,670.00	$22.00	$36,740.00
		SQFT	3	1	340.00	$10.50	$3,570.00
		SQFT	4	2	2,760.00	$8.78	$24,230.00
		SQFT	5	1	130.00	$13.00	$1,690.00
		SQFT	7	6	7,980.00	$8.90	$71,050.00
		SQFT	8	2	1,750.00	$10.15	$17,760.00
		SQFT	12	1	8,660.00	$8.00	$69,280.00
	Unit Sub Total	**SQFT**		**14**	**23,290.00**	**$9.63**	**$224,320.00**
	Item Code 560233 **Total No. of Proj.**			**20**		**Total Amount**	**$478,195.00**
560234	FURNISH LAMINATED PANEL SIGN (25.4 MM-TYPE A)	M2	7	1	15.00	$135.00	$2,025.00
		M2	11	2	233.00	$207.04	$48,240.00
	Unit Sub Total	**M2**		**3**	**248.00**	**$202.68**	**$50,265.00**
	Item Code 560234 **Total No. of Proj.**			**3**		**Total Amount**	**$50,265.00**
560235	FURNISH LAMINATED PANEL SIGN (25.4 MM-TYPE B)	M2	4	1	41.00	$20.00	$820.00
		M2	7	1	8.00	$150.00	$1,200.00
	Unit Sub Total	**M2**		**2**	**49.00**	**$41.22**	**$2,020.00**
	Item Code 560235 **Total No. of Proj.**			**2**		**Total Amount**	**$2,020.00**
560238	FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-UNFRAMED)	M2	2	1	3.10	$300.00	$930.00
		M2	3	1	20.00	$100.00	$2,000.00
		M2	4	2	46.00	$41.41	$1,905.00
		M2	6	2	36.40	$125.60	$4,572.00
		M2	7	4	229.40	$93.20	$21,381.00
		M2	10	1	23.00	$124.00	$2,852.00
		M2	11	2	132.00	$150.67	$19,888.00
	Unit Sub Total	**M2**		**13**	**489.90**	**$109.26**	**$53,528.00**
	Item Code 560238 **Total No. of Proj.**			**13**		**Total Amount**	**$53,528.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
560239	FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-UNFRAMED)	M2	3	1	15.00	$120.00	$1,800.00
		M2	4	2	39.00	$21.92	$855.00
		M2	6	1	24.00	$140.00	$3,360.00
		M2	7	4	184.00	$94.11	$17,317.00
		M2	10	1	9.00	$161.00	$1,449.00
		M2	11	3	126.00	$146.40	$18,447.00
	Unit Sub Total	**M2**		**12**	**397.00**	**$108.89**	**$43,228.00**
	Item Code 560239 Total No. of Proj.			**12**		**Total Amount**	**$43,228.00**
560241	FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-FRAMED)	M2	3	1	1.50	$140.00	$210.00
		M2	4	2	13.00	$105.00	$1,365.00
		M2	7	2	41.00	$120.39	$4,936.00
		M2	10	1	8.00	$173.00	$1,384.00
		M2	11	1	17.00	$170.00	$2,890.00
	Unit Sub Total	**M2**		**7**	**80.50**	**$133.98**	**$10,785.00**
	Item Code 560241 Total No. of Proj.			**7**		**Total Amount**	**$10,785.00**
560242	FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-FRAMED)	M2	3	1	6.00	$150.00	$900.00
		M2	4	1	2.00	$30.00	$60.00
		M2	7	1	5.00	$140.00	$700.00
		M2	11	2	80.00	$240.33	$19,226.00
	Unit Sub Total	**M2**		**5**	**93.00**	**$224.58**	**$20,886.00**
	Item Code 560242 Total No. of Proj.			**5**		**Total Amount**	**$20,886.00**
560244	FURNISH LAMINATED PANEL SIGN (1"-TYPE A)	SQFT	3	4	4,715.00	$11.84	$55,806.00
		SQFT	5	1	330.00	$20.70	$6,831.00
		SQFT	6	3	1,760.00	$20.18	$35,510.00
		SQFT	7	1	300.00	$14.00	$4,200.00
		SQFT	8	1	200.00	$15.00	$3,000.00
		SQFT	10	1	520.00	$18.87	$9,812.40
		SQFT	11	1	310.00	$20.00	$6,200.00
		SQFT	12	7	10,860.00	$14.35	$155,803.50
	Unit Sub Total	**SQFT**		**19**	**18,995.00**	**$14.59**	**$277,162.90**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 560244 Total No. of Proj.			**19**		**Total Amount**	**$277,162.90**
560245	FURNISH LAMINATED PANEL SIGN (1"-TYPE B)	SQFT	3	1	150.00	$10.00	$1,500.00
		SQFT	4	1	56.00	$50.00	$2,800.00
		SQFT	5	1	95.00	$18.00	$1,710.00
		SQFT	8	1	65.00	$15.00	$975.00
		SQFT	11	1	120.00	$25.00	$3,000.00
		SQFT	12	3	383.00	$15.56	$5,958.00
	Unit Sub Total	**SQFT**		**8**	**869.00**	**$18.35**	**$15,943.00**
	Item Code 560245 Total No. of Proj.			**8**		**Total Amount**	**$15,943.00**
560246	FURNISH LAMINATED PANEL SIGN (2 1/2"-TYPE B)	SQFT	5	1	170.00	$20.00	$3,400.00
		SQFT	12	2	570.00	$19.66	$11,207.50
	Unit Sub Total	**SQFT**		**3**	**740.00**	**$19.74**	**$14,607.50**
	Item Code 560246 Total No. of Proj.			**3**		**Total Amount**	**$14,607.50**
560247	FURNISH LAMINATED PANEL SIGN (2 1/2"-TYPE H)	SQFT	8	1	140.00	$16.00	$2,240.00
		SQFT	11	1	160.00	$32.00	$5,120.00
	Unit Sub Total	**SQFT**		**2**	**300.00**	**$24.53**	**$7,360.00**
	Item Code 560247 Total No. of Proj.			**2**		**Total Amount**	**$7,360.00**
560248	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-UNFRAMED)	SQFT	2	14	654.00	$20.44	$13,368.92
		SQFT	3	6	1,552.00	$11.40	$17,699.00
		SQFT	4	18	4,528.00	$9.89	$44,796.00
		SQFT	5	3	1,130.00	$10.68	$12,070.00
		SQFT	6	10	444.00	$26.20	$11,632.00
		SQFT	7	4	259.00	$11.13	$2,882.00
		SQFT	8	5	283.00	$14.22	$4,025.00
		SQFT	9	6	279.00	$16.47	$4,594.00
		SQFT	10	6	816.00	$9.59	$7,828.90
		SQFT	11	9	977.00	$13.98	$13,662.00
		SQFT	12	15	3,662.20	$9.04	$33,117.60
	Unit Sub Total	**SQFT**		**96**	**14,584.20**	**$11.36**	**$165,675.42**
	Item Code 560248 Total No. of Proj.			**96**		**Total Amount**	**$165,675.42**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
560249	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-UNFRAMED)	SQFT	2	4	85.00	$29.40	$2,499.00
		SQFT	3	7	1,781.50	$11.32	$20,166.48
		SQFT	4	6	810.00	$10.58	$8,570.00
		SQFT	5	5	1,508.00	$11.24	$16,957.30
		SQFT	6	4	708.00	$15.48	$10,962.00
		SQFT	8	5	350.00	$9.30	$3,254.00
		SQFT	9	3	219.00	$13.01	$2,848.50
		SQFT	10	4	125.00	$12.11	$1,514.00
		SQFT	11	4	527.00	$12.69	$6,687.50
		SQFT	12	10	2,805.00	$9.27	$26,008.46
	Unit Sub Total	**SQFT**		**52**	**8,918.50**	**$11.15**	**$99,467.24**
	Item Code 560249 Total No. of Proj.			**52**		**Total Amount**	**$99,467.24**
560251	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-FRAMED)	SQFT	2	5	277.00	$22.34	$6,188.92
		SQFT	3	2	142.00	$10.39	$1,475.00
		SQFT	4	5	235.00	$13.15	$3,090.50
		SQFT	5	2	269.00	$12.42	$3,341.85
		SQFT	6	1	21.00	$12.00	$252.00
		SQFT	8	1	66.00	$10.00	$660.00
		SQFT	10	4	164.00	$12.91	$2,117.20
		SQFT	11	1	15.00	$16.00	$240.00
		SQFT	12	8	666.00	$11.92	$7,939.78
	Unit Sub Total	**SQFT**		**29**	**1,855.00**	**$13.64**	**$25,305.25**
	Item Code 560251 Total No. of Proj.			**29**		**Total Amount**	**$25,305.25**
560252	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-FRAMED)	SQFT	2	6	850.00	$23.18	$19,706.00
		SQFT	3	5	907.00	$12.76	$11,572.00
		SQFT	4	5	586.00	$12.76	$7,475.50
		SQFT	5	3	259.00	$16.12	$4,175.50
		SQFT	6	1	380.00	$18.00	$6,840.00
		SQFT	9	1	22.00	$36.00	$792.00
		SQFT	10	1	150.00	$13.00	$1,950.00
		SQFT	11	2	400.00	$16.31	$6,522.50
		SQFT	12	8	1,703.00	$14.96	$25,484.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**SQFT**		**32**	**5,257.00**	**$16.08**	**$84,517.50**
	Item Code 560252 Total No. of Proj.			**32**		**Total Amount**	**$84,517.50**
561004	30" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	12	1	10.00	$900.00	$9,000.00
	Unit Sub Total	**LF**		**1**	**10.00**	**$900.00**	**$9,000.00**
	Item Code 561004 Total No. of Proj.			**1**		**Total Amount**	**$9,000.00**
561005	36" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	3	1	15.00	$710.00	$10,650.00
		LF	4	3	175.00	$359.00	$62,825.00
		LF	11	1	30.00	$500.00	$15,000.00
	Unit Sub Total	**LF**		**5**	**220.00**	**$402.16**	**$88,475.00**
	Item Code 561005 Total No. of Proj.			**5**		**Total Amount**	**$88,475.00**
561009	920 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	M	11	1	34.00	$1,100.00	$37,400.00
	Unit Sub Total	**M**		**1**	**34.00**	**$1,100.00**	**$37,400.00**
	Item Code 561009 Total No. of Proj.			**1**		**Total Amount**	**$37,400.00**
561012	1220 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	M	10	1	6.00	$450.00	$2,700.00
	Unit Sub Total	**M**		**1**	**6.00**	**$450.00**	**$2,700.00**
	Item Code 561012 Total No. of Proj.			**1**		**Total Amount**	**$2,700.00**
561013	1372 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	M	7	3	96.00	$1,990.10	$191,050.00
	Unit Sub Total	**M**		**3**	**96.00**	**$1,990.10**	**$191,050.00**
	Item Code 561013 Total No. of Proj.			**3**		**Total Amount**	**$191,050.00**
561014	54" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	2	1	210.00	$495.00	$103,950.00
		LF	3	3	285.00	$1,642.77	$468,190.00
		LF	6	1	120.00	$500.00	$60,000.00
		LF	10	1	38.00	$520.20	$19,767.60
		LF	12	1	140.00	$450.00	$63,000.00
	Unit Sub Total	**LF**		**7**	**793.00**	**$901.52**	**$714,907.60**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 561014 Total No. of Proj.			**7**		**Total Amount**	**$714,907.60**
561015	1524 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	M	4	1	59.00	$3,200.00	$188,800.00
		M	7	5	553.80	$2,061.55	$1,141,684.80
		M	11	1	23.00	$2,000.00	$46,000.00
	Unit Sub Total	**M**		**7**	**635.80**	**$2,164.97**	**$1,376,484.80**
	Item Code 561015 Total No. of Proj.			**7**		**Total Amount**	**$1,376,484.80**
561016	60" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	2	2	158.00	$652.15	$103,040.00
		LF	3	3	418.00	$1,843.20	$770,458.00
		LF	4	3	323.00	$843.82	$272,553.00
		LF	5	2	110.00	$542.00	$59,620.00
		LF	6	3	175.00	$571.89	$100,080.00
		LF	7	7	284.00	$689.08	$195,700.00
		LF	8	3	232.00	$617.24	$143,200.00
		LF	10	2	194.00	$633.20	$122,840.00
		LF	12	5	1,316.00	$692.93	$911,900.00
	Unit Sub Total	**LF**		**30**	**3,210.00**	**$834.70**	**$2,679,391.00**
	Item Code 561016 Total No. of Proj.			**30**		**Total Amount**	**$2,679,391.00**
562001	METAL (ROADSIDE SIGN)	LB	4	1	16.00	$15.00	$240.00
		LB	7	1	75.00	$6.00	$450.00
	Unit Sub Total	**LB**		**2**	**91.00**	**$7.58**	**$690.00**
	Item Code 562001 Total No. of Proj.			**2**		**Total Amount**	**$690.00**
562002	METAL (BARRIER MOUNTED SIGN)	EA	6	2	8.00	$1,105.00	$8,840.00
	Unit Sub Total	**EA**		**2**	**8.00**	**$1,105.00**	**$8,840.00**
562002	METAL (BARRIER MOUNTED SIGN)	KG	4	2	3,197.00	$22.50	$71,940.00
		KG	7	3	7,290.00	$6.82	$49,750.00
		KG	10	1	165.00	$20.00	$3,300.00
		KG	11	1	290.00	$19.00	$5,510.00
	Unit Sub Total	**KG**		**7**	**10,942.00**	**$11.93**	**$130,500.00**
562002	METAL (BARRIER MOUNTED SIGN)	LB	4	2	5,540.00	$10.39	$57,565.50
		LB	12	1	850.00	$8.00	$6,800.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LB**		**3**	**6,390.00**	**$10.07**	**$64,365.50**
	Item Code 562002	**Total No. of Proj.**			**12**		**Total Amount**	**$203,705.50**
562004	METAL (RAIL MOUNTED SIGN)		KG	4	1	3,300.00	$13.00	$42,900.00
			KG	11	1	160.00	$39.60	$6,336.00
		Unit Sub Total	**KG**		**2**	**3,460.00**	**$14.23**	**$49,236.00**
562004	METAL (RAIL MOUNTED SIGN)		LB	4	1	590.00	$2.20	$1,298.00
			LB	6	1	610.00	$10.00	$6,100.00
			LB	10	1	4,770.00	$8.16	$38,923.20
			LB	12	3	5,130.00	$11.75	$60,300.00
		Unit Sub Total	**LB**		**6**	**11,100.00**	**$9.61**	**$106,621.20**
	Item Code 562004	**Total No. of Proj.**			**8**		**Total Amount**	**$155,857.20**
562007	ROADSIDE SIGN (METAL POST)		EA	7	1	3.00	$200.00	$600.00
		Unit Sub Total	**EA**		**1**	**3.00**	**$200.00**	**$600.00**
	Item Code 562007	**Total No. of Proj.**			**1**		**Total Amount**	**$600.00**
566011	ROADSIDE SIGN - ONE POST		EA	1	2	21.00	$311.90	$6,550.00
			EA	2	16	109.00	$301.61	$32,875.00
			EA	3	8	216.00	$186.46	$40,275.00
			EA	4	21	304.00	$228.85	$69,571.80
			EA	5	6	197.00	$240.76	$47,430.00
			EA	6	11	104.00	$280.08	$29,128.00
			EA	7	5	318.00	$336.60	$107,040.00
			EA	8	7	44.00	$306.64	$13,492.00
			EA	9	7	49.00	$211.84	$10,380.00
			EA	10	7	105.00	$164.71	$17,294.40
			EA	11	11	249.00	$518.45	$129,095.00
			EA	12	12	283.00	$336.76	$95,303.04
		Unit Sub Total	**EA**		**113**	**1,999.00**	**$299.37**	**$598,434.24**
	Item Code 566011	**Total No. of Proj.**			**113**		**Total Amount**	**$598,434.24**
566012	ROADSIDE SIGN - TWO POST		EA	2	7	44.00	$461.36	$20,300.00
			EA	3	6	39.00	$407.44	$15,890.00
			EA	4	5	42.00	$365.24	$15,340.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
566012	ROADSIDE SIGN - TWO POST	EA	5	1	10.00	$365.00	$3,650.00
		EA	6	3	14.00	$340.43	$4,766.00
		EA	7	4	7.00	$742.86	$5,200.00
		EA	8	1	4.00	$500.00	$2,000.00
		EA	9	1	4.00	$260.00	$1,040.00
		EA	10	5	20.00	$337.70	$6,754.00
		EA	11	4	33.00	$818.03	$26,995.00
		EA	12	8	70.00	$966.98	$67,688.71
	Unit Sub Total	**EA**		**45**	**287.00**	**$591.02**	**$169,623.71**
	Item Code 566012 Total No. of Proj.			**45**		**Total Amount**	**$169,623.71**
568001	INSTALL SIGN (STRAP AND SADDLE BRACKET METHOD)	EA	2	1	6.00	$310.00	$1,860.00
		EA	3	5	58.00	$88.09	$5,109.00
		EA	4	11	203.00	$109.85	$22,300.00
		EA	7	7	101.00	$163.46	$16,509.00
		EA	8	1	10.00	$100.00	$1,000.00
		EA	11	8	134.00	$103.02	$13,804.40
		EA	12	8	109.00	$151.39	$16,501.68
	Unit Sub Total	**EA**		**41**	**621.00**	**$124.13**	**$77,084.08**
	Item Code 568001 Total No. of Proj.			**41**		**Total Amount**	**$77,084.08**
568007	INSTALL SIGN OVERLAY	M2	4	1	3.00	$25.00	$75.00
	Unit Sub Total	**M2**		**1**	**3.00**	**$25.00**	**$75.00**
568007	INSTALL SIGN OVERLAY	SQFT	4	1	24.00	$15.00	$360.00
		SQFT	7	1	200.00	$5.00	$1,000.00
	Unit Sub Total	**SQFT**		**2**	**224.00**	**$6.07**	**$1,360.00**
	Item Code 568007 Total No. of Proj.			**3**		**Total Amount**	**$1,435.00**
568015	INSTALL SIGN (MAST-ARM HANGER METHOD)	EA	11	1	3.00	$214.00	$642.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$214.00**	**$642.00**
	Item Code 568015 Total No. of Proj.			**1**		**Total Amount**	**$642.00**
568016	INSTALL SIGN PANEL ON EXISTING FRAME	EA	5	1	3.00	$1,750.00	$5,250.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$1,750.00**	**$5,250.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
568016	INSTALL SIGN PANEL ON EXISTING FRAME	M2	4	1	16.00	$25.00	$400.00
		M2	7	2	50.00	$100.00	$5,000.00
	Unit Sub Total	**M2**		**3**	**66.00**	**$81.82**	**$5,400.00**
568016	INSTALL SIGN PANEL ON EXISTING FRAME	SQFT	3	2	640.00	$8.86	$5,670.00
		SQFT	4	1	200.00	$300.00	$60,000.00
		SQFT	7	1	5,880.00	$7.00	$41,160.00
		SQFT	12	3	1,000.00	$14.33	$14,333.00
	Unit Sub Total	**SQFT**		**7**	**7,720.00**	**$15.69**	**$121,163.00**
	Item Code 568016 Total No. of Proj.			**11**		**Total Amount**	**$131,813.00**
568017	INSTALL ROADSIDE SIGN PANEL ON EXISTING POST	EA	3	1	13.00	$175.00	$2,275.00
		EA	4	3	54.00	$104.95	$5,667.40
		EA	6	1	4.00	$82.00	$328.00
		EA	8	1	1.00	$75.00	$75.00
		EA	10	1	2.00	$75.00	$150.00
		EA	11	3	24.00	$169.79	$4,075.00
		EA	12	6	77.00	$109.65	$8,443.20
	Unit Sub Total	**EA**		**16**	**175.00**	**$120.08**	**$21,013.60**
568017	INSTALL ROADSIDE SIGN PANEL ON EXISTING POST	M2	11	1	2.00	$195.00	$390.00
	Unit Sub Total	**M2**		**1**	**2.00**	**$195.00**	**$390.00**
	Item Code 568017 Total No. of Proj.			**17**		**Total Amount**	**$21,403.60**
568020	INSTALL SIGN PANEL ON EXISTING STRUCTURE	SQFT	8	1	405.00	$10.00	$4,050.00
	Unit Sub Total	**SQFT**		**1**	**405.00**	**$10.00**	**$4,050.00**
	Item Code 568020 Total No. of Proj.			**1**		**Total Amount**	**$4,050.00**
568023	INSTALL ROADSIDE SIGN (LAMINATED WOOD BOX POST)	EA	2	1	2.00	$5,000.00	$10,000.00
		EA	5	1	1.00	$5,000.00	$5,000.00
		EA	7	1	1.00	$2,600.00	$2,600.00
		EA	8	2	3.00	$1,133.33	$3,400.00
		EA	10	1	3.00	$765.00	$2,295.00
		EA	12	3	9.00	$3,577.78	$32,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**9**	**19.00**	**$2,920.79**	**$55,495.00**
	Item Code 568023	**Total No. of Proj.**			**9**		**Total Amount**	**$55,495.00**
570115	ABUTMENT LUMBER BLOCKING		M3	7	1	3.00	$3,915.00	$11,745.00
		Unit Sub Total	**M3**		**1**	**3.00**	**$3,915.00**	**$11,745.00**
570115	ABUTMENT LUMBER BLOCKING		MFBM	11	1	0.30	$65,000.00	$19,500.00
		Unit Sub Total	**MFBM**		**1**	**0.30**	**$65,000.00**	**$19,500.00**
	Item Code 570115	**Total No. of Proj.**			**2**		**Total Amount**	**$31,245.00**
575004	TIMBER LAGGING		MFBM	1	4	141.20	$2,713.95	$383,210.00
			MFBM	4	3	206.00	$2,038.83	$420,000.00
			MFBM	5	2	151.00	$3,415.89	$515,800.00
			MFBM	12	1	5.00	$2,800.00	$14,000.00
		Unit Sub Total	**MFBM**		**10**	**503.20**	**$2,649.07**	**$1,333,010.00**
	Item Code 575004	**Total No. of Proj.**			**10**		**Total Amount**	**$1,333,010.00**
590106	CLEAN STRUCTURAL STEEL (EXISTING BRIDGE)		LS	1	2	2.00	$275,606.00	$551,212.00
			LS	5	1	1.00	$466,400.00	$466,400.00
			LS	7	1	1.00	$210,000.00	$210,000.00
			LS	8	1	1.00	$6,500.00	$6,500.00
			LS	10	1	1.00	$51,612.00	$51,612.00
			LS	11	1	1.00	$600,200.00	$600,200.00
		Unit Sub Total	**LS**		**7**	**7.00**	**$269,417.71**	**$1,885,924.00**
	Item Code 590106	**Total No. of Proj.**			**7**		**Total Amount**	**$1,885,924.00**
590111	PAINT STRUCTURAL STEEL (EXISTING BRIDGE)		LS	1	2	2.00	$321,718.50	$643,437.00
			LS	5	1	1.00	$551,688.50	$551,688.50
			LS	7	1	1.00	$310,000.00	$310,000.00
			LS	8	1	1.00	$14,000.00	$14,000.00
			LS	10	1	1.00	$227,660.00	$227,660.00
			LS	11	1	1.00	$225,000.00	$225,000.00
		Unit Sub Total	**LS**		**7**	**7.00**	**$281,683.64**	**$1,971,785.50**
	Item Code 590111	**Total No. of Proj.**			**7**		**Total Amount**	**$1,971,785.50**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
590115	CLEAN AND PAINT STRUCTURAL STEEL	LS	2	1	1.00	$9,000.00	$9,000.00
		LS	4	3	3.00	$416,666.67	$1,250,000.00
		LS	7	4	4.00	$295,263.75	$1,181,055.00
		LS	10	1	1.00	$23,000.00	$23,000.00
		LS	11	1	1.00	$25,000.00	$25,000.00
		LS	12	2	2.00	$17,308.50	$34,617.00
	Unit Sub Total	**LS**		**12**	**12.00**	**$210,222.67**	**$2,522,672.00**
	Item Code 590115 Total No. of Proj.			**12**		**Total Amount**	**$2,522,672.00**
590116	CLEAN AND PAINT STRUCTURAL STEEL (EXISTING BRIDGE)	LS	2	2	2.00	$1,890,979.00	$3,781,958.00
		LS	7	1	1.00	$505,000.00	$505,000.00
		LS	12	1	1.00	$169,046.50	$169,046.50
	Unit Sub Total	**LS**		**4**	**4.00**	**$1,114,001.13**	**$4,456,004.50**
	Item Code 590116 Total No. of Proj.			**4**		**Total Amount**	**$4,456,004.50**
590135	SPOT BLAST CLEAN AND PAINT UNDERCOAT	M2	7	2	55.00	$1,331.65	$73,241.00
	Unit Sub Total	**M2**		**2**	**55.00**	**$1,331.65**	**$73,241.00**
590135	SPOT BLAST CLEAN AND PAINT UNDERCOAT	SQFT	1	2	17,525.00	$13.26	$232,455.00
		SQFT	2	2	6,051.00	$21.05	$127,400.00
		SQFT	4	2	6,490.00	$89.83	$583,000.00
		SQFT	5	1	16,500.00	$23.88	$394,020.00
		SQFT	7	1	4,800.00	$76.00	$364,800.00
		SQFT	8	1	1,800.00	$14.70	$26,460.00
		SQFT	10	1	2,130.00	$23.50	$50,055.00
		SQFT	11	2	5,210.00	$15.24	$79,400.00
	Unit Sub Total	**SQFT**		**12**	**60,506.00**	**$30.70**	**$1,857,590.00**
	Item Code 590135 Total No. of Proj.			**14**		**Total Amount**	**$1,930,831.00**
590229	CLEAN AND PAINT BRIDGE RAILING	LS	4	1	1.00	$1,000.00	$1,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$1,000.00**	**$1,000.00**
	Item Code 590229 Total No. of Proj.			**1**		**Total Amount**	**$1,000.00**
590301	WORK AREA MONITORING	LS	1	2	2.00	$9,460.00	$18,920.00
		LS	2	2	2.00	$12,500.00	$25,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
590301	WORK AREA MONITORING	LS	3	1	1.00	$1,000.00	$1,000.00
		LS	4	1	1.00	$30,000.00	$30,000.00
		LS	6	1	1.00	$1,000.00	$1,000.00
		LS	7	4	4.00	$34,468.75	$137,875.00
		LS	8	1	1.00	$12,000.00	$12,000.00
		LS	10	2	2.00	$4,696.50	$9,393.00
		LS	11	2	2.00	$10,000.00	$20,000.00
		LS	12	2	2.00	$6,940.00	$13,880.00
	Unit Sub Total	**LS**		**18**	**18.00**	**$14,948.22**	**$269,068.00**
	Item Code 590301 Total No. of Proj.			**18**		**Total Amount**	**$269,068.00**
597401	PAINT CURB (2-COAT)	LF	1	1	5,320.00	$4.60	$24,472.00
		LF	2	2	266.00	$3.52	$936.00
	Unit Sub Total	**LF**		**3**	**5,586.00**	**$4.55**	**$25,408.00**
597401	PAINT CURB (2-COAT)	SQFT	7	1	160.00	$3.00	$480.00
	Unit Sub Total	**SQFT**		**1**	**160.00**	**$3.00**	**$480.00**
	Item Code 597401 Total No. of Proj.			**4**		**Total Amount**	**$25,888.00**
597600	PREPARE AND PAINT CONCRETE	SQFT	4	1	470.00	$2.00	$940.00
		SQFT	6	1	12,900.00	$1.20	$15,480.00
		SQFT	12	1	2,500.00	$2.00	$5,000.00
	Unit Sub Total	**SQFT**		**3**	**15,870.00**	**$1.35**	**$21,420.00**
	Item Code 597600 Total No. of Proj.			**3**		**Total Amount**	**$21,420.00**
597601	PREPARE AND STAIN CONCRETE	M2	2	1	239.00	$50.00	$11,950.00
		M2	3	1	2,618.00	$10.00	$26,180.00
		M2	4	2	3,257.00	$14.30	$46,564.00
		M2	10	1	4,620.00	$37.00	$170,940.00
	Unit Sub Total	**M2**		**5**	**10,734.00**	**$23.82**	**$255,634.00**
597601	PREPARE AND STAIN CONCRETE	SQFT	6	1	135,000.00	$0.90	$121,500.00
		SQFT	8	1	27,000.00	$1.25	$33,750.00
		SQFT	12	1	1,017.00	$2.40	$2,440.80
	Unit Sub Total	**SQFT**		**3**	**163,017.00**	**$0.97**	**$157,690.80**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 597601 Total No. of Proj.			**8**		**Total Amount**	**$413,324.80**
610001	FIELD LEAKAGE TESTING	LF	12	1	1,650.00	$20.00	$33,000.00
	Unit Sub Total	**LF**		**1**	**1,650.00**	**$20.00**	**$33,000.00**
	Item Code 610001 Total No. of Proj.			**1**		**Total Amount**	**$33,000.00**
620020	8" ALTERNATIVE PIPE CULVERT	LF	4	1	2.00	$350.00	$700.00
	Unit Sub Total	**LF**		**1**	**2.00**	**$350.00**	**$700.00**
	Item Code 620020 Total No. of Proj.			**1**		**Total Amount**	**$700.00**
620060	12" ALTERNATIVE PIPE CULVERT	LF	2	1	260.00	$45.00	$11,700.00
		LF	3	1	25.00	$37.84	$946.00
		LF	4	4	581.00	$64.83	$37,664.00
	Unit Sub Total	**LF**		**6**	**866.00**	**$58.09**	**$50,310.00**
	Item Code 620060 Total No. of Proj.			**6**		**Total Amount**	**$50,310.00**
620061	12" ALTERNATIVE PIPE CULVERT (TYPE A)	LF	4	1	320.00	$43.00	$13,760.00
	Unit Sub Total	**LF**		**1**	**320.00**	**$43.00**	**$13,760.00**
	Item Code 620061 Total No. of Proj.			**1**		**Total Amount**	**$13,760.00**
620062	12" ALTERNATIVE PIPE CULVERT (TYPE B)	LF	4	1	240.00	$42.00	$10,080.00
	Unit Sub Total	**LF**		**1**	**240.00**	**$42.00**	**$10,080.00**
	Item Code 620062 Total No. of Proj.			**1**		**Total Amount**	**$10,080.00**
620080	15" ALTERNATIVE PIPE CULVERT	LF	3	1	1,110.00	$44.80	$49,728.00
		LF	4	1	660.00	$70.00	$46,200.00
	Unit Sub Total	**LF**		**2**	**1,770.00**	**$54.20**	**$95,928.00**
	Item Code 620080 Total No. of Proj.			**2**		**Total Amount**	**$95,928.00**
620100	18" ALTERNATIVE PIPE CULVERT	LF	1	1	31.00	$222.00	$6,882.00
		LF	2	1	600.00	$215.00	$129,000.00
		LF	3	1	2,400.00	$53.00	$127,200.00
		LF	4	6	16,608.00	$40.00	$664,274.50
		LF	5	4	1,627.80	$98.32	$160,044.40
		LF	6	1	340.00	$135.00	$45,900.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
620100	18" ALTERNATIVE PIPE CULVERT	LF	10	1	1,020.00	$56.85	$57,987.00
		LF	11	1	410.00	$96.00	$39,360.00
		LF	12	3	4,610.00	$51.91	$239,300.00
	Unit Sub Total	**LF**		**19**	**27,646.80**	**$53.17**	**$1,469,947.90**
	Item Code 620100 Total No. of Proj.			**19**		**Total Amount**	**$1,469,947.90**
620101	18" ALTERNATIVE PIPE CULVERT (TYPE A)	LF	4	2	495.00	$61.44	$30,415.00
	Unit Sub Total	**LF**		**2**	**495.00**	**$61.44**	**$30,415.00**
	Item Code 620101 Total No. of Proj.			**2**		**Total Amount**	**$30,415.00**
620102	18" ALTERNATIVE PIPE CULVERT (TYPE B)	LF	4	2	4,950.00	$65.64	$324,900.00
	Unit Sub Total	**LF**		**2**	**4,950.00**	**$65.64**	**$324,900.00**
	Item Code 620102 Total No. of Proj.			**2**		**Total Amount**	**$324,900.00**
620140	24" ALTERNATIVE PIPE CULVERT	LF	1	6	972.00	$148.05	$143,900.00
		LF	2	2	1,220.00	$63.64	$77,643.20
		LF	3	1	280.00	$99.00	$27,720.00
		LF	4	3	3,560.00	$59.10	$210,400.00
		LF	5	5	9,963.00	$68.95	$686,998.00
		LF	6	2	3,160.00	$53.91	$170,340.00
		LF	11	1	2,130.00	$66.00	$140,580.00
		LF	12	3	14,080.00	$60.66	$854,050.00
	Unit Sub Total	**LF**		**23**	**35,365.00**	**$65.36**	**$2,311,631.20**
	Item Code 620140 Total No. of Proj.			**23**		**Total Amount**	**$2,311,631.20**
620180	30" ALTERNATIVE PIPE CULVERT	LF	1	1	160.00	$115.00	$18,400.00
		LF	4	1	460.00	$75.00	$34,500.00
		LF	5	1	960.00	$110.00	$105,600.00
		LF	12	1	170.00	$95.00	$16,150.00
	Unit Sub Total	**LF**		**4**	**1,750.00**	**$99.80**	**$174,650.00**
	Item Code 620180 Total No. of Proj.			**4**		**Total Amount**	**$174,650.00**
620220	36" ALTERNATIVE PIPE CULVERT	LF	2	1	44.00	$110.00	$4,840.00
		LF	3	1	176.00	$255.00	$44,880.00
		LF	4	3	2,866.00	$84.40	$241,880.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
620220	36" ALTERNATIVE PIPE CULVERT	LF	5	1	460.00	$97.00	$44,620.00
		LF	12	2	6,380.00	$71.02	$453,100.00
	Unit Sub Total	**LF**		**8**	**9,926.00**	**$79.52**	**$789,320.00**
	Item Code 620220 Total No. of Proj.			**8**		**Total Amount**	**$789,320.00**
620260	42" ALTERNATIVE PIPE CULVERT	LF	4	1	280.00	$250.00	$70,000.00
	Unit Sub Total	**LF**		**1**	**280.00**	**$250.00**	**$70,000.00**
	Item Code 620260 Total No. of Proj.			**1**		**Total Amount**	**$70,000.00**
620300	48" ALTERNATIVE PIPE CULVERT	LF	2	1	460.00	$95.00	$43,700.00
		LF	4	1	1,180.00	$100.00	$118,000.00
		LF	5	1	2,460.00	$94.00	$231,240.00
		LF	12	1	91.00	$160.00	$14,560.00
	Unit Sub Total	**LF**		**4**	**4,191.00**	**$97.23**	**$407,500.00**
	Item Code 620300 Total No. of Proj.			**4**		**Total Amount**	**$407,500.00**
620380	60" ALTERNATIVE PIPE CULVERT	LF	5	1	28.00	$204.00	$5,712.00
	Unit Sub Total	**LF**		**1**	**28.00**	**$204.00**	**$5,712.00**
	Item Code 620380 Total No. of Proj.			**1**		**Total Amount**	**$5,712.00**
620715	18" ALTERNATIVE SLOTTED PIPE	LF	4	1	230.00	$100.00	$23,000.00
		LF	8	1	1,600.00	$61.00	$97,600.00
	Unit Sub Total	**LF**		**2**	**1,830.00**	**$65.90**	**$120,600.00**
	Item Code 620715 Total No. of Proj.			**2**		**Total Amount**	**$120,600.00**
620902	200 MM ALTERNATIVE PIPE CULVERT	M	11	1	48.00	$170.00	$8,160.00
	Unit Sub Total	**M**		**1**	**48.00**	**$170.00**	**$8,160.00**
	Item Code 620902 Total No. of Proj.			**1**		**Total Amount**	**$8,160.00**
620904	300 MM ALTERNATIVE PIPE CULVERT	M	3	1	340.00	$225.00	$76,500.00
		M	4	2	198.00	$201.84	$39,964.00
		M	11	1	220.00	$175.00	$38,500.00
	Unit Sub Total	**M**		**4**	**758.00**	**$204.44**	**$154,964.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 620904 Total No. of Proj.			**4**		**Total Amount**	**$154,964.00**
620908	375 MM ALTERNATIVE PIPE CULVERT	M	3	1	190.00	$250.00	$47,500.00
	Unit Sub Total	**M**		**1**	**190.00**	**$250.00**	**$47,500.00**
	Item Code 620908 Total No. of Proj.			**1**		**Total Amount**	**$47,500.00**
620909	450 MM ALTERNATIVE PIPE CULVERT	M	4	2	690.00	$243.48	$168,000.00
		M	6	1	1,090.00	$155.00	$168,950.00
		M	10	1	47.00	$160.00	$7,520.00
		M	11	2	1,562.00	$142.54	$222,640.00
	Unit Sub Total	**M**		**6**	**3,389.00**	**$167.34**	**$567,110.00**
	Item Code 620909 Total No. of Proj.			**6**		**Total Amount**	**$567,110.00**
620910	450 MM ALTERNATIVE PIPE CULVERT (TYPE A)	M	3	1	320.00	$350.00	$112,000.00
		M	4	1	3,420.00	$132.00	$451,440.00
	Unit Sub Total	**M**		**2**	**3,740.00**	**$150.65**	**$563,440.00**
	Item Code 620910 Total No. of Proj.			**2**		**Total Amount**	**$563,440.00**
620911	450 MM ALTERNATIVE PIPE CULVERT (TYPE B)	M	3	1	53.00	$400.00	$21,200.00
		M	4	1	330.00	$148.00	$48,840.00
	Unit Sub Total	**M**		**2**	**383.00**	**$182.87**	**$70,040.00**
	Item Code 620911 Total No. of Proj.			**2**		**Total Amount**	**$70,040.00**
620913	600 MM ALTERNATIVE PIPE CULVERT	M	4	2	118.00	$292.37	$34,500.00
		M	6	1	690.00	$175.00	$120,750.00
		M	10	1	580.00	$155.00	$89,900.00
		M	11	2	1,180.00	$214.83	$253,500.00
	Unit Sub Total	**M**		**6**	**2,568.00**	**$194.18**	**$498,650.00**
	Item Code 620913 Total No. of Proj.			**6**		**Total Amount**	**$498,650.00**
620914	600 MM ALTERNATIVE PIPE CULVERT (TYPE A)	M	4	1	430.00	$160.00	$68,800.00
	Unit Sub Total	**M**		**1**	**430.00**	**$160.00**	**$68,800.00**
	Item Code 620914 Total No. of Proj.			**1**		**Total Amount**	**$68,800.00**
620915	600 MM ALTERNATIVE PIPE CULVERT (TYPE B)	M	4	1	210.00	$160.00	$33,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**1**	**210.00**	**$160.00**	**$33,600.00**
	Item Code 620915 Total No. of Proj.			**1**		**Total Amount**	**$33,600.00**
620919	750 MM ALTERNATIVE PIPE CULVERT	M	4	1	115.00	$210.00	$24,150.00
	Unit Sub Total	**M**		**1**	**115.00**	**$210.00**	**$24,150.00**
	Item Code 620919 Total No. of Proj.			**1**		**Total Amount**	**$24,150.00**
620924	900 MM ALTERNATIVE PIPE CULVERT	M	4	1	27.00	$300.00	$8,100.00
		M	6	1	870.00	$215.00	$187,050.00
		M	11	1	70.00	$295.00	$20,650.00
	Unit Sub Total	**M**		**3**	**967.00**	**$223.16**	**$215,800.00**
	Item Code 620924 Total No. of Proj.			**3**		**Total Amount**	**$215,800.00**
620930	1050 MM ALTERNATIVE PIPE CULVERT	M	4	1	140.00	$310.00	$43,400.00
	Unit Sub Total	**M**		**1**	**140.00**	**$310.00**	**$43,400.00**
	Item Code 620930 Total No. of Proj.			**1**		**Total Amount**	**$43,400.00**
620933	1200 MM ALTERNATIVE PIPE CULVERT	M	4	1	75.00	$525.00	$39,375.00
		M	6	1	200.00	$275.00	$55,000.00
	Unit Sub Total	**M**		**2**	**275.00**	**$343.18**	**$94,375.00**
	Item Code 620933 Total No. of Proj.			**2**		**Total Amount**	**$94,375.00**
621110	450 MM ALTERNATIVE SLOTTED PIPE	M	4	1	120.00	$325.00	$39,000.00
	Unit Sub Total	**M**		**1**	**120.00**	**$325.00**	**$39,000.00**
	Item Code 621110 Total No. of Proj.			**1**		**Total Amount**	**$39,000.00**
625299	42" X 29" ALTERNATIVE PIPE ARCH CULVERT	LF	2	1	570.00	$105.04	$59,872.80
	Unit Sub Total	**LF**		**1**	**570.00**	**$105.04**	**$59,872.80**
	Item Code 625299 Total No. of Proj.			**1**		**Total Amount**	**$59,872.80**
641101	12" PLASTIC PIPE	LF	4	1	30.00	$99.00	$2,970.00
	Unit Sub Total	**LF**		**1**	**30.00**	**$99.00**	**$2,970.00**
	Item Code 641101 Total No. of Proj.			**1**		**Total Amount**	**$2,970.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
641104	15" PLASTIC PIPE	LF	6	1	120.00	$60.00	$7,200.00
	Unit Sub Total	**LF**		**1**	**120.00**	**$60.00**	**$7,200.00**
	Item Code 641104 Total No. of Proj.			**1**		**Total Amount**	**$7,200.00**
641107	18" PLASTIC PIPE	LF	4	5	1,670.00	$61.81	$103,225.00
		LF	6	1	83.00	$65.00	$5,395.00
	Unit Sub Total	**LF**		**6**	**1,753.00**	**$61.96**	**$108,620.00**
	Item Code 641107 Total No. of Proj.			**6**		**Total Amount**	**$108,620.00**
641113	24" PLASTIC PIPE	LF	1	1	180.00	$175.00	$31,500.00
		LF	4	4	864.00	$60.44	$52,218.00
		LF	5	1	770.00	$77.00	$59,290.00
	Unit Sub Total	**LF**		**6**	**1,814.00**	**$78.84**	**$143,008.00**
	Item Code 641113 Total No. of Proj.			**6**		**Total Amount**	**$143,008.00**
641119	30" PLASTIC PIPE	LF	4	1	34.00	$73.00	$2,482.00
	Unit Sub Total	**LF**		**1**	**34.00**	**$73.00**	**$2,482.00**
	Item Code 641119 Total No. of Proj.			**1**		**Total Amount**	**$2,482.00**
641125	36" PLASTIC PIPE	LF	4	1	1,880.00	$170.00	$319,600.00
	Unit Sub Total	**LF**		**1**	**1,880.00**	**$170.00**	**$319,600.00**
	Item Code 641125 Total No. of Proj.			**1**		**Total Amount**	**$319,600.00**
641132	300 MM PLASTIC PIPE	M	7	3	278.00	$77.57	$21,564.00
	Unit Sub Total	**M**		**3**	**278.00**	**$77.57**	**$21,564.00**
	Item Code 641132 Total No. of Proj.			**3**		**Total Amount**	**$21,564.00**
641155	450 MM SLOTTED PLASTIC PIPE	M	11	1	60.00	$470.00	$28,200.00
	Unit Sub Total	**M**		**1**	**60.00**	**$470.00**	**$28,200.00**
	Item Code 641155 Total No. of Proj.			**1**		**Total Amount**	**$28,200.00**
650010	12" REINFORCED CONCRETE PIPE	LF	2	1	43.00	$135.00	$5,805.00
		LF	3	1	26.00	$195.00	$5,070.00
		LF	4	2	142.00	$113.73	$16,150.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
650010	12" REINFORCED CONCRETE PIPE	LF	7	1	12.00	$220.00	$2,640.00
	Unit Sub Total	**LF**		**5**	**223.00**	**$133.03**	**$29,665.00**
	Item Code 650010 Total No. of Proj.			**5**		**Total Amount**	**$29,665.00**
650012	15" REINFORCED CONCRETE PIPE	LF	4	2	79.00	$97.47	$7,700.00
		LF	5	1	39.00	$45.00	$1,755.00
	Unit Sub Total	**LF**		**3**	**118.00**	**$80.13**	**$9,455.00**
	Item Code 650012 Total No. of Proj.			**3**		**Total Amount**	**$9,455.00**
650014	18" REINFORCED CONCRETE PIPE	LF	2	1	14.00	$160.00	$2,240.00
		LF	3	2	163.00	$62.30	$10,155.00
		LF	4	2	183.00	$114.36	$20,927.00
		LF	6	1	54.00	$150.00	$8,100.00
		LF	8	1	320.00	$100.00	$32,000.00
		LF	10	3	960.00	$137.03	$131,550.00
		LF	11	2	343.00	$104.46	$35,830.00
		LF	12	3	3,017.00	$57.12	$172,320.00
	Unit Sub Total	**LF**		**15**	**5,054.00**	**$81.74**	**$413,122.00**
	Item Code 650014 Total No. of Proj.			**15**		**Total Amount**	**$413,122.00**
650018	24" REINFORCED CONCRETE PIPE	LF	1	1	15.00	$100.00	$1,500.00
		LF	2	1	64.00	$135.00	$8,640.00
		LF	3	2	730.00	$41.56	$30,340.00
		LF	5	1	2.00	$1,390.00	$2,780.00
		LF	6	2	77.40	$200.05	$15,484.00
		LF	8	1	130.00	$75.00	$9,750.00
		LF	10	4	1,100.00	$140.87	$154,960.00
		LF	11	2	200.00	$135.35	$27,070.00
		LF	12	3	8,620.00	$67.45	$581,460.00
	Unit Sub Total	**LF**		**17**	**10,938.40**	**$76.06**	**$831,984.00**
	Item Code 650018 Total No. of Proj.			**17**		**Total Amount**	**$831,984.00**
650022	30" REINFORCED CONCRETE PIPE	LF	3	1	32.00	$80.00	$2,560.00
		LF	4	1	4.00	$220.00	$880.00
		LF	12	1	80.00	$83.00	$6,640.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**3**	**116.00**	**$86.90**	**$10,080.00**
	Item Code 650022	**Total No. of Proj.**			**3**		**Total Amount**	**$10,080.00**
650026	36" REINFORCED CONCRETE PIPE		LF	2	1	10.00	$250.00	$2,500.00
			LF	3	1	85.00	$100.00	$8,500.00
			LF	5	1	900.00	$120.00	$108,000.00
			LF	12	1	320.00	$103.00	$32,960.00
		Unit Sub Total	**LF**		**4**	**1,315.00**	**$115.56**	**$151,960.00**
	Item Code 650026	**Total No. of Proj.**			**4**		**Total Amount**	**$151,960.00**
650030	42" REINFORCED CONCRETE PIPE		LF	5	1	200.00	$140.00	$28,000.00
		Unit Sub Total	**LF**		**1**	**200.00**	**$140.00**	**$28,000.00**
	Item Code 650030	**Total No. of Proj.**			**1**		**Total Amount**	**$28,000.00**
650034	48" REINFORCED CONCRETE PIPE		LF	3	1	210.00	$100.00	$21,000.00
			LF	4	1	8.00	$650.00	$5,200.00
			LF	10	1	32.00	$250.00	$8,000.00
			LF	12	1	30.00	$345.00	$10,350.00
		Unit Sub Total	**LF**		**4**	**280.00**	**$159.11**	**$44,550.00**
	Item Code 650034	**Total No. of Proj.**			**4**		**Total Amount**	**$44,550.00**
650046	66" REINFORCED CONCRETE PIPE		LF	5	1	320.00	$280.00	$89,600.00
		Unit Sub Total	**LF**		**1**	**320.00**	**$280.00**	**$89,600.00**
	Item Code 650046	**Total No. of Proj.**			**1**		**Total Amount**	**$89,600.00**
650067	300 MM REINFORCED CONCRETE PIPE		M	6	1	14.00	$600.00	$8,400.00
			M	7	1	11.00	$325.00	$3,575.00
		Unit Sub Total	**M**		**2**	**25.00**	**$479.00**	**$11,975.00**
	Item Code 650067	**Total No. of Proj.**			**2**		**Total Amount**	**$11,975.00**
650068	375 MM REINFORCED CONCRETE PIPE		M	4	1	312.00	$150.00	$46,800.00
		Unit Sub Total	**M**		**1**	**312.00**	**$150.00**	**$46,800.00**
	Item Code 650068	**Total No. of Proj.**			**1**		**Total Amount**	**$46,800.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
650069	450 MM REINFORCED CONCRETE PIPE	M	6	1	130.00	$420.00	$54,600.00
		M	7	5	1,178.00	$212.92	$250,821.00
	Unit Sub Total	**M**		**6**	**1,308.00**	**$233.50**	**$305,421.00**
	Item Code 650069 Total No. of Proj.			**6**		**Total Amount**	**$305,421.00**
650075	600 MM REINFORCED CONCRETE PIPE	M	4	1	3.00	$1,000.00	$3,000.00
		M	7	4	6,840.00	$198.00	$1,354,320.00
	Unit Sub Total	**M**		**5**	**6,843.00**	**$198.35**	**$1,357,320.00**
	Item Code 650075 Total No. of Proj.			**5**		**Total Amount**	**$1,357,320.00**
650076	675 MM REINFORCED CONCRETE PIPE	M	7	1	9.00	$400.00	$3,600.00
	Unit Sub Total	**M**		**1**	**9.00**	**$400.00**	**$3,600.00**
	Item Code 650076 Total No. of Proj.			**1**		**Total Amount**	**$3,600.00**
650077	750 MM REINFORCED CONCRETE PIPE	M	4	1	31.00	$500.00	$15,500.00
		M	7	1	160.00	$290.00	$46,400.00
	Unit Sub Total	**M**		**2**	**191.00**	**$324.08**	**$61,900.00**
	Item Code 650077 Total No. of Proj.			**2**		**Total Amount**	**$61,900.00**
650078	825 MM REINFORCED CONCRETE PIPE	M	7	1	32.00	$400.00	$12,800.00
	Unit Sub Total	**M**		**1**	**32.00**	**$400.00**	**$12,800.00**
	Item Code 650078 Total No. of Proj.			**1**		**Total Amount**	**$12,800.00**
650079	900 MM REINFORCED CONCRETE PIPE	M	4	1	60.00	$600.00	$36,000.00
		M	7	1	31.00	$331.00	$10,261.00
	Unit Sub Total	**M**		**2**	**91.00**	**$508.36**	**$46,261.00**
	Item Code 650079 Total No. of Proj.			**2**		**Total Amount**	**$46,261.00**
650080	975 MM REINFORCED CONCRETE PIPE	M	7	1	2.20	$1,300.00	$2,860.00
	Unit Sub Total	**M**		**1**	**2.20**	**$1,300.00**	**$2,860.00**
	Item Code 650080 Total No. of Proj.			**1**		**Total Amount**	**$2,860.00**
650084	1200 MM REINFORCED CONCRETE PIPE	M	4	1	3.00	$1,500.00	$4,500.00
	Unit Sub Total	**M**		**1**	**3.00**	**$1,500.00**	**$4,500.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 650084 Total No. of Proj.			**1**		**Total Amount**	**$4,500.00**
650089	1500 MM REINFORCED CONCRETE PIPE	M	4	1	280.00	$925.00	$259,000.00
	Unit Sub Total	**M**		**1**	**280.00**	**$925.00**	**$259,000.00**
	Item Code 650089 Total No. of Proj.			**1**		**Total Amount**	**$259,000.00**
650092	1800 MM REINFORCED CONCRETE PIPE	M	4	1	39.00	$1,200.00	$46,800.00
	Unit Sub Total	**M**		**1**	**39.00**	**$1,200.00**	**$46,800.00**
	Item Code 650092 Total No. of Proj.			**1**		**Total Amount**	**$46,800.00**
650105	18" REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	LF	5	1	20.00	$54.00	$1,080.00
	Unit Sub Total	**LF**		**1**	**20.00**	**$54.00**	**$1,080.00**
	Item Code 650105 Total No. of Proj.			**1**		**Total Amount**	**$1,080.00**
650107	24" REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	LF	5	1	220.00	$72.00	$15,840.00
	Unit Sub Total	**LF**		**1**	**220.00**	**$72.00**	**$15,840.00**
	Item Code 650107 Total No. of Proj.			**1**		**Total Amount**	**$15,840.00**
650127	450 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	M	10	1	180.00	$155.00	$27,900.00
	Unit Sub Total	**M**		**1**	**180.00**	**$155.00**	**$27,900.00**
	Item Code 650127 Total No. of Proj.			**1**		**Total Amount**	**$27,900.00**
650128	600 MM REINFORCED CONCRETE PIPE (RUBBER GASKET JOINT)	M	10	1	250.00	$210.00	$52,500.00
	Unit Sub Total	**M**		**1**	**250.00**	**$210.00**	**$52,500.00**
	Item Code 650128 Total No. of Proj.			**1**		**Total Amount**	**$52,500.00**
650211	18" REINFORCED CONCRETE PIPE (CLASS II)	LF	2	1	410.00	$85.00	$34,850.00
	Unit Sub Total	**LF**		**1**	**410.00**	**$85.00**	**$34,850.00**
	Item Code 650211 Total No. of Proj.			**1**		**Total Amount**	**$34,850.00**
650416	24" REINFORCED CONCRETE PIPE (CLASS IV)	LF	12	1	74.00	$85.00	$6,290.00
	Unit Sub Total	**LF**		**1**	**74.00**	**$85.00**	**$6,290.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 650416 Total No. of Proj.			**1**		**Total Amount**	**$6,290.00**
650432	48" REINFORCED CONCRETE PIPE (CLASS IV)	LF	4	1	220.00	$110.00	$24,200.00
	Unit Sub Total	**LF**		**1**	**220.00**	**$110.00**	**$24,200.00**
	Item Code 650432 Total No. of Proj.			**1**		**Total Amount**	**$24,200.00**
650511	18" REINFORCED CONCRETE PIPE (CLASS V)	LF	4	1	140.00	$50.00	$7,000.00
		LF	6	1	440.00	$90.00	$39,600.00
	Unit Sub Total	**LF**		**2**	**580.00**	**$80.34**	**$46,600.00**
	Item Code 650511 Total No. of Proj.			**2**		**Total Amount**	**$46,600.00**
652215	24" REINFORCED CONCRETE PIPE (CLASS II, RUBBER GASKET JOINT)	LF	2	1	42.00	$275.00	$11,550.00
	Unit Sub Total	**LF**		**1**	**42.00**	**$275.00**	**$11,550.00**
	Item Code 652215 Total No. of Proj.			**1**		**Total Amount**	**$11,550.00**
655316	JACKED 24" REINFORCED CONCRETE PIPE (CLASS III)	LF	5	1	81.00	$510.00	$41,310.00
	Unit Sub Total	**LF**		**1**	**81.00**	**$510.00**	**$41,310.00**
	Item Code 655316 Total No. of Proj.			**1**		**Total Amount**	**$41,310.00**
655416	JACKED 24" REINFORCED CONCRETE PIPE (CLASS IV)	LF	5	1	170.00	$550.00	$93,500.00
	Unit Sub Total	**LF**		**1**	**170.00**	**$550.00**	**$93,500.00**
	Item Code 655416 Total No. of Proj.			**1**		**Total Amount**	**$93,500.00**
655432	JACKED 48" REINFORCED CONCRETE PIPE (CLASS IV)	LF	4	1	210.00	$750.00	$157,500.00
	Unit Sub Total	**LF**		**1**	**210.00**	**$750.00**	**$157,500.00**
	Item Code 655432 Total No. of Proj.			**1**		**Total Amount**	**$157,500.00**
655574	JACKED 600 MM REINFORCED CONCRETE PIPE (CLASS V)	M	7	2	168.00	$2,087.50	$350,700.00
	Unit Sub Total	**M**		**2**	**168.00**	**$2,087.50**	**$350,700.00**
	Item Code 655574 Total No. of Proj.			**2**		**Total Amount**	**$350,700.00**
664008	300 MM CORRUGATED STEEL PIPE	M	10	1	60.00	$55.00	$3,300.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**1**	**60.00**	**$55.00**	**$3,300.00**
	Item Code 664008 Total No. of Proj.			**1**		**Total Amount**	**$3,300.00**
664009	300 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	M	4	1	10.00	$250.00	$2,500.00
	Unit Sub Total	**M**		**1**	**10.00**	**$250.00**	**$2,500.00**
	Item Code 664009 Total No. of Proj.			**1**		**Total Amount**	**$2,500.00**
664014	450 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	M	7	1	10.00	$399.00	$3,990.00
	Unit Sub Total	**M**		**1**	**10.00**	**$399.00**	**$3,990.00**
	Item Code 664014 Total No. of Proj.			**1**		**Total Amount**	**$3,990.00**
664015	450 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	M	4	1	10.00	$250.00	$2,500.00
		M	7	1	7.00	$300.00	$2,100.00
	Unit Sub Total	**M**		**2**	**17.00**	**$270.59**	**$4,600.00**
	Item Code 664015 Total No. of Proj.			**2**		**Total Amount**	**$4,600.00**
664019	600 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	M	7	1	14.00	$240.00	$3,360.00
	Unit Sub Total	**M**		**1**	**14.00**	**$240.00**	**$3,360.00**
	Item Code 664019 Total No. of Proj.			**1**		**Total Amount**	**$3,360.00**
664020	600 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	M	4	1	7.00	$300.00	$2,100.00
	Unit Sub Total	**M**		**1**	**7.00**	**$300.00**	**$2,100.00**
	Item Code 664020 Total No. of Proj.			**1**		**Total Amount**	**$2,100.00**
664022	600 MM CORRUGATED STEEL PIPE (3.51 MM THICK)	M	2	1	79.00	$225.00	$17,775.00
	Unit Sub Total	**M**		**1**	**79.00**	**$225.00**	**$17,775.00**
	Item Code 664022 Total No. of Proj.			**1**		**Total Amount**	**$17,775.00**
664033	900 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	M	4	1	13.00	$400.00	$5,200.00
	Unit Sub Total	**M**		**1**	**13.00**	**$400.00**	**$5,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 664033 Total No. of Proj.			**1**		**Total Amount**	**$5,200.00**
664043	1200 MM CORRUGATED STEEL PIPE (2.01 MM THICK)	M	4	1	6.00	$1,000.00	$6,000.00
	Unit Sub Total	**M**		**1**	**6.00**	**$1,000.00**	**$6,000.00**
	Item Code 664043 Total No. of Proj.			**1**		**Total Amount**	**$6,000.00**
664096	600 MM BITUMINOUS COATED CORRUGATED STEEL PIPE (2.01 MM THICK)	M	7	1	55.00	$225.00	$12,375.00
	Unit Sub Total	**M**		**1**	**55.00**	**$225.00**	**$12,375.00**
	Item Code 664096 Total No. of Proj.			**1**		**Total Amount**	**$12,375.00**
665002	6" CORRUGATED STEEL PIPE (.064" THICK)	LF	3	1	77.00	$55.00	$4,235.00
	Unit Sub Total	**LF**		**1**	**77.00**	**$55.00**	**$4,235.00**
	Item Code 665002 Total No. of Proj.			**1**		**Total Amount**	**$4,235.00**
665005	8" CORRUGATED STEEL PIPE (.064" THICK)	LF	3	1	2.00	$200.00	$400.00
	Unit Sub Total	**LF**		**1**	**2.00**	**$200.00**	**$400.00**
	Item Code 665005 Total No. of Proj.			**1**		**Total Amount**	**$400.00**
665006	8" CORRUGATED STEEL PIPE (.079" THICK)	LF	2	1	8.00	$100.00	$800.00
		LF	11	1	50.00	$90.00	$4,500.00
	Unit Sub Total	**LF**		**2**	**58.00**	**$91.38**	**$5,300.00**
	Item Code 665006 Total No. of Proj.			**2**		**Total Amount**	**$5,300.00**
665010	12" CORRUGATED STEEL PIPE	LF	4	2	137.00	$54.09	$7,410.00
		LF	5	1	30.00	$83.00	$2,490.00
	Unit Sub Total	**LF**		**3**	**167.00**	**$59.28**	**$9,900.00**
	Item Code 665010 Total No. of Proj.			**3**		**Total Amount**	**$9,900.00**
665011	12" CORRUGATED STEEL PIPE (.064" THICK)	LF	3	1	2.00	$200.00	$400.00
	Unit Sub Total	**LF**		**1**	**2.00**	**$200.00**	**$400.00**
	Item Code 665011 Total No. of Proj.			**1**		**Total Amount**	**$400.00**
665012	12" CORRUGATED STEEL PIPE (.079" THICK)	LF	3	1	49.00	$60.00	$2,940.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
665012	12" CORRUGATED STEEL PIPE (.079" THICK)	LF	5	1	25.00	$100.00	$2,500.00
	Unit Sub Total	**LF**		**2**	**74.00**	**$73.51**	**$5,440.00**
	Item Code 665012 Total No. of Proj.			**2**		**Total Amount**	**$5,440.00**
665014	15" CORRUGATED STEEL PIPE (.079" THICK)	LF	6	1	310.00	$70.00	$21,700.00
	Unit Sub Total	**LF**		**1**	**310.00**	**$70.00**	**$21,700.00**
	Item Code 665014 Total No. of Proj.			**1**		**Total Amount**	**$21,700.00**
665015	15" CORRUGATED STEEL PIPE (.109" THICK)	LF	3	1	290.00	$100.00	$29,000.00
	Unit Sub Total	**LF**		**1**	**290.00**	**$100.00**	**$29,000.00**
	Item Code 665015 Total No. of Proj.			**1**		**Total Amount**	**$29,000.00**
665016	18" CORRUGATED STEEL PIPE (.064" THICK)	LF	2	1	3.10	$500.00	$1,550.00
		LF	3	1	9.00	$200.00	$1,800.00
		LF	4	1	84.00	$67.00	$5,628.00
	Unit Sub Total	**LF**		**3**	**96.10**	**$93.42**	**$8,978.00**
	Item Code 665016 Total No. of Proj.			**3**		**Total Amount**	**$8,978.00**
665017	18" CORRUGATED STEEL PIPE (.079" THICK)	LF	3	1	150.00	$60.00	$9,000.00
		LF	4	1	34.00	$100.00	$3,400.00
		LF	6	1	190.00	$105.00	$19,950.00
		LF	8	3	216.00	$105.37	$22,760.00
	Unit Sub Total	**LF**		**6**	**590.00**	**$93.41**	**$55,110.00**
	Item Code 665017 Total No. of Proj.			**6**		**Total Amount**	**$55,110.00**
665018	18" CORRUGATED STEEL PIPE (.109" THICK)	LF	2	6	986.00	$63.59	$62,701.20
		LF	3	2	193.00	$100.00	$19,300.00
		LF	4	1	10.00	$100.00	$1,000.00
		LF	8	1	80.00	$190.00	$15,200.00
		LF	10	1	3.00	$230.00	$690.00
	Unit Sub Total	**LF**		**11**	**1,272.00**	**$77.74**	**$98,891.20**
	Item Code 665018 Total No. of Proj.			**11**		**Total Amount**	**$98,891.20**
665022	24" CORRUGATED STEEL PIPE (.064" THICK)	LF	3	1	3.00	$250.00	$750.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**1**	**3.00**	**$250.00**	**$750.00**
	Item Code 665022 Total No. of Proj.			**1**		**Total Amount**	**$750.00**
665023	24" CORRUGATED STEEL PIPE (.079" THICK)	LF	3	1	1,350.00	$30.00	$40,500.00
		LF	5	1	420.00	$63.65	$26,733.00
		LF	8	1	2.00	$650.00	$1,300.00
	Unit Sub Total	**LF**		**3**	**1,772.00**	**$38.68**	**$68,533.00**
	Item Code 665023 Total No. of Proj.			**3**		**Total Amount**	**$68,533.00**
665024	24" CORRUGATED STEEL PIPE (.109" THICK)	LF	2	4	910.00	$80.33	$73,100.40
		LF	8	1	150.00	$80.00	$12,000.00
	Unit Sub Total	**LF**		**5**	**1,060.00**	**$80.28**	**$85,100.40**
	Item Code 665024 Total No. of Proj.			**5**		**Total Amount**	**$85,100.40**
665025	24" CORRUGATED STEEL PIPE (.138" THICK)	LF	1	2	230.00	$150.22	$34,550.00
		LF	2	3	748.00	$141.60	$105,920.00
		LF	3	4	1,670.00	$87.55	$146,208.00
		LF	8	2	310.00	$104.84	$32,500.00
		LF	10	1	65.00	$150.00	$9,750.00
	Unit Sub Total	**LF**		**12**	**3,023.00**	**$108.81**	**$328,928.00**
	Item Code 665025 Total No. of Proj.			**12**		**Total Amount**	**$328,928.00**
665030	30" CORRUGATED STEEL PIPE (.064" THICK)	LF	10	1	75.00	$100.00	$7,500.00
	Unit Sub Total	**LF**		**1**	**75.00**	**$100.00**	**$7,500.00**
	Item Code 665030 Total No. of Proj.			**1**		**Total Amount**	**$7,500.00**
665031	30" CORRUGATED STEEL PIPE (.079" THICK)	LF	8	1	42.00	$170.00	$7,140.00
	Unit Sub Total	**LF**		**1**	**42.00**	**$170.00**	**$7,140.00**
	Item Code 665031 Total No. of Proj.			**1**		**Total Amount**	**$7,140.00**
665032	30" CORRUGATED STEEL PIPE (.109" THICK)	LF	10	1	2.00	$530.00	$1,060.00
	Unit Sub Total	**LF**		**1**	**2.00**	**$530.00**	**$1,060.00**
	Item Code 665032 Total No. of Proj.			**1**		**Total Amount**	**$1,060.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
665037	36" CORRUGATED STEEL PIPE (.109" THICK)	LF	2	3	763.10	$87.77	$66,980.00
		LF	3	1	210.00	$100.00	$21,000.00
		LF	4	2	134.00	$73.13	$9,800.00
	Unit Sub Total	**LF**		**6**	**1,107.10**	**$88.32**	**$97,780.00**
	Item Code 665037 Total No. of Proj.			**6**		**Total Amount**	**$97,780.00**
665038	36" CORRUGATED STEEL PIPE (.138" THICK)	LF	1	1	73.00	$280.50	$20,476.50
	Unit Sub Total	**LF**		**1**	**73.00**	**$280.50**	**$20,476.50**
	Item Code 665038 Total No. of Proj.			**1**		**Total Amount**	**$20,476.50**
665043	42" CORRUGATED STEEL PIPE (.138" THICK)	LF	1	1	110.00	$373.50	$41,085.00
	Unit Sub Total	**LF**		**1**	**110.00**	**$373.50**	**$41,085.00**
	Item Code 665043 Total No. of Proj.			**1**		**Total Amount**	**$41,085.00**
665075	18" CORRUGATED STEEL PIPE (.138" THICK)	LF	1	1	150.00	$155.00	$23,250.00
		LF	3	2	8.00	$172.50	$1,380.00
	Unit Sub Total	**LF**		**3**	**158.00**	**$155.89**	**$24,630.00**
	Item Code 665075 Total No. of Proj.			**3**		**Total Amount**	**$24,630.00**
665112	12" BITUMINOUS COATED CORRUGATED STEEL PIPE (.079" THICK)	LF	12	1	14.00	$330.00	$4,620.00
	Unit Sub Total	**LF**		**1**	**14.00**	**$330.00**	**$4,620.00**
	Item Code 665112 Total No. of Proj.			**1**		**Total Amount**	**$4,620.00**
665116	18" BITUMINOUS COATED CORRUGATED STEEL PIPE (.064" THICK)	LF	11	1	31.00	$90.00	$2,790.00
	Unit Sub Total	**LF**		**1**	**31.00**	**$90.00**	**$2,790.00**
	Item Code 665116 Total No. of Proj.			**1**		**Total Amount**	**$2,790.00**
665117	18" BITUMINOUS COATED CORRUGATED STEEL PIPE (.079" THICK)	LF	8	1	7.00	$245.00	$1,715.00
		LF	12	1	72.00	$95.00	$6,840.00
	Unit Sub Total	**LF**		**2**	**79.00**	**$108.29**	**$8,555.00**
	Item Code 665117 Total No. of Proj.			**2**		**Total Amount**	**$8,555.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
665118	18" BITUMINOUS COATED CORRUGATED STEEL PIPE (.109" THICK)	LF	12	1	20.00	$70.00	$1,400.00
	Unit Sub Total	**LF**		**1**	**20.00**	**$70.00**	**$1,400.00**
	Item Code 665118 Total No. of Proj.			**1**		**Total Amount**	**$1,400.00**
665123	24" BITUMINOUS COATED CORRUGATED STEEL PIPE (.079" THICK)	LF	8	1	7.00	$230.00	$1,610.00
	Unit Sub Total	**LF**		**1**	**7.00**	**$230.00**	**$1,610.00**
	Item Code 665123 Total No. of Proj.			**1**		**Total Amount**	**$1,610.00**
665136	36" BITUMINOUS COATED CORRUGATED STEEL PIPE (.079" THICK)	LF	8	1	5.00	$340.00	$1,700.00
		LF	12	1	30.00	$150.00	$4,500.00
	Unit Sub Total	**LF**		**2**	**35.00**	**$177.14**	**$6,200.00**
	Item Code 665136 Total No. of Proj.			**2**		**Total Amount**	**$6,200.00**
665712	12" SLOTTED CORRUGATED STEEL PIPE (.079" THICK)	LF	3	1	350.00	$79.00	$27,650.00
	Unit Sub Total	**LF**		**1**	**350.00**	**$79.00**	**$27,650.00**
	Item Code 665712 Total No. of Proj.			**1**		**Total Amount**	**$27,650.00**
665713	12" SLOTTED CORRUGATED STEEL PIPE (.109" THICK)	LF	5	1	34.00	$125.00	$4,250.00
	Unit Sub Total	**LF**		**1**	**34.00**	**$125.00**	**$4,250.00**
	Item Code 665713 Total No. of Proj.			**1**		**Total Amount**	**$4,250.00**
665717	18" SLOTTED CORRUGATED STEEL PIPE (.079" THICK)	LF	3	1	89.00	$60.00	$5,340.00
	Unit Sub Total	**LF**		**1**	**89.00**	**$60.00**	**$5,340.00**
	Item Code 665717 Total No. of Proj.			**1**		**Total Amount**	**$5,340.00**
665732	450 MM SLOTTED CORRUGATED STEEL PIPE (1.63 MM THICK)	M	7	2	550.00	$234.31	$128,870.00
	Unit Sub Total	**M**		**2**	**550.00**	**$234.31**	**$128,870.00**
	Item Code 665732 Total No. of Proj.			**2**		**Total Amount**	**$128,870.00**
665733	450 MM SLOTTED CORRUGATED STEEL PIPE (2.01 MM THICK)	M	7	1	10.00	$375.00	$3,750.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**1**	**10.00**	**$375.00**	**$3,750.00**
	Item Code 665733 Total No. of Proj.			**1**		**Total Amount**	**$3,750.00**
665833	450 MM BITUMINOUS COATED SLOTTED CORRUGATED STEEL PIPE (2.01 MM THICK)	M	7	1	8,530.00	$200.00	$1,706,000.00
	Unit Sub Total	**M**		**1**	**8,530.00**	**$200.00**	**$1,706,000.00**
	Item Code 665833 Total No. of Proj.			**1**		**Total Amount**	**$1,706,000.00**
667006	21" X 15" CORRUGATED STEEL PIPE ARCH (.109" THICK)	LF	2	1	29.00	$125.00	$3,625.00
		LF	3	1	320.00	$50.00	$16,000.00
	Unit Sub Total	**LF**		**2**	**349.00**	**$56.23**	**$19,625.00**
	Item Code 667006 Total No. of Proj.			**2**		**Total Amount**	**$19,625.00**
667013	28" X 20" CORRUGATED STEEL PIPE ARCH (.079" THICK)	LF	8	1	5.00	$263.00	$1,315.00
	Unit Sub Total	**LF**		**1**	**5.00**	**$263.00**	**$1,315.00**
	Item Code 667013 Total No. of Proj.			**1**		**Total Amount**	**$1,315.00**
680207	3" PLASTIC PIPE	LF	10	3	32,200.00	$8.09	$260,560.00
		LF	12	1	3,456.00	$2.00	$6,912.00
	Unit Sub Total	**LF**		**4**	**35,656.00**	**$7.50**	**$267,472.00**
	Item Code 680207 Total No. of Proj.			**4**		**Total Amount**	**$267,472.00**
680225	3" SLOTTED PLASTIC PIPE	LF	4	1	700.00	$60.00	$42,000.00
	Unit Sub Total	**LF**		**1**	**700.00**	**$60.00**	**$42,000.00**
	Item Code 680225 Total No. of Proj.			**1**		**Total Amount**	**$42,000.00**
680256	80 MM PLASTIC PIPE	M	7	1	96.00	$125.00	$12,000.00
	Unit Sub Total	**M**		**1**	**96.00**	**$125.00**	**$12,000.00**
	Item Code 680256 Total No. of Proj.			**1**		**Total Amount**	**$12,000.00**
680410	12" PERFORATED STEEL PIPE UNDERDRAIN	LF	1	1	400.00	$30.00	$12,000.00
	Unit Sub Total	**LF**		**1**	**400.00**	**$30.00**	**$12,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 680410 Total No. of Proj.			**1**		**Total Amount**	**$12,000.00**
680902	6" PERFORATED PLASTIC PIPE UNDERDRAIN	LF	1	1	97.00	$70.00	$6,790.00
		LF	4	2	580.00	$44.71	$25,930.00
		LF	7	1	990.00	$28.00	$27,720.00
	Unit Sub Total	**LF**		**4**	**1,667.00**	**$36.26**	**$60,440.00**
	Item Code 680902 Total No. of Proj.			**4**		**Total Amount**	**$60,440.00**
680903	6" NON-PERFORATED PLASTIC PIPE UNDERDRAIN	LF	1	1	120.00	$20.00	$2,400.00
	Unit Sub Total	**LF**		**1**	**120.00**	**$20.00**	**$2,400.00**
	Item Code 680903 Total No. of Proj.			**1**		**Total Amount**	**$2,400.00**
680905	8" PERFORATED PLASTIC PIPE UNDERDRAIN	LF	1	4	2,730.00	$60.05	$163,950.00
		LF	3	1	22.00	$60.00	$1,320.00
		LF	4	4	8,880.00	$26.00	$230,920.00
	Unit Sub Total	**LF**		**9**	**11,632.00**	**$34.06**	**$396,190.00**
	Item Code 680905 Total No. of Proj.			**9**		**Total Amount**	**$396,190.00**
680931	150 MM PERFORATED PLASTIC PIPE UNDERDRAIN	M	4	1	50.00	$78.00	$3,900.00
		M	7	1	212.00	$120.00	$25,440.00
	Unit Sub Total	**M**		**2**	**262.00**	**$111.98**	**$29,340.00**
	Item Code 680931 Total No. of Proj.			**2**		**Total Amount**	**$29,340.00**
680932	150 MM NON-PERFORATED PLASTIC PIPE UNDERDRAIN	M	7	1	31.00	$52.00	$1,612.00
	Unit Sub Total	**M**		**1**	**31.00**	**$52.00**	**$1,612.00**
	Item Code 680932 Total No. of Proj.			**1**		**Total Amount**	**$1,612.00**
680933	200 MM PERFORATED PLASTIC PIPE UNDERDRAIN	M	4	1	3,460.00	$67.00	$231,820.00
	Unit Sub Total	**M**		**1**	**3,460.00**	**$67.00**	**$231,820.00**
	Item Code 680933 Total No. of Proj.			**1**		**Total Amount**	**$231,820.00**
681023	6" PLASTIC PIPE	LF	2	1	25.00	$85.60	$2,140.00
		LF	7	1	46.00	$28.00	$1,288.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**2**	**71.00**	**$48.28**	**$3,428.00**
	Item Code 681023	**Total No. of Proj.**			**2**		**Total Amount**	**$3,428.00**
681066	150 MM PLASTIC PIPE		M	4	1	3.00	$50.00	$150.00
			M	7	1	16.00	$150.00	$2,400.00
		Unit Sub Total	**M**		**2**	**19.00**	**$134.21**	**$2,550.00**
	Item Code 681066	**Total No. of Proj.**			**2**		**Total Amount**	**$2,550.00**
681103	3" PLASTIC PIPE (EDGE DRAIN)		LF	2	3	22,000.00	$11.99	$263,740.00
			LF	4	4	14,510.00	$6.82	$98,980.00
			LF	5	1	1,550.00	$13.00	$20,150.00
			LF	6	1	2,000.00	$10.00	$20,000.00
			LF	12	1	5,160.00	$11.70	$60,372.00
		Unit Sub Total	**LF**		**10**	**45,220.00**	**$10.24**	**$463,242.00**
	Item Code 681103	**Total No. of Proj.**			**10**		**Total Amount**	**$463,242.00**
681107	3" PLASTIC PIPE (EDGE DRAIN OUTLET)		LF	2	2	112.00	$68.04	$7,620.00
			LF	4	2	1,420.00	$25.56	$36,300.00
			LF	5	1	430.00	$21.00	$9,030.00
			LF	12	1	750.00	$13.70	$10,275.00
		Unit Sub Total	**LF**		**6**	**2,712.00**	**$23.31**	**$63,225.00**
	Item Code 681107	**Total No. of Proj.**			**6**		**Total Amount**	**$63,225.00**
681108	6" PLASTIC PIPE (EDGE DRAIN)		LF	2	1	630.00	$22.00	$13,860.00
		Unit Sub Total	**LF**		**1**	**630.00**	**$22.00**	**$13,860.00**
	Item Code 681108	**Total No. of Proj.**			**1**		**Total Amount**	**$13,860.00**
681111	CLEANOUT ASSEMBLY (EDGE DRAIN)		EA	2	1	95.00	$300.00	$28,500.00
		Unit Sub Total	**EA**		**1**	**95.00**	**$300.00**	**$28,500.00**
	Item Code 681111	**Total No. of Proj.**			**1**		**Total Amount**	**$28,500.00**
681113	6" PLASTIC PIPE (EDGE DRAIN OUTLET)		LF	2	1	41.00	$62.00	$2,542.00
		Unit Sub Total	**LF**		**1**	**41.00**	**$62.00**	**$2,542.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 681113 Total No. of Proj.			**1**		**Total Amount**	**$2,542.00**
681132	GEOCOMPOSITE DRAIN	SQFT	4	1	132,800.00	$1.00	$132,800.00
	Unit Sub Total	**SQFT**		**1**	**132,800.00**	**$1.00**	**$132,800.00**
681132	GEOCOMPOSITE DRAIN	SQYD	12	1	53.00	$50.00	$2,650.00
	Unit Sub Total	**SQYD**		**1**	**53.00**	**$50.00**	**$2,650.00**
	Item Code 681132 Total No. of Proj.			**2**		**Total Amount**	**$135,450.00**
681137	80 MM PLASTIC PIPE (EDGE DRAIN OUTLET)	M	7	1	580.00	$42.00	$24,360.00
	Unit Sub Total	**M**		**1**	**580.00**	**$42.00**	**$24,360.00**
	Item Code 681137 Total No. of Proj.			**1**		**Total Amount**	**$24,360.00**
681501	FURNISH AND INSTALL DRAIN PIPE (HORIZONTAL DRAIN)	LF	1	1	1,320.00	$1.00	$1,320.00
		LF	5	1	1,800.00	$8.70	$15,660.00
	Unit Sub Total	**LF**		**2**	**3,120.00**	**$5.44**	**$16,980.00**
	Item Code 681501 Total No. of Proj.			**2**		**Total Amount**	**$16,980.00**
681502	DRILL HOLE (HORIZONTAL DRAIN)	LF	1	1	1,260.00	$18.00	$22,680.00
		LF	5	1	1,800.00	$20.00	$36,000.00
	Unit Sub Total	**LF**		**2**	**3,060.00**	**$19.18**	**$58,680.00**
	Item Code 681502 Total No. of Proj.			**2**		**Total Amount**	**$58,680.00**
681510	HORIZONTAL DRAIN CONNECTOR UNIT	EA	1	1	12.00	$150.00	$1,800.00
	Unit Sub Total	**EA**		**1**	**12.00**	**$150.00**	**$1,800.00**
	Item Code 681510 Total No. of Proj.			**1**		**Total Amount**	**$1,800.00**
681512	8" COLLECTOR SYSTEM (HORIZONTAL DRAIN)	LF	1	1	130.00	$20.00	$2,600.00
	Unit Sub Total	**LF**		**1**	**130.00**	**$20.00**	**$2,600.00**
	Item Code 681512 Total No. of Proj.			**1**		**Total Amount**	**$2,600.00**
681988	FILTER FABRIC (UNDERDRAIN)	SQYD	5	1	3,930.00	$0.60	$2,358.00
	Unit Sub Total	**SQYD**		**1**	**3,930.00**	**$0.60**	**$2,358.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 681988	**Total No. of Proj.**			**1**		**Total Amount**	**$2,358.00**
681990	FILTER FABRIC		M2	7	1	240.00	$2.10	$504.00
		Unit Sub Total	**M2**		**1**	**240.00**	**$2.10**	**$504.00**
681990	FILTER FABRIC		SQFT	8	1	450.00	$3.60	$1,620.00
		Unit Sub Total	**SQFT**		**1**	**450.00**	**$3.60**	**$1,620.00**
681990	FILTER FABRIC		SQYD	3	1	420.00	$5.00	$2,100.00
			SQYD	4	3	85,160.00	$1.01	$86,385.00
		Unit Sub Total	**SQYD**		**4**	**85,580.00**	**$1.03**	**$88,485.00**
	Item Code 681990	**Total No. of Proj.**			**6**		**Total Amount**	**$90,609.00**
682001	PERMEABLE MATERIAL		CY	3	2	164.00	$63.29	$10,380.00
		Unit Sub Total	**CY**		**2**	**164.00**	**$63.29**	**$10,380.00**
	Item Code 682001	**Total No. of Proj.**			**2**		**Total Amount**	**$10,380.00**
682020	CLASS 1 PERMEABLE MATERIAL		CY	1	1	38.00	$95.00	$3,610.00
			CY	2	1	500.00	$25.00	$12,500.00
			CY	4	1	55.00	$100.00	$5,500.00
		Unit Sub Total	**CY**		**3**	**593.00**	**$36.44**	**$21,610.00**
	Item Code 682020	**Total No. of Proj.**			**3**		**Total Amount**	**$21,610.00**
682022	CLASS 1 PERMEABLE MATERIAL (BLANKET)		CY	1	2	204.00	$49.02	$10,000.00
		Unit Sub Total	**CY**		**2**	**204.00**	**$49.02**	**$10,000.00**
	Item Code 682022	**Total No. of Proj.**			**2**		**Total Amount**	**$10,000.00**
682040	CLASS 2 PERMEABLE MATERIAL		CY	3	1	7.00	$97.00	$679.00
		Unit Sub Total	**CY**		**1**	**7.00**	**$97.00**	**$679.00**
	Item Code 682040	**Total No. of Proj.**			**1**		**Total Amount**	**$679.00**
682045	CLASS 3 PERMEABLE MATERIAL		CY	4	3	1,391.00	$77.17	$107,341.70
		Unit Sub Total	**CY**		**3**	**1,391.00**	**$77.17**	**$107,341.70**
682045	CLASS 3 PERMEABLE MATERIAL		M3	4	1	540.00	$70.00	$37,800.00
			M3	7	1	3,160.00	$95.00	$300,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M3**		**2**	**3,700.00**	**$91.35**	**$338,000.00**
	Item Code 682045 Total No. of Proj.			**5**		**Total Amount**	**$445,341.70**
682048	CLASS 3 PERMEABLE MATERIAL (UNDERDRAIN)	CY	5	1	1,530.00	$122.00	$186,660.00
	Unit Sub Total	**CY**		**1**	**1,530.00**	**$122.00**	**$186,660.00**
	Item Code 682048 Total No. of Proj.			**1**		**Total Amount**	**$186,660.00**
682049	CLASS 3 PERMEABLE MATERIAL (BLANKET)	CY	4	1	1,070.00	$55.00	$58,850.00
	Unit Sub Total	**CY**		**1**	**1,070.00**	**$55.00**	**$58,850.00**
	Item Code 682049 Total No. of Proj.			**1**		**Total Amount**	**$58,850.00**
685000	6" ALTERNATIVE PIPE UNDERDRAIN	LF	1	1	140.00	$40.00	$5,600.00
	Unit Sub Total	**LF**		**1**	**140.00**	**$40.00**	**$5,600.00**
	Item Code 685000 Total No. of Proj.			**1**		**Total Amount**	**$5,600.00**
685020	8" ALTERNATIVE PIPE UNDERDRAIN	LF	1	1	1,000.00	$30.00	$30,000.00
		LF	5	1	950.00	$10.00	$9,500.00
	Unit Sub Total	**LF**		**2**	**1,950.00**	**$20.26**	**$39,500.00**
	Item Code 685020 Total No. of Proj.			**2**		**Total Amount**	**$39,500.00**
690104	8" CORRUGATED STEEL PIPE DOWNDRAIN	LF	1	4	506.00	$35.41	$17,919.00
		LF	3	1	15.00	$50.00	$750.00
		LF	4	1	200.00	$32.00	$6,400.00
	Unit Sub Total	**LF**		**6**	**721.00**	**$34.77**	**$25,069.00**
	Item Code 690104 Total No. of Proj.			**6**		**Total Amount**	**$25,069.00**
690110	12" CORRUGATED STEEL PIPE DOWNDRAIN	LF	1	1	28.00	$35.00	$980.00
		LF	4	1	10.00	$400.00	$4,000.00
		LF	5	1	220.00	$21.00	$4,620.00
		LF	6	1	280.00	$23.00	$6,440.00
	Unit Sub Total	**LF**		**4**	**538.00**	**$29.81**	**$16,040.00**
	Item Code 690110 Total No. of Proj.			**4**		**Total Amount**	**$16,040.00**
690111	12" CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK)	LF	6	1	10.00	$300.00	$3,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**1**	**10.00**	**$300.00**	**$3,000.00**
	Item Code 690111 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
690112	12" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	5	1	210.00	$38.00	$7,980.00
		LF	6	1	50.00	$80.00	$4,000.00
	Unit Sub Total	**LF**		**2**	**260.00**	**$46.08**	**$11,980.00**
	Item Code 690112 Total No. of Proj.			**2**		**Total Amount**	**$11,980.00**
690115	15" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	3	1	2,320.00	$30.00	$69,600.00
	Unit Sub Total	**LF**		**1**	**2,320.00**	**$30.00**	**$69,600.00**
	Item Code 690115 Total No. of Proj.			**1**		**Total Amount**	**$69,600.00**
690116	18" CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK)	LF	4	1	23.00	$67.00	$1,541.00
		LF	5	1	41.00	$37.00	$1,517.00
		LF	6	1	170.00	$100.00	$17,000.00
	Unit Sub Total	**LF**		**3**	**234.00**	**$85.72**	**$20,058.00**
	Item Code 690116 Total No. of Proj.			**3**		**Total Amount**	**$20,058.00**
690117	18" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	5	1	510.00	$42.00	$21,420.00
	Unit Sub Total	**LF**		**1**	**510.00**	**$42.00**	**$21,420.00**
	Item Code 690117 Total No. of Proj.			**1**		**Total Amount**	**$21,420.00**
690118	18" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	3	1	210.00	$50.00	$10,500.00
		LF	4	1	120.00	$120.00	$14,400.00
		LF	7	1	48.00	$116.00	$5,568.00
	Unit Sub Total	**LF**		**3**	**378.00**	**$80.60**	**$30,468.00**
	Item Code 690118 Total No. of Proj.			**3**		**Total Amount**	**$30,468.00**
690122	24" CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK)	LF	1	1	68.00	$55.00	$3,740.00
	Unit Sub Total	**LF**		**1**	**68.00**	**$55.00**	**$3,740.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 690122 Total No. of Proj.			**1**		**Total Amount**	**$3,740.00**
690123	24" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	1	1	29.00	$50.00	$1,450.00
		LF	3	1	74.00	$60.00	$4,440.00
		LF	4	1	45.00	$69.00	$3,105.00
	Unit Sub Total	**LF**		**3**	**148.00**	**$60.78**	**$8,995.00**
	Item Code 690123 Total No. of Proj.			**3**		**Total Amount**	**$8,995.00**
690124	24" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	7	1	83.00	$85.00	$7,055.00
	Unit Sub Total	**LF**		**1**	**83.00**	**$85.00**	**$7,055.00**
	Item Code 690124 Total No. of Proj.			**1**		**Total Amount**	**$7,055.00**
690125	24" CORRUGATED STEEL PIPE DOWNDRAIN (.138" THICK)	LF	1	1	22.00	$100.00	$2,200.00
		LF	2	1	250.00	$75.00	$18,750.00
		LF	3	1	40.00	$70.00	$2,800.00
		LF	5	1	370.00	$58.00	$21,460.00
	Unit Sub Total	**LF**		**4**	**682.00**	**$66.29**	**$45,210.00**
	Item Code 690125 Total No. of Proj.			**4**		**Total Amount**	**$45,210.00**
690131	30" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	4	1	52.00	$75.00	$3,900.00
	Unit Sub Total	**LF**		**1**	**52.00**	**$75.00**	**$3,900.00**
	Item Code 690131 Total No. of Proj.			**1**		**Total Amount**	**$3,900.00**
690134	30" CORRUGATED STEEL PIPE DOWNDRAIN (.138" THICK)	LF	5	1	70.00	$63.00	$4,410.00
	Unit Sub Total	**LF**		**1**	**70.00**	**$63.00**	**$4,410.00**
	Item Code 690134 Total No. of Proj.			**1**		**Total Amount**	**$4,410.00**
690136	36" CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	4	1	32.00	$100.00	$3,200.00
	Unit Sub Total	**LF**		**1**	**32.00**	**$100.00**	**$3,200.00**
	Item Code 690136 Total No. of Proj.			**1**		**Total Amount**	**$3,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
690138	36" CORRUGATED STEEL PIPE DOWNDRAIN (.138" THICK)	LF	1	1	74.00	$85.75	$6,345.50
	Unit Sub Total	**LF**		**1**	**74.00**	**$85.75**	**$6,345.50**
	Item Code 690138 Total No. of Proj.			**1**		**Total Amount**	**$6,345.50**
690148	48" CORRUGATED STEEL PIPE DOWNDRAIN (.138" THICK)	LF	5	1	340.00	$83.00	$28,220.00
	Unit Sub Total	**LF**		**1**	**340.00**	**$83.00**	**$28,220.00**
	Item Code 690148 Total No. of Proj.			**1**		**Total Amount**	**$28,220.00**
690156	200 MM CORRUGATED STEEL PIPE DOWNDRAIN (2.01 MM THICK)	M	3	1	35.00	$300.00	$10,500.00
	Unit Sub Total	**M**		**1**	**35.00**	**$300.00**	**$10,500.00**
	Item Code 690156 Total No. of Proj.			**1**		**Total Amount**	**$10,500.00**
690159	300 MM CORRUGATED STEEL PIPE DOWNDRAIN (1.63 MM THICK)	M	4	1	24.00	$250.00	$6,000.00
	Unit Sub Total	**M**		**1**	**24.00**	**$250.00**	**$6,000.00**
	Item Code 690159 Total No. of Proj.			**1**		**Total Amount**	**$6,000.00**
690212	12" BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (.079" THICK)	LF	11	1	160.00	$105.00	$16,800.00
	Unit Sub Total	**LF**		**1**	**160.00**	**$105.00**	**$16,800.00**
	Item Code 690212 Total No. of Proj.			**1**		**Total Amount**	**$16,800.00**
690216	18" BITUMINOUS COATED CORRUGATED STEEL PIPE DOWNDRAIN (.064" THICK)	LF	11	1	27.00	$100.00	$2,700.00
	Unit Sub Total	**LF**		**1**	**27.00**	**$100.00**	**$2,700.00**
	Item Code 690216 Total No. of Proj.			**1**		**Total Amount**	**$2,700.00**
690960	12" PLASTIC PIPE DOWNDRAIN	LF	4	1	66.00	$24.55	$1,620.30
	Unit Sub Total	**LF**		**1**	**66.00**	**$24.55**	**$1,620.30**
	Item Code 690960 Total No. of Proj.			**1**		**Total Amount**	**$1,620.30**
691001	CORRUGATED STEEL FLUME DOWNDRAIN	LF	3	1	40.00	$100.00	$4,000.00
		LF	4	1	53.00	$55.00	$2,915.00
	Unit Sub Total	**LF**		**2**	**93.00**	**$74.35**	**$6,915.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 691001 Total No. of Proj.			**2**		**Total Amount**	**$6,915.00**
691004	10" CORRUGATED STEEL FLUME DOWNDRAIN	LF	3	1	310.00	$40.00	$12,400.00
	Unit Sub Total	**LF**		**1**	**310.00**	**$40.00**	**$12,400.00**
	Item Code 691004 Total No. of Proj.			**1**		**Total Amount**	**$12,400.00**
691900	FLUME DOWNDRAIN	LF	6	1	96.00	$30.00	$2,880.00
		LF	10	1	23.00	$50.00	$1,150.00
	Unit Sub Total	**LF**		**2**	**119.00**	**$33.87**	**$4,030.00**
	Item Code 691900 Total No. of Proj.			**2**		**Total Amount**	**$4,030.00**
691902	10" FLUME DOWNDRAIN	LF	4	1	63.00	$25.25	$1,590.75
		LF	6	1	150.00	$53.00	$7,950.00
	Unit Sub Total	**LF**		**2**	**213.00**	**$44.79**	**$9,540.75**
	Item Code 691902 Total No. of Proj.			**2**		**Total Amount**	**$9,540.75**
692001	ENTRANCE TAPER	EA	2	1	8.00	$3,500.00	$28,000.00
		EA	4	1	1.00	$547.00	$547.00
	Unit Sub Total	**EA**		**2**	**9.00**	**$3,171.89**	**$28,547.00**
	Item Code 692001 Total No. of Proj.			**2**		**Total Amount**	**$28,547.00**
692003	8" ENTRANCE TAPER	EA	1	3	14.00	$375.00	$5,250.00
		EA	3	1	1.00	$450.00	$450.00
	Unit Sub Total	**EA**		**4**	**15.00**	**$380.00**	**$5,700.00**
	Item Code 692003 Total No. of Proj.			**4**		**Total Amount**	**$5,700.00**
692005	12" ENTRANCE TAPER	EA	1	1	1.00	$500.00	$500.00
		EA	5	3	23.00	$544.52	$12,524.00
		EA	6	2	13.00	$486.77	$6,328.00
		EA	11	1	8.00	$385.00	$3,080.00
	Unit Sub Total	**EA**		**7**	**45.00**	**$498.49**	**$22,432.00**
	Item Code 692005 Total No. of Proj.			**7**		**Total Amount**	**$22,432.00**
692006	15" ENTRANCE TAPER	EA	3	1	41.00	$600.00	$24,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**1**	**41.00**	**$600.00**	**$24,600.00**
	Item Code 692006	**Total No. of Proj.**			**1**		**Total Amount**	**$24,600.00**
692007	18" ENTRANCE TAPER		EA	5	1	1.00	$784.00	$784.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$784.00**	**$784.00**
	Item Code 692007	**Total No. of Proj.**			**1**		**Total Amount**	**$784.00**
692037	18" BITUMINOUS COATED ENTRANCE TAPER		EA	11	1	1.00	$780.00	$780.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$780.00**	**$780.00**
	Item Code 692037	**Total No. of Proj.**			**1**		**Total Amount**	**$780.00**
692101	TAPERED INLET		EA	3	1	2.00	$1,200.00	$2,400.00
			EA	4	2	4.00	$206.75	$827.00
			EA	6	1	10.00	$185.00	$1,850.00
		Unit Sub Total	**EA**		**4**	**16.00**	**$317.31**	**$5,077.00**
	Item Code 692101	**Total No. of Proj.**			**4**		**Total Amount**	**$5,077.00**
692104	10" TAPERED INLET		EA	3	1	9.00	$500.00	$4,500.00
			EA	6	1	10.00	$730.00	$7,300.00
		Unit Sub Total	**EA**		**2**	**19.00**	**$621.05**	**$11,800.00**
	Item Code 692104	**Total No. of Proj.**			**2**		**Total Amount**	**$11,800.00**
692205	12" DOWNDRAIN SLIP JOINT		EA	5	1	11.00	$420.00	$4,620.00
			EA	6	1	4.00	$562.00	$2,248.00
		Unit Sub Total	**EA**		**2**	**15.00**	**$457.87**	**$6,868.00**
	Item Code 692205	**Total No. of Proj.**			**2**		**Total Amount**	**$6,868.00**
692209	24" DOWNDRAIN SLIP JOINT		EA	1	1	1.00	$1,000.00	$1,000.00
			EA	2	1	3.00	$450.00	$1,350.00
			EA	3	1	3.00	$500.00	$1,500.00
		Unit Sub Total	**EA**		**3**	**7.00**	**$550.00**	**$3,850.00**
	Item Code 692209	**Total No. of Proj.**			**3**		**Total Amount**	**$3,850.00**
692301	ANCHOR ASSEMBLY		EA	4	3	31.00	$396.45	$12,290.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
692301	ANCHOR ASSEMBLY		EA	5	1	1.00	$200.00	$200.00
		Unit Sub Total	**EA**		**4**	**32.00**	**$390.31**	**$12,490.00**
	Item Code 692301	**Total No. of Proj.**			**4**		**Total Amount**	**$12,490.00**
692303	8" ANCHOR ASSEMBLY		EA	1	4	10.00	$309.00	$3,090.00
			EA	3	1	1.00	$250.00	$250.00
		Unit Sub Total	**EA**		**5**	**11.00**	**$303.64**	**$3,340.00**
	Item Code 692303	**Total No. of Proj.**			**5**		**Total Amount**	**$3,340.00**
692305	12" ANCHOR ASSEMBLY		EA	1	1	3.00	$350.00	$1,050.00
			EA	4	2	5.00	$600.00	$3,000.00
			EA	5	3	12.00	$448.33	$5,380.00
			EA	6	1	12.00	$112.00	$1,344.00
			EA	11	1	15.00	$180.00	$2,700.00
		Unit Sub Total	**EA**		**8**	**47.00**	**$286.68**	**$13,474.00**
	Item Code 692305	**Total No. of Proj.**			**8**		**Total Amount**	**$13,474.00**
692306	15" ANCHOR ASSEMBLY		EA	3	1	101.00	$400.00	$40,400.00
		Unit Sub Total	**EA**		**1**	**101.00**	**$400.00**	**$40,400.00**
	Item Code 692306	**Total No. of Proj.**			**1**		**Total Amount**	**$40,400.00**
692307	18" ANCHOR ASSEMBLY		EA	3	1	9.00	$400.00	$3,600.00
			EA	5	1	1.00	$325.00	$325.00
			EA	7	1	1.00	$900.00	$900.00
		Unit Sub Total	**EA**		**3**	**11.00**	**$438.64**	**$4,825.00**
	Item Code 692307	**Total No. of Proj.**			**3**		**Total Amount**	**$4,825.00**
692309	24" ANCHOR ASSEMBLY		EA	1	2	6.00	$283.33	$1,700.00
			EA	2	1	14.00	$160.00	$2,240.00
			EA	3	2	10.00	$520.00	$5,200.00
			EA	7	1	1.00	$1,660.00	$1,660.00
		Unit Sub Total	**EA**		**6**	**31.00**	**$348.39**	**$10,800.00**
	Item Code 692309	**Total No. of Proj.**			**6**		**Total Amount**	**$10,800.00**
692313	36" ANCHOR ASSEMBLY		EA	1	1	4.00	$280.50	$1,122.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**1**	**4.00**	**$280.50**	**$1,122.00**
	Item Code 692313 Total No. of Proj.			**1**		**Total Amount**	**$1,122.00**
692361	FLUME ANCHOR ASSEMBLY	EA	3	1	4.00	$200.00	$800.00
		EA	6	2	30.00	$200.00	$6,000.00
		EA	10	1	1.00	$2,500.00	$2,500.00
	Unit Sub Total	**EA**		**4**	**35.00**	**$265.71**	**$9,300.00**
	Item Code 692361 Total No. of Proj.			**4**		**Total Amount**	**$9,300.00**
692364	10" FLUME ANCHOR ASSEMBLY	EA	3	1	34.00	$100.00	$3,400.00
		EA	4	1	6.00	$94.00	$564.00
	Unit Sub Total	**EA**		**2**	**40.00**	**$99.10**	**$3,964.00**
	Item Code 692364 Total No. of Proj.			**2**		**Total Amount**	**$3,964.00**
692409	CABLE ANCHORAGE SYSTEM	LF	1	1	20.00	$145.00	$2,900.00
	Unit Sub Total	**LF**		**1**	**20.00**	**$145.00**	**$2,900.00**
692409	CABLE ANCHORAGE SYSTEM	LS	5	1	1.00	$2,000.00	$2,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$2,000.00**	**$2,000.00**
	Item Code 692409 Total No. of Proj.			**2**		**Total Amount**	**$4,900.00**
698100	18" ALTERNATIVE PIPE DOWNDRAIN	LF	11	1	130.00	$50.00	$6,500.00
	Unit Sub Total	**LF**		**1**	**130.00**	**$50.00**	**$6,500.00**
	Item Code 698100 Total No. of Proj.			**1**		**Total Amount**	**$6,500.00**
698140	24" ALTERNATIVE PIPE DOWNDRAIN	LF	1	1	52.00	$98.00	$5,096.00
	Unit Sub Total	**LF**		**1**	**52.00**	**$98.00**	**$5,096.00**
	Item Code 698140 Total No. of Proj.			**1**		**Total Amount**	**$5,096.00**
698162	450 MM ALTERNATIVE PIPE DOWNDRAIN	M	11	1	57.00	$250.00	$14,250.00
	Unit Sub Total	**M**		**1**	**57.00**	**$250.00**	**$14,250.00**
	Item Code 698162 Total No. of Proj.			**1**		**Total Amount**	**$14,250.00**
698169	600 MM ALTERNATIVE PIPE DOWNDRAIN	M	11	1	110.00	$245.00	$26,950.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M**		**1**	**110.00**	**$245.00**	**$26,950.00**
	Item Code 698169 Total No. of Proj.			**1**		**Total Amount**	**$26,950.00**
700617	DRAINAGE INLET MARKER	EA	1	1	170.00	$52.00	$8,840.00
		EA	3	2	35.00	$59.14	$2,070.00
		EA	4	7	86.00	$62.77	$5,398.00
		EA	5	1	14.00	$150.00	$2,100.00
		EA	6	2	39.00	$80.00	$3,120.00
		EA	10	1	47.00	$75.00	$3,525.00
		EA	11	1	24.00	$50.00	$1,200.00
		EA	12	1	3.00	$250.00	$750.00
	Unit Sub Total	**EA**		**16**	**418.00**	**$64.60**	**$27,003.00**
	Item Code 700617 Total No. of Proj.			**16**		**Total Amount**	**$27,003.00**
700637	36" CORRUGATED STEEL PIPE INLET (.064" THICK)	LF	10	1	5.00	$700.00	$3,500.00
	Unit Sub Total	**LF**		**1**	**5.00**	**$700.00**	**$3,500.00**
	Item Code 700637 Total No. of Proj.			**1**		**Total Amount**	**$3,500.00**
700638	36" CORRUGATED STEEL PIPE INLET (.079" THICK)	LF	1	1	12.00	$750.00	$9,000.00
	Unit Sub Total	**LF**		**1**	**12.00**	**$750.00**	**$9,000.00**
	Item Code 700638 Total No. of Proj.			**1**		**Total Amount**	**$9,000.00**
700639	36" CORRUGATED STEEL PIPE INLET (.109" THICK)	LF	1	1	6.00	$282.00	$1,692.00
		LF	2	3	36.00	$252.78	$9,100.00
		LF	3	1	9.00	$300.00	$2,700.00
		LF	4	1	3.50	$530.00	$1,855.00
		LF	8	1	3.00	$1,010.00	$3,030.00
	Unit Sub Total	**LF**		**7**	**57.50**	**$319.60**	**$18,377.00**
	Item Code 700639 Total No. of Proj.			**7**		**Total Amount**	**$18,377.00**
700640	36" CORRUGATED STEEL PIPE INLET (.138" THICK)	LF	1	1	6.00	$315.00	$1,890.00
		LF	5	1	30.00	$330.00	$9,900.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LF**		**2**	**36.00**	**$327.50**	**$11,790.00**
	Item Code 700640 Total No. of Proj.			**2**		**Total Amount**	**$11,790.00**
700641	36" CORRUGATED STEEL PIPE INLET (.168" THICK)	LF	1	3	38.40	$304.82	$11,705.00
		LF	6	1	27.00	$250.00	$6,750.00
		LF	8	1	20.00	$230.00	$4,600.00
	Unit Sub Total	**LF**		**5**	**85.40**	**$269.96**	**$23,055.00**
	Item Code 700641 Total No. of Proj.			**5**		**Total Amount**	**$23,055.00**
700655	48" CORRUGATED STEEL PIPE INLET (.109" THICK)	LF	2	1	16.00	$550.00	$8,800.00
	Unit Sub Total	**LF**		**1**	**16.00**	**$550.00**	**$8,800.00**
	Item Code 700655 Total No. of Proj.			**1**		**Total Amount**	**$8,800.00**
700658	900 MM CORRUGATED STEEL PIPE INLET (2.01 MM THICK)	M	6	1	6.00	$775.00	$4,650.00
	Unit Sub Total	**M**		**1**	**6.00**	**$775.00**	**$4,650.00**
	Item Code 700658 Total No. of Proj.			**1**		**Total Amount**	**$4,650.00**
700659	900 MM CORRUGATED STEEL PIPE INLET (2.77 MM THICK)	M	3	1	12.00	$2,000.00	$24,000.00
	Unit Sub Total	**M**		**1**	**12.00**	**$2,000.00**	**$24,000.00**
	Item Code 700659 Total No. of Proj.			**1**		**Total Amount**	**$24,000.00**
703220	18" CORRUGATED STEEL PIPE RISER (.168" THICK)	LF	5	1	9.00	$83.00	$747.00
	Unit Sub Total	**LF**		**1**	**9.00**	**$83.00**	**$747.00**
	Item Code 703220 Total No. of Proj.			**1**		**Total Amount**	**$747.00**
703223	24" CORRUGATED STEEL PIPE RISER (.079" THICK)	LF	6	1	6.00	$300.00	$1,800.00
	Unit Sub Total	**LF**		**1**	**6.00**	**$300.00**	**$1,800.00**
	Item Code 703223 Total No. of Proj.			**1**		**Total Amount**	**$1,800.00**
703233	GRATED LINE DRAIN	LF	4	1	70.00	$84.00	$5,880.00
		LF	6	2	1,316.00	$87.97	$115,772.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
703233	GRATED LINE DRAIN	LF	11	1	110.00	$110.00	$12,100.00
		LF	12	4	6,400.00	$65.87	$421,580.00
	Unit Sub Total	**LF**		**8**	**7,896.00**	**$70.33**	**$555,332.00**
703233	GRATED LINE DRAIN	M	11	1	67.00	$430.00	$28,810.00
	Unit Sub Total	**M**		**1**	**67.00**	**$430.00**	**$28,810.00**
	Item Code 703233 Total No. of Proj.			**9**		**Total Amount**	**$584,142.00**
703288	1200 MM CORRUGATED STEEL PIPE RISER (2.77 MM THICK)	M	7	2	3.80	$2,418.42	$9,190.00
	Unit Sub Total	**M**		**2**	**3.80**	**$2,418.42**	**$9,190.00**
	Item Code 703288 Total No. of Proj.			**2**		**Total Amount**	**$9,190.00**
703317	18" BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (.079" THICK)	LF	12	1	19.00	$110.00	$2,090.00
	Unit Sub Total	**LF**		**1**	**19.00**	**$110.00**	**$2,090.00**
	Item Code 703317 Total No. of Proj.			**1**		**Total Amount**	**$2,090.00**
703354	48" BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (.079" THICK)	LF	12	1	8.00	$125.00	$1,000.00
	Unit Sub Total	**LF**		**1**	**8.00**	**$125.00**	**$1,000.00**
	Item Code 703354 Total No. of Proj.			**1**		**Total Amount**	**$1,000.00**
703361	450 MM BITUMINOUS COATED CORRUGATED STEEL PIPE RISER (2.01 MM THICK)	M	7	1	33.00	$1,200.00	$39,600.00
	Unit Sub Total	**M**		**1**	**33.00**	**$1,200.00**	**$39,600.00**
	Item Code 703361 Total No. of Proj.			**1**		**Total Amount**	**$39,600.00**
703450	WELDED STEEL PIPE CASING (BRIDGE)	LF	4	1	9.00	$100.00	$900.00
		LF	12	2	119.00	$155.08	$18,455.00
	Unit Sub Total	**LF**		**3**	**128.00**	**$151.21**	**$19,355.00**
703450	WELDED STEEL PIPE CASING (BRIDGE)	M	2	1	40.00	$225.00	$9,000.00
		M	4	1	25.00	$500.00	$12,500.00
		M	7	1	46.00	$550.00	$25,300.00
		M	10	1	24.00	$240.00	$5,760.00
	Unit Sub Total	**M**		**4**	**135.00**	**$389.33**	**$52,560.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 703450 Total No. of Proj.			**7**		**Total Amount**	**$71,915.00**
703460	24" WELDED STEEL PIPE CASING (BRIDGE)	LF	3	1	136.00	$100.00	$13,600.00
		LF	4	2	475.00	$162.97	$77,410.00
		LF	5	1	158.00	$400.00	$63,200.00
		LF	11	1	80.00	$250.00	$20,000.00
		LF	12	2	382.00	$140.24	$53,570.00
	Unit Sub Total	**LF**		**7**	**1,231.00**	**$185.04**	**$227,780.00**
	Item Code 703460 Total No. of Proj.			**7**		**Total Amount**	**$227,780.00**
703481	600 MM WELDED STEEL PIPE CASING (BRIDGE)	M	11	1	50.00	$670.00	$33,500.00
	Unit Sub Total	**M**		**1**	**50.00**	**$670.00**	**$33,500.00**
	Item Code 703481 Total No. of Proj.			**1**		**Total Amount**	**$33,500.00**
703509	6" WELDED STEEL PIPE (.134" THICK)	LF	12	1	57.00	$70.00	$3,990.00
	Unit Sub Total	**LF**		**1**	**57.00**	**$70.00**	**$3,990.00**
	Item Code 703509 Total No. of Proj.			**1**		**Total Amount**	**$3,990.00**
703515	8" WELDED STEEL PIPE (.134" THICK)	LF	4	1	170.00	$190.00	$32,300.00
		LF	12	1	57.00	$80.00	$4,560.00
	Unit Sub Total	**LF**		**2**	**227.00**	**$162.38**	**$36,860.00**
	Item Code 703515 Total No. of Proj.			**2**		**Total Amount**	**$36,860.00**
703522	150 MM WELDED STEEL PIPE (3.40 MM THICK)	M	4	1	8.00	$250.00	$2,000.00
	Unit Sub Total	**M**		**1**	**8.00**	**$250.00**	**$2,000.00**
	Item Code 703522 Total No. of Proj.			**1**		**Total Amount**	**$2,000.00**
703533	12" WELDED STEEL PIPE (.250" THICK)	LF	4	1	59.00	$100.00	$5,900.00
	Unit Sub Total	**LF**		**1**	**59.00**	**$100.00**	**$5,900.00**
	Item Code 703533 Total No. of Proj.			**1**		**Total Amount**	**$5,900.00**
703542	300 MM WELDED STEEL PIPE (2.67 MM THICK)	M	4	1	61.00	$275.00	$16,775.00
	Unit Sub Total	**M**		**1**	**61.00**	**$275.00**	**$16,775.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 703542 Total No. of Proj.			**1**		**Total Amount**	**$16,775.00**
703543	300 MM WELDED STEEL PIPE (3.40 MM THICK)	M	4	1	3.10	$700.00	$2,170.00
	Unit Sub Total	**M**		**1**	**3.10**	**$700.00**	**$2,170.00**
	Item Code 703543 Total No. of Proj.			**1**		**Total Amount**	**$2,170.00**
703575	24" WELDED STEEL PIPE (.250" THICK)	LF	1	1	140.00	$585.00	$81,900.00
	Unit Sub Total	**LF**		**1**	**140.00**	**$585.00**	**$81,900.00**
	Item Code 703575 Total No. of Proj.			**1**		**Total Amount**	**$81,900.00**
703620	36" WELDED STEEL PIPE (.375" THICK)	LF	1	1	72.00	$450.00	$32,400.00
	Unit Sub Total	**LF**		**1**	**72.00**	**$450.00**	**$32,400.00**
	Item Code 703620 Total No. of Proj.			**1**		**Total Amount**	**$32,400.00**
704133	JACKED 12" WELDED STEEL PIPE (.250" THICK)	LF	2	1	250.00	$120.79	$30,197.50
	Unit Sub Total	**LF**		**1**	**250.00**	**$120.79**	**$30,197.50**
	Item Code 704133 Total No. of Proj.			**1**		**Total Amount**	**$30,197.50**
704157	JACKED 18" WELDED STEEL PIPE (.375" THICK)	LF	6	1	200.00	$384.00	$76,800.00
	Unit Sub Total	**LF**		**1**	**200.00**	**$384.00**	**$76,800.00**
	Item Code 704157 Total No. of Proj.			**1**		**Total Amount**	**$76,800.00**
704189	JACKED 600 MM WELDED STEEL PIPE (6.35 MM THICK)	M	6	1	27.00	$1,900.00	$51,300.00
	Unit Sub Total	**M**		**1**	**27.00**	**$1,900.00**	**$51,300.00**
	Item Code 704189 Total No. of Proj.			**1**		**Total Amount**	**$51,300.00**
705007	12" STEEL FLARED END SECTION	EA	3	1	3.00	$200.00	$600.00
		EA	6	2	14.00	$122.00	$1,708.00
	Unit Sub Total	**EA**		**3**	**17.00**	**$135.76**	**$2,308.00**
	Item Code 705007 Total No. of Proj.			**3**		**Total Amount**	**$2,308.00**
705011	18" STEEL FLARED END SECTION	EA	1	3	4.00	$462.50	$1,850.00
		EA	2	3	34.00	$313.36	$10,654.30
		EA	3	3	20.00	$474.00	$9,480.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
705011	18" STEEL FLARED END SECTION		EA	5	1	1.00	$418.00	$418.00
			EA	6	1	4.00	$600.00	$2,400.00
			EA	7	1	1.00	$1,400.00	$1,400.00
			EA	8	3	8.00	$912.50	$7,300.00
		Unit Sub Total	**EA**		**15**	**72.00**	**$465.31**	**$33,502.30**
	Item Code 705011	**Total No. of Proj.**			**15**		**Total Amount**	**$33,502.30**
705015	24" STEEL FLARED END SECTION		EA	1	3	5.00	$257.00	$1,285.00
			EA	2	5	15.00	$271.90	$4,078.56
			EA	3	3	29.00	$655.17	$19,000.00
			EA	5	1	1.00	$618.00	$618.00
			EA	6	1	3.00	$800.00	$2,400.00
			EA	7	1	1.00	$1,330.00	$1,330.00
			EA	8	1	1.00	$1,350.00	$1,350.00
			EA	10	1	1.00	$200.00	$200.00
		Unit Sub Total	**EA**		**16**	**56.00**	**$540.39**	**$30,261.56**
	Item Code 705015	**Total No. of Proj.**			**16**		**Total Amount**	**$30,261.56**
705019	30" STEEL FLARED END SECTION		EA	3	1	10.00	$550.00	$5,500.00
		Unit Sub Total	**EA**		**1**	**10.00**	**$550.00**	**$5,500.00**
	Item Code 705019	**Total No. of Proj.**			**1**		**Total Amount**	**$5,500.00**
705023	36" STEEL FLARED END SECTION		EA	1	1	1.00	$661.50	$661.50
			EA	2	1	2.00	$450.00	$900.00
			EA	3	1	9.00	$700.00	$6,300.00
			EA	6	1	2.00	$2,150.00	$4,300.00
		Unit Sub Total	**EA**		**4**	**14.00**	**$868.68**	**$12,161.50**
	Item Code 705023	**Total No. of Proj.**			**4**		**Total Amount**	**$12,161.50**
705027	42" STEEL FLARED END SECTION		EA	3	1	3.00	$800.00	$2,400.00
		Unit Sub Total	**EA**		**1**	**3.00**	**$800.00**	**$2,400.00**
	Item Code 705027	**Total No. of Proj.**			**1**		**Total Amount**	**$2,400.00**
705031	48" STEEL FLARED END SECTION		EA	3	1	5.00	$900.00	$4,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**1**	**5.00**	**$900.00**	**$4,500.00**
	Item Code 705031 Total No. of Proj.			**1**		**Total Amount**	**$4,500.00**
705044	450 MM STEEL FLARED END SECTION	EA	7	1	1.00	$525.00	$525.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$525.00**	**$525.00**
	Item Code 705044 Total No. of Proj.			**1**		**Total Amount**	**$525.00**
705045	600 MM STEEL FLARED END SECTION	EA	2	1	2.00	$400.00	$800.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$400.00**	**$800.00**
	Item Code 705045 Total No. of Proj.			**1**		**Total Amount**	**$800.00**
705204	18" CONCRETE FLARED END SECTION	EA	3	2	5.00	$551.40	$2,757.00
		EA	10	2	5.00	$808.00	$4,040.00
	Unit Sub Total	**EA**		**4**	**10.00**	**$679.70**	**$6,797.00**
	Item Code 705204 Total No. of Proj.			**4**		**Total Amount**	**$6,797.00**
705206	24" CONCRETE FLARED END SECTION	EA	3	2	7.00	$546.71	$3,827.00
		EA	6	3	25.00	$702.28	$17,557.00
		EA	10	2	4.00	$891.23	$3,564.90
	Unit Sub Total	**EA**		**7**	**36.00**	**$693.03**	**$24,948.90**
	Item Code 705206 Total No. of Proj.			**7**		**Total Amount**	**$24,948.90**
705208	30" CONCRETE FLARED END SECTION	EA	4	1	1.00	$700.00	$700.00
		EA	6	1	2.00	$900.00	$1,800.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$833.33**	**$2,500.00**
	Item Code 705208 Total No. of Proj.			**2**		**Total Amount**	**$2,500.00**
705212	42" CONCRETE FLARED END SECTION	EA	4	1	1.00	$980.00	$980.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$980.00**	**$980.00**
	Item Code 705212 Total No. of Proj.			**1**		**Total Amount**	**$980.00**
705214	48" CONCRETE FLARED END SECTION	EA	4	1	1.00	$1,300.00	$1,300.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,300.00**	**$1,300.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 705214 Total No. of Proj.			**1**		**Total Amount**	**$1,300.00**
705220	300 MM CONCRETE FLARED END SECTION	EA	7	1	1.00	$1,050.00	$1,050.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,050.00**	**$1,050.00**
	Item Code 705220 Total No. of Proj.			**1**		**Total Amount**	**$1,050.00**
705222	450 MM CONCRETE FLARED END SECTION	EA	6	1	1.00	$6,132.00	$6,132.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$6,132.00**	**$6,132.00**
	Item Code 705222 Total No. of Proj.			**1**		**Total Amount**	**$6,132.00**
705224	600 MM CONCRETE FLARED END SECTION	EA	7	1	5.00	$1,025.00	$5,125.00
	Unit Sub Total	**EA**		**1**	**5.00**	**$1,025.00**	**$5,125.00**
	Item Code 705224 Total No. of Proj.			**1**		**Total Amount**	**$5,125.00**
705307	12" ALTERNATIVE FLARED END SECTION	EA	4	1	1.00	$400.00	$400.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$400.00**	**$400.00**
	Item Code 705307 Total No. of Proj.			**1**		**Total Amount**	**$400.00**
705309	15" ALTERNATIVE FLARED END SECTION	EA	5	1	1.00	$88.00	$88.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$88.00**	**$88.00**
	Item Code 705309 Total No. of Proj.			**1**		**Total Amount**	**$88.00**
705311	18" ALTERNATIVE FLARED END SECTION	EA	4	4	22.00	$297.27	$6,540.00
		EA	5	2	9.00	$344.16	$3,097.40
		EA	10	2	39.00	$312.95	$12,205.00
		EA	12	4	18.00	$426.56	$7,678.00
	Unit Sub Total	**EA**		**12**	**88.00**	**$335.46**	**$29,520.40**
	Item Code 705311 Total No. of Proj.			**12**		**Total Amount**	**$29,520.40**
705315	24" ALTERNATIVE FLARED END SECTION	EA	1	2	3.00	$350.00	$1,050.00
		EA	2	1	8.00	$218.38	$1,747.04
		EA	4	2	7.00	$214.29	$1,500.00
		EA	5	3	47.00	$390.02	$18,330.90
		EA	10	1	15.00	$500.00	$7,500.00
		EA	12	3	9.00	$603.33	$5,430.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**12**	**89.00**	**$399.53**	**$35,557.94**
	Item Code 705315 Total No. of Proj.			**12**		**Total Amount**	**$35,557.94**
705319	30" ALTERNATIVE FLARED END SECTION	EA	1	1	1.00	$500.00	$500.00
		EA	5	2	4.00	$503.49	$2,013.97
		EA	10	1	4.00	$525.00	$2,100.00
		EA	12	1	1.00	$1,160.00	$1,160.00
	Unit Sub Total	**EA**		**5**	**10.00**	**$577.40**	**$5,773.97**
	Item Code 705319 Total No. of Proj.			**5**		**Total Amount**	**$5,773.97**
705321	36" ALTERNATIVE FLARED END SECTION	EA	4	2	3.00	$766.67	$2,300.00
		EA	5	1	4.00	$702.72	$2,810.88
	Unit Sub Total	**EA**		**3**	**7.00**	**$730.13**	**$5,110.88**
	Item Code 705321 Total No. of Proj.			**3**		**Total Amount**	**$5,110.88**
705325	48" ALTERNATIVE FLARED END SECTION	EA	12	1	1.00	$1,300.00	$1,300.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,300.00**	**$1,300.00**
	Item Code 705325 Total No. of Proj.			**1**		**Total Amount**	**$1,300.00**
705334	300 MM ALTERNATIVE FLARED END SECTION	EA	3	1	27.00	$500.00	$13,500.00
		EA	10	1	2.00	$200.00	$400.00
	Unit Sub Total	**EA**		**2**	**29.00**	**$479.31**	**$13,900.00**
	Item Code 705334 Total No. of Proj.			**2**		**Total Amount**	**$13,900.00**
705336	450 MM ALTERNATIVE FLARED END SECTION	EA	3	1	10.00	$800.00	$8,000.00
		EA	4	2	4.00	$262.50	$1,050.00
		EA	6	1	54.00	$215.00	$11,610.00
		EA	10	1	1.00	$250.00	$250.00
	Unit Sub Total	**EA**		**5**	**69.00**	**$303.04**	**$20,910.00**
	Item Code 705336 Total No. of Proj.			**5**		**Total Amount**	**$20,910.00**
705337	600 MM ALTERNATIVE FLARED END SECTION	EA	4	2	5.00	$400.00	$2,000.00
		EA	6	1	32.00	$255.00	$8,160.00
		EA	10	1	7.00	$325.00	$2,275.00
		EA	11	1	8.00	$280.00	$2,240.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**5**	**52.00**	**$282.21**	**$14,675.00**
	Item Code 705337 Total No. of Proj.			**5**		**Total Amount**	**$14,675.00**
705338	750 MM ALTERNATIVE FLARED END SECTION	EA	4	1	3.00	$500.00	$1,500.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$500.00**	**$1,500.00**
	Item Code 705338 Total No. of Proj.			**1**		**Total Amount**	**$1,500.00**
705339	900 MM ALTERNATIVE FLARED END SECTION	EA	6	1	26.00	$510.00	$13,260.00
		EA	11	1	2.00	$285.00	$570.00
	Unit Sub Total	**EA**		**2**	**28.00**	**$493.93**	**$13,830.00**
	Item Code 705339 Total No. of Proj.			**2**		**Total Amount**	**$13,830.00**
705403	21" X 15" STEEL FLARED END PIPE ARCH SECTION	EA	3	1	2.00	$798.00	$1,596.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$798.00**	**$1,596.00**
	Item Code 705403 Total No. of Proj.			**1**		**Total Amount**	**$1,596.00**
705500	AUTOMATIC DRAINAGE GATE	EA	10	1	3.00	$1,500.00	$4,500.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$1,500.00**	**$4,500.00**
	Item Code 705500 Total No. of Proj.			**1**		**Total Amount**	**$4,500.00**
705566	600 MM AUTOMATIC DRAINAGE GATE	EA	7	1	1.00	$1,550.00	$1,550.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,550.00**	**$1,550.00**
	Item Code 705566 Total No. of Proj.			**1**		**Total Amount**	**$1,550.00**
705651	600 MM SLIDE HEADGATE	EA	4	1	2.00	$2,800.00	$5,600.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$2,800.00**	**$5,600.00**
	Item Code 705651 Total No. of Proj.			**1**		**Total Amount**	**$5,600.00**
706584	DEBRIS RACK CAGE	EA	4	1	1.00	$2,500.00	$2,500.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$2,500.00**	**$2,500.00**
	Item Code 706584 Total No. of Proj.			**1**		**Total Amount**	**$2,500.00**
707050	DRAINAGE INLET	EA	3	1	1.00	$1,700.00	$1,700.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,700.00**	**$1,700.00**
	Item Code 707050 Total No. of Proj.			**1**		**Total Amount**	**$1,700.00**
707051	DRAINAGE MANHOLE	EA	4	1	1.00	$5,000.00	$5,000.00
		EA	5	1	1.00	$4,200.00	$4,200.00
	Unit Sub Total	**EA**		**2**	**2.00**	**$4,600.00**	**$9,200.00**
	Item Code 707051 Total No. of Proj.			**2**		**Total Amount**	**$9,200.00**
707102	12" PRECAST CONCRETE PIPE INLET	LF	7	1	2.00	$1,100.00	$2,200.00
	Unit Sub Total	**LF**		**1**	**2.00**	**$1,100.00**	**$2,200.00**
	Item Code 707102 Total No. of Proj.			**1**		**Total Amount**	**$2,200.00**
707117	36" PRECAST CONCRETE PIPE INLET	LF	2	1	6.40	$200.00	$1,280.00
		LF	3	1	7.00	$2,600.00	$18,200.00
		LF	5	1	26.00	$215.00	$5,590.00
		LF	10	1	19.00	$400.00	$7,600.00
		LF	11	1	4.80	$325.00	$1,560.00
		LF	12	1	80.00	$300.00	$24,000.00
	Unit Sub Total	**LF**		**6**	**143.20**	**$406.63**	**$58,230.00**
	Item Code 707117 Total No. of Proj.			**6**		**Total Amount**	**$58,230.00**
707225	48" PRECAST CONCRETE PIPE MANHOLE	EA	6	1	2.00	$10,500.00	$21,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$10,500.00**	**$21,000.00**
707225	48" PRECAST CONCRETE PIPE MANHOLE	LF	3	1	40.00	$694.40	$27,776.00
	Unit Sub Total	**LF**		**1**	**40.00**	**$694.40**	**$27,776.00**
	Item Code 707225 Total No. of Proj.			**2**		**Total Amount**	**$48,776.00**
707241	72" PRECAST CONCRETE PIPE MANHOLE	LF	2	1	13.00	$150.00	$1,950.00
	Unit Sub Total	**LF**		**1**	**13.00**	**$150.00**	**$1,950.00**
	Item Code 707241 Total No. of Proj.			**1**		**Total Amount**	**$1,950.00**
707242	600 MM PRECAST CONCRETE PIPE MANHOLE	M	7	1	5.70	$1,450.00	$8,265.00
	Unit Sub Total	**M**		**1**	**5.70**	**$1,450.00**	**$8,265.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 707242 Total No. of Proj.			**1**		**Total Amount**	**$8,265.00**
707244	900 MM PRECAST CONCRETE PIPE MANHOLE	M	7	3	7.80	$854.10	$6,662.00
	Unit Sub Total	**M**		**3**	**7.80**	**$854.10**	**$6,662.00**
	Item Code 707244 Total No. of Proj.			**3**		**Total Amount**	**$6,662.00**
707467	36" REINFORCED CONCRETE PIPE RISER	LF	11	1	13.00	$208.00	$2,704.00
	Unit Sub Total	**LF**		**1**	**13.00**	**$208.00**	**$2,704.00**
	Item Code 707467 Total No. of Proj.			**1**		**Total Amount**	**$2,704.00**
708021	36" ALTERNATIVE PIPE INLET	LF	10	2	75.00	$211.12	$15,833.85
	Unit Sub Total	**LF**		**2**	**75.00**	**$211.12**	**$15,833.85**
	Item Code 708021 Total No. of Proj.			**2**		**Total Amount**	**$15,833.85**
708064	450 MM ALTERNATIVE PIPE RISER	M	11	1	12.00	$820.00	$9,840.00
	Unit Sub Total	**M**		**1**	**12.00**	**$820.00**	**$9,840.00**
	Item Code 708064 Total No. of Proj.			**1**		**Total Amount**	**$9,840.00**
708068	900 MM ALTERNATIVE PIPE RISER	M	11	1	24.00	$500.00	$12,000.00
	Unit Sub Total	**M**		**1**	**24.00**	**$500.00**	**$12,000.00**
	Item Code 708068 Total No. of Proj.			**1**		**Total Amount**	**$12,000.00**
717077	200 MM POLYVINYL CHLORIDE SEWER PIPE	M	4	1	250.00	$200.00	$50,000.00
	Unit Sub Total	**M**		**1**	**250.00**	**$200.00**	**$50,000.00**
	Item Code 717077 Total No. of Proj.			**1**		**Total Amount**	**$50,000.00**
719200	SEWER MANHOLE	EA	2	1	5.00	$6,301.91	$31,509.55
		EA	4	1	8.00	$7,000.00	$56,000.00
	Unit Sub Total	**EA**		**2**	**13.00**	**$6,731.50**	**$87,509.55**
	Item Code 719200 Total No. of Proj.			**2**		**Total Amount**	**$87,509.55**
719305	MANHOLE (TYPE A)	EA	5	1	6.00	$3,500.00	$21,000.00
	Unit Sub Total	**EA**		**1**	**6.00**	**$3,500.00**	**$21,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 719305 Total No. of Proj.			**1**		**Total Amount**	**$21,000.00**
719306	MANHOLE (TYPE B)	EA	10	1	1.00	$2,300.00	$2,300.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$2,300.00**	**$2,300.00**
	Item Code 719306 Total No. of Proj.			**1**		**Total Amount**	**$2,300.00**
719569	MINOR CONCRETE (PIPE ENCASEMENT)	M3	4	1	9.00	$1,000.00	$9,000.00
	Unit Sub Total	**M3**		**1**	**9.00**	**$1,000.00**	**$9,000.00**
	Item Code 719569 Total No. of Proj.			**1**		**Total Amount**	**$9,000.00**
719589	MINOR CONCRETE (BACKFILL)	CY	1	1	3.20	$130.00	$416.00
		CY	3	1	110.00	$124.00	$13,640.00
		CY	4	2	266.00	$191.88	$51,040.00
		CY	12	2	52.00	$67.75	$3,523.00
	Unit Sub Total	**CY**		**6**	**431.20**	**$159.13**	**$68,619.00**
	Item Code 719589 Total No. of Proj.			**6**		**Total Amount**	**$68,619.00**
719598	CLASS 4 CONCRETE (BACKFILL)	CY	3	1	28.00	$300.00	$8,400.00
	Unit Sub Total	**CY**		**1**	**28.00**	**$300.00**	**$8,400.00**
719598	CLASS 4 CONCRETE (BACKFILL)	M3	11	1	8.00	$650.00	$5,200.00
	Unit Sub Total	**M3**		**1**	**8.00**	**$650.00**	**$5,200.00**
	Item Code 719598 Total No. of Proj.			**2**		**Total Amount**	**$13,600.00**
720104	ROCK SLOPE PROTECTION (1 TON, METHOD A)	CY	3	1	2,250.00	$62.00	$139,500.00
		CY	4	1	680.00	$70.00	$47,600.00
	Unit Sub Total	**CY**		**2**	**2,930.00**	**$63.86**	**$187,100.00**
	Item Code 720104 Total No. of Proj.			**2**		**Total Amount**	**$187,100.00**
720106	ROCK SLOPE PROTECTION (1/2 TON, METHOD A)	CY	1	1	43.00	$90.00	$3,870.00
		CY	3	1	7,300.00	$60.00	$438,000.00
		CY	4	1	440.00	$70.00	$30,800.00
		CY	8	1	34.00	$105.00	$3,570.00
		CY	12	1	48.00	$130.00	$6,240.00
	Unit Sub Total	**CY**		**5**	**7,865.00**	**$61.35**	**$482,480.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 720106 Total No. of Proj.			**5**		**Total Amount**	**$482,480.00**
720107	ROCK SLOPE PROTECTION(GRANULAR MATERIAL)	CY	2	2	83.00	$111.14	$9,225.00
	Unit Sub Total	**CY**		**2**	**83.00**	**$111.14**	**$9,225.00**
	Item Code 720107 Total No. of Proj.			**2**		**Total Amount**	**$9,225.00**
720117	ROCK SLOPE PROTECTION (4T, METHOD A)	CY	4	1	25.00	$160.00	$4,000.00
		CY	5	1	500.00	$136.00	$68,000.00
	Unit Sub Total	**CY**		**2**	**525.00**	**$137.14**	**$72,000.00**
	Item Code 720117 Total No. of Proj.			**2**		**Total Amount**	**$72,000.00**
720118	ROCK SLOPE PROTECTION (2T, METHOD A)	M3	7	1	3,370.00	$130.00	$438,100.00
	Unit Sub Total	**M3**		**1**	**3,370.00**	**$130.00**	**$438,100.00**
720118	ROCK SLOPE PROTECTION (2T, METHOD A)	TON	1	1	60.00	$90.00	$5,400.00
	Unit Sub Total	**TON**		**1**	**60.00**	**$90.00**	**$5,400.00**
	Item Code 720118 Total No. of Proj.			**2**		**Total Amount**	**$443,500.00**
720119	ROCK SLOPE PROTECTION (1T, METHOD A)	M3	6	1	6,080.00	$75.00	$456,000.00
	Unit Sub Total	**M3**		**1**	**6,080.00**	**$75.00**	**$456,000.00**
	Item Code 720119 Total No. of Proj.			**1**		**Total Amount**	**$456,000.00**
721004	ROCK SLOPE PROTECTION (1 TON, METHOD B)	CY	1	1	15.00	$145.00	$2,175.00
		CY	12	1	19.00	$200.00	$3,800.00
	Unit Sub Total	**CY**		**2**	**34.00**	**$175.74**	**$5,975.00**
	Item Code 721004 Total No. of Proj.			**2**		**Total Amount**	**$5,975.00**
721006	ROCK SLOPE PROTECTION (1/2 TON, METHOD B)	CY	1	3	163.00	$86.07	$14,030.00
		CY	2	1	14.00	$155.00	$2,170.00
		CY	4	1	510.00	$81.00	$41,310.00
		CY	5	1	4,280.00	$56.00	$239,680.00
		CY	11	1	1,320.00	$60.00	$79,200.00
	Unit Sub Total	**CY**		**7**	**6,287.00**	**$59.87**	**$376,390.00**
	Item Code 721006 Total No. of Proj.			**7**		**Total Amount**	**$376,390.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
721007	ROCK SLOPE PROTECTION (1/4 TON, METHOD B)	CY	1	5	1,685.00	$104.93	$176,805.00
		CY	3	2	12,890.00	$50.71	$653,700.00
		CY	4	3	600.00	$112.71	$67,628.00
		CY	5	3	3,354.00	$112.76	$378,210.00
		CY	12	1	34.00	$138.00	$4,692.00
	Unit Sub Total	**CY**		**14**	**18,563.00**	**$69.01**	**$1,281,035.00**
721007	ROCK SLOPE PROTECTION (1/4 TON, METHOD B)	M3	4	1	2,100.00	$100.00	$210,000.00
	Unit Sub Total	**M3**		**1**	**2,100.00**	**$100.00**	**$210,000.00**
721007	ROCK SLOPE PROTECTION (1/4 TON, METHOD B)	TON	2	1	78.00	$50.00	$3,900.00
	Unit Sub Total	**TON**		**1**	**78.00**	**$50.00**	**$3,900.00**
	Item Code 721007 Total No. of Proj.			**16**		**Total Amount**	**$1,494,935.00**
721008	ROCK SLOPE PROTECTION (LIGHT, METHOD B)	CY	1	8	81.90	$217.00	$17,772.50
		CY	2	1	55.00	$250.00	$13,750.00
		CY	3	3	369.00	$71.10	$26,237.00
		CY	4	2	990.00	$65.72	$65,058.00
		CY	5	1	3,700.00	$62.00	$229,400.00
		CY	6	1	620.00	$90.00	$55,800.00
		CY	8	1	120.00	$120.00	$14,400.00
		CY	10	3	77.00	$123.18	$9,485.00
		CY	12	2	14.00	$236.29	$3,308.00
	Unit Sub Total	**CY**		**22**	**6,026.90**	**$72.21**	**$435,210.50**
721008	ROCK SLOPE PROTECTION (LIGHT, METHOD B)	M3	4	1	343.00	$160.00	$54,880.00
		M3	6	1	3,530.00	$70.00	$247,100.00
	Unit Sub Total	**M3**		**2**	**3,873.00**	**$77.97**	**$301,980.00**
721008	ROCK SLOPE PROTECTION (LIGHT, METHOD B)	TON	1	1	12.00	$490.00	$5,880.00
		TON	2	1	250.00	$55.55	$13,887.50
	Unit Sub Total	**TON**		**2**	**262.00**	**$75.45**	**$19,767.50**
	Item Code 721008 Total No. of Proj.			**26**		**Total Amount**	**$756,958.00**
721009	ROCK SLOPE PROTECTION (FACING, METHOD B)	CY	1	6	121.60	$207.65	$25,250.00
		CY	2	2	32.00	$88.31	$2,826.00
		CY	3	1	350.00	$70.00	$24,500.00
		CY	4	3	15.10	$310.80	$4,693.10

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
721009	ROCK SLOPE PROTECTION (FACING, METHOD B)	CY	5	1	2.00	$250.00	$500.00
		CY	6	1	16.00	$1,205.00	$19,280.00
		CY	7	2	12.00	$380.00	$4,560.00
		CY	8	1	6.00	$108.00	$648.00
		CY	9	1	9.00	$250.00	$2,250.00
		CY	12	3	246.00	$102.78	$25,284.00
	Unit Sub Total	**CY**		**21**	**809.70**	**$135.59**	**$109,791.10**
721009	ROCK SLOPE PROTECTION (FACING, METHOD B)	M3	2	1	25.00	$115.00	$2,875.00
		M3	4	1	150.00	$120.00	$18,000.00
		M3	6	2	1,117.00	$71.44	$79,800.00
		M3	7	4	84.60	$209.70	$17,740.80
		M3	10	1	44.00	$140.00	$6,160.00
		M3	11	2	81.00	$152.62	$12,362.00
	Unit Sub Total	**M3**		**11**	**1,501.60**	**$91.19**	**$136,937.80**
721009	ROCK SLOPE PROTECTION (FACING, METHOD B)	TON	2	1	100.00	$55.55	$5,555.00
		TON	12	2	52.00	$208.31	$10,832.00
	Unit Sub Total	**TON**		**3**	**152.00**	**$107.81**	**$16,387.00**
	Item Code 721009 Total No. of Proj.			**35**		**Total Amount**	**$263,115.90**
721010	ROCK SLOPE PROTECTION (BACKING NO. 1, METHOD B)	CY	2	2	142.00	$51.83	$7,360.00
		CY	4	5	588.00	$84.40	$49,625.00
		CY	5	1	1,630.00	$76.00	$123,880.00
		CY	8	1	18.00	$105.00	$1,890.00
		CY	10	1	240.00	$146.80	$35,232.00
		CY	11	1	510.00	$60.00	$30,600.00
	Unit Sub Total	**CY**		**11**	**3,128.00**	**$79.47**	**$248,587.00**
721010	ROCK SLOPE PROTECTION (BACKING NO. 1, METHOD B)	TON	2	1	2.20	$124.06	$272.93
		TON	4	1	59.00	$90.00	$5,310.00
	Unit Sub Total	**TON**		**2**	**61.20**	**$91.22**	**$5,582.93**
	Item Code 721010 Total No. of Proj.			**13**		**Total Amount**	**$254,169.93**
721011	ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	CY	1	4	236.00	$117.17	$27,651.00
		CY	2	2	13.00	$168.23	$2,187.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
721011	ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	CY	3	1	4.50	$142.44	$640.98
		CY	4	5	213.00	$153.93	$32,787.50
		CY	5	2	2,301.00	$76.33	$175,641.00
		CY	6	3	19.20	$221.06	$4,244.40
		CY	8	2	9.70	$424.23	$4,115.00
		CY	10	1	160.00	$30.00	$4,800.00
		CY	11	1	10.00	$290.00	$2,900.00
		CY	12	1	13.00	$163.00	$2,119.00
	Unit Sub Total	**CY**		**22**	**2,979.40**	**$86.29**	**$257,085.88**
721011	ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	M3	4	2	54.00	$163.89	$8,850.00
	Unit Sub Total	**M3**		**2**	**54.00**	**$163.89**	**$8,850.00**
721011	ROCK SLOPE PROTECTION (BACKING NO. 2, METHOD B)	TON	4	1	86.00	$190.00	$16,340.00
	Unit Sub Total	**TON**		**1**	**86.00**	**$190.00**	**$16,340.00**
	Item Code 721011 Total No. of Proj.			**25**		**Total Amount**	**$282,275.88**
721012	ROCK SLOPE PROTECTION (BACKING NO. 3, METHOD B)	CY	1	2	69.50	$129.04	$8,968.50
		CY	2	1	15.00	$160.00	$2,400.00
		CY	4	2	71.30	$152.95	$10,905.00
		CY	6	1	4.00	$195.00	$780.00
	Unit Sub Total	**CY**		**6**	**159.80**	**$144.26**	**$23,053.50**
721012	ROCK SLOPE PROTECTION (BACKING NO. 3, METHOD B)	M3	4	1	0.30	$3,000.00	$900.00
		M3	11	1	45.00	$155.00	$6,975.00
	Unit Sub Total	**M3**		**2**	**45.30**	**$173.84**	**$7,875.00**
721012	ROCK SLOPE PROTECTION (BACKING NO. 3, METHOD B)	TON	2	4	195.70	$67.13	$13,137.00
	Unit Sub Total	**TON**		**4**	**195.70**	**$67.13**	**$13,137.00**
	Item Code 721012 Total No. of Proj.			**12**		**Total Amount**	**$44,065.50**
721023	ROCK SLOPE PROTECTION (1/2T, METHOD B)	CY	4	1	25.00	$156.00	$3,900.00
	Unit Sub Total	**CY**		**1**	**25.00**	**$156.00**	**$3,900.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 721023 Total No. of Proj.			**1**		**Total Amount**	**$3,900.00**
721024	ROCK SLOPE PROTECTION (1/4T, METHOD B)	CY	1	1	55.00	$122.50	$6,737.50
		CY	4	2	600.00	$158.23	$94,940.00
	Unit Sub Total	**CY**		**3**	**655.00**	**$155.23**	**$101,677.50**
721024	ROCK SLOPE PROTECTION (1/4T, METHOD B)	M3	6	1	170.00	$70.00	$11,900.00
	Unit Sub Total	**M3**		**1**	**170.00**	**$70.00**	**$11,900.00**
	Item Code 721024 Total No. of Proj.			**4**		**Total Amount**	**$113,577.50**
721400	CONCRETE (SLOPE PROTECTION)	CY	5	1	75.00	$370.00	$27,750.00
	Unit Sub Total	**CY**		**1**	**75.00**	**$370.00**	**$27,750.00**
721400	CONCRETE (SLOPE PROTECTION)	M3	11	1	150.00	$720.00	$108,000.00
	Unit Sub Total	**M3**		**1**	**150.00**	**$720.00**	**$108,000.00**
	Item Code 721400 Total No. of Proj.			**2**		**Total Amount**	**$135,750.00**
721410	CONCRETE (GUTTER LINING)	M3	4	1	5.00	$1,000.00	$5,000.00
	Unit Sub Total	**M3**		**1**	**5.00**	**$1,000.00**	**$5,000.00**
	Item Code 721410 Total No. of Proj.			**1**		**Total Amount**	**$5,000.00**
721420	CONCRETE (DITCH LINING)	CY	5	1	510.00	$390.00	$198,900.00
		CY	11	1	24.00	$400.00	$9,600.00
		CY	12	2	1,450.00	$300.62	$435,900.00
	Unit Sub Total	**CY**		**4**	**1,984.00**	**$324.80**	**$644,400.00**
	Item Code 721420 Total No. of Proj.			**4**		**Total Amount**	**$644,400.00**
721430	CONCRETE (CHANNEL LINING)	M3	4	1	3.00	$1,500.00	$4,500.00
		M3	7	1	195.00	$590.00	$115,050.00
	Unit Sub Total	**M3**		**2**	**198.00**	**$603.79**	**$119,550.00**
	Item Code 721430 Total No. of Proj.			**2**		**Total Amount**	**$119,550.00**
721431	CONCRETE (CONCRETE APRON)	CY	5	1	73.00	$675.00	$49,275.00
	Unit Sub Total	**CY**		**1**	**73.00**	**$675.00**	**$49,275.00**
	Item Code 721431 Total No. of Proj.			**1**		**Total Amount**	**$49,275.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
721501	CONCRETE (CONCRETED-ROCK SLOPE PROTECTION)	CY	3	1	12.00	$400.00	$4,800.00
	Unit Sub Total	**CY**		**1**	**12.00**	**$400.00**	**$4,800.00**
	Item Code 721501 Total No. of Proj.			**1**		**Total Amount**	**$4,800.00**
721609	CONCRETED-ROCK SLOPE PROTECTION (FACING, METHOD B)	CY	3	1	60.00	$250.00	$15,000.00
	Unit Sub Total	**CY**		**1**	**60.00**	**$250.00**	**$15,000.00**
721609	CONCRETED-ROCK SLOPE PROTECTION (FACING, METHOD B)	M3	2	1	40.00	$210.00	$8,400.00
		M3	3	1	9.00	$500.00	$4,500.00
	Unit Sub Total	**M3**		**2**	**49.00**	**$263.27**	**$12,900.00**
	Item Code 721609 Total No. of Proj.			**3**		**Total Amount**	**$27,900.00**
721616	CONCRETED-ROCK SLOPE PROTECTION (COBBLE, METHOD B)	M3	3	1	28.00	$350.00	$9,800.00
	Unit Sub Total	**M3**		**1**	**28.00**	**$350.00**	**$9,800.00**
	Item Code 721616 Total No. of Proj.			**1**		**Total Amount**	**$9,800.00**
721810	SLOPE PAVING (CONCRETE)	CY	4	2	167.00	$980.54	$163,750.00
		CY	6	1	2.00	$2,500.00	$5,000.00
		CY	11	1	1,190.00	$510.00	$606,900.00
		CY	12	5	689.00	$548.39	$377,840.00
	Unit Sub Total	**CY**		**9**	**2,048.00**	**$563.23**	**$1,153,490.00**
721810	SLOPE PAVING (CONCRETE)	M3	4	1	33.00	$750.00	$24,750.00
		M3	7	1	205.00	$500.00	$102,500.00
		M3	11	2	199.00	$746.48	$148,550.00
	Unit Sub Total	**M3**		**4**	**437.00**	**$631.12**	**$275,800.00**
	Item Code 721810 Total No. of Proj.			**13**		**Total Amount**	**$1,429,290.00**
722020	GABION	CF	3	1	410.00	$9.00	$3,690.00
	Unit Sub Total	**CF**		**1**	**410.00**	**$9.00**	**$3,690.00**
722020	GABION	CY	2	1	350.00	$225.00	$78,750.00
		CY	10	1	2,400.00	$143.10	$343,440.00
	Unit Sub Total	**CY**		**2**	**2,750.00**	**$153.52**	**$422,190.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
722020	GABION	M3	7	3	104.00	$341.59	$35,525.00
	Unit Sub Total	**M3**		**3**	**104.00**	**$341.59**	**$35,525.00**
	Item Code 722020 Total No. of Proj.			**6**		**Total Amount**	**$461,405.00**
727901	MINOR CONCRETE (DITCH LINING)	CY	3	1	270.00	$188.00	$50,760.00
		CY	4	3	32.30	$620.20	$20,032.50
		CY	11	1	69.00	$390.00	$26,910.00
		CY	12	1	240.00	$394.00	$94,560.00
	Unit Sub Total	**CY**		**6**	**611.30**	**$314.51**	**$192,262.50**
727901	MINOR CONCRETE (DITCH LINING)	M3	4	1	52.00	$400.00	$20,800.00
		M3	7	1	130.00	$520.00	$67,600.00
		M3	11	1	75.00	$400.00	$30,000.00
	Unit Sub Total	**M3**		**3**	**257.00**	**$460.70**	**$118,400.00**
	Item Code 727901 Total No. of Proj.			**9**		**Total Amount**	**$310,662.50**
727905	MINOR CONCRETE (CHANNEL LINING)	CY	4	1	4.00	$650.00	$2,600.00
		CY	7	1	4.40	$650.00	$2,860.00
	Unit Sub Total	**CY**		**2**	**8.40**	**$650.00**	**$5,460.00**
	Item Code 727905 Total No. of Proj.			**2**		**Total Amount**	**$5,460.00**
727906	MINOR CONCRETE (GUTTER LINING)	M3	7	2	34.00	$346.47	$11,780.00
	Unit Sub Total	**M3**		**2**	**34.00**	**$346.47**	**$11,780.00**
	Item Code 727906 Total No. of Proj.			**2**		**Total Amount**	**$11,780.00**
729000	FILTER FABRIC	M2	2	1	200.00	$5.00	$1,000.00
	Unit Sub Total	**M2**		**1**	**200.00**	**$5.00**	**$1,000.00**
729000	FILTER FABRIC	SQYD	2	2	2,915.00	$2.03	$5,905.00
		SQYD	3	1	37.00	$6.16	$227.92
	Unit Sub Total	**SQYD**		**3**	**2,952.00**	**$2.08**	**$6,132.92**
	Item Code 729000 Total No. of Proj.			**4**		**Total Amount**	**$7,132.92**
729010	ROCK SLOPE PROTECTION FABRIC	M2	3	1	210.00	$3.00	$630.00
		M2	4	3	2,081.00	$1.85	$3,850.00
		M2	6	2	11,109.00	$3.05	$33,930.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
729010	ROCK SLOPE PROTECTION FABRIC		M2	7	4	235.00	$10.34	$2,428.75
			M2	10	1	67.00	$3.00	$201.00
			M2	11	2	276.00	$8.50	$2,346.00
		Unit Sub Total	**M2**		**13**	**13,978.00**	**$3.10**	**$43,385.75**
729010	ROCK SLOPE PROTECTION FABRIC		SQFT	1	1	600.00	$1.00	$600.00
			SQFT	4	2	900.00	$5.31	$4,775.00
			SQFT	12	1	160.00	$0.50	$80.00
		Unit Sub Total	**SQFT**		**4**	**1,660.00**	**$3.29**	**$5,455.00**
729010	ROCK SLOPE PROTECTION FABRIC		SQYD	1	15	1,777.00	$5.71	$10,151.00
			SQYD	2	3	561.00	$2.44	$1,369.20
			SQYD	3	6	21,176.00	$2.83	$60,016.26
			SQYD	4	16	11,647.00	$3.25	$37,869.50
			SQYD	5	5	17,432.00	$1.14	$19,897.00
			SQYD	6	3	999.00	$5.51	$5,502.50
			SQYD	7	2	32.00	$27.94	$894.20
			SQYD	8	4	506.00	$11.86	$5,999.00
			SQYD	9	2	64.00	$16.41	$1,050.00
			SQYD	10	5	1,470.00	$3.33	$4,894.00
			SQYD	11	2	1,274.00	$5.35	$6,812.00
			SQYD	12	5	9,222.00	$2.95	$27,227.00
		Unit Sub Total	**SQYD**		**68**	**66,160.00**	**$2.75**	**$181,681.66**
	Item Code 729010	**Total No. of Proj.**			**85**		**Total Amount**	**$230,522.41**
731501	MINOR CONCRETE (CURB)		CY	2	2	65.00	$690.00	$44,850.00
			CY	3	1	1.10	$710.00	$781.00
			CY	4	6	261.20	$535.75	$139,938.80
			CY	7	1	45.00	$850.00	$38,250.00
			CY	11	2	74.00	$406.76	$30,100.00
			CY	12	3	363.00	$371.38	$134,810.00
		Unit Sub Total	**CY**		**15**	**809.30**	**$480.33**	**$388,729.80**
731501	MINOR CONCRETE (CURB)		LF	3	1	580.00	$17.00	$9,860.00
			LF	6	2	185.00	$14.94	$2,763.00
		Unit Sub Total	**LF**		**3**	**765.00**	**$16.50**	**$12,623.00**
731501	MINOR CONCRETE (CURB)		M3	7	1	12.00	$800.00	$9,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**M3**		**1**	**12.00**	**$800.00**	**$9,600.00**
	Item Code 731501 Total No. of Proj.			**19**		**Total Amount**	**$410,952.80**
731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)	CY	2	9	288.20	$693.10	$199,750.03
		CY	3	2	10.00	$1,247.50	$12,475.00
		CY	4	16	2,519.50	$502.23	$1,265,360.80
		CY	5	2	716.50	$283.64	$203,226.50
		CY	6	7	1,602.00	$556.25	$891,114.00
		CY	8	2	22.00	$541.82	$11,920.00
		CY	9	2	96.00	$411.08	$39,464.08
		CY	10	2	19.20	$1,224.38	$23,508.00
		CY	11	6	505.00	$518.33	$261,756.00
		CY	12	7	992.00	$347.11	$344,330.04
	Unit Sub Total	**CY**		**55**	**6,770.40**	**$480.46**	**$3,252,904.45**
731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)	M3	4	3	795.00	$370.23	$294,330.00
		M3	6	2	168.00	$561.83	$94,388.00
		M3	7	1	190.00	$400.00	$76,000.00
		M3	10	1	780.00	$400.00	$312,000.00
	Unit Sub Total	**M3**		**7**	**1,933.00**	**$401.82**	**$776,718.00**
	Item Code 731502 Total No. of Proj.			**62**		**Total Amount**	**$4,029,622.45**
731504	MINOR CONCRETE (CURB AND GUTTER)	CY	2	1	12.00	$750.00	$9,000.00
		CY	3	2	49.90	$783.67	$39,105.00
		CY	4	1	140.00	$400.00	$56,000.00
		CY	6	2	59.00	$388.64	$22,930.00
		CY	8	1	130.00	$288.00	$37,440.00
		CY	12	1	2.00	$700.00	$1,400.00
	Unit Sub Total	**CY**		**8**	**392.90**	**$422.18**	**$165,875.00**
731504	MINOR CONCRETE (CURB AND GUTTER)	LF	7	1	4.30	$482.00	$2,072.60
	Unit Sub Total	**LF**		**1**	**4.30**	**$482.00**	**$2,072.60**
731504	MINOR CONCRETE (CURB AND GUTTER)	M3	3	1	18.00	$750.00	$13,500.00
	Unit Sub Total	**M3**		**1**	**18.00**	**$750.00**	**$13,500.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 731504 Total No. of Proj.			**10**		**Total Amount**	**$181,447.60**
731505	MINOR CONCRETE (CURB AND SIDEWALK)	CY	11	1	14.00	$750.00	$10,500.00
	Unit Sub Total	**CY**		**1**	**14.00**	**$750.00**	**$10,500.00**
731505	MINOR CONCRETE (CURB AND SIDEWALK)	M3	7	2	610.80	$454.86	$277,830.00
	Unit Sub Total	**M3**		**2**	**610.80**	**$454.86**	**$277,830.00**
	Item Code 731505 Total No. of Proj.			**3**		**Total Amount**	**$288,330.00**
731507	MINOR CONCRETE (GUTTER DEPRESSION)	CY	4	1	9.00	$1,300.00	$11,700.00
	Unit Sub Total	**CY**		**1**	**9.00**	**$1,300.00**	**$11,700.00**
	Item Code 731507 Total No. of Proj.			**1**		**Total Amount**	**$11,700.00**
731508	MINOR CONCRETE (EXPOSED AGGREGATE CONCRETE)	M2	11	1	5,110.00	$55.00	$281,050.00
	Unit Sub Total	**M2**		**1**	**5,110.00**	**$55.00**	**$281,050.00**
	Item Code 731508 Total No. of Proj.			**1**		**Total Amount**	**$281,050.00**
731511	MINOR CONCRETE (ISLAND PAVING)	CY	4	1	17.00	$300.00	$5,100.00
		CY	7	1	3.00	$510.00	$1,530.00
	Unit Sub Total	**CY**		**2**	**20.00**	**$331.50**	**$6,630.00**
	Item Code 731511 Total No. of Proj.			**2**		**Total Amount**	**$6,630.00**
731516	MINOR CONCRETE (DRIVEWAY)	CY	4	1	28.00	$300.00	$8,400.00
		CY	8	1	52.00	$216.00	$11,232.00
	Unit Sub Total	**CY**		**2**	**80.00**	**$245.40**	**$19,632.00**
	Item Code 731516 Total No. of Proj.			**2**		**Total Amount**	**$19,632.00**
731517	MINOR CONCRETE (GUTTER)	CY	3	1	3.30	$416.67	$1,375.01
		CY	4	2	85.00	$679.76	$57,780.00
		CY	5	1	14.00	$510.00	$7,140.00
		CY	6	1	80.00	$850.00	$68,000.00
		CY	8	1	130.00	$550.00	$71,500.00
	Unit Sub Total	**CY**		**6**	**312.30**	**$658.97**	**$205,795.01**
731517	MINOR CONCRETE (GUTTER)	LF	4	2	1,058.00	$30.00	$31,740.00
		LF	6	1	1,680.00	$28.00	$47,040.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
731517	MINOR CONCRETE (GUTTER)	LF	8	2	72.00	$88.90	$6,401.00
		LF	12	1	219.00	$35.00	$7,665.00
	Unit Sub Total	**LF**		**6**	**3,029.00**	**$30.65**	**$92,846.00**
731517	MINOR CONCRETE (GUTTER)	M3	4	1	2.00	$1,600.00	$3,200.00
		M3	7	2	25.00	$660.00	$16,500.00
	Unit Sub Total	**M3**		**3**	**27.00**	**$729.63**	**$19,700.00**
	Item Code 731517 Total No. of Proj.			**15**		**Total Amount**	**$318,341.01**
731519	MINOR CONCRETE (STAMPED CONCRETE)	M2	7	1	3,610.00	$68.35	$246,743.50
		M2	11	1	4,850.00	$55.00	$266,750.00
	Unit Sub Total	**M2**		**2**	**8,460.00**	**$60.70**	**$513,493.50**
731519	MINOR CONCRETE (STAMPED CONCRETE)	SQFT	12	1	2,100.00	$6.90	$14,490.00
	Unit Sub Total	**SQFT**		**1**	**2,100.00**	**$6.90**	**$14,490.00**
731519	MINOR CONCRETE (STAMPED CONCRETE)	SQYD	3	1	1,490.00	$65.00	$96,850.00
	Unit Sub Total	**SQYD**		**1**	**1,490.00**	**$65.00**	**$96,850.00**
	Item Code 731519 Total No. of Proj.			**4**		**Total Amount**	**$624,833.50**
731521	MINOR CONCRETE (SIDEWALK)	CY	2	2	61.00	$801.97	$48,920.00
		CY	4	6	618.00	$330.99	$204,550.70
		CY	8	1	40.00	$255.00	$10,200.00
		CY	12	3	214.00	$290.89	$62,250.00
	Unit Sub Total	**CY**		**12**	**933.00**	**$349.33**	**$325,920.70**
731521	MINOR CONCRETE (SIDEWALK)	M3	3	1	10.00	$750.00	$7,500.00
		M3	7	1	360.20	$500.00	$180,100.00
	Unit Sub Total	**M3**		**2**	**370.20**	**$506.75**	**$187,600.00**
	Item Code 731521 Total No. of Proj.			**14**		**Total Amount**	**$513,520.70**
731530	MINOR CONCRETE (TEXTURED PAVING)	CY	5	1	42.00	$636.00	$26,712.00
		CY	11	1	170.00	$407.00	$69,190.00
	Unit Sub Total	**CY**		**2**	**212.00**	**$452.37**	**$95,902.00**
731530	MINOR CONCRETE (TEXTURED PAVING)	M2	7	3	11,550.00	$57.30	$661,762.00
	Unit Sub Total	**M2**		**3**	**11,550.00**	**$57.30**	**$661,762.00**
731530	MINOR CONCRETE (TEXTURED PAVING)	SQFT	2	1	9,090.00	$15.00	$136,350.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
731530	MINOR CONCRETE (TEXTURED PAVING)	SQFT	6	1	4,210.00	$6.00	$25,260.00
		SQFT	7	1	6,400.00	$5.00	$32,000.00
		SQFT	11	1	2,040.00	$11.00	$22,440.00
		SQFT	12	2	19,400.00	$5.60	$108,600.00
	Unit Sub Total	**SQFT**		**6**	**41,140.00**	**$7.89**	**$324,650.00**
	Item Code 731530 Total No. of Proj.			**11**		**Total Amount**	**$1,082,314.00**
731623	MINOR CONCRETE (CURB RAMP)	CY	4	2	99.00	$694.74	$68,779.15
		CY	6	1	1.00	$1,800.00	$1,800.00
		CY	8	1	9.00	$600.00	$5,400.00
		CY	12	3	18.00	$902.78	$16,250.00
	Unit Sub Total	**CY**		**7**	**127.00**	**$726.21**	**$92,229.15**
731623	MINOR CONCRETE (CURB RAMP)	M3	3	1	4.00	$750.00	$3,000.00
		M3	7	1	13.00	$1,410.00	$18,330.00
	Unit Sub Total	**M3**		**2**	**17.00**	**$1,254.71**	**$21,330.00**
	Item Code 731623 Total No. of Proj.			**9**		**Total Amount**	**$113,559.15**
731627	MINOR CONCRETE (CURB, SIDEWALK AND CURB RAMP)	CY	3	1	32.00	$392.00	$12,544.00
		CY	4	2	394.00	$592.32	$233,374.00
		CY	5	1	27.00	$531.00	$14,337.00
		CY	6	1	13.00	$630.00	$8,190.00
		CY	7	2	65.00	$501.92	$32,625.00
		CY	12	1	29.00	$500.00	$14,500.00
	Unit Sub Total	**CY**		**8**	**560.00**	**$563.52**	**$315,570.00**
	Item Code 731627 Total No. of Proj.			**8**		**Total Amount**	**$315,570.00**
731656	CURB RAMP DETECTABLE WARNING SURFACE	EA	4	1	65.00	$460.00	$29,900.00
	Unit Sub Total	**EA**		**1**	**65.00**	**$460.00**	**$29,900.00**
731656	CURB RAMP DETECTABLE WARNING SURFACE	M2	7	1	2.40	$520.00	$1,248.00
	Unit Sub Total	**M2**		**1**	**2.40**	**$520.00**	**$1,248.00**
731656	CURB RAMP DETECTABLE WARNING SURFACE	SQFT	2	1	24.00	$21.46	$515.04
		SQFT	4	1	210.00	$35.00	$7,350.00
		SQFT	7	2	144.00	$51.33	$7,392.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
731656	CURB RAMP DETECTABLE WARNING SURFACE	SQFT	8	1	192.00	$20.85	$4,003.20
		SQFT	11	2	475.00	$42.90	$20,376.00
		SQFT	12	1	34.00	$50.00	$1,700.00
	Unit Sub Total	**SQFT**		**8**	**1,079.00**	**$38.31**	**$41,336.24**
	Item Code 731656 Total No. of Proj.			**10**		**Total Amount**	**$72,484.24**
740500	DRAINAGE PUMPING EQUIPMENT	LS	4	1	1.00	$400,000.00	$400,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$400,000.00**	**$400,000.00**
	Item Code 740500 Total No. of Proj.			**1**		**Total Amount**	**$400,000.00**
741001	PUMPING PLANT ELECTRICAL EQUIPMENT	LS	4	1	1.00	$180,000.00	$180,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$180,000.00**	**$180,000.00**
	Item Code 741001 Total No. of Proj.			**1**		**Total Amount**	**$180,000.00**
750001	MISCELLANEOUS IRON AND STEEL	KG	2	1	430.00	$3.00	$1,290.00
		KG	3	1	4,190.00	$4.00	$16,760.00
		KG	4	3	45,931.00	$2.73	$125,524.00
		KG	6	3	5,677.00	$3.30	$18,761.40
		KG	7	5	161,667.00	$2.83	$457,042.25
		KG	10	1	5,577.00	$2.00	$11,154.00
		KG	11	2	17,670.00	$3.52	$62,120.00
	Unit Sub Total	**KG**		**16**	**241,142.00**	**$2.87**	**$692,651.65**
750001	MISCELLANEOUS IRON AND STEEL	LB	1	12	19,096.00	$3.85	$73,502.77
		LB	2	15	36,157.00	$2.13	$76,932.05
		LB	3	11	69,187.00	$1.61	$111,316.86
		LB	4	23	122,207.00	$1.96	$239,903.21
		LB	5	10	52,456.00	$1.50	$78,719.65
		LB	6	7	26,771.00	$2.68	$71,614.50
		LB	7	2	478.00	$2.45	$1,171.00
		LB	8	5	12,572.00	$1.42	$17,864.00
		LB	9	2	2,266.00	$4.80	$10,887.50
		LB	10	5	21,279.00	$1.76	$37,540.60
		LB	11	5	30,646.00	$1.38	$42,184.60
		LB	12	7	318,372.00	$1.34	$427,924.10

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LB**		**104**	**711,487.00**	**$1.67**	**$1,189,560.84**
	Item Code 750001	**Total No. of Proj.**			**120**		**Total Amount**	**$1,882,212.49**
750007	FRAME AND GRATE		EA	6	1	12.00	$475.00	$5,700.00
		Unit Sub Total	**EA**		**1**	**12.00**	**$475.00**	**$5,700.00**
	Item Code 750007	**Total No. of Proj.**			**1**		**Total Amount**	**$5,700.00**
750010	MANHOLE FRAME AND COVER		EA	5	1	1.00	$330.00	$330.00
			EA	6	2	3.00	$983.33	$2,950.00
			EA	10	1	1.00	$275.00	$275.00
		Unit Sub Total	**EA**		**4**	**5.00**	**$711.00**	**$3,555.00**
	Item Code 750010	**Total No. of Proj.**			**4**		**Total Amount**	**$3,555.00**
750030	INLET FRAME AND GRATE		EA	7	1	8.00	$750.00	$6,000.00
		Unit Sub Total	**EA**		**1**	**8.00**	**$750.00**	**$6,000.00**
	Item Code 750030	**Total No. of Proj.**			**1**		**Total Amount**	**$6,000.00**
750041	ISOLATION CASING		KG	2	1	1,802.00	$10.00	$18,020.00
			KG	7	1	17,165.00	$12.00	$205,980.00
		Unit Sub Total	**KG**		**2**	**18,967.00**	**$11.81**	**$224,000.00**
750041	ISOLATION CASING		LB	3	1	44,655.00	$3.00	$133,965.00
			LB	5	1	15,266.00	$5.10	$77,856.60
			LB	12	1	49,700.00	$3.00	$149,100.00
		Unit Sub Total	**LB**		**3**	**109,621.00**	**$3.29**	**$360,921.60**
	Item Code 750041	**Total No. of Proj.**			**5**		**Total Amount**	**$584,921.60**
750496	MISCELLANEOUS METAL (RESTRAINER - PIPE TYPE)		KG	10	1	3,100.00	$12.00	$37,200.00
		Unit Sub Total	**KG**		**1**	**3,100.00**	**$12.00**	**$37,200.00**
750496	MISCELLANEOUS METAL (RESTRAINER - PIPE TYPE)		LB	3	1	129.00	$48.00	$6,192.00
			LB	12	1	3,960.00	$3.80	$15,048.00
		Unit Sub Total	**LB**		**2**	**4,089.00**	**$5.19**	**$21,240.00**
	Item Code 750496	**Total No. of Proj.**			**3**		**Total Amount**	**$58,440.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
750498	MISCELLANEOUS METAL (RESTRAINER - CABLE TYPE)	KG	4	1	1,647.00	$30.00	$49,410.00
		KG	7	3	20,376.00	$20.73	$422,408.00
		KG	10	1	3,100.00	$11.00	$34,100.00
	Unit Sub Total	**KG**		**5**	**25,123.00**	**$20.14**	**$505,918.00**
750498	MISCELLANEOUS METAL (RESTRAINER - CABLE TYPE)	LB	3	2	16,560.00	$5.54	$91,760.00
		LB	4	1	1,480.00	$19.00	$28,120.00
		LB	11	1	1,200.00	$13.00	$15,600.00
		LB	12	3	21,297.00	$9.81	$208,823.00
	Unit Sub Total	**LB**		**7**	**40,537.00**	**$8.49**	**$344,303.00**
	Item Code 750498 Total No. of Proj.			**12**		**Total Amount**	**$850,221.00**
750500	MISCELLANEOUS METAL	KG	4	1	200.00	$20.00	$4,000.00
		KG	7	1	252.00	$14.00	$3,528.00
	Unit Sub Total	**KG**		**2**	**452.00**	**$16.65**	**$7,528.00**
	Item Code 750500 Total No. of Proj.			**2**		**Total Amount**	**$7,528.00**
750501	MISCELLANEOUS METAL (BRIDGE)	KG	4	2	13,400.00	$15.34	$205,600.00
		KG	7	3	42,231.00	$20.25	$855,216.85
	Unit Sub Total	**KG**		**5**	**55,631.00**	**$19.07**	**$1,060,816.85**
750501	MISCELLANEOUS METAL (BRIDGE)	LB	2	1	425.00	$32.00	$13,600.00
		LB	4	4	86,873.00	$7.76	$674,269.00
		LB	5	1	5,796.00	$5.10	$29,559.60
		LB	7	3	11,880.00	$6.07	$72,080.00
		LB	8	1	2,300.00	$4.50	$10,350.00
		LB	11	1	1,500.00	$5.00	$7,500.00
		LB	12	6	90,595.00	$3.68	$333,357.30
	Unit Sub Total	**LB**		**17**	**199,369.00**	**$5.72**	**$1,140,715.90**
	Item Code 750501 Total No. of Proj.			**22**		**Total Amount**	**$2,201,532.75**
750502	MISCELLANEOUS METAL (RETAINING WALL)	KG	4	1	720.00	$15.00	$10,800.00
	Unit Sub Total	**KG**		**1**	**720.00**	**$15.00**	**$10,800.00**
750502	MISCELLANEOUS METAL (RETAINING WALL)	LB	12	1	255.00	$4.00	$1,020.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LB**		**1**	**255.00**	**$4.00**	**$1,020.00**
	Item Code 750502	**Total No. of Proj.**			**2**		**Total Amount**	**$11,820.00**
750505	BRIDGE DECK DRAINAGE SYSTEM		KG	2	1	179.00	$12.00	$2,148.00
			KG	4	2	21,952.00	$19.62	$430,640.00
			KG	7	3	60,610.00	$19.69	$1,193,360.00
			KG	10	1	5,500.00	$11.00	$60,500.00
		Unit Sub Total	**KG**		**7**	**88,241.00**	**$19.11**	**$1,686,648.00**
750505	BRIDGE DECK DRAINAGE SYSTEM		LB	3	2	16,877.00	$3.30	$55,720.00
			LB	4	4	17,265.00	$9.11	$157,330.00
			LB	5	1	15,011.00	$6.10	$91,567.10
			LB	12	4	119,248.00	$5.22	$622,380.00
		Unit Sub Total	**LB**		**11**	**168,401.00**	**$5.50**	**$926,997.10**
	Item Code 750505	**Total No. of Proj.**			**18**		**Total Amount**	**$2,613,645.10**
750520	PUMPING PLANT METAL WORK		LB	4	1	12,100.00	$14.00	$169,400.00
		Unit Sub Total	**LB**		**1**	**12,100.00**	**$14.00**	**$169,400.00**
	Item Code 750520	**Total No. of Proj.**			**1**		**Total Amount**	**$169,400.00**
760011	WELL DEVELOPMENT		LS	10	1	1.00	$10,000.00	$10,000.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$10,000.00**	**$10,000.00**
	Item Code 760011	**Total No. of Proj.**			**1**		**Total Amount**	**$10,000.00**
760012	TESTING WELL		HR	10	1	8.00	$500.00	$4,000.00
		Unit Sub Total	**HR**		**1**	**8.00**	**$500.00**	**$4,000.00**
	Item Code 760012	**Total No. of Proj.**			**1**		**Total Amount**	**$4,000.00**
760021	DRILL PILOT HOLE		LF	10	1	300.00	$26.00	$7,800.00
		Unit Sub Total	**LF**		**1**	**300.00**	**$26.00**	**$7,800.00**
	Item Code 760021	**Total No. of Proj.**			**1**		**Total Amount**	**$7,800.00**
760022	REAMING WATER WELL		LF	10	1	300.00	$50.00	$15,000.00
		Unit Sub Total	**LF**		**1**	**300.00**	**$50.00**	**$15,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 760022 Total No. of Proj.			**1**		**Total Amount**	**$15,000.00**
760025	CONDUCTOR CASING	LF	10	1	50.00	$350.00	$17,500.00
	Unit Sub Total	**LF**		**1**	**50.00**	**$350.00**	**$17,500.00**
	Item Code 760025 Total No. of Proj.			**1**		**Total Amount**	**$17,500.00**
760030	BLANK WELL CASING	LF	10	1	290.00	$10.00	$2,900.00
	Unit Sub Total	**LF**		**1**	**290.00**	**$10.00**	**$2,900.00**
	Item Code 760030 Total No. of Proj.			**1**		**Total Amount**	**$2,900.00**
760035	WELL SCREEN	LF	10	1	70.00	$14.00	$980.00
	Unit Sub Total	**LF**		**1**	**70.00**	**$14.00**	**$980.00**
	Item Code 760035 Total No. of Proj.			**1**		**Total Amount**	**$980.00**
760080	WATER SUPPLY SYSTEM	LS	10	1	1.00	$4,000.00	$4,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$4,000.00**	**$4,000.00**
	Item Code 760080 Total No. of Proj.			**1**		**Total Amount**	**$4,000.00**
760090	MOBILIZATION, DEMOBILIZATION, AND FINAL CLEANUP	LS	2	1	1.00	$168,850.00	$168,850.00
		LS	10	1	1.00	$13,000.00	$13,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$90,925.00**	**$181,850.00**
	Item Code 760090 Total No. of Proj.			**2**		**Total Amount**	**$181,850.00**
800001	FENCE (TYPE BW, METAL POST)	LF	4	1	170.00	$15.00	$2,550.00
	Unit Sub Total	**LF**		**1**	**170.00**	**$15.00**	**$2,550.00**
	Item Code 800001 Total No. of Proj.			**1**		**Total Amount**	**$2,550.00**
800007	FENCE (TYPE BW, 5 STRAND, METAL POST)	LF	4	2	8,790.00	$5.00	$43,950.00
		LF	5	3	41,290.00	$3.43	$141,512.00
	Unit Sub Total	**LF**		**5**	**50,080.00**	**$3.70**	**$185,462.00**
800007	FENCE (TYPE BW, 5 STRAND, METAL POST)	M	6	1	26,300.00	$8.00	$210,400.00
	Unit Sub Total	**M**		**1**	**26,300.00**	**$8.00**	**$210,400.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 800007 Total No. of Proj.			**6**		**Total Amount**	**$395,862.00**
800008	FENCE (TYPE BW, 4-STRAND, METAL POST)	LF	2	1	120.00	$20.00	$2,400.00
	Unit Sub Total	**LF**		**1**	**120.00**	**$20.00**	**$2,400.00**
800008	FENCE (TYPE BW, 4-STRAND, METAL POST)	M	11	1	10,500.00	$8.00	$84,000.00
	Unit Sub Total	**M**		**1**	**10,500.00**	**$8.00**	**$84,000.00**
	Item Code 800008 Total No. of Proj.			**2**		**Total Amount**	**$86,400.00**
800010	FENCE (TYPE BW, 4-STRAND, WOOD POST)	LF	8	1	200.00	$18.00	$3,600.00
	Unit Sub Total	**LF**		**1**	**200.00**	**$18.00**	**$3,600.00**
	Item Code 800010 Total No. of Proj.			**1**		**Total Amount**	**$3,600.00**
800051	FENCE (TYPE WM, METAL POST)	LF	4	1	350.00	$5.00	$1,750.00
		LF	10	1	2,900.00	$4.50	$13,050.00
	Unit Sub Total	**LF**		**2**	**3,250.00**	**$4.55**	**$14,800.00**
800051	FENCE (TYPE WM, METAL POST)	M	3	1	1,030.00	$20.00	$20,600.00
	Unit Sub Total	**M**		**1**	**1,030.00**	**$20.00**	**$20,600.00**
	Item Code 800051 Total No. of Proj.			**3**		**Total Amount**	**$35,400.00**
800052	FENCE (TYPE WM, WOOD POST)	LF	1	1	540.00	$12.00	$6,480.00
	Unit Sub Total	**LF**		**1**	**540.00**	**$12.00**	**$6,480.00**
	Item Code 800052 Total No. of Proj.			**1**		**Total Amount**	**$6,480.00**
800054	FENCE (TYPE WM, MODIFIED)	LF	5	1	9,000.00	$6.00	$54,000.00
	Unit Sub Total	**LF**		**1**	**9,000.00**	**$6.00**	**$54,000.00**
	Item Code 800054 Total No. of Proj.			**1**		**Total Amount**	**$54,000.00**
800300	CHAIN LINK FENCE	LF	3	1	26.00	$63.80	$1,658.80
	Unit Sub Total	**LF**		**1**	**26.00**	**$63.80**	**$1,658.80**
	Item Code 800300 Total No. of Proj.			**1**		**Total Amount**	**$1,658.80**
800302	CHAIN LINK FENCE (TYPE CL-3, VINYL-CLAD)	LF	4	2	1,015.00	$25.44	$25,825.00
	Unit Sub Total	**LF**		**2**	**1,015.00**	**$25.44**	**$25,825.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 800302 Total No. of Proj.			**2**		**Total Amount**	**$25,825.00**
800320	CHAIN LINK FENCE (TYPE CL-4)	LF	3	1	50.00	$80.00	$4,000.00
		LF	4	2	3,830.00	$8.11	$31,060.00
		LF	11	3	674.00	$17.65	$11,896.00
		LF	12	1	1,680.00	$10.00	$16,800.00
	Unit Sub Total	**LF**		**7**	**6,234.00**	**$10.23**	**$63,756.00**
	Item Code 800320 Total No. of Proj.			**7**		**Total Amount**	**$63,756.00**
800321	CHAIN LINK FENCE (TYPE CL-4, VINYL-CLAD)	LF	4	3	1,429.00	$18.13	$25,908.00
		LF	11	2	1,090.00	$24.26	$26,440.00
	Unit Sub Total	**LF**		**5**	**2,519.00**	**$20.78**	**$52,348.00**
	Item Code 800321 Total No. of Proj.			**5**		**Total Amount**	**$52,348.00**
800360	CHAIN LINK FENCE (TYPE CL-6)	LF	3	3	1,940.00	$20.34	$39,456.00
		LF	4	5	1,765.00	$16.05	$28,320.00
		LF	5	1	130.00	$19.00	$2,470.00
		LF	6	3	8,987.00	$10.54	$94,732.00
		LF	8	3	1,470.00	$27.73	$40,760.00
		LF	10	2	12,059.00	$10.90	$131,470.00
		LF	11	2	1,500.00	$15.27	$22,899.00
		LF	12	6	7,815.00	$16.21	$126,685.00
	Unit Sub Total	**LF**		**25**	**35,666.00**	**$13.65**	**$486,792.00**
	Item Code 800360 Total No. of Proj.			**25**		**Total Amount**	**$486,792.00**
800361	CHAIN LINK FENCE (TYPE CL-6, VINYL-CLAD)	LF	4	3	1,525.00	$29.40	$44,840.00
		LF	5	1	3,060.00	$14.00	$42,840.00
		LF	11	1	550.00	$25.00	$13,750.00
	Unit Sub Total	**LF**		**5**	**5,135.00**	**$19.75**	**$101,430.00**
	Item Code 800361 Total No. of Proj.			**5**		**Total Amount**	**$101,430.00**
800382	CHAIN LINK FENCE (TYPE CL-0.9, VINYL-CLAD)	M	4	1	2,790.00	$32.00	$89,280.00
	Unit Sub Total	**M**		**1**	**2,790.00**	**$32.00**	**$89,280.00**
	Item Code 800382 Total No. of Proj.			**1**		**Total Amount**	**$89,280.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
800389	CHAIN LINK FENCE (TYPE CL-1.5)	LF	12	1	525.00	$21.00	$11,025.00
	Unit Sub Total	**LF**		**1**	**525.00**	**$21.00**	**$11,025.00**
	Item Code 800389 Total No. of Proj.			**1**		**Total Amount**	**$11,025.00**
800391	CHAIN LINK FENCE (TYPE CL-1.8)	M	4	1	2,410.00	$30.00	$72,300.00
		M	7	3	3,976.00	$41.69	$165,753.40
		M	10	1	730.00	$32.00	$23,360.00
	Unit Sub Total	**M**		**5**	**7,116.00**	**$36.74**	**$261,413.40**
	Item Code 800391 Total No. of Proj.			**5**		**Total Amount**	**$261,413.40**
800600	CHAIN LINK FENCE (ROCK BARRIER)	LF	1	1	1,350.00	$30.00	$40,500.00
	Unit Sub Total	**LF**		**1**	**1,350.00**	**$30.00**	**$40,500.00**
	Item Code 800600 Total No. of Proj.			**1**		**Total Amount**	**$40,500.00**
800701	WOOD FENCE	LF	4	1	80.00	$70.00	$5,600.00
	Unit Sub Total	**LF**		**1**	**80.00**	**$70.00**	**$5,600.00**
800701	WOOD FENCE	M	4	1	15.00	$300.00	$4,500.00
		M	7	1	89.00	$200.00	$17,800.00
	Unit Sub Total	**M**		**2**	**104.00**	**$214.42**	**$22,300.00**
	Item Code 800701 Total No. of Proj.			**3**		**Total Amount**	**$27,900.00**
800705	WIRE MESH AND WOOD FENCE	LF	4	1	88.00	$45.00	$3,960.00
	Unit Sub Total	**LF**		**1**	**88.00**	**$45.00**	**$3,960.00**
	Item Code 800705 Total No. of Proj.			**1**		**Total Amount**	**$3,960.00**
801110	4' WIRE MESH GATE	EA	9	1	12.00	$1,000.00	$12,000.00
		EA	10	1	3.00	$800.00	$2,400.00
	Unit Sub Total	**EA**		**2**	**15.00**	**$960.00**	**$14,400.00**
	Item Code 801110 Total No. of Proj.			**2**		**Total Amount**	**$14,400.00**
801130	6' WIRE MESH GATE	EA	4	1	5.00	$600.00	$3,000.00
	Unit Sub Total	**EA**		**1**	**5.00**	**$600.00**	**$3,000.00**
	Item Code 801130 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
801190	12' WIRE MESH GATE	EA	9	1	7.00	$1,400.00	$9,800.00
	Unit Sub Total	**EA**		**1**	**7.00**	**$1,400.00**	**$9,800.00**
	Item Code 801190 Total No. of Proj.			**1**		**Total Amount**	**$9,800.00**
801230	16' WIRE MESH GATE	EA	4	1	1.00	$850.00	$850.00
		EA	9	1	4.00	$1,800.00	$7,200.00
	Unit Sub Total	**EA**		**2**	**5.00**	**$1,610.00**	**$8,050.00**
	Item Code 801230 Total No. of Proj.			**2**		**Total Amount**	**$8,050.00**
801273	4.6 M WIRE MESH GATE	EA	3	1	1.00	$2,000.00	$2,000.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$2,000.00**	**$2,000.00**
	Item Code 801273 Total No. of Proj.			**1**		**Total Amount**	**$2,000.00**
801900	CHAIN LINK GATE	EA	3	2	3.00	$1,366.33	$4,099.00
		EA	7	1	2.00	$1,165.00	$2,330.00
	Unit Sub Total	**EA**		**3**	**5.00**	**$1,285.80**	**$6,429.00**
	Item Code 801900 Total No. of Proj.			**3**		**Total Amount**	**$6,429.00**
802500	3' CHAIN LINK GATE (TYPE CL-6)	EA	12	1	12.00	$750.00	$9,000.00
	Unit Sub Total	**EA**		**1**	**12.00**	**$750.00**	**$9,000.00**
	Item Code 802500 Total No. of Proj.			**1**		**Total Amount**	**$9,000.00**
802501	4' CHAIN LINK GATE (TYPE CL-6)	EA	4	2	7.00	$1,379.42	$9,655.96
		EA	5	1	1.00	$800.00	$800.00
		EA	10	5	14.00	$1,097.38	$15,363.25
		EA	12	2	2.00	$1,000.00	$2,000.00
	Unit Sub Total	**EA**		**10**	**24.00**	**$1,159.13**	**$27,819.21**
	Item Code 802501 Total No. of Proj.			**10**		**Total Amount**	**$27,819.21**
802502	4' CHAIN LINK GATE (TYPE CL-6, VINYL-CLAD)	LF	4	1	12.00	$250.00	$3,000.00
	Unit Sub Total	**LF**		**1**	**12.00**	**$250.00**	**$3,000.00**
	Item Code 802502 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
802510	5' CHAIN LINK GATE (TYPE CL-6)	EA	4	1	4.00	$1,500.00	$6,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
802510	5' CHAIN LINK GATE (TYPE CL-6)	EA	12	1	1.00	$200.00	$200.00
	Unit Sub Total	**EA**		**2**	**5.00**	**$1,240.00**	**$6,200.00**
	Item Code 802510 Total No. of Proj.			**2**		**Total Amount**	**$6,200.00**
802520	6' CHAIN LINK GATE (TYPE CL-6)	EA	6	2	4.00	$1,008.25	$4,033.00
		EA	8	1	21.00	$750.00	$15,750.00
		EA	11	1	2.00	$800.00	$1,600.00
	Unit Sub Total	**EA**		**4**	**27.00**	**$791.96**	**$21,383.00**
	Item Code 802520 Total No. of Proj.			**4**		**Total Amount**	**$21,383.00**
802540	8' CHAIN LINK GATE (TYPE CL-6)	EA	4	1	2.00	$800.00	$1,600.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$800.00**	**$1,600.00**
	Item Code 802540 Total No. of Proj.			**1**		**Total Amount**	**$1,600.00**
802560	10' CHAIN LINK GATE (TYPE CL-6)	EA	4	1	2.00	$1,000.00	$2,000.00
		EA	12	1	2.00	$1,000.00	$2,000.00
	Unit Sub Total	**EA**		**2**	**4.00**	**$1,000.00**	**$4,000.00**
	Item Code 802560 Total No. of Proj.			**2**		**Total Amount**	**$4,000.00**
802580	12' CHAIN LINK GATE (TYPE CL-6)	EA	3	1	2.00	$678.50	$1,357.00
		EA	4	1	1.00	$1,436.51	$1,436.51
		EA	8	1	1.00	$2,222.00	$2,222.00
		EA	10	1	3.00	$2,040.00	$6,120.00
		EA	12	1	5.00	$1,700.00	$8,500.00
	Unit Sub Total	**EA**		**5**	**12.00**	**$1,636.29**	**$19,635.51**
	Item Code 802580 Total No. of Proj.			**5**		**Total Amount**	**$19,635.51**
802589	1.5 M CHAIN LINK GATE (TYPE CL-1.8)	EA	7	2	3.00	$806.67	$2,420.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$806.67**	**$2,420.00**
	Item Code 802589 Total No. of Proj.			**2**		**Total Amount**	**$2,420.00**
802590	1.8 M CHAIN LINK GATE (TYPE CL-1.8)	EA	7	1	3.00	$645.00	$1,935.00
	Unit Sub Total	**EA**		**1**	**3.00**	**$645.00**	**$1,935.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 802590 Total No. of Proj.			**1**		**Total Amount**	**$1,935.00**
802592	2.4 M CHAIN LINK GATE (TYPE CL-1.8)	EA	3	1	15.00	$1,100.00	$16,500.00
	Unit Sub Total	**EA**		**1**	**15.00**	**$1,100.00**	**$16,500.00**
	Item Code 802592 Total No. of Proj.			**1**		**Total Amount**	**$16,500.00**
802595	3.0 M CHAIN LINK GATE (TYPE CL-1.8)	EA	4	1	7.00	$900.00	$6,300.00
		EA	7	2	39.00	$1,122.69	$43,785.00
	Unit Sub Total	**EA**		**3**	**46.00**	**$1,088.80**	**$50,085.00**
	Item Code 802595 Total No. of Proj.			**3**		**Total Amount**	**$50,085.00**
802596	3.7 M CHAIN LINK GATE (TYPE CL-1.8)	EA	7	1	4.00	$970.00	$3,880.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$970.00**	**$3,880.00**
	Item Code 802596 Total No. of Proj.			**1**		**Total Amount**	**$3,880.00**
802620	16' CHAIN LINK GATE (TYPE CL-6)	EA	4	2	3.00	$1,253.33	$3,760.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$1,253.33**	**$3,760.00**
	Item Code 802620 Total No. of Proj.			**2**		**Total Amount**	**$3,760.00**
802660	20' CHAIN LINK GATE (TYPE CL-6)	EA	3	1	2.00	$2,000.00	$4,000.00
		EA	12	1	1.00	$1,700.00	$1,700.00
	Unit Sub Total	**EA**		**2**	**3.00**	**$1,900.00**	**$5,700.00**
	Item Code 802660 Total No. of Proj.			**2**		**Total Amount**	**$5,700.00**
802671	4.3 M CHAIN LINK GATE (TYPE CL-1.8)	EA	7	1	2.00	$1,035.00	$2,070.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$1,035.00**	**$2,070.00**
	Item Code 802671 Total No. of Proj.			**1**		**Total Amount**	**$2,070.00**
802672	4.9 M CHAIN LINK GATE (TYPE CL-1.8)	EA	7	1	5.00	$1,140.00	$5,700.00
	Unit Sub Total	**EA**		**1**	**5.00**	**$1,140.00**	**$5,700.00**
	Item Code 802672 Total No. of Proj.			**1**		**Total Amount**	**$5,700.00**
802675	6.1 M CHAIN LINK GATE (TYPE CL-1.8)	EA	10	1	4.00	$1,800.00	$7,200.00
	Unit Sub Total	**EA**		**1**	**4.00**	**$1,800.00**	**$7,200.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 802675 Total No. of Proj.			**1**		**Total Amount**	**$7,200.00**
802900	CHAIN LINK FENCE (TYPE CL-8, EXTENSION ARM)	LF	4	1	48.00	$45.00	$2,160.00
	Unit Sub Total	**LF**		**1**	**48.00**	**$45.00**	**$2,160.00**
	Item Code 802900 Total No. of Proj.			**1**		**Total Amount**	**$2,160.00**
802902	4' CHAIN LINK GATE (TYPE CL-8, EXTENSION ARM)	EA	4	1	2.00	$850.00	$1,700.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$850.00**	**$1,700.00**
	Item Code 802902 Total No. of Proj.			**1**		**Total Amount**	**$1,700.00**
810110	SURVEY MONUMENT	EA	2	2	11.00	$763.64	$8,400.00
		EA	4	1	4.00	$1,500.00	$6,000.00
		EA	5	2	30.00	$391.67	$11,750.00
		EA	6	1	3.00	$250.00	$750.00
		EA	8	1	13.00	$565.00	$7,345.00
	Unit Sub Total	**EA**		**7**	**61.00**	**$561.39**	**$34,245.00**
	Item Code 810110 Total No. of Proj.			**7**		**Total Amount**	**$34,245.00**
810111	SURVEY MONUMENT (TYPE A)	EA	2	1	6.00	$500.00	$3,000.00
		EA	5	1	2.00	$9.00	$18.00
		EA	6	1	23.00	$400.00	$9,200.00
	Unit Sub Total	**EA**		**3**	**31.00**	**$394.13**	**$12,218.00**
	Item Code 810111 Total No. of Proj.			**3**		**Total Amount**	**$12,218.00**
810116	SURVEY MONUMENT (TYPE D)	EA	4	1	4.00	$800.00	$3,200.00
		EA	5	1	5.00	$550.00	$2,750.00
		EA	6	1	43.00	$350.00	$15,050.00
		EA	8	1	5.00	$1,040.00	$5,200.00
		EA	10	1	7.00	$500.00	$3,500.00
		EA	12	1	1.00	$280.00	$280.00
	Unit Sub Total	**EA**		**6**	**65.00**	**$461.23**	**$29,980.00**
	Item Code 810116 Total No. of Proj.			**6**		**Total Amount**	**$29,980.00**
820101	MARKER	EA	12	1	3.00	$75.00	$225.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**1**	**3.00**	**$75.00**	**$225.00**
	Item Code 820101	**Total No. of Proj.**			**1**		**Total Amount**	**$225.00**
820105	DELINEATOR (SPECIAL)		EA	9	2	386.00	$77.44	$29,890.00
		Unit Sub Total	**EA**		**2**	**386.00**	**$77.44**	**$29,890.00**
	Item Code 820105	**Total No. of Proj.**			**2**		**Total Amount**	**$29,890.00**
820107	DELINEATOR (CLASS 1)		EA	1	2	10.00	$64.00	$640.00
			EA	2	4	97.00	$47.06	$4,565.00
			EA	3	10	1,139.00	$34.04	$38,770.00
			EA	4	7	995.00	$33.98	$33,812.00
			EA	5	5	583.00	$30.46	$17,761.00
			EA	6	8	503.00	$34.97	$17,590.00
			EA	7	3	142.00	$41.16	$5,845.00
			EA	8	3	38.00	$40.32	$1,532.00
			EA	10	8	488.00	$30.99	$15,121.80
			EA	11	6	835.00	$33.98	$28,372.20
			EA	12	11	758.00	$41.56	$31,501.24
		Unit Sub Total	**EA**		**67**	**5,588.00**	**$34.99**	**$195,510.24**
	Item Code 820107	**Total No. of Proj.**			**67**		**Total Amount**	**$195,510.24**
820108	DELINEATOR (CLASS 2)		EA	2	8	1,223.00	$16.56	$20,257.00
			EA	3	5	3,477.00	$38.60	$134,200.00
			EA	8	4	46.00	$41.67	$1,917.00
			EA	9	4	183.00	$41.48	$7,590.00
			EA	10	2	17.00	$48.53	$825.00
		Unit Sub Total	**EA**		**23**	**4,946.00**	**$33.32**	**$164,789.00**
	Item Code 820108	**Total No. of Proj.**			**23**		**Total Amount**	**$164,789.00**
820110	MILEPOST MARKER		EA	2	8	113.00	$36.57	$4,132.00
			EA	3	2	31.00	$39.26	$1,217.00
			EA	4	1	2.00	$50.00	$100.00
			EA	5	1	10.00	$40.00	$400.00
			EA	6	1	15.00	$40.00	$600.00
			EA	8	2	13.00	$46.62	$606.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
820110	MILEPOST MARKER	EA	9	1	4.00	$75.00	$300.00
		EA	10	1	2.00	$65.00	$130.00
		EA	11	15	197.00	$90.85	$17,897.00
	Unit Sub Total	**EA**		**32**	**387.00**	**$65.59**	**$25,382.00**
	Item Code 820110 Total No. of Proj.			**32**		**Total Amount**	**$25,382.00**
820111	UNDERDRAIN MARKER	EA	1	3	9.00	$85.00	$765.00
	Unit Sub Total	**EA**		**3**	**9.00**	**$85.00**	**$765.00**
	Item Code 820111 Total No. of Proj.			**3**		**Total Amount**	**$765.00**
820112	MARKER (CULVERT)	EA	1	12	91.00	$60.71	$5,525.00
		EA	2	12	150.00	$58.79	$8,819.00
		EA	3	6	566.00	$25.95	$14,690.00
		EA	9	2	16.00	$56.25	$900.00
	Unit Sub Total	**EA**		**32**	**823.00**	**$36.37**	**$29,934.00**
	Item Code 820112 Total No. of Proj.			**32**		**Total Amount**	**$29,934.00**
820115	SNOW POLE MARKER	EA	3	1	10.00	$30.00	$300.00
		EA	8	1	2.00	$250.00	$500.00
		EA	10	1	600.00	$90.00	$54,000.00
	Unit Sub Total	**EA**		**3**	**612.00**	**$89.54**	**$54,800.00**
	Item Code 820115 Total No. of Proj.			**3**		**Total Amount**	**$54,800.00**
820118	GUARD RAILING DELINEATOR	EA	1	7	3,138.00	$29.24	$91,768.00
		EA	3	1	30.00	$30.00	$900.00
		EA	4	14	1,745.00	$12.78	$22,300.50
		EA	5	5	60.00	$18.53	$1,112.00
		EA	6	1	12.00	$20.00	$240.00
		EA	7	2	278.00	$21.50	$5,978.00
		EA	8	3	266.00	$12.86	$3,420.00
		EA	10	9	479.00	$28.59	$13,695.00
		EA	11	5	299.00	$19.43	$5,810.00
		EA	12	4	65.00	$24.36	$1,583.50
	Unit Sub Total	**EA**		**51**	**6,372.00**	**$23.04**	**$146,807.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 820118	**Total No. of Proj.**			**51**		**Total Amount**	**$146,807.00**
820130	OBJECT MARKER		EA	4	4	37.00	$41.29	$1,527.60
			EA	5	2	34.00	$40.00	$1,360.00
			EA	6	2	8.00	$45.00	$360.00
			EA	8	3	25.00	$68.92	$1,723.00
			EA	9	1	4.00	$42.00	$168.00
			EA	10	1	16.00	$40.00	$640.00
			EA	11	1	4.00	$75.00	$300.00
		Unit Sub Total	**EA**		**14**	**128.00**	**$47.49**	**$6,078.60**
	Item Code 820130	**Total No. of Proj.**			**14**		**Total Amount**	**$6,078.60**
820131	OBJECT MARKER (TYPE K)		EA	2	1	1.00	$60.00	$60.00
			EA	6	1	6.00	$40.00	$240.00
		Unit Sub Total	**EA**		**2**	**7.00**	**$42.86**	**$300.00**
	Item Code 820131	**Total No. of Proj.**			**2**		**Total Amount**	**$300.00**
820132	OBJECT MARKER (TYPE L)		EA	2	2	4.00	$55.00	$220.00
			EA	6	1	8.00	$35.00	$280.00
			EA	10	6	53.00	$42.45	$2,250.00
		Unit Sub Total	**EA**		**9**	**65.00**	**$42.31**	**$2,750.00**
	Item Code 820132	**Total No. of Proj.**			**9**		**Total Amount**	**$2,750.00**
820134	OBJECT MARKER (TYPE P)		EA	1	1	33.00	$35.00	$1,155.00
			EA	3	1	10.00	$75.00	$750.00
			EA	4	6	255.00	$53.17	$13,558.15
			EA	5	3	9.00	$64.44	$580.00
			EA	6	1	4.00	$69.00	$276.00
			EA	8	1	2.00	$85.00	$170.00
			EA	10	2	20.00	$43.00	$860.00
		Unit Sub Total	**EA**		**15**	**333.00**	**$52.10**	**$17,349.15**
	Item Code 820134	**Total No. of Proj.**			**15**		**Total Amount**	**$17,349.15**
820135	OBJECT MARKER (TYPE R)		EA	4	1	1.00	$105.00	$105.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$105.00**	**$105.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 820135 Total No. of Proj.			**1**		**Total Amount**	**$105.00**
820141	OBJECT MARKER (TYPE K-1)	EA	2	1	4.00	$60.00	$240.00
		EA	3	2	9.00	$37.78	$340.00
		EA	4	2	72.00	$39.58	$2,850.00
		EA	9	1	2.00	$45.00	$90.00
		EA	10	1	4.00	$25.00	$100.00
		EA	12	1	13.00	$40.00	$520.00
	Unit Sub Total	**EA**		**8**	**104.00**	**$39.81**	**$4,140.00**
	Item Code 820141 Total No. of Proj.			**8**		**Total Amount**	**$4,140.00**
820143	OBJECT MARKER (TYPE K-2)	EA	4	1	5.00	$30.00	$150.00
	Unit Sub Total	**EA**		**1**	**5.00**	**$30.00**	**$150.00**
	Item Code 820143 Total No. of Proj.			**1**		**Total Amount**	**$150.00**
820151	OBJECT MARKER (TYPE L-1)	EA	1	5	212.00	$42.53	$9,017.00
		EA	2	7	255.00	$45.86	$11,695.00
		EA	3	16	297.00	$45.42	$13,490.00
		EA	4	15	746.00	$38.02	$28,363.75
		EA	5	2	3.00	$42.33	$127.00
		EA	6	1	6.00	$60.00	$360.00
		EA	8	2	37.00	$50.00	$1,850.00
		EA	9	1	8.00	$65.00	$520.00
		EA	10	5	102.00	$60.99	$6,220.60
	Unit Sub Total	**EA**		**54**	**1,666.00**	**$43.00**	**$71,643.35**
	Item Code 820151 Total No. of Proj.			**54**		**Total Amount**	**$71,643.35**
820180	INSTALL MEDIAN MILEAGE PANEL	EA	7	2	78.00	$125.00	$9,750.00
	Unit Sub Total	**EA**		**2**	**78.00**	**$125.00**	**$9,750.00**
	Item Code 820180 Total No. of Proj.			**2**		**Total Amount**	**$9,750.00**
832001	METAL BEAM GUARD RAILING	LF	1	2	175.00	$52.57	$9,200.00
		LF	2	3	355.00	$58.45	$20,750.00
		LF	3	5	10,783.00	$23.19	$250,009.00
		LF	4	11	3,240.50	$31.64	$102,539.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
832001	METAL BEAM GUARD RAILING	LF	7	3	330.00	$25.85	$8,530.00
		LF	9	1	230.00	$45.00	$10,350.00
		LF	11	4	4,840.00	$25.97	$125,700.00
	Unit Sub Total	**LF**		**29**	**19,953.50**	**$26.42**	**$527,078.00**
832001	METAL BEAM GUARD RAILING	M	2	1	260.00	$65.00	$16,900.00
		M	7	2	3,210.00	$73.98	$237,475.50
		M	11	2	820.00	$73.27	$60,080.00
	Unit Sub Total	**M**		**5**	**4,290.00**	**$73.30**	**$314,455.50**
	Item Code 832001 Total No. of Proj.			**34**		**Total Amount**	**$841,533.50**
832002	METAL BEAM GUARD RAILING (STEEL POST)	LF	1	2	5,280.00	$21.86	$115,400.00
		LF	2	6	113,490.00	$18.42	$2,090,090.00
		LF	3	4	34,260.00	$18.04	$617,920.00
		LF	5	5	4,740.00	$23.16	$109,780.00
		LF	6	7	6,170.00	$28.52	$175,980.00
		LF	8	5	9,590.00	$22.53	$216,106.00
		LF	10	2	670.00	$30.69	$20,560.00
		LF	11	2	223.00	$30.57	$6,816.00
	Unit Sub Total	**LF**		**33**	**174,423.00**	**$19.22**	**$3,352,652.00**
832002	METAL BEAM GUARD RAILING (STEEL POST)	M	4	1	50.00	$150.00	$7,500.00
	Unit Sub Total	**M**		**1**	**50.00**	**$150.00**	**$7,500.00**
	Item Code 832002 Total No. of Proj.			**34**		**Total Amount**	**$3,360,152.00**
832003	METAL BEAM GUARD RAILING (WOOD POST)	LF	1	7	23,220.00	$21.19	$492,122.00
		LF	2	4	17,960.00	$17.47	$313,850.00
		LF	3	8	14,130.00	$18.09	$255,619.50
		LF	4	14	25,977.00	$24.94	$647,810.00
		LF	5	1	130.00	$38.00	$4,940.00
		LF	7	4	3,400.00	$24.12	$82,000.00
		LF	8	4	10,770.00	$17.97	$193,578.00
		LF	10	6	11,420.00	$17.76	$202,790.60
		LF	12	9	35,047.00	$19.56	$685,682.00
	Unit Sub Total	**LF**		**57**	**142,054.00**	**$20.26**	**$2,878,392.10**
832003	METAL BEAM GUARD RAILING (WOOD POST)	M	3	1	490.00	$60.00	$29,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
832003	METAL BEAM GUARD RAILING (WOOD POST)	M	4	2	300.00	$58.40	$17,520.00
		M	7	1	330.00	$70.00	$23,100.00
	Unit Sub Total	**M**		**4**	**1,120.00**	**$62.52**	**$70,020.00**
	Item Code 832003 Total No. of Proj.			**61**		**Total Amount**	**$2,948,412.10**
832004	METAL BEAM GUARD RAILING (SPECIAL)	EA	3	1	1.00	$500.00	$500.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$500.00**	**$500.00**
832004	METAL BEAM GUARD RAILING (SPECIAL)	LF	1	1	40.00	$219.00	$8,760.00
		LF	3	1	580.00	$46.00	$26,680.00
	Unit Sub Total	**LF**		**2**	**620.00**	**$57.16**	**$35,440.00**
	Item Code 832004 Total No. of Proj.			**3**		**Total Amount**	**$35,940.00**
832008	METAL BEAM GUARD RAILING (ELEMENT)	EA	1	2	490.00	$27.63	$13,540.00
	Unit Sub Total	**EA**		**2**	**490.00**	**$27.63**	**$13,540.00**
	Item Code 832008 Total No. of Proj.			**2**		**Total Amount**	**$13,540.00**
832012	METAL BEAM GUARD RAILING (7' WOOD POST)	LF	1	3	905.00	$28.80	$26,061.00
		LF	2	1	600.00	$21.00	$12,600.00
		LF	3	1	19,800.00	$21.00	$415,800.00
	Unit Sub Total	**LF**		**5**	**21,305.00**	**$21.33**	**$454,461.00**
	Item Code 832012 Total No. of Proj.			**5**		**Total Amount**	**$454,461.00**
832013	METAL BEAM GUARD RAILING (7' POST)	LF	3	2	2,060.00	$18.77	$38,675.00
		LF	9	1	480.00	$55.00	$26,400.00
	Unit Sub Total	**LF**		**3**	**2,540.00**	**$25.62**	**$65,075.00**
	Item Code 832013 Total No. of Proj.			**3**		**Total Amount**	**$65,075.00**
832014	METAL BEAM GUARD RAILING (8' POST)	LF	1	2	88.00	$57.87	$5,092.50
		LF	12	1	20.00	$25.00	$500.00
	Unit Sub Total	**LF**		**3**	**108.00**	**$51.78**	**$5,592.50**
	Item Code 832014 Total No. of Proj.			**3**		**Total Amount**	**$5,592.50**
832061	METAL BEAM GUARD RAILING (2.1 M WOOD POST)	M	7	1	2,380.00	$84.00	$199,920.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**M**		**1**	**2,380.00**	**$84.00**	**$199,920.00**
	Item Code 832061	**Total No. of Proj.**			**1**		**Total Amount**	**$199,920.00**
832070	VEGETATION CONTROL (MINOR CONCRETE)		M2	2	1	600.00	$50.00	$30,000.00
		Unit Sub Total	**M2**		**1**	**600.00**	**$50.00**	**$30,000.00**
832070	VEGETATION CONTROL (MINOR CONCRETE)		SQYD	1	3	37,854.00	$33.53	$1,269,268.00
			SQYD	2	3	6,310.00	$31.70	$200,010.00
			SQYD	3	5	35,660.00	$30.06	$1,071,860.00
			SQYD	4	5	3,430.00	$62.01	$212,700.00
			SQYD	5	1	2,600.00	$69.00	$179,400.00
			SQYD	7	2	430.00	$62.23	$26,760.00
			SQYD	8	2	3,840.00	$34.75	$133,440.00
			SQYD	10	1	690.00	$36.00	$24,840.00
			SQYD	12	4	6,588.00	$32.98	$217,280.00
		Unit Sub Total	**SQYD**		**26**	**97,402.00**	**$34.25**	**$3,335,558.00**
	Item Code 832070	**Total No. of Proj.**			**27**		**Total Amount**	**$3,365,558.00**
833020	CHAIN LINK RAILING		LF	12	1	480.00	$58.00	$27,840.00
		Unit Sub Total	**LF**		**1**	**480.00**	**$58.00**	**$27,840.00**
833020	CHAIN LINK RAILING		M	7	1	478.20	$100.00	$47,820.00
		Unit Sub Total	**M**		**1**	**478.20**	**$100.00**	**$47,820.00**
	Item Code 833020	**Total No. of Proj.**			**2**		**Total Amount**	**$75,660.00**
833023	CHAIN LINK RAILING (TYPE 3L)		M	7	1	900.00	$372.25	$335,025.00
		Unit Sub Total	**M**		**1**	**900.00**	**$372.25**	**$335,025.00**
	Item Code 833023	**Total No. of Proj.**			**1**		**Total Amount**	**$335,025.00**
833032	CHAIN LINK RAILING (TYPE 7)		LF	7	1	793.00	$57.80	$45,835.40
			LF	12	2	1,678.00	$55.86	$93,739.00
		Unit Sub Total	**LF**		**3**	**2,471.00**	**$56.48**	**$139,574.40**
833032	CHAIN LINK RAILING (TYPE 7)		M	7	2	548.00	$194.96	$106,837.80
			M	11	1	228.00	$200.00	$45,600.00
		Unit Sub Total	**M**		**3**	**776.00**	**$196.44**	**$152,437.80**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 833032 Total No. of Proj.			**6**		**Total Amount**	**$292,012.20**
833033	CHAIN LINK RAILING (TYPE 7 MODIFIED)	LF	5	1	331.00	$105.00	$34,755.00
	Unit Sub Total	**LF**		**1**	**331.00**	**$105.00**	**$34,755.00**
833033	CHAIN LINK RAILING (TYPE 7 MODIFIED)	M	7	1	345.00	$194.00	$66,930.00
		M	10	1	656.00	$280.00	$183,680.00
	Unit Sub Total	**M**		**2**	**1,001.00**	**$250.36**	**$250,610.00**
	Item Code 833033 Total No. of Proj.			**3**		**Total Amount**	**$285,365.00**
833040	PICKET RAILING	LF	4	1	600.00	$45.00	$27,000.00
	Unit Sub Total	**LF**		**1**	**600.00**	**$45.00**	**$27,000.00**
	Item Code 833040 Total No. of Proj.			**1**		**Total Amount**	**$27,000.00**
833077	PEDESTRIAN BARRICADE	EA	6	2	13.00	$1,153.85	$15,000.00
	Unit Sub Total	**EA**		**2**	**13.00**	**$1,153.85**	**$15,000.00**
	Item Code 833077 Total No. of Proj.			**2**		**Total Amount**	**$15,000.00**
833079	INSTALL CONCRETE BARRIER (TYPE K)	LF	4	1	1,890.00	$8.00	$15,120.00
	Unit Sub Total	**LF**		**1**	**1,890.00**	**$8.00**	**$15,120.00**
	Item Code 833079 Total No. of Proj.			**1**		**Total Amount**	**$15,120.00**
833080	CONCRETE BARRIER (TYPE K)	LF	4	1	9,100.00	$9.00	$81,900.00
		LF	6	1	100.00	$47.00	$4,700.00
	Unit Sub Total	**LF**		**2**	**9,200.00**	**$9.41**	**$86,600.00**
833080	CONCRETE BARRIER (TYPE K)	M	4	2	571.00	$34.96	$19,960.00
		M	7	1	18.00	$120.00	$2,160.00
	Unit Sub Total	**M**		**3**	**589.00**	**$37.56**	**$22,120.00**
	Item Code 833080 Total No. of Proj.			**5**		**Total Amount**	**$108,720.00**
833085	PIPE HANDRAILING	LF	4	4	1,944.00	$57.58	$111,941.10
	Unit Sub Total	**LF**		**4**	**1,944.00**	**$57.58**	**$111,941.10**
	Item Code 833085 Total No. of Proj.			**4**		**Total Amount**	**$111,941.10**
833087	PIPE HANDRAILING (POST TYPE)	LF	2	2	52.00	$140.00	$7,280.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**2**	**52.00**	**$140.00**	**$7,280.00**
833087	PIPE HANDRAILING (POST TYPE)		M	7	1	134.00	$81.25	$10,887.50
		Unit Sub Total	**M**		**1**	**134.00**	**$81.25**	**$10,887.50**
	Item Code 833087	**Total No. of Proj.**			**3**		**Total Amount**	**$18,167.50**
833088	TUBULAR HANDRAILING		LF	4	1	200.00	$87.55	$17,510.00
			LF	5	1	373.00	$50.00	$18,650.00
			LF	6	1	83.00	$130.00	$10,790.00
			LF	9	1	270.00	$245.00	$66,150.00
			LF	12	1	1,084.00	$44.00	$47,696.00
		Unit Sub Total	**LF**		**5**	**2,010.00**	**$80.00**	**$160,796.00**
	Item Code 833088	**Total No. of Proj.**			**5**		**Total Amount**	**$160,796.00**
833128	CONCRETE BARRIER (TYPE 25 MODIFIED)		LF	3	1	8.00	$100.00	$800.00
		Unit Sub Total	**LF**		**1**	**8.00**	**$100.00**	**$800.00**
	Item Code 833128	**Total No. of Proj.**			**1**		**Total Amount**	**$800.00**
833138	CONCRETE BARRIER (TYPE 25R)		LF	3	1	153.00	$300.00	$45,900.00
		Unit Sub Total	**LF**		**1**	**153.00**	**$300.00**	**$45,900.00**
	Item Code 833138	**Total No. of Proj.**			**1**		**Total Amount**	**$45,900.00**
833140	CONCRETE BARRIER (TYPE 26)		M	11	1	114.00	$390.00	$44,460.00
		Unit Sub Total	**M**		**1**	**114.00**	**$390.00**	**$44,460.00**
	Item Code 833140	**Total No. of Proj.**			**1**		**Total Amount**	**$44,460.00**
833142	CONCRETE BARRIER (TYPE 26 MODIFIED)		LF	4	1	744.00	$230.00	$171,120.00
			LF	5	1	152.00	$219.00	$33,288.00
			LF	7	1	793.00	$176.00	$139,568.00
			LF	12	2	2,748.00	$129.63	$356,232.00
		Unit Sub Total	**LF**		**5**	**4,437.00**	**$157.81**	**$700,208.00**
833142	CONCRETE BARRIER (TYPE 26 MODIFIED)		M	4	1	274.00	$450.00	$123,300.00
			M	11	1	114.00	$230.00	$26,220.00
		Unit Sub Total	**M**		**2**	**388.00**	**$385.36**	**$149,520.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 833142 Total No. of Proj.			**7**		**Total Amount**	**$849,728.00**
833143	CONCRETE BARRIER (TYPE 26A MODIFIED)	LF	5	1	388.00	$141.00	$54,708.00
	Unit Sub Total	**LF**		**1**	**388.00**	**$141.00**	**$54,708.00**
	Item Code 833143 Total No. of Proj.			**1**		**Total Amount**	**$54,708.00**
833179	CONCRETE BARRIER (TYPE 27S)	LF	10	1	4.00	$112.20	$448.80
	Unit Sub Total	**LF**		**1**	**4.00**	**$112.20**	**$448.80**
	Item Code 833179 Total No. of Proj.			**1**		**Total Amount**	**$448.80**
833187	CONCRETE BARRIER (TYPE 27 MODIFIED)	LF	4	1	188.00	$100.00	$18,800.00
		LF	5	1	111.00	$100.00	$11,100.00
	Unit Sub Total	**LF**		**2**	**299.00**	**$100.00**	**$29,900.00**
	Item Code 833187 Total No. of Proj.			**2**		**Total Amount**	**$29,900.00**
839220	DOUBLE METAL BEAM GUARD RAILING (WOOD POST)	LF	1	3	3,150.00	$47.07	$148,275.00
		LF	2	2	1,200.00	$26.83	$32,200.00
		LF	3	2	1,880.00	$28.05	$52,740.00
		LF	4	1	25.00	$50.00	$1,250.00
		LF	10	1	1,780.00	$24.00	$42,720.00
		LF	12	2	580.00	$29.17	$16,920.00
	Unit Sub Total	**LF**		**11**	**8,615.00**	**$34.14**	**$294,105.00**
	Item Code 839220 Total No. of Proj.			**11**		**Total Amount**	**$294,105.00**
839301	SINGLE THRIE BEAM BARRIER	LF	2	1	410.00	$25.00	$10,250.00
		LF	6	2	370.00	$27.59	$10,210.00
	Unit Sub Total	**LF**		**3**	**780.00**	**$26.23**	**$20,460.00**
	Item Code 839301 Total No. of Proj.			**3**		**Total Amount**	**$20,460.00**
839302	SINGLE THRIE BEAM BARRIER (WOOD POST)	LF	3	1	25.00	$80.00	$2,000.00
		LF	7	1	780.00	$29.00	$22,620.00
		LF	10	1	190.00	$23.00	$4,370.00
	Unit Sub Total	**LF**		**3**	**995.00**	**$29.14**	**$28,990.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 839302 Total No. of Proj.			**3**		**Total Amount**	**$28,990.00**
839303	SINGLE THRIE BEAM BARRIER (STEEL POST)	LF	3	1	6,730.00	$20.50	$137,965.00
		LF	5	2	4,950.00	$25.57	$126,550.00
		LF	6	1	18,200.00	$24.00	$436,800.00
	Unit Sub Total	**LF**		**4**	**29,880.00**	**$23.47**	**$701,315.00**
	Item Code 839303 Total No. of Proj.			**4**		**Total Amount**	**$701,315.00**
839310	DOUBLE THRIE BEAM BARRIER	LF	6	2	170.00	$42.06	$7,150.00
	Unit Sub Total	**LF**		**2**	**170.00**	**$42.06**	**$7,150.00**
	Item Code 839310 Total No. of Proj.			**2**		**Total Amount**	**$7,150.00**
839311	DOUBLE THRIE BEAM BARRIER (WOOD POST)	LF	1	1	1,440.00	$24.00	$34,560.00
		LF	2	1	2,830.00	$33.00	$93,390.00
		LF	3	1	50.00	$80.00	$4,000.00
	Unit Sub Total	**LF**		**3**	**4,320.00**	**$30.54**	**$131,950.00**
	Item Code 839311 Total No. of Proj.			**3**		**Total Amount**	**$131,950.00**
839312	DOUBLE THRIE BEAM BARRIER (STEEL POST)	LF	6	1	5,570.00	$36.00	$200,520.00
		LF	7	1	520.00	$44.50	$23,140.00
	Unit Sub Total	**LF**		**2**	**6,090.00**	**$36.73**	**$223,660.00**
	Item Code 839312 Total No. of Proj.			**2**		**Total Amount**	**$223,660.00**
839481	CONCRETE BARRIER (TYPE 50)	LF	4	1	400.00	$100.00	$40,000.00
	Unit Sub Total	**LF**		**1**	**400.00**	**$100.00**	**$40,000.00**
	Item Code 839481 Total No. of Proj.			**1**		**Total Amount**	**$40,000.00**
839491	CONCRETE BARRIER (TYPE 50E)	LF	11	1	73.00	$500.00	$36,500.00
	Unit Sub Total	**LF**		**1**	**73.00**	**$500.00**	**$36,500.00**
	Item Code 839491 Total No. of Proj.			**1**		**Total Amount**	**$36,500.00**
839521	CABLE RAILING	LF	1	3	283.00	$58.30	$16,498.00
		LF	2	5	1,180.00	$34.61	$40,839.90
		LF	3	1	32.00	$125.00	$4,000.00
		LF	4	3	2,583.00	$20.48	$52,904.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839521	CABLE RAILING	LF	5	2	1,020.00	$23.29	$23,760.00
		LF	6	2	4,310.00	$8.39	$36,170.00
		LF	7	1	9,760.00	$17.50	$170,800.00
		LF	8	1	4,219.00	$6.00	$25,314.00
		LF	9	1	160.00	$48.00	$7,680.00
		LF	10	1	1,370.00	$10.20	$13,974.00
		LF	12	5	3,606.00	$15.66	$56,468.00
	Unit Sub Total	**LF**		**25**	**28,523.00**	**$15.72**	**$448,407.90**
839521	CABLE RAILING	M	3	1	35.00	$60.00	$2,100.00
		M	4	2	94.00	$71.15	$6,688.00
		M	7	3	2,386.30	$36.25	$86,502.14
	Unit Sub Total	**M**		**6**	**2,515.30**	**$37.88**	**$95,290.14**
	Item Code 839521 Total No. of Proj.			**31**		**Total Amount**	**$543,698.04**
839527	CABLE RAILING (MODIFIED)	M	2	1	55.00	$175.00	$9,625.00
	Unit Sub Total	**M**		**1**	**55.00**	**$175.00**	**$9,625.00**
	Item Code 839527 Total No. of Proj.			**1**		**Total Amount**	**$9,625.00**
839540	TRANSITION RAILING (TYPE STB)	EA	2	1	10.00	$3,475.00	$34,750.00
		EA	3	2	2.00	$3,500.00	$7,000.00
		EA	5	3	11.00	$3,770.00	$41,470.00
		EA	7	1	2.00	$3,500.00	$7,000.00
		EA	10	1	6.00	$3,000.00	$18,000.00
	Unit Sub Total	**EA**		**8**	**31.00**	**$3,490.97**	**$108,220.00**
	Item Code 839540 Total No. of Proj.			**8**		**Total Amount**	**$108,220.00**
839541	TRANSITION RAILING (TYPE WB)	EA	1	8	316.00	$3,201.42	$1,011,650.00
		EA	2	13	146.00	$3,547.81	$517,980.00
		EA	3	10	180.00	$3,858.44	$694,520.00
		EA	4	16	370.00	$3,120.65	$1,154,640.00
		EA	5	7	31.00	$3,667.26	$113,685.00
		EA	6	9	80.00	$2,861.53	$228,922.00
		EA	7	6	113.00	$3,212.39	$363,000.00
		EA	8	2	28.00	$3,010.00	$84,280.00
		EA	9	1	8.00	$3,200.00	$25,600.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839541	TRANSITION RAILING (TYPE WB)	EA	10	6	80.00	$2,582.40	$206,592.00
		EA	11	5	14.00	$3,332.14	$46,650.00
		EA	12	9	43.00	$3,018.02	$129,775.00
	Unit Sub Total	**EA**		**92**	**1,409.00**	**$3,248.61**	**$4,577,294.00**
	Item Code 839541 Total No. of Proj.			**92**		**Total Amount**	**$4,577,294.00**
839542	TRANSITION RAILING (TYPE DTB)	EA	2	1	2.00	$3,200.00	$6,400.00
		EA	6	2	3.00	$1,690.00	$5,070.00
	Unit Sub Total	**EA**		**3**	**5.00**	**$2,294.00**	**$11,470.00**
	Item Code 839542 Total No. of Proj.			**3**		**Total Amount**	**$11,470.00**
839553	END SECTION	EA	1	1	16.00	$100.00	$1,600.00
		EA	9	1	1.00	$345.00	$345.00
	Unit Sub Total	**EA**		**2**	**17.00**	**$114.41**	**$1,945.00**
	Item Code 839553 Total No. of Proj.			**2**		**Total Amount**	**$1,945.00**
839555	END CAP	EA	4	1	2.00	$1,400.00	$2,800.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$1,400.00**	**$2,800.00**
	Item Code 839555 Total No. of Proj.			**1**		**Total Amount**	**$2,800.00**
839561	RAIL TENSIONING ASSEMBLY	EA	1	2	18.00	$661.11	$11,900.00
		EA	2	2	29.00	$517.24	$15,000.00
		EA	3	1	2.00	$200.00	$400.00
		EA	4	1	2.00	$200.00	$400.00
		EA	6	1	18.00	$563.00	$10,134.00
		EA	10	2	29.00	$284.66	$8,255.00
		EA	11	1	2.00	$270.00	$540.00
		EA	12	1	1.00	$300.00	$300.00
	Unit Sub Total	**EA**		**11**	**101.00**	**$464.64**	**$46,929.00**
	Item Code 839561 Total No. of Proj.			**11**		**Total Amount**	**$46,929.00**
839565	TERMINAL SYSTEM (TYPE SRT)	EA	2	1	2.00	$2,600.00	$5,200.00
		EA	3	1	1.00	$2,100.00	$2,100.00
		EA	6	1	4.00	$2,300.00	$9,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**3**	**7.00**	**$2,357.14**	**$16,500.00**
	Item Code 839565	**Total No. of Proj.**			**3**		**Total Amount**	**$16,500.00**
839566	TERMINAL SYSTEM (TYPE CAT)		EA	1	2	20.00	$3,766.00	$75,320.00
			EA	2	1	2.00	$4,500.00	$9,000.00
			EA	3	1	1.00	$5,100.00	$5,100.00
			EA	4	1	1.00	$3,600.00	$3,600.00
			EA	7	1	2.00	$6,000.00	$12,000.00
			EA	12	1	1.00	$5,000.00	$5,000.00
		Unit Sub Total	**EA**		**7**	**27.00**	**$4,074.81**	**$110,020.00**
	Item Code 839566	**Total No. of Proj.**			**7**		**Total Amount**	**$110,020.00**
839567	TERMINAL SYSTEM (TYPE CAT) BACKUP		EA	1	1	14.00	$1,000.00	$14,000.00
			EA	2	1	2.00	$600.00	$1,200.00
			EA	3	1	1.00	$300.00	$300.00
			EA	12	1	1.00	$230.00	$230.00
		Unit Sub Total	**EA**		**4**	**18.00**	**$873.89**	**$15,730.00**
	Item Code 839567	**Total No. of Proj.**			**4**		**Total Amount**	**$15,730.00**
839568	TERMINAL ANCHOR ASSEMBLY (TYPE SFT)		EA	1	2	82.00	$693.78	$56,890.00
			EA	2	4	134.00	$582.46	$78,050.00
			EA	3	3	22.00	$663.64	$14,600.00
			EA	4	2	12.00	$800.00	$9,600.00
			EA	7	2	6.00	$654.17	$3,925.00
			EA	8	1	1.00	$1,200.00	$1,200.00
			EA	10	1	3.00	$816.00	$2,448.00
			EA	12	2	29.00	$644.83	$18,700.00
		Unit Sub Total	**EA**		**17**	**289.00**	**$641.57**	**$185,413.00**
	Item Code 839568	**Total No. of Proj.**			**17**		**Total Amount**	**$185,413.00**
839569	TERMINAL ANCHOR ASSEMBLY (TYPE CA)		EA	7	1	1.00	$900.00	$900.00
		Unit Sub Total	**EA**		**1**	**1.00**	**$900.00**	**$900.00**
	Item Code 839569	**Total No. of Proj.**			**1**		**Total Amount**	**$900.00**
839572	RETURN CAP (TYPE TA)		EA	7	1	1.00	$500.00	$500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**1**	**1.00**	**$500.00**	**$500.00**
	Item Code 839572	**Total No. of Proj.**			**1**		**Total Amount**	**$500.00**
839576	END CAP (TYPE A)		EA	1	1	14.00	$155.25	$2,173.50
			EA	2	3	15.00	$189.00	$2,835.00
			EA	3	4	14.00	$121.29	$1,698.00
			EA	4	2	2.00	$201.00	$402.00
			EA	7	2	23.00	$182.39	$4,195.00
			EA	8	1	2.00	$190.00	$380.00
			EA	12	1	2.00	$275.00	$550.00
		Unit Sub Total	**EA**		**14**	**72.00**	**$169.91**	**$12,233.50**
	Item Code 839576	**Total No. of Proj.**			**14**		**Total Amount**	**$12,233.50**
839578	END CAP (TYPE TC)		EA	1	1	51.00	$100.00	$5,100.00
			EA	2	2	11.00	$168.18	$1,850.00
			EA	3	3	119.00	$229.08	$27,260.00
			EA	8	1	2.00	$230.00	$460.00
			EA	12	2	6.00	$216.67	$1,300.00
		Unit Sub Total	**EA**		**9**	**189.00**	**$190.32**	**$35,970.00**
	Item Code 839578	**Total No. of Proj.**			**9**		**Total Amount**	**$35,970.00**
839581	END ANCHOR ASSEMBLY (TYPE SFT)		EA	1	5	140.00	$732.43	$102,540.00
			EA	2	4	45.00	$702.22	$31,600.00
			EA	3	13	225.00	$587.33	$132,150.00
			EA	4	20	218.00	$586.98	$127,962.40
			EA	5	5	11.00	$698.64	$7,685.00
			EA	6	10	72.00	$696.22	$50,128.00
			EA	7	5	47.00	$600.43	$28,220.00
			EA	8	3	8.00	$725.00	$5,800.00
			EA	10	4	30.00	$739.00	$22,170.00
			EA	11	5	28.00	$601.79	$16,850.00
			EA	12	5	43.00	$418.14	$17,980.00
		Unit Sub Total	**EA**		**79**	**867.00**	**$626.40**	**$543,085.40**
	Item Code 839581	**Total No. of Proj.**			**79**		**Total Amount**	**$543,085.40**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839582	END ANCHOR ASSEMBLY (TYPE CA)	EA	7	1	1.00	$1,500.00	$1,500.00
	Unit Sub Total	**EA**		**1**	**1.00**	**$1,500.00**	**$1,500.00**
	Item Code 839582 Total No. of Proj.			**1**		**Total Amount**	**$1,500.00**
839584	ALTERNATIVE IN-LINE TERMINAL SYSTEM	EA	1	7	76.00	$2,887.37	$219,440.00
		EA	2	7	56.00	$2,245.54	$125,750.00
		EA	3	8	52.00	$2,846.63	$148,025.00
		EA	4	15	103.00	$2,485.44	$256,000.00
		EA	5	3	5.00	$2,859.00	$14,295.00
		EA	6	1	7.00	$2,500.00	$17,500.00
		EA	7	8	55.00	$2,657.35	$146,154.00
		EA	8	5	38.00	$2,502.11	$95,080.00
		EA	9	1	3.00	$3,000.00	$9,000.00
		EA	10	3	23.00	$2,304.35	$53,000.00
		EA	11	2	4.00	$3,125.00	$12,500.00
		EA	12	5	22.00	$2,704.55	$59,500.00
	Unit Sub Total	**EA**		**65**	**444.00**	**$2,604.15**	**$1,156,244.00**
	Item Code 839584 Total No. of Proj.			**65**		**Total Amount**	**$1,156,244.00**
839585	ALTERNATIVE FLARED TERMINAL SYSTEM	EA	1	12	277.00	$2,327.74	$644,785.00
		EA	2	16	161.00	$2,069.29	$333,155.00
		EA	3	14	232.00	$2,251.29	$522,300.00
		EA	4	21	738.00	$2,053.53	$1,515,504.00
		EA	5	6	35.00	$2,270.60	$79,471.00
		EA	6	9	66.00	$2,371.64	$156,528.00
		EA	7	5	79.00	$2,274.41	$179,678.00
		EA	8	6	15.00	$2,443.33	$36,650.00
		EA	9	2	9.00	$2,644.44	$23,800.00
		EA	10	10	78.00	$2,065.40	$161,101.00
		EA	11	5	26.00	$2,532.69	$65,850.00
		EA	12	10	69.00	$2,208.70	$152,400.00
	Unit Sub Total	**EA**		**116**	**1,785.00**	**$2,168.75**	**$3,871,222.00**
	Item Code 839585 Total No. of Proj.			**116**		**Total Amount**	**$3,871,222.00**
839591	CRASH CUSHION, SAND FILLED	EA	2	1	1.00	$5,500.00	$5,500.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839591	CRASH CUSHION, SAND FILLED	EA	4	2	4.00	$1,500.00	$6,000.00
		EA	7	1	3.00	$500.00	$1,500.00
	Unit Sub Total	**EA**		**4**	**8.00**	**$1,625.00**	**$13,000.00**
	Item Code 839591 Total No. of Proj.			**4**		**Total Amount**	**$13,000.00**
839601	CRASH CUSHION (TYPE CAT)	EA	1	1	46.00	$8,625.00	$396,750.00
		EA	2	2	29.00	$5,103.45	$148,000.00
		EA	3	1	150.00	$4,800.00	$720,000.00
		EA	4	2	5.00	$5,076.40	$25,382.00
		EA	6	1	3.00	$5,000.00	$15,000.00
		EA	7	2	4.00	$5,900.00	$23,600.00
		EA	10	2	29.00	$4,165.52	$120,800.00
		EA	12	1	1.00	$5,500.00	$5,500.00
	Unit Sub Total	**EA**		**12**	**267.00**	**$5,449.56**	**$1,455,032.00**
	Item Code 839601 Total No. of Proj.			**12**		**Total Amount**	**$1,455,032.00**
839602	CRASH CUSHION (TYPE CAT) BACKUP	EA	1	1	46.00	$1,150.00	$52,900.00
		EA	2	1	1.00	$500.00	$500.00
		EA	3	1	150.00	$200.00	$30,000.00
		EA	4	1	4.00	$500.00	$2,000.00
		EA	6	1	3.00	$300.00	$900.00
		EA	7	1	2.00	$6,500.00	$13,000.00
		EA	10	2	29.00	$237.45	$6,886.00
	Unit Sub Total	**EA**		**8**	**235.00**	**$451.86**	**$106,186.00**
	Item Code 839602 Total No. of Proj.			**8**		**Total Amount**	**$106,186.00**
839603	CRASH CUSHION (ADIEM)	EA	3	1	2.00	$5,000.00	$10,000.00
		EA	8	1	9.00	$10,000.00	$90,000.00
	Unit Sub Total	**EA**		**2**	**11.00**	**$9,090.91**	**$100,000.00**
	Item Code 839603 Total No. of Proj.			**2**		**Total Amount**	**$100,000.00**
839604	CRASH CUSHION (REACT 9CBB)	EA	4	2	6.00	$50,000.00	$300,000.00
		EA	7	2	3.00	$54,600.00	$163,800.00
		EA	11	2	4.00	$35,500.00	$142,000.00
		EA	12	2	3.00	$58,333.33	$175,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**8**	**16.00**	**$48,800.00**	**$780,800.00**
	Item Code 839604	**Total No. of Proj.**			**8**		**Total Amount**	**$780,800.00**
839605	CRASH CUSHION (REACT 9SCBS)		EA	4	1	1.00	$55,000.00	$55,000.00
			EA	7	4	9.00	$54,950.00	$494,550.00
			EA	12	3	8.00	$49,725.00	$397,800.00
		Unit Sub Total	**EA**		**8**	**18.00**	**$52,630.56**	**$947,350.00**
	Item Code 839605	**Total No. of Proj.**			**8**		**Total Amount**	**$947,350.00**
839631	CRASH CUSHION MODULE, SAND FILLED		EA	4	1	14.00	$250.00	$3,500.00
		Unit Sub Total	**EA**		**1**	**14.00**	**$250.00**	**$3,500.00**
	Item Code 839631	**Total No. of Proj.**			**1**		**Total Amount**	**$3,500.00**
839701	CONCRETE BARRIER (TYPE 60)		LF	2	1	29.00	$250.00	$7,250.00
			LF	3	2	290.00	$73.66	$21,360.00
			LF	4	4	35,840.00	$40.43	$1,448,905.00
			LF	5	1	11,300.00	$31.00	$350,300.00
			LF	6	6	37,530.00	$28.41	$1,066,175.00
			LF	8	1	300.00	$50.00	$15,000.00
			LF	12	3	14,900.00	$47.26	$704,100.00
		Unit Sub Total	**LF**		**18**	**100,189.00**	**$36.06**	**$3,613,090.00**
839701	CONCRETE BARRIER (TYPE 60)		M	4	1	290.00	$310.00	$89,900.00
			M	7	3	1,773.00	$103.58	$183,640.00
			M	11	1	350.00	$150.00	$52,500.00
		Unit Sub Total	**M**		**5**	**2,413.00**	**$135.12**	**$326,040.00**
	Item Code 839701	**Total No. of Proj.**			**23**		**Total Amount**	**$3,939,130.00**
839702	CONCRETE BARRIER (TYPE 60A)		LF	6	2	659.00	$62.38	$41,110.00
			LF	12	1	1,170.00	$55.00	$64,350.00
		Unit Sub Total	**LF**		**3**	**1,829.00**	**$57.66**	**$105,460.00**
839702	CONCRETE BARRIER (TYPE 60A)		M	7	1	337.00	$134.00	$45,158.00
		Unit Sub Total	**M**		**1**	**337.00**	**$134.00**	**$45,158.00**
	Item Code 839702	**Total No. of Proj.**			**4**		**Total Amount**	**$150,618.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839703	CONCRETE BARRIER (TYPE 60C)	LF	2	2	290.00	$169.59	$49,180.00
		LF	3	2	2,640.00	$22.50	$59,400.00
		LF	4	3	15,150.00	$49.46	$749,325.00
		LF	6	4	34,510.00	$48.76	$1,682,650.00
		LF	8	1	9,800.00	$37.00	$362,600.00
		LF	12	3	2,720.00	$68.05	$185,090.00
	Unit Sub Total	**LF**		**15**	**65,110.00**	**$47.43**	**$3,088,245.00**
839703	CONCRETE BARRIER (TYPE 60C)	M	7	4	3,929.20	$153.67	$603,802.40
	Unit Sub Total	**M**		**4**	**3,929.20**	**$153.67**	**$603,802.40**
	Item Code 839703 Total No. of Proj.			**19**		**Total Amount**	**$3,692,047.40**
839704	CONCRETE BARRIER (TYPE 60D)	LF	4	2	2,823.00	$36.59	$103,305.00
		LF	6	2	4,300.00	$31.72	$136,400.00
		LF	8	1	4,219.00	$20.00	$84,380.00
		LF	12	3	4,413.00	$33.03	$145,782.00
	Unit Sub Total	**LF**		**8**	**15,755.00**	**$29.82**	**$469,867.00**
839704	CONCRETE BARRIER (TYPE 60D)	M	4	2	1,300.00	$183.83	$238,980.00
		M	7	2	1,576.00	$148.71	$234,374.70
	Unit Sub Total	**M**		**4**	**2,876.00**	**$164.59**	**$473,354.70**
	Item Code 839704 Total No. of Proj.			**12**		**Total Amount**	**$943,221.70**
839705	CONCRETE BARRIER (TYPE 60E)	LF	2	1	50.00	$160.00	$8,000.00
		LF	3	1	150.00	$230.00	$34,500.00
		LF	4	1	160.00	$300.00	$48,000.00
		LF	6	2	215.00	$125.07	$26,890.00
		LF	12	1	380.00	$90.00	$34,200.00
	Unit Sub Total	**LF**		**6**	**955.00**	**$158.73**	**$151,590.00**
	Item Code 839705 Total No. of Proj.			**6**		**Total Amount**	**$151,590.00**
839706	CONCRETE BARRIER (TYPE 60G)	LF	2	1	580.00	$137.00	$79,460.00
		LF	8	1	4,360.00	$55.00	$239,800.00
		LF	12	3	10,670.00	$51.17	$545,980.00
	Unit Sub Total	**LF**		**5**	**15,610.00**	**$55.43**	**$865,240.00**
839706	CONCRETE BARRIER (TYPE 60G)	M	3	1	330.00	$380.00	$125,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839706	CONCRETE BARRIER (TYPE 60G)	M	7	2	3,070.00	$190.15	$583,756.00
	Unit Sub Total	**M**		**3**	**3,400.00**	**$208.58**	**$709,156.00**
	Item Code 839706 Total No. of Proj.			**8**		**Total Amount**	**$1,574,396.00**
839707	CONCRETE BARRIER (TYPE 60GA)	LF	12	1	2,962.00	$45.00	$133,290.00
	Unit Sub Total	**LF**		**1**	**2,962.00**	**$45.00**	**$133,290.00**
	Item Code 839707 Total No. of Proj.			**1**		**Total Amount**	**$133,290.00**
839708	CONCRETE BARRIER (TYPE 60GC)	LF	12	2	6,010.00	$95.74	$575,380.00
	Unit Sub Total	**LF**		**2**	**6,010.00**	**$95.74**	**$575,380.00**
839708	CONCRETE BARRIER (TYPE 60GC)	M	7	1	730.00	$390.00	$284,700.00
	Unit Sub Total	**M**		**1**	**730.00**	**$390.00**	**$284,700.00**
	Item Code 839708 Total No. of Proj.			**3**		**Total Amount**	**$860,080.00**
839709	CONCRETE BARRIER (TYPE 60GE)	LF	12	1	130.00	$300.00	$39,000.00
	Unit Sub Total	**LF**		**1**	**130.00**	**$300.00**	**$39,000.00**
839709	CONCRETE BARRIER (TYPE 60GE)	M	7	1	270.00	$450.00	$121,500.00
	Unit Sub Total	**M**		**1**	**270.00**	**$450.00**	**$121,500.00**
	Item Code 839709 Total No. of Proj.			**2**		**Total Amount**	**$160,500.00**
839710	CONCRETE BARRIER (TYPE 60S)	LF	3	1	1,470.00	$33.00	$48,510.00
		LF	11	1	22,100.00	$36.00	$795,600.00
		LF	12	1	1,060.00	$58.00	$61,480.00
	Unit Sub Total	**LF**		**3**	**24,630.00**	**$36.77**	**$905,590.00**
839710	CONCRETE BARRIER (TYPE 60S)	M	7	1	900.00	$160.00	$144,000.00
	Unit Sub Total	**M**		**1**	**900.00**	**$160.00**	**$144,000.00**
	Item Code 839710 Total No. of Proj.			**4**		**Total Amount**	**$1,049,590.00**
839712	CONCRETE BARRIER (TYPE 60SC)	LF	10	1	2,390.00	$113.00	$270,070.00
	Unit Sub Total	**LF**		**1**	**2,390.00**	**$113.00**	**$270,070.00**
839712	CONCRETE BARRIER (TYPE 60SC)	M	7	1	250.00	$800.00	$200,000.00
		M	11	1	140.00	$475.00	$66,500.00
	Unit Sub Total	**M**		**2**	**390.00**	**$683.33**	**$266,500.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 839712 Total No. of Proj.			**3**		**Total Amount**	**$536,570.00**
839714	CONCRETE BARRIER (TYPE 80)	LF	1	2	581.00	$277.54	$161,250.00
		LF	6	1	249.00	$258.00	$64,242.00
	Unit Sub Total	**LF**		**3**	**830.00**	**$271.68**	**$225,492.00**
	Item Code 839714 Total No. of Proj.			**3**		**Total Amount**	**$225,492.00**
839717	CONCRETE BARRIER (TYPE 732 MODIFIED)	LF	3	1	4,235.00	$65.00	$275,275.00
		LF	4	2	1,120.00	$76.33	$85,492.72
		LF	5	1	4,030.00	$75.00	$302,250.00
	Unit Sub Total	**LF**		**4**	**9,385.00**	**$70.65**	**$663,017.72**
839717	CONCRETE BARRIER (TYPE 732 MODIFIED)	M	4	2	4,406.00	$264.90	$1,167,160.00
		M	7	2	539.00	$210.23	$113,312.00
		M	10	1	1,461.00	$220.00	$321,420.00
	Unit Sub Total	**M**		**5**	**6,406.00**	**$250.06**	**$1,601,892.00**
	Item Code 839717 Total No. of Proj.			**9**		**Total Amount**	**$2,264,909.72**
839720	CONCRETE BARRIER (TYPE 732)	LF	2	1	391.00	$90.00	$35,190.00
		LF	3	1	6,662.00	$20.00	$133,240.00
		LF	4	1	518.00	$75.00	$38,850.00
		LF	5	1	640.00	$160.00	$102,400.00
		LF	6	1	352.00	$104.00	$36,608.00
		LF	8	1	78.00	$206.00	$16,068.00
		LF	10	1	147.00	$120.00	$17,640.00
	Unit Sub Total	**LF**		**7**	**8,788.00**	**$43.24**	**$379,996.00**
839720	CONCRETE BARRIER (TYPE 732)	M	4	1	105.00	$220.00	$23,100.00
		M	11	1	416.00	$310.00	$128,960.00
	Unit Sub Total	**M**		**2**	**521.00**	**$291.86**	**$152,060.00**
	Item Code 839720 Total No. of Proj.			**9**		**Total Amount**	**$532,056.00**
839721	CONCRETE BARRIER (TYPE 732A)	LF	4	1	2,868.00	$65.00	$186,420.00
		LF	10	1	7,960.00	$51.00	$405,960.00
		LF	11	1	900.00	$84.00	$75,600.00
	Unit Sub Total	**LF**		**3**	**11,728.00**	**$56.96**	**$667,980.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
839721	CONCRETE BARRIER (TYPE 732A)	M	4	1	26.00	$325.00	$8,450.00
	Unit Sub Total	**M**		**1**	**26.00**	**$325.00**	**$8,450.00**
	Item Code 839721 Total No. of Proj.			**4**		**Total Amount**	**$676,430.00**
839723	CONCRETE BARRIER (TYPE 732B)	LF	3	1	150.00	$60.00	$9,000.00
	Unit Sub Total	**LF**		**1**	**150.00**	**$60.00**	**$9,000.00**
839723	CONCRETE BARRIER (TYPE 732B)	M	4	1	194.00	$250.00	$48,500.00
	Unit Sub Total	**M**		**1**	**194.00**	**$250.00**	**$48,500.00**
	Item Code 839723 Total No. of Proj.			**2**		**Total Amount**	**$57,500.00**
839725	CONCRETE BARRIER (TYPE 736)	LF	2	2	981.00	$65.27	$64,026.00
		LF	11	1	379.00	$84.00	$31,836.00
		LF	12	1	748.00	$60.00	$44,880.00
	Unit Sub Total	**LF**		**4**	**2,108.00**	**$66.77**	**$140,742.00**
839725	CONCRETE BARRIER (TYPE 736)	M	4	1	661.00	$220.00	$145,420.00
	Unit Sub Total	**M**		**1**	**661.00**	**$220.00**	**$145,420.00**
	Item Code 839725 Total No. of Proj.			**5**		**Total Amount**	**$286,162.00**
839726	CONCRETE BARRIER (TYPE 736A)	LF	12	1	72.00	$170.00	$12,240.00
	Unit Sub Total	**LF**		**1**	**72.00**	**$170.00**	**$12,240.00**
839726	CONCRETE BARRIER (TYPE 736A)	M	7	2	1,489.00	$186.03	$276,998.00
	Unit Sub Total	**M**		**2**	**1,489.00**	**$186.03**	**$276,998.00**
	Item Code 839726 Total No. of Proj.			**3**		**Total Amount**	**$289,238.00**
839727	CONCRETE BARRIER (TYPE 736 MODIFIED)	LF	4	3	3,433.00	$94.32	$323,804.00
		LF	5	1	156.00	$180.00	$28,080.00
		LF	12	6	32,142.00	$65.99	$2,121,094.00
	Unit Sub Total	**LF**		**10**	**35,731.00**	**$69.21**	**$2,472,978.00**
839727	CONCRETE BARRIER (TYPE 736 MODIFIED)	M	7	5	2,890.00	$222.22	$642,222.40
	Unit Sub Total	**M**		**5**	**2,890.00**	**$222.22**	**$642,222.40**
	Item Code 839727 Total No. of Proj.			**15**		**Total Amount**	**$3,115,200.40**
839731	CONCRETE BARRIER (TYPE 736B)	LF	12	1	300.00	$138.00	$41,400.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**1**	**300.00**	**$138.00**	**$41,400.00**
839731	CONCRETE BARRIER (TYPE 736B)		M	4	1	120.00	$290.00	$34,800.00
			M	7	2	65.00	$270.91	$17,609.00
		Unit Sub Total	**M**		**3**	**185.00**	**$283.29**	**$52,409.00**
	Item Code 839731	**Total No. of Proj.**			**4**		**Total Amount**	**$93,809.00**
839734	CONCRETE BARRIER (TYPE 736SV)		LF	4	1	295.00	$110.00	$32,450.00
			LF	12	4	9,254.00	$107.99	$999,375.00
		Unit Sub Total	**LF**		**5**	**9,549.00**	**$108.06**	**$1,031,825.00**
839734	CONCRETE BARRIER (TYPE 736SV)		M	7	4	4,701.60	$348.99	$1,640,788.80
		Unit Sub Total	**M**		**4**	**4,701.60**	**$348.99**	**$1,640,788.80**
	Item Code 839734	**Total No. of Proj.**			**9**		**Total Amount**	**$2,672,613.80**
839737	CONCRETE BARRIER (TYPE 742B)		LF	4	1	1,050.00	$125.00	$131,250.00
		Unit Sub Total	**LF**		**1**	**1,050.00**	**$125.00**	**$131,250.00**
	Item Code 839737	**Total No. of Proj.**			**1**		**Total Amount**	**$131,250.00**
840501	THERMOPLASTIC TRAFFIC STRIPE		LF	1	1	3,440.00	$1.15	$3,956.00
			LF	4	4	92,280.00	$0.31	$28,677.00
			LF	6	1	5,550.00	$0.34	$1,887.00
			LF	7	1	2,000.00	$0.80	$1,600.00
			LF	8	2	4,140.00	$0.69	$2,870.60
			LF	11	2	1,900.00	$1.24	$2,365.00
		Unit Sub Total	**LF**		**11**	**109,310.00**	**$0.38**	**$41,355.60**
840501	THERMOPLASTIC TRAFFIC STRIPE		M	4	1	5,500.00	$1.00	$5,500.00
			M	7	1	6,630.00	$0.80	$5,304.00
		Unit Sub Total	**M**		**2**	**12,130.00**	**$0.89**	**$10,804.00**
	Item Code 840501	**Total No. of Proj.**			**13**		**Total Amount**	**$52,159.60**
840504	4" THERMOPLASTIC TRAFFIC STRIPE		LF	1	29	2,448,060.00	$0.30	$731,020.50
			LF	2	4	20,030.00	$0.83	$16,600.00
			LF	3	33	3,043,801.00	$0.28	$863,916.16
			LF	4	53	2,750,260.00	$0.34	$935,594.10
			LF	5	20	1,712,580.00	$0.28	$470,996.10

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840504	4" THERMOPLASTIC TRAFFIC STRIPE	LF	6	29	3,394,340.00	$0.26	$898,524.80
		LF	7	34	3,327,840.00	$0.32	$1,051,058.50
		LF	8	1	90,900.00	$0.30	$27,270.00
		LF	10	13	834,980.00	$0.31	$262,171.30
		LF	11	8	107,420.00	$0.57	$61,426.00
		LF	12	22	1,300,850.00	$0.28	$361,992.80
	Unit Sub Total	**LF**		**246**	**19,031,061.00**	**$0.30**	**$5,680,570.26**
	Item Code 840504 Total No. of Proj.			**246**		**Total Amount**	**$5,680,570.26**
840505	6" THERMOPLASTIC TRAFFIC STRIPE	LF	1	2	1,909.00	$2.19	$4,189.00
		LF	3	1	660.00	$2.30	$1,518.00
		LF	4	5	69,240.00	$0.36	$25,139.50
		LF	7	3	9,800.00	$0.39	$3,834.00
		LF	12	1	4,260.00	$0.70	$2,982.00
	Unit Sub Total	**LF**		**12**	**85,869.00**	**$0.44**	**$37,662.50**
	Item Code 840505 Total No. of Proj.			**12**		**Total Amount**	**$37,662.50**
840506	8" THERMOPLASTIC TRAFFIC STRIPE	LF	1	11	26,750.00	$0.53	$14,114.20
		LF	2	1	3,200.00	$1.50	$4,800.00
		LF	3	25	91,742.00	$0.66	$60,508.94
		LF	4	33	163,543.00	$0.84	$136,708.13
		LF	5	13	70,720.00	$0.51	$35,879.70
		LF	6	19	43,140.00	$0.84	$36,413.40
		LF	7	26	138,680.00	$0.65	$89,742.70
		LF	8	4	6,105.00	$0.72	$4,370.00
		LF	10	6	23,710.00	$0.88	$20,747.50
		LF	11	21	98,533.00	$0.82	$80,349.50
		LF	12	19	124,940.00	$0.72	$89,961.80
	Unit Sub Total	**LF**		**178**	**791,063.00**	**$0.73**	**$573,595.87**
	Item Code 840506 Total No. of Proj.			**178**		**Total Amount**	**$573,595.87**
840508	8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)	LF	1	1	110.00	$1.00	$110.00
		LF	2	1	3,090.00	$1.25	$3,862.50
		LF	3	5	16,490.00	$0.47	$7,783.00
		LF	4	13	81,290.00	$0.64	$52,004.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840508	8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)	LF	5	3	5,380.00	$0.29	$1,580.20
		LF	6	2	3,670.00	$0.81	$2,971.00
		LF	7	12	99,110.00	$0.54	$53,119.00
		LF	9	1	96.00	$8.00	$768.00
		LF	10	2	3,590.00	$0.70	$2,513.00
		LF	11	10	53,160.00	$0.61	$32,314.00
		LF	12	11	94,252.00	$0.59	$55,525.00
	Unit Sub Total	**LF**		**61**	**360,238.00**	**$0.59**	**$212,549.70**
	Item Code 840508 Total No. of Proj.			**61**		**Total Amount**	**$212,549.70**
840515	THERMOPLASTIC PAVEMENT MARKING	M2	2	1	6.00	$80.00	$480.00
		M2	3	1	290.00	$30.00	$8,700.00
		M2	4	3	753.00	$32.61	$24,558.00
		M2	6	2	350.00	$35.00	$12,250.00
		M2	7	4	1,850.00	$39.05	$72,247.00
		M2	10	1	810.00	$33.00	$26,730.00
		M2	11	3	1,340.00	$36.62	$49,072.00
	Unit Sub Total	**M2**		**15**	**5,399.00**	**$35.94**	**$194,037.00**
840515	THERMOPLASTIC PAVEMENT MARKING	SQFT	1	11	39,540.00	$3.56	$140,630.50
		SQFT	2	26	38,425.00	$4.82	$185,200.90
		SQFT	3	23	52,517.00	$3.10	$163,010.05
		SQFT	4	41	97,410.00	$2.98	$289,955.50
		SQFT	5	25	55,309.00	$4.80	$265,344.50
		SQFT	6	33	42,952.00	$3.49	$149,840.00
		SQFT	7	31	120,265.00	$2.67	$320,639.40
		SQFT	8	19	34,468.00	$2.75	$94,953.00
		SQFT	9	5	1,304.00	$5.80	$7,569.00
		SQFT	10	26	47,230.00	$3.23	$152,410.60
		SQFT	11	23	21,406.00	$3.99	$85,345.20
		SQFT	12	18	48,316.00	$2.57	$124,190.60
	Unit Sub Total	**SQFT**		**281**	**599,142.00**	**$3.30**	**$1,979,089.25**
	Item Code 840515 Total No. of Proj.			**296**		**Total Amount**	**$2,173,126.25**
840519	THERMOPLASTIC CROSSWALK AND PAVEMENT MARKING	SQFT	5	1	560.00	$6.00	$3,360.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**SQFT**		**1**	**560.00**	**$6.00**	**$3,360.00**
	Item Code 840519	**Total No. of Proj.**			**1**		**Total Amount**	**$3,360.00**
840521	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 6-1)		LF	3	2	1,660.00	$0.29	$481.50
			LF	4	2	530.00	$0.62	$330.00
			LF	5	1	210.00	$0.30	$63.00
			LF	6	1	91.00	$1.00	$91.00
			LF	7	4	835.00	$0.54	$452.00
			LF	11	1	300.00	$0.80	$240.00
			LF	12	4	3,530.00	$0.73	$2,593.10
		Unit Sub Total	**LF**		**15**	**7,156.00**	**$0.59**	**$4,250.60**
	Item Code 840521	**Total No. of Proj.**			**15**		**Total Amount**	**$4,250.60**
840523	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)		LF	1	6	5,750.00	$0.92	$5,287.60
			LF	3	8	16,070.00	$0.23	$3,622.40
			LF	4	2	300.00	$0.33	$100.00
			LF	5	3	2,370.00	$0.39	$923.10
			LF	6	9	17,930.00	$0.18	$3,183.90
			LF	7	1	120.00	$0.25	$30.00
			LF	10	1	1,900.00	$0.28	$532.00
			LF	11	1	100.00	$1.00	$100.00
		Unit Sub Total	**LF**		**31**	**44,540.00**	**$0.31**	**$13,779.00**
	Item Code 840523	**Total No. of Proj.**			**31**		**Total Amount**	**$13,779.00**
840525	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)		LF	1	14	131,710.00	$0.37	$48,688.10
			LF	2	1	6,800.00	$0.45	$3,060.00
			LF	3	24	1,053,110.00	$0.20	$210,263.50
			LF	4	11	357,460.00	$0.17	$61,644.50
			LF	5	12	392,430.00	$0.23	$92,220.10
			LF	6	23	1,118,910.00	$0.20	$225,633.50
			LF	7	30	2,135,560.00	$0.21	$458,943.20
			LF	10	3	378,600.00	$0.17	$63,437.00
			LF	11	2	20,900.00	$0.50	$10,480.00
			LF	12	18	1,314,870.00	$0.18	$241,384.50

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**LF**		**138**	**6,910,350.00**	**$0.20**	**$1,415,754.40**
	Item Code 840525	**Total No. of Proj.**			**138**		**Total Amount**	**$1,415,754.40**
840526	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 17-7)		LF	1	1	8,060.00	$0.50	$4,030.00
			LF	2	1	150.00	$0.45	$67.50
			LF	3	13	40,666.00	$0.31	$12,479.62
			LF	4	19	125,370.00	$0.20	$25,673.80
			LF	5	6	23,540.00	$0.28	$6,482.50
			LF	6	10	127,930.00	$0.20	$25,393.10
			LF	7	23	143,870.00	$0.25	$36,145.70
			LF	10	2	5,410.00	$0.14	$751.00
			LF	11	6	5,390.00	$0.86	$4,618.00
			LF	12	15	30,894.00	$0.30	$9,259.00
		Unit Sub Total	**LF**		**96**	**511,280.00**	**$0.24**	**$124,900.22**
	Item Code 840526	**Total No. of Proj.**			**96**		**Total Amount**	**$124,900.22**
840545	4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED, BROKEN 36-12)		LF	3	3	313,000.00	$1.69	$527,900.00
			LF	9	1	12,700.00	$1.20	$15,240.00
			LF	10	1	4,500.00	$0.85	$3,825.00
		Unit Sub Total	**LF**		**5**	**330,200.00**	**$1.66**	**$546,965.00**
	Item Code 840545	**Total No. of Proj.**			**5**		**Total Amount**	**$546,965.00**
840550	8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)		LF	7	5	17,910.00	$0.54	$9,753.00
			LF	12	7	61,410.00	$0.62	$38,354.00
		Unit Sub Total	**LF**		**12**	**79,320.00**	**$0.61**	**$48,107.00**
	Item Code 840550	**Total No. of Proj.**			**12**		**Total Amount**	**$48,107.00**
840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)		LF	1	4	8,890.00	$2.90	$25,757.50
			LF	2	31	2,520,512.00	$0.20	$501,501.00
			LF	4	2	209,070.00	$0.25	$51,560.00
			LF	5	16	1,266,139.00	$0.49	$620,582.30
			LF	6	2	26,900.00	$0.21	$5,765.00
			LF	8	31	5,027,820.00	$0.14	$714,268.70

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	LF	10	25	1,968,740.00	$0.21	$407,262.50
	Unit Sub Total	**LF**		**111**	**11,028,071.00**	**$0.21**	**$2,326,697.00**
840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	M	6	1	45,400.00	$0.40	$18,160.00
		M	10	1	20,300.00	$1.65	$33,495.00
	Unit Sub Total	**M**		**2**	**65,700.00**	**$0.79**	**$51,655.00**
	Item Code 840560 Total No. of Proj.			**113**		**Total Amount**	**$2,378,352.00**
840561	100 MM THERMOPLASTIC TRAFFIC STRIPE	M	2	1	3,060.00	$2.20	$6,732.00
		M	3	1	17,400.00	$0.50	$8,700.00
		M	4	2	23,510.00	$0.94	$22,130.00
		M	6	2	2,300.00	$0.99	$2,266.00
		M	7	4	195,560.00	$0.81	$157,950.00
		M	11	1	60.00	$2.75	$165.00
	Unit Sub Total	**M**		**11**	**241,890.00**	**$0.82**	**$197,943.00**
	Item Code 840561 Total No. of Proj.			**11**		**Total Amount**	**$197,943.00**
840562	150 MM THERMOPLASTIC TRAFFIC STRIPE	M	4	1	490.00	$1.50	$735.00
	Unit Sub Total	**M**		**1**	**490.00**	**$1.50**	**$735.00**
	Item Code 840562 Total No. of Proj.			**1**		**Total Amount**	**$735.00**
840563	200 MM THERMOPLASTIC TRAFFIC STRIPE	M	2	1	180.00	$5.50	$990.00
		M	3	1	860.00	$1.00	$860.00
		M	4	2	4,890.00	$2.11	$10,320.00
		M	6	2	1,250.00	$1.99	$2,482.50
		M	7	4	27,220.00	$1.50	$40,766.50
		M	11	3	14,040.00	$2.82	$39,629.00
	Unit Sub Total	**M**		**13**	**48,440.00**	**$1.96**	**$95,048.00**
	Item Code 840563 Total No. of Proj.			**13**		**Total Amount**	**$95,048.00**
840564	200 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 3.66 M - 0.92 M)	M	4	2	3,720.00	$1.78	$6,635.00
		M	7	4	8,540.00	$1.50	$12,819.40
		M	11	3	2,280.00	$1.71	$3,892.50
	Unit Sub Total	**M**		**9**	**14,540.00**	**$1.61**	**$23,346.90**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 840564 Total No. of Proj.			**9**		**Total Amount**	**$23,346.90**
840567	100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 1.83 M - 0.30 M)	M	7	1	40.00	$1.00	$40.00
		M	11	1	120.00	$3.00	$360.00
	Unit Sub Total	**M**		**2**	**160.00**	**$2.50**	**$400.00**
	Item Code 840567 Total No. of Proj.			**2**		**Total Amount**	**$400.00**
840568	100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 3.66 M - 0.92 M)	M	2	1	130.00	$1.75	$227.50
		M	3	1	190.00	$1.00	$190.00
	Unit Sub Total	**M**		**2**	**320.00**	**$1.30**	**$417.50**
	Item Code 840568 Total No. of Proj.			**2**		**Total Amount**	**$417.50**
840570	100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 10.98 M - 3.66 M)	M	3	1	3,980.00	$0.50	$1,990.00
		M	6	2	22,180.00	$0.40	$8,917.00
		M	7	4	163,000.00	$0.65	$105,459.00
	Unit Sub Total	**M**		**7**	**189,160.00**	**$0.62**	**$116,366.00**
	Item Code 840570 Total No. of Proj.			**7**		**Total Amount**	**$116,366.00**
840571	100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 5.18 M - 2.14 M)	M	7	4	1,679.00	$0.71	$1,195.31
		M	11	2	2,970.00	$1.80	$5,340.00
	Unit Sub Total	**M**		**6**	**4,649.00**	**$1.41**	**$6,535.31**
	Item Code 840571 Total No. of Proj.			**6**		**Total Amount**	**$6,535.31**
840574	200 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 10.98 M - 3.66 M)	M	7	1	1,600.00	$1.00	$1,600.00
	Unit Sub Total	**M**		**1**	**1,600.00**	**$1.00**	**$1,600.00**
	Item Code 840574 Total No. of Proj.			**1**		**Total Amount**	**$1,600.00**
840577	200 MM TWO-COMPONENT PAINT TRAFFIC STRIPE	M	7	1	600.00	$11.00	$6,600.00
	Unit Sub Total	**M**		**1**	**600.00**	**$11.00**	**$6,600.00**
	Item Code 840577 Total No. of Proj.			**1**		**Total Amount**	**$6,600.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840580	4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED) (BROKEN 17-7)	LF	3	1	1,580.00	$5.15	$8,137.00
		LF	9	1	10,300.00	$1.20	$12,360.00
	Unit Sub Total	**LF**		**2**	**11,880.00**	**$1.73**	**$20,497.00**
	Item Code 840580 Total No. of Proj.			**2**		**Total Amount**	**$20,497.00**
840581	4" THERMOPLASTIC TRAFFIC STRIPE (RECESSED)	LF	3	5	597,400.00	$2.07	$1,239,275.00
		LF	9	1	46,900.00	$1.50	$70,350.00
		LF	10	1	78,000.00	$1.60	$124,800.00
	Unit Sub Total	**LF**		**7**	**722,300.00**	**$1.99**	**$1,434,425.00**
	Item Code 840581 Total No. of Proj.			**7**		**Total Amount**	**$1,434,425.00**
840582	4" TWO-COMPONENT PAINT TRAFFIC STRIPE	LF	2	2	496,200.00	$0.37	$183,040.00
		LF	3	7	1,918,500.00	$0.26	$503,126.00
		LF	7	1	139,000.00	$0.80	$111,200.00
		LF	11	1	22,800.00	$0.65	$14,820.00
	Unit Sub Total	**LF**		**11**	**2,576,500.00**	**$0.32**	**$812,186.00**
	Item Code 840582 Total No. of Proj.			**11**		**Total Amount**	**$812,186.00**
840584	8" TWO-COMPONENT PAINT TRAFFIC STRIPE	LF	2	2	10,960.00	$1.47	$16,070.00
		LF	3	4	15,570.00	$0.74	$11,487.60
		LF	7	1	1,580.00	$2.00	$3,160.00
		LF	11	1	4,100.00	$1.30	$5,330.00
	Unit Sub Total	**LF**		**8**	**32,210.00**	**$1.12**	**$36,047.60**
	Item Code 840584 Total No. of Proj.			**8**		**Total Amount**	**$36,047.60**
840608	4" TWO-COMPONENT PAINT TRAFFIC STRIPE (BROKEN 17-7)	LF	2	2	3,070.00	$1.47	$4,520.00
	Unit Sub Total	**LF**		**2**	**3,070.00**	**$1.47**	**$4,520.00**
	Item Code 840608 Total No. of Proj.			**2**		**Total Amount**	**$4,520.00**
840653	PAINT TRAFFIC STRIPE	M	7	1	69,000.00	$0.45	$31,050.00
	Unit Sub Total	**M**		**1**	**69,000.00**	**$0.45**	**$31,050.00**
	Item Code 840653 Total No. of Proj.			**1**		**Total Amount**	**$31,050.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840655	PAINT TRAFFIC STRIPE (1-COAT)	LF	1	5	238,750.00	$0.15	$35,660.50
	Unit Sub Total	**LF**		**5**	**238,750.00**	**$0.15**	**$35,660.50**
	Item Code 840655 Total No. of Proj.			**5**		**Total Amount**	**$35,660.50**
840656	PAINT TRAFFIC STRIPE (2-COAT)	LF	2	1	340.00	$2.31	$785.40
		LF	3	2	2,110.00	$1.75	$3,697.00
		LF	4	3	75,210.00	$0.45	$34,220.00
		LF	6	8	842,100.00	$0.10	$83,412.00
		LF	7	1	2,000.00	$0.25	$500.00
		LF	9	19	2,126,860.00	$0.12	$255,233.40
		LF	10	4	206,820.00	$0.19	$39,193.00
		LF	11	26	3,816,380.00	$0.13	$491,679.50
		LF	12	15	1,360,060.00	$0.11	$149,445.10
	Unit Sub Total	**LF**		**79**	**8,431,880.00**	**$0.13**	**$1,058,165.40**
840656	PAINT TRAFFIC STRIPE (2-COAT)	M	6	1	200.00	$4.00	$800.00
		M	7	3	177,670.00	$0.43	$75,608.50
		M	10	1	2,580.00	$1.65	$4,257.00
		M	11	3	168,700.00	$0.58	$97,678.00
	Unit Sub Total	**M**		**8**	**349,150.00**	**$0.51**	**$178,343.50**
	Item Code 840656 Total No. of Proj.			**87**		**Total Amount**	**$1,236,508.90**
840660	PAINT PAVEMENT MARKING	M2	7	1	24.00	$36.75	$882.00
	Unit Sub Total	**M2**		**1**	**24.00**	**$36.75**	**$882.00**
840660	PAINT PAVEMENT MARKING	SQFT	4	1	200.00	$5.00	$1,000.00
		SQFT	6	1	25.00	$24.00	$600.00
	Unit Sub Total	**SQFT**		**2**	**225.00**	**$7.11**	**$1,600.00**
	Item Code 840660 Total No. of Proj.			**3**		**Total Amount**	**$2,482.00**
840661	TWO-COMPONENT PAINT PAVEMENT MARKING	SQFT	3	8	18,590.00	$4.94	$91,909.60
	Unit Sub Total	**SQFT**		**8**	**18,590.00**	**$4.94**	**$91,909.60**
	Item Code 840661 Total No. of Proj.			**8**		**Total Amount**	**$91,909.60**
840666	PAINT PAVEMENT MARKING (2-COAT)	M2	4	1	4.00	$50.00	$200.00
		M2	6	1	2.40	$350.00	$840.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
840666	PAINT PAVEMENT MARKING (2-COAT)	M2	7	1	17.00	$16.00	$272.00
		M2	10	1	170.00	$33.00	$5,610.00
	Unit Sub Total	**M2**		**4**	**193.40**	**$35.79**	**$6,922.00**
840666	PAINT PAVEMENT MARKING (2-COAT)	SQFT	1	1	69.00	$1.00	$69.00
		SQFT	2	1	3.00	$128.13	$384.39
		SQFT	4	2	2,460.00	$2.15	$5,280.00
		SQFT	6	1	3,560.00	$2.00	$7,120.00
		SQFT	9	7	19,130.00	$1.79	$34,149.00
		SQFT	10	2	947.00	$2.99	$2,836.00
		SQFT	12	5	3,267.00	$2.09	$6,824.40
	Unit Sub Total	**SQFT**		**19**	**29,436.00**	**$1.92**	**$56,662.79**
	Item Code 840666 Total No. of Proj.			**23**		**Total Amount**	**$63,584.79**
842000	PARKING BUMPER (PRECAST CONCRETE)	EA	2	1	2.00	$80.00	$160.00
		EA	3	1	49.00	$29.12	$1,426.88
		EA	4	6	256.00	$69.15	$17,702.40
		EA	6	1	1.00	$100.00	$100.00
	Unit Sub Total	**EA**		**9**	**308.00**	**$62.95**	**$19,389.28**
	Item Code 842000 Total No. of Proj.			**9**		**Total Amount**	**$19,389.28**
850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	1	8	29,732.00	$1.99	$59,278.00
		EA	3	3	3,730.00	$1.82	$6,801.50
		EA	4	32	109,117.00	$1.76	$191,770.10
		EA	5	17	111,310.00	$1.21	$135,038.30
		EA	6	2	10,120.00	$1.23	$12,479.00
		EA	7	30	239,630.00	$1.14	$272,024.80
		EA	8	10	47,900.00	$1.09	$52,386.00
		EA	10	3	6,940.00	$2.51	$17,440.00
		EA	11	23	130,853.00	$1.29	$168,463.00
		EA	12	18	128,100.00	$1.19	$152,973.40
	Unit Sub Total	**EA**		**146**	**817,432.00**	**$1.31**	**$1,068,654.10**
	Item Code 850101 Total No. of Proj.			**146**		**Total Amount**	**$1,068,654.10**
850102	PAVEMENT MARKER (REFLECTIVE)	EA	4	5	1,241.00	$12.68	$15,733.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**5**	**1,241.00**	**$12.68**	**$15,733.00**
	Item Code 850102	**Total No. of Proj.**			**5**		**Total Amount**	**$15,733.00**
850110	PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE C)		EA	7	1	1,240.00	$2.60	$3,224.00
		Unit Sub Total	**EA**		**1**	**1,240.00**	**$2.60**	**$3,224.00**
	Item Code 850110	**Total No. of Proj.**			**1**		**Total Amount**	**$3,224.00**
850111	PAVEMENT MARKER (RETROREFLECTIVE)		EA	1	20	46,157.00	$2.96	$136,826.00
			EA	2	10	14,490.00	$3.27	$47,347.55
			EA	3	30	82,033.00	$3.11	$255,025.60
			EA	4	51	94,365.00	$3.35	$316,252.30
			EA	5	34	115,875.00	$2.55	$295,869.70
			EA	6	32	73,746.00	$2.76	$203,258.00
			EA	7	37	154,341.00	$2.68	$413,195.00
			EA	8	23	82,047.00	$2.25	$184,328.50
			EA	10	32	74,074.00	$2.93	$216,854.30
			EA	11	31	93,769.00	$3.23	$303,016.30
			EA	12	23	83,005.00	$2.62	$217,065.40
		Unit Sub Total	**EA**		**323**	**913,902.00**	**$2.83**	**$2,589,038.65**
850111	PAVEMENT MARKER (RETROREFLECTIVE)		SQFT	3	1	243.00	$5.00	$1,215.00
		Unit Sub Total	**SQFT**		**1**	**243.00**	**$5.00**	**$1,215.00**
	Item Code 850111	**Total No. of Proj.**			**324**		**Total Amount**	**$2,590,253.65**
850112	PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE G)		EA	4	1	18.00	$10.00	$180.00
			EA	7	3	13,910.00	$2.58	$35,866.00
		Unit Sub Total	**EA**		**4**	**13,928.00**	**$2.59**	**$36,046.00**
	Item Code 850112	**Total No. of Proj.**			**4**		**Total Amount**	**$36,046.00**
850113	PAVEMENT MARKER (RETROREFLECTIVE-SPECIAL TYPE H)		EA	1	1	87.00	$4.50	$391.50
			EA	7	2	6,110.00	$2.61	$15,938.00
		Unit Sub Total	**EA**		**3**	**6,197.00**	**$2.64**	**$16,329.50**
	Item Code 850113	**Total No. of Proj.**			**3**		**Total Amount**	**$16,329.50**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
850121	PAVEMENT MARKER (NON-REFLECTIVE-RECESSED)	EA	2	1	740.00	$25.00	$18,500.00
	Unit Sub Total	**EA**		**1**	**740.00**	**$25.00**	**$18,500.00**
	Item Code 850121 Total No. of Proj.			**1**		**Total Amount**	**$18,500.00**
850122	PAVEMENT MARKER (RETROREFLECTIVE-RECESSED)	EA	1	13	8,332.00	$19.14	$159,441.50
		EA	2	22	70,341.00	$6.19	$435,107.10
		EA	3	4	12,490.00	$6.75	$84,260.00
		EA	4	1	2,820.00	$7.30	$20,586.00
		EA	5	1	6,060.00	$7.82	$47,389.20
		EA	6	2	10,880.00	$8.26	$89,880.00
		EA	7	1	3,910.00	$8.00	$31,280.00
		EA	8	10	66,389.00	$8.66	$575,146.00
		EA	9	1	940.00	$8.50	$7,990.00
		EA	10	1	4,370.00	$5.20	$22,724.00
		EA	11	1	4,950.00	$20.00	$99,000.00
	Unit Sub Total	**EA**		**57**	**191,482.00**	**$8.21**	**$1,572,803.80**
850122	PAVEMENT MARKER (RETROREFLECTIVE-RECESSED)	LF	8	1	1,920.00	$7.00	$13,440.00
	Unit Sub Total	**LF**		**1**	**1,920.00**	**$7.00**	**$13,440.00**
	Item Code 850122 Total No. of Proj.			**58**		**Total Amount**	**$1,586,243.80**
860090	MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	LS	1	10	10.00	$1,190.00	$11,900.00
		LS	2	17	17.00	$1,477.16	$25,111.75
		LS	3	24	24.00	$1,924.25	$46,182.00
		LS	4	39	39.00	$4,410.20	$171,997.78
		LS	5	17	17.00	$1,328.29	$22,581.00
		LS	6	29	29.00	$2,154.34	$62,476.00
		LS	7	36	36.00	$2,740.00	$98,640.00
		LS	8	17	17.00	$946.78	$16,095.20
		LS	9	8	8.00	$681.25	$5,450.00
		LS	10	37	37.00	$1,131.88	$41,879.50
		LS	11	38	38.00	$1,879.14	$71,407.50
		LS	12	32	32.00	$3,228.19	$103,301.97
	Unit Sub Total	**LS**		**304**	**304.00**	**$2,227.05**	**$677,022.70**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 860090 Total No. of Proj.			**304**		**Total Amount**	**$677,022.70**
860140	42" CAST-IN-DRILLED-HOLE CONCRETE PILE (HIGH MAST LIGHTING)	LS	3	1	1.00	$4,700.00	$4,700.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$4,700.00**	**$4,700.00**
	Item Code 860140 Total No. of Proj.			**1**		**Total Amount**	**$4,700.00**
860150	SIGNAL AND LIGHTING (TEMPORARY)	LS	4	2	2.00	$275,000.00	$550,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$275,000.00**	**$550,000.00**
	Item Code 860150 Total No. of Proj.			**2**		**Total Amount**	**$550,000.00**
860201	SIGNAL AND LIGHTING	LS	2	4	4.00	$137,006.00	$548,024.00
		LS	3	2	2.00	$163,000.00	$326,000.00
		LS	6	3	3.00	$178,594.00	$535,782.00
		LS	7	1	1.00	$100,000.00	$100,000.00
		LS	10	1	1.00	$182,624.00	$182,624.00
		LS	11	3	3.00	$84,000.00	$252,000.00
		LS	12	2	2.00	$134,167.00	$268,334.00
	Unit Sub Total	**LS**		**16**	**16.00**	**$138,297.75**	**$2,212,764.00**
	Item Code 860201 Total No. of Proj.			**16**		**Total Amount**	**$2,212,764.00**
860251	SIGNAL AND LIGHTING (LOCATION 1)	LS	4	5	5.00	$134,950.88	$674,754.41
		LS	10	2	2.00	$128,000.00	$256,000.00
		LS	11	1	1.00	$160,000.00	$160,000.00
		LS	12	2	2.00	$105,960.61	$211,921.22
	Unit Sub Total	**LS**		**10**	**10.00**	**$130,267.56**	**$1,302,675.63**
	Item Code 860251 Total No. of Proj.			**10**		**Total Amount**	**$1,302,675.63**
860252	SIGNAL AND LIGHTING (LOCATION 2)	LS	4	4	4.00	$150,311.71	$601,246.85
		LS	10	2	2.00	$122,500.00	$245,000.00
		LS	11	1	1.00	$140,000.00	$140,000.00
		LS	12	2	2.00	$101,299.75	$202,599.49
	Unit Sub Total	**LS**		**9**	**9.00**	**$132,094.04**	**$1,188,846.34**
	Item Code 860252 Total No. of Proj.			**9**		**Total Amount**	**$1,188,846.34**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
860253	SIGNAL AND LIGHTING (LOCATION 3)	LS	4	2	2.00	$132,000.00	$264,000.00
		LS	10	1	1.00	$110,000.00	$110,000.00
		LS	12	1	1.00	$120,000.00	$120,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$123,500.00**	**$494,000.00**
	Item Code 860253 Total No. of Proj.			**4**		**Total Amount**	**$494,000.00**
860254	SIGNAL AND LIGHTING (LOCATION 4)	LS	4	1	1.00	$100,000.00	$100,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$100,000.00**	**$100,000.00**
	Item Code 860254 Total No. of Proj.			**1**		**Total Amount**	**$100,000.00**
860300	SIGNAL AND LIGHTING (CITY STREET LOCATION 1)	LS	4	1	1.00	$191,435.77	$191,435.77
		LS	5	1	1.00	$138,000.00	$138,000.00
		LS	7	1	1.00	$82,000.00	$82,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$137,145.26**	**$411,435.77**
	Item Code 860300 Total No. of Proj.			**3**		**Total Amount**	**$411,435.77**
860301	SIGNAL AND LIGHTING	LS	5	1	1.00	$109,100.00	$109,100.00
		LS	6	1	1.00	$177,983.10	$177,983.10
		LS	11	2	2.00	$180,763.50	$361,527.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$162,152.53**	**$648,610.10**
	Item Code 860301 Total No. of Proj.			**4**		**Total Amount**	**$648,610.10**
860302	SIGNAL AND LIGHTING (CITY STREET LOCATION 2)	LS	4	1	1.00	$7,556.68	$7,556.68
		LS	5	1	1.00	$104,000.00	$104,000.00
		LS	7	1	1.00	$91,000.00	$91,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$67,518.89**	**$202,556.68**
	Item Code 860302 Total No. of Proj.			**3**		**Total Amount**	**$202,556.68**
860400	LIGHTING (TEMPORARY)	LS	4	2	2.00	$87,972.29	$175,944.58
		LS	7	4	4.00	$134,625.00	$538,500.00
		LS	12	1	1.00	$6,000.00	$6,000.00
	Unit Sub Total	**LS**		**7**	**7.00**	**$102,920.65**	**$720,444.58**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 860400 Total No. of Proj.			**7**		**Total Amount**	**$720,444.58**
860401	LIGHTING	LS	2	1	1.00	$9,130.00	$9,130.00
		LS	3	5	5.00	$65,228.60	$326,143.00
		LS	4	1	1.00	$130,000.00	$130,000.00
		LS	6	1	1.00	$50,000.00	$50,000.00
		LS	7	1	1.00	$157,500.00	$157,500.00
		LS	11	1	1.00	$15,000.00	$15,000.00
		LS	12	1	1.00	$62,500.00	$62,500.00
	Unit Sub Total	**LS**		**11**	**11.00**	**$68,206.64**	**$750,273.00**
	Item Code 860401 Total No. of Proj.			**11**		**Total Amount**	**$750,273.00**
860402	LIGHTING (CITY STREET)	LS	2	1	1.00	$49,000.00	$49,000.00
		LS	4	4	4.00	$141,284.64	$565,138.54
		LS	5	1	1.00	$73,000.00	$73,000.00
		LS	7	1	1.00	$267,000.00	$267,000.00
		LS	12	1	1.00	$72,000.00	$72,000.00
	Unit Sub Total	**LS**		**8**	**8.00**	**$128,267.32**	**$1,026,138.54**
	Item Code 860402 Total No. of Proj.			**8**		**Total Amount**	**$1,026,138.54**
860403	HIGHWAY LIGHTING	LS	4	1	1.00	$32,760.00	$32,760.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$32,760.00**	**$32,760.00**
	Item Code 860403 Total No. of Proj.			**1**		**Total Amount**	**$32,760.00**
860407	LIGHTING (PARKING LOT)	LS	4	1	1.00	$50,000.00	$50,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$50,000.00**	**$50,000.00**
	Item Code 860407 Total No. of Proj.			**1**		**Total Amount**	**$50,000.00**
860415	LIGHTING (STAGE CONSTRUCTION)	LS	3	1	1.00	$100,000.00	$100,000.00
		LS	12	2	2.00	$115,000.00	$230,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$110,000.00**	**$330,000.00**
	Item Code 860415 Total No. of Proj.			**3**		**Total Amount**	**$330,000.00**
860420	LIGHTING (TUNNEL)	LS	12	1	1.00	$25,100.00	$25,100.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$25,100.00**	**$25,100.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 860420 Total No. of Proj.			**1**		**Total Amount**	**$25,100.00**
860435	LIGHTING (DETOUR)	LS	4	1	1.00	$50,000.00	$50,000.00
		LS	10	1	1.00	$35,000.00	$35,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$42,500.00**	**$85,000.00**
	Item Code 860435 Total No. of Proj.			**2**		**Total Amount**	**$85,000.00**
860460	LIGHTING AND SIGN ILLUMINATION	LS	2	1	1.00	$99,800.00	$99,800.00
		LS	4	5	5.00	$264,140.04	$1,320,700.20
		LS	5	1	1.00	$59,000.00	$59,000.00
		LS	7	1	1.00	$1,521,000.00	$1,521,000.00
		LS	10	1	1.00	$108,120.00	$108,120.00
		LS	11	2	2.00	$166,250.00	$332,500.00
		LS	12	5	5.00	$536,601.00	$2,683,005.00
	Unit Sub Total	**LS**		**16**	**16.00**	**$382,757.83**	**$6,124,125.20**
	Item Code 860460 Total No. of Proj.			**16**		**Total Amount**	**$6,124,125.20**
860461	LIGHTING (LOCATION 1)	LS	4	1	1.00	$15,000.00	$15,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$15,000.00**	**$15,000.00**
	Item Code 860461 Total No. of Proj.			**1**		**Total Amount**	**$15,000.00**
860501	SIGN ILLUMINATION	LS	3	3	3.00	$67,066.67	$201,200.00
		LS	7	2	2.00	$6,750.00	$13,500.00
		LS	8	1	1.00	$10,000.00	$10,000.00
	Unit Sub Total	**LS**		**6**	**6.00**	**$37,450.00**	**$224,700.00**
	Item Code 860501 Total No. of Proj.			**6**		**Total Amount**	**$224,700.00**
860508	MODIFY SIGN ILLUMINATION	LS	3	1	1.00	$10,100.00	$10,100.00
		LS	5	1	1.00	$13,000.00	$13,000.00
		LS	7	4	4.00	$24,325.00	$97,300.00
		LS	8	1	1.00	$4,000.00	$4,000.00
	Unit Sub Total	**LS**		**7**	**7.00**	**$17,771.43**	**$124,400.00**
	Item Code 860508 Total No. of Proj.			**7**		**Total Amount**	**$124,400.00**
860520	HIGHWAY ADVISORY RADIO SYSTEM	LS	2	1	1.00	$200,000.00	$200,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
860520	HIGHWAY ADVISORY RADIO SYSTEM	LS	6	1	1.00	$172,000.00	$172,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$186,000.00**	**$372,000.00**
	Item Code 860520 Total No. of Proj.			**2**		**Total Amount**	**$372,000.00**
860530	CHANGEABLE MESSAGE SIGN SYSTEM	LS	3	1	1.00	$57,000.00	$57,000.00
		LS	7	1	1.00	$52,000.00	$52,000.00
		LS	8	1	1.00	$25,399.00	$25,399.00
		LS	10	1	1.00	$42,840.00	$42,840.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$44,309.75**	**$177,239.00**
	Item Code 860530 Total No. of Proj.			**4**		**Total Amount**	**$177,239.00**
860551	LIGHTING AND SIGN ILLUMINATION (LOCATION 1)	LS	4	1	1.00	$15,000.00	$15,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$15,000.00**	**$15,000.00**
	Item Code 860551 Total No. of Proj.			**1**		**Total Amount**	**$15,000.00**
860552	LIGHTING AND SIGN ILLUMINATION (LOCATION 2)	LS	4	1	1.00	$5,000.00	$5,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$5,000.00**	**$5,000.00**
	Item Code 860552 Total No. of Proj.			**1**		**Total Amount**	**$5,000.00**
860553	LIGHTING AND SIGN ILLUMINATION (LOCATION 3)	LS	4	1	1.00	$15,000.00	$15,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$15,000.00**	**$15,000.00**
	Item Code 860553 Total No. of Proj.			**1**		**Total Amount**	**$15,000.00**
860554	LIGHTING AND SIGN ILLUMINATION (LOCATION 4)	LS	4	1	1.00	$40,000.00	$40,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$40,000.00**	**$40,000.00**
	Item Code 860554 Total No. of Proj.			**1**		**Total Amount**	**$40,000.00**
860601	FLASHING BEACON	LS	7	1	1.00	$10,500.00	$10,500.00
		LS	11	1	1.00	$36,000.00	$36,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$23,250.00**	**$46,500.00**
	Item Code 860601 Total No. of Proj.			**2**		**Total Amount**	**$46,500.00**
860603	FLASHING BEACON AND LIGHTING	LS	2	1	1.00	$71,700.00	$71,700.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$71,700.00**	**$71,700.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 860603 Total No. of Proj.			**1**		**Total Amount**	**$71,700.00**
860604	FLASHING BEACON SYSTEM	LS	2	1	1.00	$45,000.00	$45,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$45,000.00**	**$45,000.00**
	Item Code 860604 Total No. of Proj.			**1**		**Total Amount**	**$45,000.00**
860615	MODIFY FLASHING BEACON	LS	4	1	1.00	$40,000.00	$40,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$40,000.00**	**$40,000.00**
	Item Code 860615 Total No. of Proj.			**1**		**Total Amount**	**$40,000.00**
860703	INTERCONNECTION CONDUIT AND CABLE	LS	4	1	1.00	$65,491.18	$65,491.18
	Unit Sub Total	**LS**		**1**	**1.00**	**$65,491.18**	**$65,491.18**
	Item Code 860703 Total No. of Proj.			**1**		**Total Amount**	**$65,491.18**
860750	INTERCONNECTION SYSTEM	LS	4	1	1.00	$96,000.00	$96,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$96,000.00**	**$96,000.00**
	Item Code 860750 Total No. of Proj.			**1**		**Total Amount**	**$96,000.00**
860760	LIGHTING CONDUIT (CITY STREET)	LS	12	1	1.00	$3,000.00	$3,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$3,000.00**	**$3,000.00**
	Item Code 860760 Total No. of Proj.			**1**		**Total Amount**	**$3,000.00**
860761	LIGHTING CONDUIT (BRIDGE)	LF	11	1	450.00	$15.00	$6,750.00
	Unit Sub Total	**LF**		**1**	**450.00**	**$15.00**	**$6,750.00**
860761	LIGHTING CONDUIT (BRIDGE)	LS	7	1	1.00	$106,000.00	$106,000.00
		LS	11	1	1.00	$11,250.00	$11,250.00
		LS	12	1	1.00	$10,000.00	$10,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$42,416.67**	**$127,250.00**
	Item Code 860761 Total No. of Proj.			**4**		**Total Amount**	**$134,000.00**
860791	COMMUNICATION CONDUIT	LF	5	2	580.00	$10.84	$6,290.00
		LF	8	1	100.00	$12.00	$1,200.00
	Unit Sub Total	**LF**		**3**	**680.00**	**$11.01**	**$7,490.00**
860791	COMMUNICATION CONDUIT	LS	4	1	1.00	$250,000.00	$250,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
860791	COMMUNICATION CONDUIT	LS	6	1	1.00	$100,000.00	$100,000.00
		LS	10	1	1.00	$54,000.00	$54,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$134,666.67**	**$404,000.00**
	Item Code 860791 Total No. of Proj.			**6**		**Total Amount**	**$411,490.00**
860792	COMMUNICATION CONDUIT (BRIDGE)	M	7	3	1,452.00	$184.66	$268,130.00
	Unit Sub Total	**M**		**3**	**1,452.00**	**$184.66**	**$268,130.00**
	Item Code 860792 Total No. of Proj.			**3**		**Total Amount**	**$268,130.00**
860796	SPRINKLER CONTROL CONDUIT (BRIDGE)	LF	11	1	450.00	$15.00	$6,750.00
		LF	12	2	1,170.00	$16.26	$19,020.00
	Unit Sub Total	**LF**		**3**	**1,620.00**	**$15.91**	**$25,770.00**
860796	SPRINKLER CONTROL CONDUIT (BRIDGE)	LS	7	3	3.00	$21,350.00	$64,050.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$21,350.00**	**$64,050.00**
860796	SPRINKLER CONTROL CONDUIT (BRIDGE)	M	7	1	33.00	$110.00	$3,630.00
		M	11	2	330.00	$50.00	$16,500.00
	Unit Sub Total	**M**		**3**	**363.00**	**$55.45**	**$20,130.00**
	Item Code 860796 Total No. of Proj.			**9**		**Total Amount**	**$109,950.00**
860797	ELECTRIC SERVICE (IRRIGATION)	LS	3	1	1.00	$5,400.00	$5,400.00
		LS	4	4	4.00	$29,254.00	$117,016.00
		LS	5	2	2.00	$16,500.00	$33,000.00
		LS	7	4	4.00	$21,055.00	$84,220.00
		LS	8	1	1.00	$10,000.00	$10,000.00
		LS	10	4	4.00	$12,383.75	$49,535.00
		LS	11	2	2.00	$28,050.00	$56,100.00
		LS	12	4	4.00	$13,375.00	$53,500.00
	Unit Sub Total	**LS**		**22**	**22.00**	**$18,580.50**	**$408,771.00**
	Item Code 860797 Total No. of Proj.			**22**		**Total Amount**	**$408,771.00**
860798	BOOSTER PUMP ELECTRICAL SYSTEM	LS	3	1	1.00	$12,000.00	$12,000.00
		LS	10	1	1.00	$1,680.00	$1,680.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$6,840.00**	**$13,680.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 860798	**Total No. of Proj.**			**2**		**Total Amount**	**$13,680.00**
860810	INDUCTIVE LOOP DETECTOR		EA	8	11	948.00	$290.33	$275,235.00
			EA	10	1	170.00	$750.00	$127,500.00
			EA	11	5	56.00	$801.61	$44,890.00
			EA	12	4	935.00	$374.01	$349,694.70
		Unit Sub Total	**EA**		**21**	**2,109.00**	**$378.06**	**$797,319.70**
860810	INDUCTIVE LOOP DETECTOR		LS	2	1	1.00	$12,150.00	$12,150.00
			LS	5	3	3.00	$17,166.67	$51,500.00
			LS	6	1	1.00	$6,000.00	$6,000.00
			LS	10	1	1.00	$5,000.00	$5,000.00
			LS	12	4	4.00	$29,950.00	$119,800.00
		Unit Sub Total	**LS**		**10**	**10.00**	**$19,445.00**	**$194,450.00**
	Item Code 860810	**Total No. of Proj.**			**31**		**Total Amount**	**$991,769.70**
860811	DETECTOR LOOP		EA	9	2	6.00	$1,300.00	$7,800.00
			EA	11	1	400.00	$400.00	$160,000.00
		Unit Sub Total	**EA**		**3**	**406.00**	**$413.30**	**$167,800.00**
860811	DETECTOR LOOP		LS	5	2	2.00	$17,500.00	$35,000.00
			LS	6	3	3.00	$23,983.33	$71,950.00
		Unit Sub Total	**LS**		**5**	**5.00**	**$21,390.00**	**$106,950.00**
	Item Code 860811	**Total No. of Proj.**			**8**		**Total Amount**	**$274,750.00**
860812	MICROWAVE VEHICLE DETECTION SYSTEM		EA	10	1	11.00	$14,500.00	$159,500.00
		Unit Sub Total	**EA**		**1**	**11.00**	**$14,500.00**	**$159,500.00**
860812	MICROWAVE VEHICLE DETECTION SYSTEM		LS	3	1	1.00	$452,000.00	$452,000.00
			LS	5	2	2.00	$292,290.00	$584,580.00
			LS	10	1	1.00	$73,950.00	$73,950.00
		Unit Sub Total	**LS**		**4**	**4.00**	**$277,632.50**	**$1,110,530.00**
	Item Code 860812	**Total No. of Proj.**			**5**		**Total Amount**	**$1,270,030.00**
860889	MODIFY TRAFFIC MONITORING STATION		LS	2	3	3.00	$9,958.33	$29,875.00
			LS	3	3	3.00	$28,329.00	$84,987.00
			LS	6	4	4.00	$21,887.50	$87,550.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
860889	MODIFY TRAFFIC MONITORING STATION	LS	7	4	4.00	$32,437.50	$129,750.00
		LS	8	1	1.00	$8,000.00	$8,000.00
		LS	10	4	4.00	$66,567.50	$266,270.00
		LS	11	1	1.00	$8,000.00	$8,000.00
		LS	12	2	2.00	$6,750.00	$13,500.00
	Unit Sub Total	**LS**		**22**	**22.00**	**$28,542.36**	**$627,932.00**
	Item Code 860889 Total No. of Proj.			**22**		**Total Amount**	**$627,932.00**
860890	MODIFY TRAFFIC MONITORING STATION (COUNT)	LS	3	7	7.00	$16,114.29	$112,800.00
	Unit Sub Total	**LS**		**7**	**7.00**	**$16,114.29**	**$112,800.00**
	Item Code 860890 Total No. of Proj.			**7**		**Total Amount**	**$112,800.00**
860925	TRAFFIC MONITORING STATION (COUNT)	LS	2	1	1.00	$6,175.00	$6,175.00
		LS	3	4	4.00	$14,594.25	$58,377.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$12,910.40**	**$64,552.00**
	Item Code 860925 Total No. of Proj.			**5**		**Total Amount**	**$64,552.00**
860930	TRAFFIC MONITORING STATION	LS	2	11	11.00	$23,107.27	$254,180.00
		LS	3	1	1.00	$29,000.00	$29,000.00
		LS	6	3	3.00	$21,666.67	$65,000.00
		LS	10	1	1.00	$55,000.00	$55,000.00
		LS	11	1	1.00	$59,244.00	$59,244.00
		LS	12	1	1.00	$24,900.00	$24,900.00
	Unit Sub Total	**LS**		**18**	**18.00**	**$27,073.56**	**$487,324.00**
	Item Code 860930 Total No. of Proj.			**18**		**Total Amount**	**$487,324.00**
860931	TRAFFIC MONITORING STATION (LOCATION 1)	LS	6	1	1.00	$20,000.00	$20,000.00
		LS	11	2	2.00	$17,950.00	$35,900.00
		LS	12	2	2.00	$32,500.00	$65,000.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$24,180.00**	**$120,900.00**
	Item Code 860931 Total No. of Proj.			**5**		**Total Amount**	**$120,900.00**
860932	TRAFFIC MONITORING STATION (LOCATION 2)	LS	6	1	1.00	$20,000.00	$20,000.00
		LS	11	2	2.00	$17,950.00	$35,900.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
860932	TRAFFIC MONITORING STATION (LOCATION 2)	LS	12	2	2.00	$32,500.00	$65,000.00
	Unit Sub Total	**LS**		**5**	**5.00**	**$24,180.00**	**$120,900.00**
	Item Code 860932 Total No. of Proj.			**5**		**Total Amount**	**$120,900.00**
860933	TRAFFIC MONITORING STATION (LOCATION 3)	LS	12	2	2.00	$27,500.00	$55,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$27,500.00**	**$55,000.00**
	Item Code 860933 Total No. of Proj.			**2**		**Total Amount**	**$55,000.00**
860990	CLOSED CIRCUIT TELEVISION SYSTEM	LS	2	2	2.00	$131,000.00	$262,000.00
		LS	3	1	1.00	$37,000.00	$37,000.00
		LS	4	1	1.00	$27,000.00	$27,000.00
		LS	5	2	2.00	$46,100.00	$92,200.00
		LS	6	1	1.00	$44,700.00	$44,700.00
		LS	10	1	1.00	$44,370.00	$44,370.00
		LS	12	1	1.00	$67,000.00	$67,000.00
	Unit Sub Total	**LS**		**9**	**9.00**	**$63,807.78**	**$574,270.00**
	Item Code 860990 Total No. of Proj.			**9**		**Total Amount**	**$574,270.00**
861088	MODIFY RAMP METERING SYSTEM	LS	3	2	2.00	$47,100.00	$94,200.00
		LS	7	6	6.00	$221,083.33	$1,326,500.00
		LS	12	3	3.00	$37,666.67	$113,000.00
	Unit Sub Total	**LS**		**11**	**11.00**	**$139,427.27**	**$1,533,700.00**
	Item Code 861088 Total No. of Proj.			**11**		**Total Amount**	**$1,533,700.00**
861100	RAMP METERING SYSTEM	LS	3	2	2.00	$62,500.00	$125,000.00
		LS	7	1	1.00	$56,000.00	$56,000.00
		LS	12	1	1.00	$9,000.00	$9,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$47,500.00**	**$190,000.00**
	Item Code 861100 Total No. of Proj.			**4**		**Total Amount**	**$190,000.00**
861101	RAMP METERING SYSTEM (LOCATION 1)	LS	4	3	3.00	$81,333.33	$244,000.00
		LS	6	1	1.00	$59,696.00	$59,696.00
		LS	11	1	1.00	$150,000.00	$150,000.00
		LS	12	2	2.00	$27,000.00	$54,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LS**		**7**	**7.00**	**$72,528.00**	**$507,696.00**
	Item Code 861101 Total No. of Proj.			**7**		**Total Amount**	**$507,696.00**
861102	RAMP METERING SYSTEM (LOCATION 2)	LS	4	3	3.00	$109,333.33	$328,000.00
		LS	6	1	1.00	$55,487.00	$55,487.00
		LS	11	1	1.00	$225,000.00	$225,000.00
		LS	12	3	3.00	$21,333.33	$64,000.00
	Unit Sub Total	**LS**		**8**	**8.00**	**$84,060.88**	**$672,487.00**
	Item Code 861102 Total No. of Proj.			**8**		**Total Amount**	**$672,487.00**
861103	RAMP METERING SYSTEM (LOCATION 3)	LS	4	3	3.00	$54,666.67	$164,000.00
		LS	6	1	1.00	$32,359.00	$32,359.00
		LS	12	3	3.00	$12,333.33	$37,000.00
	Unit Sub Total	**LS**		**7**	**7.00**	**$33,337.00**	**$233,359.00**
	Item Code 861103 Total No. of Proj.			**7**		**Total Amount**	**$233,359.00**
861104	RAMP METERING SYSTEM (LOCATION 4)	LS	4	3	3.00	$106,666.67	$320,000.00
		LS	6	1	1.00	$50,880.00	$50,880.00
		LS	12	2	2.00	$14,500.00	$29,000.00
	Unit Sub Total	**LS**		**6**	**6.00**	**$66,646.67**	**$399,880.00**
	Item Code 861104 Total No. of Proj.			**6**		**Total Amount**	**$399,880.00**
861105	RAMP METERING SYSTEM (LOCATION 5)	LS	4	2	2.00	$56,000.00	$112,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$56,000.00**	**$112,000.00**
	Item Code 861105 Total No. of Proj.			**2**		**Total Amount**	**$112,000.00**
861106	RAMP METERING SYSTEM (LOCATION 6)	LS	4	2	2.00	$51,000.00	$102,000.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$51,000.00**	**$102,000.00**
	Item Code 861106 Total No. of Proj.			**2**		**Total Amount**	**$102,000.00**
861107	RAMP METERING SYSTEM (LOCATION 7)	LS	4	1	1.00	$70,000.00	$70,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$70,000.00**	**$70,000.00**
	Item Code 861107 Total No. of Proj.			**1**		**Total Amount**	**$70,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
861203	HIGH SPEED WEIGH-IN-MOTION SYSTEM	LS	4	2	2.00	$199,851.50	$399,703.00
		LS	5	1	1.00	$237,175.00	$237,175.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$212,292.67**	**$636,878.00**
	Item Code 861203 Total No. of Proj.			**3**		**Total Amount**	**$636,878.00**
861295	RELOCATE EXTINGUISHABLE MESSAGE SIGN	LS	4	1	1.00	$15,000.00	$15,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$15,000.00**	**$15,000.00**
	Item Code 861295 Total No. of Proj.			**1**		**Total Amount**	**$15,000.00**
861303	RELOCATE FLASHING BEACON	LS	11	1	1.00	$9,900.00	$9,900.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$9,900.00**	**$9,900.00**
	Item Code 861303 Total No. of Proj.			**1**		**Total Amount**	**$9,900.00**
861491	MODIFY SIGNAL (LOCATION 1)	LS	10	5	5.00	$9,370.00	$46,850.00
		LS	11	1	1.00	$17,010.00	$17,010.00
	Unit Sub Total	**LS**		**6**	**6.00**	**$10,643.33**	**$63,860.00**
	Item Code 861491 Total No. of Proj.			**6**		**Total Amount**	**$63,860.00**
861492	MODIFY SIGNAL (LOCATION 2)	LS	10	5	5.00	$11,700.00	$58,500.00
		LS	11	1	1.00	$11,400.00	$11,400.00
	Unit Sub Total	**LS**		**6**	**6.00**	**$11,650.00**	**$69,900.00**
	Item Code 861492 Total No. of Proj.			**6**		**Total Amount**	**$69,900.00**
861493	MODIFY SIGNAL (LOCATION 3)	LS	10	3	3.00	$11,733.33	$35,200.00
		LS	11	1	1.00	$8,100.00	$8,100.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$10,825.00**	**$43,300.00**
	Item Code 861493 Total No. of Proj.			**4**		**Total Amount**	**$43,300.00**
861494	MODIFY SIGNAL (LOCATION 4)	LS	10	1	1.00	$11,000.00	$11,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$11,000.00**	**$11,000.00**
	Item Code 861494 Total No. of Proj.			**1**		**Total Amount**	**$11,000.00**
861495	MODIFY SIGNAL (LOCATION 5)	LS	10	1	1.00	$17,800.00	$17,800.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$17,800.00**	**$17,800.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 861495 Total No. of Proj.			**1**		**Total Amount**	**$17,800.00**
861497	MODIFY SIGNAL AND LIGHTING (LOCATION 1)	LS	4	2	2.00	$166,500.00	$333,000.00
		LS	6	2	2.00	$43,950.00	$87,900.00
		LS	7	1	1.00	$50,000.00	$50,000.00
		LS	11	1	1.00	$4,000.00	$4,000.00
		LS	12	1	1.00	$170,000.00	$170,000.00
	Unit Sub Total	**LS**		**7**	**7.00**	**$92,128.57**	**$644,900.00**
	Item Code 861497 Total No. of Proj.			**7**		**Total Amount**	**$644,900.00**
861498	MODIFY SIGNAL AND LIGHTING (LOCATION 2)	LS	4	2	2.00	$79,000.00	$158,000.00
		LS	6	2	2.00	$20,600.00	$41,200.00
		LS	7	1	1.00	$80,000.00	$80,000.00
		LS	11	2	2.00	$10,000.00	$20,000.00
		LS	12	1	1.00	$40,500.00	$40,500.00
	Unit Sub Total	**LS**		**8**	**8.00**	**$42,462.50**	**$339,700.00**
	Item Code 861498 Total No. of Proj.			**8**		**Total Amount**	**$339,700.00**
861499	MODIFY SIGNAL AND LIGHTING (LOCATION 3)	LS	4	1	1.00	$75,000.00	$75,000.00
		LS	6	2	2.00	$23,950.00	$47,900.00
		LS	7	1	1.00	$97,000.00	$97,000.00
		LS	11	2	2.00	$25,750.00	$51,500.00
	Unit Sub Total	**LS**		**6**	**6.00**	**$45,233.33**	**$271,400.00**
	Item Code 861499 Total No. of Proj.			**6**		**Total Amount**	**$271,400.00**
861500	MODIFY SIGNAL AND LIGHTING (LOCATION 4)	LS	4	1	1.00	$25,746.00	$25,746.00
		LS	6	2	2.00	$16,000.00	$32,000.00
		LS	11	1	1.00	$33,000.00	$33,000.00
	Unit Sub Total	**LS**		**4**	**4.00**	**$22,686.50**	**$90,746.00**
	Item Code 861500 Total No. of Proj.			**4**		**Total Amount**	**$90,746.00**
861501	MODIFY SIGNAL AND LIGHTING	LS	1	1	1.00	$112,333.00	$112,333.00
		LS	4	1	1.00	$25,000.00	$25,000.00
		LS	6	3	3.00	$113,333.33	$340,000.00
		LS	7	2	2.00	$39,500.00	$79,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
861501	MODIFY SIGNAL AND LIGHTING	LS	8	1	1.00	$37,000.00	$37,000.00
		LS	11	1	1.00	$73,500.00	$73,500.00
	Unit Sub Total	**LS**		**9**	**9.00**	**$74,092.56**	**$666,833.00**
	Item Code 861501 Total No. of Proj.			**9**		**Total Amount**	**$666,833.00**
861502	MODIFY SIGNAL	LS	3	3	3.00	$90,566.67	$271,700.00
		LS	5	5	5.00	$12,746.00	$63,730.00
		LS	6	1	1.00	$11,000.00	$11,000.00
	Unit Sub Total	**LS**		**9**	**9.00**	**$38,492.22**	**$346,430.00**
	Item Code 861502 Total No. of Proj.			**9**		**Total Amount**	**$346,430.00**
861503	MODIFY LIGHTING	LS	3	1	1.00	$1,246,641.00	$1,246,641.00
		LS	6	5	5.00	$27,160.00	$135,800.00
		LS	7	1	1.00	$54,900.00	$54,900.00
		LS	10	1	1.00	$93,000.00	$93,000.00
	Unit Sub Total	**LS**		**8**	**8.00**	**$191,292.63**	**$1,530,341.00**
	Item Code 861503 Total No. of Proj.			**8**		**Total Amount**	**$1,530,341.00**
861504	MODIFY LIGHTING AND SIGN ILLUMINATION	LS	3	1	1.00	$102,000.00	$102,000.00
		LS	4	1	1.00	$17,500.00	$17,500.00
		LS	6	3	3.00	$65,205.33	$195,616.00
		LS	7	4	4.00	$372,500.00	$1,490,000.00
		LS	8	1	1.00	$175,000.00	$175,000.00
		LS	11	1	1.00	$20,000.00	$20,000.00
		LS	12	1	1.00	$52,000.00	$52,000.00
	Unit Sub Total	**LS**		**12**	**12.00**	**$171,009.67**	**$2,052,116.00**
	Item Code 861504 Total No. of Proj.			**12**		**Total Amount**	**$2,052,116.00**
861505	MODIFY SIGNAL AND LIGHTING (LOCATION 5)	LS	4	1	1.00	$16,500.00	$16,500.00
		LS	6	1	1.00	$6,800.00	$6,800.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$11,650.00**	**$23,300.00**
	Item Code 861505 Total No. of Proj.			**2**		**Total Amount**	**$23,300.00**
861506	MODIFY SIGNAL AND LIGHTING (LOCATION 6)	LS	4	1	1.00	$21,000.00	$21,000.00
		LS	6	1	1.00	$55,000.00	$55,000.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Unit Sub Total	**LS**		**2**	**2.00**	**$38,000.00**	**$76,000.00**
	Item Code 861506 Total No. of Proj.			**2**		**Total Amount**	**$76,000.00**
861507	MODIFY SIGNAL AND LIGHTING (LOCATION 7)	LS	4	1	1.00	$25,000.00	$25,000.00
		LS	6	1	1.00	$2,900.00	$2,900.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$13,950.00**	**$27,900.00**
	Item Code 861507 Total No. of Proj.			**2**		**Total Amount**	**$27,900.00**
861508	MODIFY SIGNAL AND LIGHTING (LOCATION 8)	LS	4	1	1.00	$24,000.00	$24,000.00
		LS	6	1	1.00	$2,600.00	$2,600.00
	Unit Sub Total	**LS**		**2**	**2.00**	**$13,300.00**	**$26,600.00**
	Item Code 861508 Total No. of Proj.			**2**		**Total Amount**	**$26,600.00**
861509	MODIFY SIGNAL AND LIGHTING (LOCATION 9)	LS	4	1	1.00	$26,000.00	$26,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$26,000.00**	**$26,000.00**
	Item Code 861509 Total No. of Proj.			**1**		**Total Amount**	**$26,000.00**
861511	MODIFY LIGHTING (LOCATION 1)	LS	11	1	1.00	$26,000.00	$26,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$26,000.00**	**$26,000.00**
	Item Code 861511 Total No. of Proj.			**1**		**Total Amount**	**$26,000.00**
861512	MODIFY LIGHTING (LOCATION 2)	LS	11	1	1.00	$25,000.00	$25,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$25,000.00**	**$25,000.00**
	Item Code 861512 Total No. of Proj.			**1**		**Total Amount**	**$25,000.00**
861513	MODIFY LIGHTING (LOCATION 3)	LS	11	1	1.00	$24,000.00	$24,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$24,000.00**	**$24,000.00**
	Item Code 861513 Total No. of Proj.			**1**		**Total Amount**	**$24,000.00**
861514	MODIFY LIGHTING (LOCATION 4)	LS	11	1	1.00	$1,000.00	$1,000.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$1,000.00**	**$1,000.00**
	Item Code 861514 Total No. of Proj.			**1**		**Total Amount**	**$1,000.00**
862065	REPLACE PULL BOX	EA	11	1	2.00	$600.00	$1,200.00

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION		UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
		Unit Sub Total	**EA**		**1**	**2.00**	**$600.00**	**$1,200.00**
862065	REPLACE PULL BOX		LS	3	1	1.00	$1,000.00	$1,000.00
			LS	4	1	1.00	$1,200.00	$1,200.00
			LS	6	2	2.00	$2,550.00	$5,100.00
		Unit Sub Total	**LS**		**4**	**4.00**	**$1,825.00**	**$7,300.00**
	Item Code 862065	**Total No. of Proj.**			**5**		**Total Amount**	**$8,500.00**
867014	12 SINGLEMODE FIBER OPTIC CABLE		M	7	1	2,400.00	$10.60	$25,440.00
		Unit Sub Total	**M**		**1**	**2,400.00**	**$10.60**	**$25,440.00**
	Item Code 867014	**Total No. of Proj.**			**1**		**Total Amount**	**$25,440.00**
867130	FIBER OPTIC SPLICE CLOSURE		EA	4	1	8.00	$8,900.00	$71,200.00
			EA	7	1	24.00	$1,696.00	$40,704.00
		Unit Sub Total	**EA**		**2**	**32.00**	**$3,497.00**	**$111,904.00**
	Item Code 867130	**Total No. of Proj.**			**2**		**Total Amount**	**$111,904.00**
869034	NO. 5(T) PULL BOX		EA	8	1	2.00	$1,000.00	$2,000.00
		Unit Sub Total	**EA**		**1**	**2.00**	**$1,000.00**	**$2,000.00**
	Item Code 869034	**Total No. of Proj.**			**1**		**Total Amount**	**$2,000.00**
869035	NO. 5 PULL BOX		EA	7	1	13.00	$1,060.00	$13,780.00
		Unit Sub Total	**EA**		**1**	**13.00**	**$1,060.00**	**$13,780.00**
	Item Code 869035	**Total No. of Proj.**			**1**		**Total Amount**	**$13,780.00**
869039	COMMUNICATION PULL BOX		EA	7	1	37.00	$1,484.00	$54,908.00
		Unit Sub Total	**EA**		**1**	**37.00**	**$1,484.00**	**$54,908.00**
	Item Code 869039	**Total No. of Proj.**			**1**		**Total Amount**	**$54,908.00**
869040	PULL BOX		EA	11	2	48.00	$265.42	$12,740.00
		Unit Sub Total	**EA**		**2**	**48.00**	**$265.42**	**$12,740.00**
869040	PULL BOX		LS	11	1	1.00	$600.00	$600.00
		Unit Sub Total	**LS**		**1**	**1.00**	**$600.00**	**$600.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
	Item Code 869040 Total No. of Proj.			**3**		**Total Amount**	**$13,340.00**
869042	ADJUST PULL BOX	EA	2	1	2.00	$250.00	$500.00
		EA	4	1	1.00	$250.00	$250.00
		EA	6	1	2.00	$150.00	$300.00
	Unit Sub Total	**EA**		**3**	**5.00**	**$210.00**	**$1,050.00**
	Item Code 869042 Total No. of Proj.			**3**		**Total Amount**	**$1,050.00**
869047	SPLICE VAULT	EA	7	1	15.00	$5,300.00	$79,500.00
	Unit Sub Total	**EA**		**1**	**15.00**	**$5,300.00**	**$79,500.00**
	Item Code 869047 Total No. of Proj.			**1**		**Total Amount**	**$79,500.00**
869050	GUARD POST	EA	2	2	12.00	$1,035.00	$12,420.00
		EA	7	1	1.00	$800.00	$800.00
	Unit Sub Total	**EA**		**3**	**13.00**	**$1,016.92**	**$13,220.00**
	Item Code 869050 Total No. of Proj.			**3**		**Total Amount**	**$13,220.00**
869070	POWER AND TELEPHONE SERVICE	LS	3	1	1.00	$18,200.00	$18,200.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$18,200.00**	**$18,200.00**
	Item Code 869070 Total No. of Proj.			**1**		**Total Amount**	**$18,200.00**
869075	SYSTEM TESTING AND DOCUMENTATION	LS	7	4	4.00	$47,125.00	$188,500.00
		LS	12	5	5.00	$30,300.00	$151,500.00
	Unit Sub Total	**LS**		**9**	**9.00**	**$37,777.78**	**$340,000.00**
	Item Code 869075 Total No. of Proj.			**9**		**Total Amount**	**$340,000.00**
869080	TRAINING	LS	12	3	3.00	$8,333.33	$25,000.00
	Unit Sub Total	**LS**		**3**	**3.00**	**$8,333.33**	**$25,000.00**
	Item Code 869080 Total No. of Proj.			**3**		**Total Amount**	**$25,000.00**
994444	KIOSK	EA	7	1	2.00	$7,000.00	$14,000.00
	Unit Sub Total	**EA**		**1**	**2.00**	**$7,000.00**	**$14,000.00**
	Item Code 994444 Total No. of Proj.			**1**		**Total Amount**	**$14,000.00**

CONTRACT ITEM COST DATA

ITEM CODE	ITEM DESCRIPTION	UNIT	DIST	NO. OF PROJ	QUANTITY	AVE PRICE PER UNIT	TOTAL AMOUNT
994650	BUILDING WORK	LS	2	1	1.00	$238,449.85	$238,449.85
		LS	3	4	4.00	$1,170,466.79	$4,681,867.16
		LS	4	2	2.00	$1,797,612.72	$3,595,225.44
		LS	6	3	3.00	$2,297,666.67	$6,893,000.00
		LS	9	3	3.00	$753,643.37	$2,260,930.10
		LS	10	2	2.00	$194,653.50	$389,307.00
		LS	11	2	2.00	$585,966.00	$1,171,932.00
		LS	12	1	1.00	$28,000.00	$28,000.00
	Unit Sub Total	**LS**		**18**	**18.00**	**$1,069,928.42**	**$19,258,711.55**
	Item Code 994650 Total No. of Proj.			**18**		**Total Amount**	**$19,258,711.55**
994900	DRINKING FOUNTAIN	LS	4	1	1.00	$2,500.00	$2,500.00
	Unit Sub Total	**LS**		**1**	**1.00**	**$2,500.00**	**$2,500.00**
	Item Code 994900 Total No. of Proj.			**1**		**Total Amount**	**$2,500.00**
994901	TRASH RECEPTACLE	EA	4	1	1.00	$1,000.00	$1,000.00
		EA	11	1	14.00	$658.00	$9,212.00
	Unit Sub Total	**EA**		**2**	**15.00**	**$680.80**	**$10,212.00**
	Item Code 994901 Total No. of Proj.			**2**		**Total Amount**	**$10,212.00**
999990	MOBILIZATION	LS	1	26	26.00	$86,408.35	$2,246,617.00
		LS	2	21	21.00	$303,241.50	$6,368,071.45
		LS	3	37	37.00	$532,313.72	$19,695,607.71
		LS	4	66	66.00	$593,141.76	$39,147,356.38
		LS	5	23	23.00	$185,145.78	$4,258,352.93
		LS	6	21	21.00	$463,683.13	$9,737,345.81
		LS	7	62	62.00	$313,260.10	$19,422,126.27
		LS	8	11	11.00	$138,159.31	$1,519,752.40
		LS	9	8	8.00	$42,744.61	$341,956.91
		LS	10	24	24.00	$239,727.95	$5,753,470.84
		LS	11	31	31.00	$212,253.21	$6,579,849.50
		LS	12	28	28.00	$694,399.92	$19,443,197.63
	Unit Sub Total	**LS**		**358**	**358.00**	**$375,736.61**	**$134,513,704.83**
	Item Code 999990 Total No. of Proj.			**358**		**Total Amount**	**$134,513,704.83**

APPENDIX A

Conversion Factors From English Units to SI Units

Unit	Abbr.	Multiply:	Unit	Abbr.
Acre	ACRE	0.4046856	Hectare	HA
Calendar Day	CDAY	1	Calendar Day	CDAY
Cubic Foot	CF	0.02831685	Cubic Meter	M3
Cubic Yard	CY	0.7645549	Cubic Meter	M3
Each	EA	1	Each	EA
Gallon	GAL	3.785412	Liter	L
Hour	HR	1	Hour	H
Pound	LB	0.4535924	Kilogram	KG
Linear Foot	LF	0.3048	Meter	M
Lane Mile	LNMI	1.609344	Lane Kilometer	LNKM
Lump Sum	LS	1	Lump Sum	LS
Thousand Foot Board Measure	MFBM	2.359737	Cubic Meter	M3
Mile	MI	1.609344	Kilometer	KM
Square Foot	SQFT	0.09290304	Square Meter	M2
Square Yard	SQYD	0.8361274	Square Meter	M2
Station (100 Ft)	STA	0.3048	Station (100 m)	STA
Tablet	TAB	1	Tablet	TAB
Ton	TON	0.9071847	Tonne (1000 kg)	TONN
Track Foot	TF	1	Track Foot	TF
Working Day	WDAY	1	Working Day	WDAY

APPENDIX B

Conversion Factors From SI Units to English Units

Unit	Abbr.	Multiply:	Unit	Abbr.
Hectare	HA	2.471054	Acre	ACRE
Calendar Day	CDAY	1	Calendar Day	CDAY
Cubic Meter	M3	35.31467	Cubic Foot	CF
Cubic Meter	M3	1.307951	Cubic Yard	CY
Each	EA	1	Each	EA
Liter	L	0.2641720	Gallon	GAL
Hour	H	1	Hour	HR
Kilogram	KG	2.204623	Pound	LB
Meter	M	3.280840	Linear Foot	LF
Lane Kilometer	LNKM	0.6213712	Lane Mile	LNMI
Lump Sum	LS	1	Lump Sum	LS
Cubic Meter	M3	0.4237760	Thousand Foot Board Measure	MFBM
Kilometer	KM	0.6213712	Mile	MI
Square Meter	M2	10.76391	Square Foot	SQFT
Square Meter	M2	1.195990	Square Yard	SQYD
Station (100 m)	STA	3.280840	Station (100 Ft)	STA
Tablet	TAB	1	Tablet	TAB
Tonne (1000 kg)	TONN	1.102312	Ton	TON
Track Foot	TF	1	Track Foot	TF
Working Day	WDAY	1	Working Day	WDAY